SEWAGE WORKS JOURNAL

VOL. XIII MARCH, 1941 No. 2

Special Features

Reorganization of Federation

New Constitution and By-Laws

Annual Report of Research Committee

Sludge Deposits—Fair, Moore and Thomas

OFFICIAL PUBLICATION OF THE
FEDERATION OF SEWAGE WORKS ASSOCIATIONS

FEDERATION OF SEWAGE WORKS ASSOCIATIONS

OFFICERS

President

CHAS. A. EMERSON, Consulting Engineer, Havens and Emerson, 233 Broadway, New York, N. Y.

Vice-President

A. S. BEDELL, Div. of Sanitation, State Dept. of Health, Albany, N. Y.

Treasurer

W. W. DEBERARD, City Engineer, Chicago, Ill.

Honorary Secretary

H. E. MOSES, Chief Engineer, State Dept. of Health, Harrisburg, Pa.

Executive Secretary

W. H. WISELY, Box 18, Urbana, Ill.

Editor

F. W. MOHLMAN, Chief Chemist, The Sanitary District of Chicago, 910 South Michigan Ave., Chicago, Ill.

Board of Control

EARNEST BOYCE, Lawrence, Kansas
JOHN W. CUNNINGHAM, Portland, Ore.
N. G. DAMOOSE, Battle Creek, Mich.
H. J. DARCEY, Oklahoma City, Oklahoma
CHAS. A. DAVIS, Denver, Colo.
V. M. EHLERS, Austin, Texas
JOHN E. FARMER, The Institute of Sanitary Engineers, Worthing, Sussex, England
G. R. FRITH, Atlanta, Ga.
J. H. GARNER, The Institute of Sewage Purification, Wakefield, England
F. W. GILCREAS, Albany, N. Y.
HARRY R. HALL, Hyattsville, Md.
CHARLES G. HYDE, Berkeley, Cal.
F. W. JONES, Cleveland, Ohio
MAX LEVINE, Ames, Ia.
PHIL. J. MARTIN, JR., Tucson, Ariz.
A. P. MILLER, New York, N. Y.
H. E. MOSES, Harrisburg, Pa.
N. L. NUSSBAUMER, Buffalo, N. Y.
WM. W. PIATT, Durham, N. C.
WILLEM RUDOLFS, New Brunswick, N. J.
GEORGE S. RUSSELL, St. Louis, Mo.
GEORGE J. SCHROEPFER, St. Paul, Minn.
W. W. TOWNE, Pierre, S. D.

SEWAGE WORKS JOURNAL

REG. U. S. PAT. OFF.

A Bimonthly Journal devoted to the advancement of fundamental and practical knowledge concerning the nature, collection, treatment and disposal of sewage and industrial wastes, and the design, construction, operation and management of sewage works.

Publication Office: Prince and Lemon Sts., Lancaster, Pa.

Editorial Office: 910 So. Michigan Ave., Chicago, Ill.

Subscription Price:

Members of Local Sewage Works Associations affiliated with the Federation, $1.50 per year.

Non-members: Total fee $3.00, which includes subscription at $2.00 and service information fee of $1.00; Canada, $3.50 per year; other countries, $4.00 per year.

Foreign Subscriptions must be accompanied by International Money Order.

Single copies: United States, $1.00 each; Foreign, $1.25 each.

Manuscript may be sent to the Editor, F. W. Mohlman, 910 So. Michigan Ave., Chicago, Ill., for acceptance or rejection subject to the provisions of the Federation constitution.

Advertising copy should be sent to Arthur A. Clay, Advertising Manager, Lancaster, Pa., or 654 Madison Ave., New York, N. Y.

Subscriptions and address changes should be sent to W. H. Wisely, Executive Secretary, Lancaster, Pa., or Box 18, Urbana, Illinois.

No claims will be allowed for copies of Journals lost in the mails unless such claims are received within sixty (60) days of the date of issue and no claims will be allowed for issues lost as a result of insufficient notice of change of address. "Missing from files" cannot be accepted as the reason for honoring a claim.

Entered as second-class matter, May 7, 1934, at the post office at Lancaster, Pa., under the Act of March 3, 1879.

No COSTLY OR UNSIGHTLY GAS HOLDERS with



A typical Dorr Multdigestion System, showing range of the gas holder on the 60 ft. dia. secondary tank.

ADVANTAGES OF DORR MULTDIGESTION

Mechanical Sludge Mixing in Primary Means

- Maximum gas production —20 to 25 cu. ft. per pound volatile destroyed —⅓ or more greater than in non-stirred primaries.
- Maximum reductions—60 to 65 per cent total solids; 80 to 85 per cent volatiles.

Quiescent Sludge Settling in Secondary Means

- A clear, harmless supernatant liquor for return to process.
- A dense, compact sludge for drying, filtration or incineration.
- A combination cover and gas holder that provides ample gas storage.

THE DORR MULTDIGESTION SYSTEM

★ The Dorr Multdigestion System is unique in that no separate, unsightly gas holder is required. Adequate gas storage capacity is provided in the secondary tank cover which rises and falls with the gas production.

Secondary tank gas holders rise from 7 to 19 ft., depending on the size of the tank, and provide from 1500 to 150,000 cu. ft. of gas storage—equivalent to 6 to 12 hours of gasification. This irons out variations in the rate of gas production and assures a uniform flow of gas to heaters and engines.

A Dorr Multdigestion System with self contained gas storage, costs less than equivalent capacity with separate gas holder. This fact, together with the other advantages cited to the left, has made this system the standard of the profession.

● *Write for details on the Dorr Multdigestion System which is now serving a population of several million in more than 60 communities.*

DORRCO

THE DORR COMPANY, INC. • ENGINEERS

570 LEXINGTON AVE. • NEW YORK

ATLANTA • TORONTO • CHICAGO • DENVER • LOS ANGELES

POLISHING BIOFILTRATION EFFLUENTS



Automatic Magnetite Filter installed around chlorination chamber at Liberty, N. Y.

Contractor: E. W. Martin, Liberty, N. Y.
Consulting Engineer: W. A. Hardenbergh, New York

LIBERTY DATA

- ***Activated Sludge Equivalent***
  Removals—
  Suspended Solids 93.8 percent
  B.O.D. 93.5 percent
- ***Better Final Effluent***
  Suspended Solids 10 P.P.M.
  B.O.D. 13 P.P.M.
- ***Non-Settleables Removed***
  54 percent of all suspended solids overflowing secondary clarifier removed by filter.



AT LIBERTY

The Biofiltration System at Liberty, N. Y., plus an Automatic Magnetite Filter is giving removals and final effluents comparing favorably with other more expensive types of sewage treatment.

The data at the left represent one week's operation—Aug. 28–Sept. 5, 1940—and speak for themselves. Design was based on a peak load of 1 M.G.D. and 2 gals. per minute per sq. ft. of Automatic Magnetite Filter area.

Automatic Magnetite Filters, wherever installed, polish plant effluents to a uniform degree —remove the finest solids at a lower cost per ton than any other device operating over the same range.

Write for our bulletin and full operating data on Liberty and other recent installations.

THE AUTOMATIC MAGNETITE FILTER IS MARKETED EXCLUSIVELY BY THE DORR COMPANY, INC.

FILTRATION EQUIPMENT CORP.
10 East 40th Street · Sales Office · New York, N. Y.
COARSE SCREENS · AUTOMATIC MAGNETITE FILTERS · CONKEY VACUUM FILTERS

ALUMINUM, DEFENSE, AND YOU

ALCOA

1

WE INTERRUPT our regular messages to report what's what with aluminum.

AT THE MOMENT delivery for civilian use must make way for defense. Everybody knows the reason. Defense requires and is using more aluminum per month than peacetime America ever consumed.

NEVERTHELESS, we intend that no one shall have to forego the things aluminum can do best one minute longer than we can help.

THERE IS NO SHORTAGE of bauxite, nor of anything else, except time. And Father Time is being given the race of his life.

WE ARE MOVING, for example, 35,000 yards of earth a day at Alcoa, Tenn., to get 50 acres under a single roof by September. It will require 193 carloads of roofing felt. Some of the operations in that plant will start even before the walls are up. That's an annual rolling capacity for 120 million pounds of high strength alloy sheet coming along fast.

LAST MARCH WE STUCK the first shovel in a cow pasture near Vancouver, Wash. In September a 30 million pound plant was delivering metal. It has been doubled, already. A third 30 million pound unit starts delivering in April; a fourth in May; a fifth in June. From cow pasture to 150 million pounds annual capacity in 15 months.

A SIDELIGHT: To make that 150 million pounds of aluminum, we first have to build factories to make 120 million pounds of carbon electrodes. We have to obtain the equipment (transformers, rectifiers, and the like) to feed 162,500 kw. of electricity into the reduction furnaces. This is a generating capacity equal to that of the state of Delaware plus twice that of Mississippi.

WHAT OF TOTAL PRODUCTION? In addition to Vancouver, further installations are being made at other of our plants, so that in less than a year their total capacity will be more than double that of 1939, when 327 million pounds were produced.

IN THE VERY MIDST of this demand we have lowered the price of aluminum ingot 15%. We state, without reservation, our hope that the price can be still further reduced.

DEFENSE APPLICATIONS use aluminum for exactly the same reasons you do. Defense priorities on aluminum simply say that there are some fundamental things that aluminum does supremely well. It will do them still better as important lessons in production, fabrication, and application are learned from every additional pound being produced and used.

YOU, SIR, have been using aluminum for various structures, in sewage disposal plants and for plant and material-handling equipment and for painting. It is not easy nor convenient to have to substitute other materials temporarily. We want you to know that we intend to make this hardship as short-lived as possible. Your aluminum is on the way. It is a promise.

ALUMINUM COMPANY OF AMERICA

ASKED THIS CONSULTING ENGINEER

① LOWER INITIAL COST! Yes, the cost is lower with an Aero-Filter because the filter bed volume is only 1/7 to 1/9 that of conventional filters! And no over-size primary tanks are required! This is made possible by Aero-Filter's efficient distribution of sewage to the filter bed.

② OPERATING COST IS LOWER, TOO, because the need for costly pumping for recirculation is eliminated by Aero-Filter's distribution. Thus, maintenance and power costs are proportionately lowered, and of course fixed-charge items are lower because of the low initial plant cost.

③ ADEQUATE PURIFICATION for any of your requirements is the third reason. By a choice of a single or two-stage design and supplementary units, any degree of effluent quality may be obtained! All this—at minimum cost for plant and operation! Think *that* one over!

④ AND A PROVED BACKGROUND is something you should consider. Aero-Filter is thoroughly proved. Its basic design factors have been established and approved by state boards of health. There are 49 Aero-Filter installations in 13 states —in both Northern and Southern climates!

Send for Aero-Filter Catalog No. 329
Address 1606 W. Bruce Street, Milwaukee, Wis.

REX SANITATION EQUIPMENT
CHAIN BELT COMPANY OF MILWAUKEE

50TH ANNIVERSARY 1891 REX 1941 CHAIN BELT COMPANY

The "Shadows" Know

That Chapman



One of an Installation of
Six 48" Manually Operated
CHAPMAN CONE VALVES
Weighing 39,000 lbs. each.

THE CHAPMAN VALVE

INDIAN ORCHARD,

and wide-use shows

Automatic Cone Valves

overshadow all others in handling tough control problems in sewage disposal work

What special qualities would you list as essential in the *ideal valve* for such uses as noted in box below? Would not your list include a clear-pipe waterway? Self-cleaning action? Positive, easy operation, especially after long periods in one position? Complete protection of seats when open or closed? Quick closing without surge? Superior adaptability both to throttling and free discharge? All these and more are combined in *only* one valve we know of — the Chapman Automatic Cone. We cannot overstress its proved efficiency and dependability in sewage treatment service.

Chapman Automatic Cone Valves are plug-type with most ingenious operating mechanisms. They are made in sizes from 6″ to 48″, and equipped with manual, hydraulic, electric or automatic operators. The best evidence of outstanding merit is their widespread use in such plants as:

Tallman's Island Sewage Treatment Works, New York;

Bondi's Island Sewage Disposal Plant, Springfield, Mass.

and many other modern sewage plants.

TYPICAL USES
CHAPMAN CONE VALVES
IN
SEWAGE TREATMENT PLANTS

1. Sewage Pump Discharge Checks.
2. Control of Sludge Chamber Levels.
3. Quick Operating Valves for Grit Chambers.
4. Air Blower Checks on Activated Sludge.

MANUFACTURING CO.

MASSACHUSETTS

LINK-BELT Equipment

FOR POSITIVE RESULTS — LOW COST OPERATION

STRAIGHTLINE COLLECTORS

Link-Belt STRAIGHTLINE Sludge Collectors for the removal of sludge from rectangular settling tanks consist of two strands of especially processed malleable chain from which are suspended, at uniform intervals, scraper flights usually made from red wood. Features are peak-cap bearings, swiveling flights, cross collectors for larger tanks, and positive sludge removal at a slow, uniform speed. Automatic or semi-automatic skimming equipment is furnished when required.

Years of uninterrupted service in a great many plants throughout the country have proved the high efficiency, durability and low-cost maintenance features of these units.

Many features of the Link-Belt STRAIGHTLINE Collector are patented.

Send for Book No. SWJ-1742.

CIRCULINE COLLECTORS

Link-Belt CIRCULINE Collectors for the removal of sludge from round tanks, consist of a flight conveyor suspended from a bridge, one end of which is pivoted at the center and the other travels around the circumference of the tank. Features are positive, slow, uniform speed, positive sludge re moval and excellent distribution of flo throughout the tank. Automatic skimmin is furnished when desired.

Send for Book No. SWJ-1642.

BIO-FILTRATION System for Treating Sewage

Bio-Filtration Sewage Treatment System with Link-Belt STRAIGHTLINE and CIRCULINE Collectors brings new advantages. The system consists of high rate shallow filter beds and recirculation of the effluent from the filter beds to the primary tanks. Features are great flexibility, high rate of B.O.D. loading and the ability of such a plant to handle strong domestic and industrial sewage in single-stage or two-stage treatment, as required. Many installations of this type are now in operation and under construction.

Send for Folder No. SWJ-1881.

STRAIGHTLINE Bar Screens

Link-Belt STRAIGHTLINE Mechanically-Cleaned Bar Screens have spaced parallel bars on which the larger floating solids in incoming sewage collect, and a mechanically operated rake for removal of the accumulating solids, thus assuring an even flow of sewage through the channel. The machine may be set vertically or inclined, and used in small or large plants.

Send for Folder No. SWJ-1587.

TRITOR Screens

The Link-Belt Tritor Screen is a combina tion of screen and grit chamber. It is espe cially designed for medium and small siz plants. Its main elements are a hopper, a ba screen, and a bucket elevator for removin grit from hopper, the buckets being perforate for drainage. On return run, rake teeth o buckets clean the screen. An adjustable we regulates velocity of flow through hoppe

Send for Folder No. SWJ-1587.

INDUSTRIAL WASTE SCREENS

The Link-Belt Industrial Waste Screen is an efficient and economical unit for the removal of objectionable suspended solids from industrial waste before the water is discharged into sewers or streams. The screenings come off the machine with a minimum of moisture. Units are available in several sizes and with coarse or fine screen medium. Wastes from canneries, textile mills, steel mills, etc., are handled successfully by these screens.

Send for Folder No. SWJ-1877.

STRAIGHTLINE Grit Collectors and Washers

The Link-Belt STRAIGHTLINE Grit Collector and Washer effectively collects, washes and removes settled grit and separates it from putrescible organic matter. This unit consists of a scraper type collector with pitched flights which turns the material over and over and discharges it into a washing ar dewatering screw at the influent end of th tank, from which it is carried up an inclin to a point of discharge.

Send for Folder No. SWJ-1942.

LINK-BELT WATER and SEWAGE TREATMENT PLANT EQUIPMENT INCLUDES: STRAIGHTLINE Mixers for Flocculation Tanks; STRAIGHTLINE Scum Breakers for Digestion Tanks; Elevated Diffusers; Traveling Water-Intake Screens; Roto-Louvre Dryers for sludge and other wet materials; P.I.V. Gear Variable Speed Drive for Pumps; Coal and Ashes Handling Machinery; Car Spotters and Haulage Systems; Shovels-Cranes-Draglines—Crawler, Tractor and Truck Mounted; and a complete line of elevating, conveying and power transmitting equipment. Catalogs sent on request.

LINK-BELT COMPANY

Specialists in the Manufacture of Equipment for Water and Sewage Treatment Plants

PHILADELPHIA	CHICAGO	LOS ANGELES	CLEVELAND
2045 W. Hunting Park Ave.	300 W. Pershing Road	361 S. Anderson St.	548 Rockefeller Bldg.

Atlanta..Baltimore..Boston..Buffalo..Dallas..Denver..Detroit..Grand Rapids..Houston..Huntington, W. Va...Indianapo Kansas City, Mo...Louisville..New Orleans..New York..Oakland, Calif...Pittsburgh..Portland, Ore...Salt Lake City..Seatt St. Louis..St. Paul..Wilkes-Barre

In Canada—Link-Belt Limited—Toronto Plant; Montreal; Vancouver; Swastika

Shovel-Dragline-Crane Division—Link-Belt Speeder Corp., Chicago and Cedar Rapids

GENERAL CHEMICAL ALUMINUM SULFATE

SPEEDS SLUDGE DRYING

Two simple methods of applying Aluminum Sulfate Solution to sludge as it flows onto the sand beds:

← A portable hand pump.

→ A discarded drum fitted with a wooden spigot.

General Chemical Aluminum Sulfate, dry fed or solution fed, reduces the sludge drying time from 30 days or more to an average of 10 days. Alum coagulates the sludge solids and thereby separates them from the liquid, which rapidly drains away. Carbon dioxide released in the reaction renders the sludge porous, thus permitting faster evaporation.

RELIEVE YOUR OVERCROWDED DIGESTORS. KEEP YOUR SAND BEDS CLEAN AND OPEN.

General Chemical Company will be pleased to cooperate with cities and towns desirous of expediting the drying of sludge on sand beds. Write to



GENERAL CHEMICAL COMPANY

40 RECTOR STREET, NEW YORK, N. Y.

Sales Offices: Atlanta · Baltimore · Boston · Buffalo · Charlotte (N. C.) · Chicago Cleveland · Denver · Detroit · Houston · Kansas City · Milwaukee · Minneapolis Newark (N. J.) · New York · Philadelphia · Pittsburgh · Providence (R. I.) St. Louis · Utica (N. Y.)

Pacific Coast Sales Offices: San Francisco · Los Angeles

Pacific Northwest Sales Offices: Wenatchee (Wash.) · Yakima (Wash.)

In Canada: The Nichols Chemical Company, Limited · Montreal · Toronto · Vancouver

ON YOUR NEXT SEWER LINE

BE SURE YOU GET THESE FIVE SAVINGS

JM PRODUCT

Johns-Manville

TRANSITE PIPE

The MODERN Material for Sewer and Water Lines

IN ALL TYPES of municipal sewer systems, J-M Transite Sewer Pipe provides important savings on the above five points. Asbestos-cement in composition, this durable pipe comes in long, easily installed lengths that reduce the number of joints in the line. Its unusual corrosion-resistance keeps maintenance low. Joints stay tight. And in many cases, because of Transite's high carrying capacity, grades can be flatter, trenches shallower or smaller pipe used.

For details, send for Transite Sewer Pipe brochure TR-21A. And, if you are interested in low-cost water transportation, get the Transite Water Pipe brochure TR-11A. Johns-Manville, 22 East 40th Street, New York, N. Y.

FREE BOOK gives convincing facts . . . Write for your copy



★ ★ ★ ★ ★ ★ ★ ★ ★ ★ ★ ★ ★ ★ ★

Protecting airport and air school personnel with adequate sanitation facilities has prudently been arranged for under the current National Defense Program.

Well designed, properly equipped sewage treatment plants are being constructed at many points throughout the nation, making broad use of proven, time-tested P.F.T. Equipments.

Ten airports, air schools and air bases are now under construction using 12 P.F.T. Floating Cover Digesters, a number of Rotary Distributors, fourteen Siphons and many Pumps and boiler room units.

P.F.T. has led the way in sewage treatment equipment theory and design down through the years from 1893—almost half a century of doing one thing well—in the same manner have we been leaders in evidencing our interest in serving the nation during the national emergency.

"It can be done" is our watchword on National Defense commissions —over forty of which are completed or nearing production completion today.

More than Forty National Defense Projects Now Under Construction Employ the Following P.F.T. Sanitation Equipments:

- ★ *38 Floating Cover Digesters*
- ★ *11 Rotary Distributors*
- ★ *32 Siphon Installations*
- ★ *12 Sewage Sludge Pumps*
- ★ *23 Boiler Room Installations using: Flame Traps, Pressure Relief Flame Traps, Waste Gas Burners, Gauges, Drip Traps, etc.*

P.F.T *Pacific Flush-Tank Co.*

4241 RAVENSWOOD AVENUE, CHICAGO
NEW YORK CHARLOTTE, N.C.

SEWAGE TREATMENT EQUIPMENT EXCLUSIVELY SINCE 1893


For Dependable Aeration . . .
NORTON POROUS MEDIUMS
AERATION is the heart of activated sludge sewage plants all over the world—and more Norton Porous Mediums are used in this operation than any other make.
Over fifty years' experience in ceramic product manufacture and many years' experience in porous medium production are behind Norton Plates and Tubes—assuring uniform air distribution, great strength and low wet pressure loss.
NORTON COMPANY
Worcester, Mass.
Norton Grinding Wheel Co., Ltd., Welwyn, England
Norton Company of Canada, Ltd., Hamilton, Ont.
R-648
NORTON
POROUS TUBES
AND PLATES

France, Germany, Belgium, Holland and other countries where foodstuffs are not too plentiful and soil is overworked, have for years utilized their sewage sludge. France developed its use to a high degree. In Germany, it is a valuable product. Municipalities here in America are awakening to the fallacy of wasting and destroying sewage sludge by incineration, burial or dumping and incurring an added expense for such disposal.

Many cities now use one of the twelve models of Royer Sewage Sludge Disintegrators to quickly convert sludge cake into a readily marketed product. Sludge shovelled into its hopper is shredded to pea size, mixed, aerated and further dried, making it ideal for use as lawn top dressing and as a soil builder for plants and shrubs in general.

The Royer also thoroughly mixes in lime, phosphate, ammonium sulphate and other sweetening and enrichening materials in any properties desired. Properly treated sludge finds a ready market among florists, truck gardeners, parks, cemeteries, golf courses and others. A portfolio of authentic information on the subject is yours for the asking.

THE ROYER

ROYER FOUNDRY & MACHINE CO.
176 PRINGLE ST., KINGSTON, PA.


in modern sewage disposal plants
You'll find EMCO SEWAGE GAS METERS
PITTSBURGH WATER METERS
NORDSTROM LUBRICATED PLUG VALVES

EMCO SEWAGE GAS METERS FOR ACCURATE GAS MEASUREMENT

Accurate measurement of gas generated during sludge digestion and used as a source of heat and power, is essential in the operation of sewage disposal plants. The destructive effect which sewage tank gas has on conventional gas meters necessitates the use of meters especially constructed for this service. EMCO Meters for Sewage Gas are constructed from materials which laboratory tests and actual service have proven resistant to the action of this gas. A full line of sizes is available for various volume requirements.

PITTSBURGH WATER METERS MEASURE HOT AND COLD WATER

In order to definitely determine operating costs in sewage disposal plants, it is imperative to measure all water consumed. Since both hot and cold water are used in the disposal processes, it is of vital importance to install the proper meter for each service. Hundreds of thousands of Pittsburgh Water Meters have been purchased by large and small municipalities alike throughout the country. Their excellent construction, maintained accuracy and long life are time proven. Hot Water Meters are of special construction to operate under high temperatures.

NORDSTROM LUBRICATED PLUG VALVE GIVES POSITIVE CONTROL ON ALL LINES

The heterogeneous nature of the fluids in sewage disposal plants indicates the desirability of the pressure lubricated Nordstrom Plug Valve for all valve services therein. Basicly, the superiority of Nordstrom Valves over conventional types lies in their resistance to leakage and the fact that they always open or close easily. In addition, the Nordstrom Valve design is such that the presence of abrasive grit and other solid matter is of no consequence, and corrosion and erosion, common to most sewage plant valve services, are greatly nullified with the result that Nordstrom's will outlive the average valve several times over.

There is a Nordstrom Valve, ranging in size from ½ inch to 30 inch, available for every major service. In addition to standard metals, Nordstrom's are made in a variety of special alloys and in designs for unusual requirements.

Special bulletins describing and illustrating the application of EMCO Gas Meters, Pittsburgh Water Meters and Nordstrom Valves in the sewage disposal field have been prepared. Write, asking for Bulletins 1031 and 1042.

EMCO SEWAGE GAS METERS



PITTSBURGH HOT-COLD WATER METERS

NORDSTROM LUBRICATED PLUG VALVES

PITTSBURGH EQUITABLE METER COMPANY
MERCO NORDSTROM VALVE CO.

NEW YORK BUFFALO PHILADELPHIA KANSAS CITY TULSA LOS ANGELES *Main Offices* - PITTSBURGH, PA. DES MOINES CHICAGO COLUMBIA MEMPHIS OAKLAND HOUSTON

BEFORE YOU BUILD THAT NEXT SEWAGE PLANT

12" Dresser-coupled sludge line at Cleveland, Ohio

Do this one thing....

Investigate Dresser Pipe Couplings and their advantages for steel, cast-iron, and concrete sewage lines.

Used for 50 years on the world's longest and largest pipe lines. Permanently tight, flexible, easy and simple to install, strong and economical.

And...

Whether you are immediately interested or not, write for our 172-page General Catalog No. 36—full of specifications, field pictures, blue prints, etc. Many people use this as a pipe-joint handbook.

36" Dresser-coupled outfall sewer at Green Bay, Wis.



67" air main, a part of Sanitary District sewage works, Chicago, Ill.

DRESSER COUPLINGS

DRESSER MANUFACTURING CO., BRADFORD, PA.

In Canada Dresser Manufacturing Co. Limited, 60 Front St. W., Toronto, Ont.



Cast iron header conducting air to activated sludge tanks at treatment plant in Springfield, Ill.

TIGHT joints, structural strength and long life make cast iron pipe the ideal material for sewage works construction, either mains or treatment plants—and by long odds, the most economical in the end.

Look for the "Q-Check" registered trade mark.
Cast iron pipe is made in diameters from 1¼ to 84 inches.

THE CAST IRON PIPE RESEARCH ASSOCIATION, THOMAS F. WOLFE, RESEARCH ENGINEER.
1015 PEOPLES GAS BUILDING, CHICAGO, ILLINOIS

CAST IRON PIPE

THE MODERN MATERIAL FOR SEWERAGE SYSTEMS

Sewage Works Journal

Published by

Federation of Sewage Works Associations

Lancaster, Pa.

Copyright, 1941, by Federation of Sewage Works Associations

Vol. XIII March, 1941 No. 2

Sewage Research:

A Critical Review of the Literature of 1940 on Sewage and Waste Treatment and Stream Pollution. By W. Rudolfs, *Chairman*, T. R. Camp, E. J. Cleary, G. P. Edwards, H. A. Faber, A. J. Fischer, H. W. Gehm, A. E. Griffin, H. Heukelekian, R. W. Kehr, E. M. Moore, L. R. Setter, W. E. Stanley, L. W. Van Kleeck and S. I. Zack 187

Chemical Coagulation of Sewage. XII. Iron Salts and Lime. By Harry W. Gehm 239

Plant Operation:

Variations in the Chlorine Demand of Buffalo Sewage. By G. E. Symons, R. W. Simpson and S. R. Kin 249

Public Health Aspects of Sewage Treatment in Detroit. By W. M. Wallace and Arthur B. Morrill 265

Stream Pollution:

The Natural Purification of River Muds and Pollutional Sediments. By Gordon M. Fair, Edward W. Moore and Harold A. Thomas, Jr. 270

Industrial Wastes:

Chemical Precipitation of Sulfur Dye Wastes on a Pilot Plant Scale. By Ralph Porges, Robert K. Horton and Harold B. Gotaas 308

Operators' Reports and Suggestions:

Sewage Pumping Installations and Maintenance. By Newell L. Nussbaumer 318

Springfield Sanitary District's Annual Report for 1939. By C. C. Larson 324

Editorial:

A More Useful Federation 328

Proceedings of Local Associations:

Iowa Sewage Treatment Conference and Iowa Wastes Disposal Association 330

New York State Sewage Works Association 332

Federation of Sewage Works Associations 335

Federation Affairs:

Federation of Sewage Works Associations 342

Report of Secretary-Treasurer Federation of Sewage Works Associations for the Year Ending December 31, 1940 342

Federation of Sewage Works Associations—Minutes of the Annual Meeting of the Board of Control 345

Minutes of a Meeting of the Directors of Member Associations of the Federation of Sewage Works Associations as an Election Committee 349
Minutes of a Meeting of the Reorganized Board of Control (With Newly Elected Officers) of the Federation of Sewage Works Associations 350

Reviews and Abstracts:

Experiences in Operating a Chemical-Mechanical Sewage Treatment Plant. By George J. Schroepfer 357
World's Largest Sewage Disposal Plant Will be Doubled in Size 359
Heat Treatment as an Aid to Sludge Dewatering. By C. Lumb 359
City of Worcester, Massachusetts, Department of Public Works, Bureau of Sewers ... 362
Proceedings of the Fourteenth Annual Conference of the Maryland-Delaware Water and Sewerage Association 367
Flash Drying of Sludge 369

References to Sewage Literature 370

Federation of Sewage Works Associations 372

Members of Federation and Subscribers to the Journal 377

Non-Association Subscribers to Sewage Works Journal in the United States as of December 31, 1940 431

JOIN YOUR STATE OR LOCAL
SEWAGE WORKS ASSOCIATION

AFFILIATE WITH THE NATIONAL FEDERATION
OF SEWAGE WORKS ASSOCIATIONS

Members of the Federation receive
THE SEWAGE WORKS JOURNAL
for $1.50 per year

Non-members' subscription fee $3.00 per year, which includes subscription at $2.00 and service information fee of $1.00; Canada, $3.50; other countries, $4.00.

Send Subscriptions to
ARTHUR A. CLAY, Business Manager
654 Madison Ave.
New York, N. Y.

Sewage Research

A CRITICAL REVIEW OF THE LITERATURE OF 1940 ON SEWAGE AND WASTE TREATMENT AND STREAM POLLUTION

By W. Rudolfs, *Chairman*, T. R. Camp, E. J. Cleary, G. P. Edwards, H. A. Faber, A. J. Fischer, H. W. Gehm, A. E. Griffin, H. Heukelekian, R. W. Kehr, E. M. Moore, L. R. Setter, W. E. Stanley, L. W. Van Kleeck and S. I. Zack

Committee on Research, Federation of Sewage Works Associations

The literature published during 1940 pertaining to sewage and waste treatment has been extensive in this country. Foreign contributions were considerably curtailed on account of the war. Again important contributions were made in the fields of research, operation and development. The increasing importance of industrial waste treatment is evident from the review. It appears that this branch of the work, which pertains more to cleaner streams and better living conditions than to health hazards, indicates more clearly the general tendencies and future trend of thought of the whole problem. However, the health aspect of sewage treatment has been emphasized by the possibility that the dreaded infantile paralysis virus remains viable in, and is carried, by sewage. Stream surveys and contributions to fundamental research in stream pollution have been less than in previous years, which may be a coincidence with the temporary shelving of national legislation for stream pollution abatement. Studies on fundamental principles of sewage treatment, particularly the activated sludge process, have been continued. The problem is gradually clearing up, but is not solved. The necessity for a thorough exposition of theory and practice of the activated sludge process is apparent to show where we stand in practice and research. By-product recovery from sewage and waste is becoming more and more of general interest. Proper, accurate, simple and expedient analytical methods are still demanded. This is particularly evident in methods for grease and oil determinations, chemical demands of sewage, and sludge analyses. Sludge treatment and disposal is still the heart of the problem at many plants. Of particular interest, therefore, is the increase in quantities of solids caused by so-called dual treatment of sewage and garbage.

This annual review is again presented as evidence of progress. The review has been extended somewhat and this year a brief section on new aids to practice has been included. The entire review is not complete in the sense that all papers published during the year were considered, but we believe that all important papers have been used to

indicate the work accomplished, and the trends in sewage and waste treatment and stream pollution are shown.

Chemistry and Biology

Sewage and Disease. The suspicion that sewage might be a vehicle for the spread of poliomyelitis has been increasing. Successful isolation of the poliomyelitis virus from sewage of communities with poliomyelitis epidemics was reported by Paul, Trask and Cullotta.[166] Trask, Vignec and Paul [221] and Kramer, Gilliam and Milner [131] isolated the virus from human stools. Indirect evidence from statistical data obtained from different sized communities in Louisiana with and without water supply and sewage disposal systems, led Casey and Aymond [33] to conclude that the dilution of the sewage might play an important role in the incidence of poliomyelitis. In a general review of the subject Ellsworth [61] advanced evidence and arguments in favor of the water transmission of this disease. It was stated that the virus in the stools remained viable for at least 10 weeks in the refrigerator. For as long as 25 days after the onset of the disease the stools could be infective to monkeys. Virus from active cases or from carriers could be present in sewage not only during epidemics but at other times as well. Kemp and Soule [124] reported that the virus of poliomyelitis was inactivated by four hours' contact with 0.5 p.p.m. of chlorine in the form of chloramine but was not inactivated by 1.5 hours' contact.

To the information already available on the presence of typhoid bacteria in sewage and sludge and the effect of natural and artificial environmental conditions on their survival Mom and Shaeffer [156] have contributed additional information pertaining to conditions in the Netherlands East Indies. Typhoid bacteria were found regularly in municipal sewage in numbers higher than in European sewage. About 80 per cent reduction of typhoid bacteria was obtained by the passage of sewage through Imhoff tanks. The organisms were found in the sludge obtained but the recovery was lower than the removals would indicate. Digestion reduced their numbers rapidly, but did not eliminate them completely. After drying the sludge, no further typhoid bacteria could be found.

Beard [20] studied the factors influencing the longevity of typhoid bacteria in soils. He found moisture to be the most important factor. Fifty per cent of the typhoid bacteria died during the first 48 hours. The survival of the remainder extended over a period of months. In sewage-polluted soil the survival was shorter than in non-polluted soil.

There have been a number of different opinions expressed as to the effect on cattle and farm animals of sewage contaminated water. For the first time, however, the question has been subjected to controlled experimentation by Crawford and Frank.[43] The conditions of the experiment were more stringent than ordinarily would be the case, since the sewage dealt with contained not only the usual contamination from human sources but also from animals used in the U. S. Animal Disease

Station, including animals infected with tuberculosis, brucellosis, mastitis, hog cholera and other bacterial and virus diseases. It is stated that although many of the stables and barns were provided with septic tanks in which the sewage was disinfected, the causative agents of these diseases in virulent form might pass into the sewage entering the treatment plant. The sewage was treated in a trickling filter-separate sludge digestion type of a plant. The raw sewage, effluent from the plant and the sludge when fed to swine showed no harmful effect on the animals. Likewise the effluent consumed by cattle had no effect. None of the animals in the experiment manifested an unwillingness to consume the various materials. Tuberculin tests were made on all animals both during and after the test period (6 months) and showed no positive reaction. Post mortems showed no evidence of disease.

Biochemical Oxidation. Additional information relative to the effect of oxygen tension on the rate of bacterial oxidation coming from two different sources point to different conclusions. Zobell [249] reported that the rate of respiration was independent of oxygen concentration of the water within the range of 0.3–26.5 p.p.m. D.O. Zobell and Stadler [250] in a study covering the atmospheric saturation range concluded that oxygen was consumed at virtually the same rate at all oxygen tensions during 4 or 5 days unless nearly all the oxygen was depleted earlier. The rate of oxygen uptake per cell was highest during the first day irrespective of the initial dissolved oxygen and decreased gradually up to the fourth day.

The second contribution on this problem is from Viehl.[229] Average results of several series of tests showed that B.O.D. values increased with increasing D.O. values from 2 to 12.9 p.p.m. Increasing the D.O. tension from 12.9 to 40 p.p.m. had the effect of decreasing B.O.D. values. B.O.D. at 2 p.p.m. D.O. was 82 per cent of that obtained at its highest value at 12.9 p.p.m. D.O. At 40 p.p.m., B.O.D. was 73 per cent of that at 12.9 p.p.m. D.O.

Studies were also conducted by Viehl [229] on the effect of the rate of aeration, on the activated sludge process under laboratory conditions. D.O. concentrations ranging from 0.8 p.p.m. to 5.4 p.p.m. were obtained by regulating the rate of aeration. From the results obtained the author concluded that 1.5 p.p.m. D.O. was sufficient for the activated sludge process.

In an attempt to account for the rapid self-purification in streams receiving large quantities of acid mine drainage, Ruchhoft, Ettinger and Walker [185] reported that biochemical oxidation was possible in substrates containing 100 to 1000 p.p.m. free sulfuric acid with a pH of 1.9 to 3.0. The presence of large numbers of specialized organisms viable in such acid substrates was demonstrated. The purification was characterized by a lag phase which could be shortened by the addition of some old acid sewage.

A systematic study of the buffer value of sewage and the changes of the buffer value during aeration with or without activated sludge were reported by Ingols and Heukelekian.[105] It was found that the

buffer value of sewage was in the Seitz filtrate fraction. Ammonium bicarbonate was one of the important ingredients in sewage contributing to the buffer value. Aeration of activated sludge-sewage mixtures under laboratory conditions showed that the buffer values decreased rapidly and that changes in pH value were due to loss of volatile acids, to the reduction of buffer values and the oxidation of ammonia to nitrate. The reduction in the buffer values in plant aeration tanks were of smaller magnitude for presumably similar periods of aeration.

Surface Phenomena and Bacterial Growth. Conn and Conn [39] reported that bacterial numbers increased in the presence of colloids irrespective of the base with which the colloids were saturated. Colloids such as bentonite, kaolinite, etc. were found to be effective.

McCalla [146] stated that bacteria adsorb the H^+ formed by the liberation of CO_2. Continuation of this adsorption might result in a complete H^+ saturated bacteria. In the presence of other ions an exchange of H^+ for basic ions would take place enabling the cell to concentrate and bind these ions as a store for future use.

Heukelekian and Heller [90] called attention to the relation between surfaces and limiting food concentration for bacterial growths. They found that *Esch. coli* did not grow in a glucose-peptone broth of 0.5 to 2.5 p.p.m. concentration. The addition of glass beads to the medium permitted the growth at such low concentrations of food material. The effect of glass beads was noticeable up to 25 p.p.m. concentration of glucose and peptone. Beyond this concentration the numbers of *Esch. coli* with and without glass beads were practically the same. The bacterial population of stream water was similarly affected by the addition of clean sand. The addition of stones covered with biologically active slime to surface waters did not prevent the increase in the numbers of bacteria but considerably reduced the magnitude of increase. Surfaces enable bacteria to develop in substrates otherwise too dilute for growth. Development takes place either as bacterial slime or colonial growth attached to the surfaces.

According to Butterfield [32] the type of bacterial growth in dilute substrates such as slightly polluted waters with 5-day B.O.D. of 6.0 p.p.m. or less, consists of single cells. In concentrated media or grossly polluted waters with 5-day B.O.D. of 100 p.p.m. or more the growth consists of colonial forms or flocs provided the liquid is aerated.

Petroleum Products and Bacteria. Micro-organisms capable of attacking petroleum and its fractions were obtained from soil by Stone, White and Fenske.[206] Temperatures of 20° to 37° C., pH values of 6.0 to 8.0, some form of nitrogen such as ammonium sulfate and a plentiful supply of air are necessary for the breakdown of petroleum. In general the lower molecular weight fractions were found to be more susceptible to attack than were the heavy oils and tar. Oils high in paraffine hydrocarbons were more readily assimilated than those high in aromatic content. Naphthalene fractions occupied an intermediate position. Strawinski and Stone [208] found cetane, naphthalene and biphenyl the most rapidly attacked by the 18 hydrocarbons studied.

Counts ranging from 1 to 1½ billions per ml. were obtained in substrate containing no other source of carbon except the hydrocarbons. Attempts to develop cultures capable of growing in benzene and toluene were unsuccessful.

Heukelekian and Schulhoff [93] determined the effect of some of these volatile solvents on the bacterial numbers of sewage. They found that benzene up to 0.5 ml. per liter concentration had little effect on the total numbers of bacteria and *Esch. coli*. At 1.0 ml. per liter concentration a definite inhibitory effect was obtained. The numbers of bacteria with low concentration of benzene were higher than in the control after 24 hours. Carbon tetrachloride brought about only a small decrease in the numbers of bacteria after 3½ hours of contact but with 24-hour contact the reductions were considerable. Gasoline and kerosene were not as toxic as benzene or carbon tetrachloride. The effectiveness of these solvents was reduced when kept in contact with the sewage in open vessels.

Miscellaneous. Using yeast as a test organism for the biological detection of growth-promoting substances in sewages and sludge, Rudolfs and Heinemann [192] found that fresh solids gave the highest assay; oxidation reduced, but chlorination did not deter the action of growth-promoting substances responsible for stimulation of yeast growth.

A search for a non-corrosive compound inhibiting the growth of sulfate-reducing bacteria by Rogers [179] showed the effectiveness of certain dyes such as acriflavine and proflavine. These dyes in concentrations of 1 to 2,000,000 inhibited hydrogen sulfide production. Hydrogen sulfide decolorized the dye without reducing its efficiency. Large concentrations of the dyes were bactericidal, while low concentrations were bacteriostatic.

Laboratory Methods and Analytical Procedures

The often repeated but under-emphasized importance of the sewage sampling problem was discussed by Pomeroy.[170] Low daily composite suspended solid values usually occur even if sewage influents are sampled hourly and significant total solids errors may occur on primary sludge composites sampled at greater than one-minute intervals. Considering these conditions a consistently reliable solids balance awaits the development of practicable automatic samplers and improvement in sewage analyses to more adequately account for the coarser solids.

Bell [21] reports the successful use of the Jackson turbidimeter readings in the control of chemical treatment. The turbidity reduction on a given sewage was found to be proportional to the B.O.D. reduction. New equipment and arrangements in photo-electric spectrophotometry [28, 159] and photocolorimetry [203] which increase sensitivity and reliability and decrease maintenance may prove a practical and simple solution to many sewage plant control tests.

The development of the dropping mercury electrode [158, 125, 230] and sensitive or direct-acting potentiometer recorders [125, 159] has promise of becoming important in the control of sewage chlorination and aeration.

The first glass electrodes (Beckman type E) for measuring the pH in the alkaline range from pH 9.5 to 13.5 and a new sleeveless calomel electrode which minimizes maintenance attention was reported.[125]

A unique photometric study of the coloration of sulfuric acid by organic constituents in natural waters was reported by Datzko.[45] Maximum coloration was obtained by heating 25 ml. of water with 3 ml. H_2SO_4, to eliminate the water, and then continuing the heating of the residue for ten minutes at 220° to 250° C. The intensity of coloration is approximately proportional to the content of organic matter. The intensity of coloration given by unit weight of substance falls in the order of humic acid, glucose, and peptone.

West and Christiansen [236] utilized a simple microtechnic in scrubbing physiological fluids for the determination of carbon dioxide which may be modified for the determination of total carbon. An evacuated 250 ml. Erlenmeyer flask containing a standard solution of $Ba(OH)_2$ serves as the absorption tower. The tower also serves for the storage of the air used to wash the sample and gas scrubbing train. The apparatus is simple in design and requires little laboratory space. Several tests can be completed in 30 minutes. A semi-microdetermination of carbon by the wet combustion (chromic acid) of pure substances gave good check results.[24]

Fair [65] presented modification of sewage tests particularly worthy of attention. The sludge respirometer appears simple in construction and manipulation and is shown to give excellent check results on activated sludge. The use of an automobile head lamp and a bulls eye lens to obtain a Tyndall beam for observing chemical floc formation appears as a definite improvement in laboratory multiple stirring devices.

Progress in laboratory methods is in no small measure dependent on manufacturers' to supply instruments and apparatus. American instrumentation is forging ahead at an amazing rate as indicated in the comprehensive compilation of recent developments by Müller [159] and the imposing directory of instrument manufacturers published in the October, 1940, analytical issue of *Industrial and Engineering Chemistry*. The application of some of these instruments in solving specific sewage plant control and research problems should follow.

Ruchhoft and Moore [184] attribute the apparent loss from calculated initial dissolved oxygen when a dilution of mud is immediately examined by the Winkler method to the interference with the analytical procedure. This interference occurs largely in the preliminary acid treatment with the Rideal-Stewart or azide procedures or during the final acidification and titration. Removal of the solids from the sample reduced the interfering materials and the initial apparent dissolved oxygen loss. Solids may be removed by centrifuging the sample in completely filled glass stoppered bottles or flocculating with alum.

In the determination of the B.O.D. of mud samples the authors have shown that if the sludge is kept in suspension by slow rotation higher values are obtained. The precaution for removing the suspended

matter by centrifuging or flocculation should be practiced in the D.O. determination of the B.O.D.

Sedimentation

More data are accumulating which demonstrate the value of "self-flocculation" of sewage solids in the improvement of primary clarification. In laboratory experiments on 9 raw sewages from widely separated plants, Fischer and Hillman [69] have shown that 20 minutes pre-flocculation increases the removal of suspended solids after 60 minutes settling by 4 to 36 per cent over results obtained without flocculation, with an average improvement of 20 per cent. In plant-scale tests at Cedar Rapids by the same investigators, pre-flocculation for 30 to 40 minutes increased the removal in the clarifiers by 12 to 36 per cent with 1.9 hours settling. Similar improvements were obtained at Sioux Falls by pre-flocculation of the trickling filter effluent prior to final settling.

Snyder [216] discusses results obtained at Massillon, Ohio, where a sewage containing pickling liquor is treated. An increase of ten per cent in B.O.D. reduction was accomplished and an additional 92 p.p.m. of suspended solids were removed by pre-flocculation. Lime addition was tried but no improvement resulted possibly because only 10 p.p.m. CaO was used.

Gehm [79] presented laboratory studies on mechanical sewage flocculation. The characteristics of domestic sewage were studied in relation to their effect on the removal of solids by pre-flocculation. Results showed that pre-settling was somewhat detrimental to the process so far as degree of clarification obtained was concerned. The return of settleable solids did not improve the effluents obtained. The size of the sewage particles was measured and it was found that the size range between 15 and 40 microns was amenable to flocculation. Particles under 15 microns in size are not flocculated. The pH, alkalinity and acidity, and the ratio between them do not effect the removal obtained.

The suggestion has been advanced that the mixing velocity in trunk sewers with mean velocities normally from 2 to 5 f.p.s. should be adequate to perform the function of self-flocculation. This is doubtless true provided (1) the sewage is subjected to this velocity for a period of at least 20 minutes before it reaches the primary tanks, (2) there are no increments of sewage in this 20 minute-period of flow which contain much finely divided suspended matter or constituents which tend to peptize the mixture, and (3) the sewage is at no point prior to influx to the clarifers, subjected to turbulence sufficient to disrupt the floc. The first proviso requires a trunk sewer not less than ½ to 1½ miles in length. The third proviso prevents the use of pumps and meters of all types prior to settling. These limitations indicate that relatively few plants can take advantage of trunk sewer velocities for self-flocculation.

An important implication of the studies on pre-flocculation is that, in general, the first cost of tanks for self-flocculation and settling should be less than the cost of primary tanks alone for the same performance. Any transfer of detention time from settling to flocculation down to a minimum residual of about an hour for settling and up to a maximum flocculation time of about 40 minutes should improve clarification.

Considerable interest is manifest in studies of the transportation of sediment in flowing streams. These studies are resulting in correlations of bed load movement and suspended load with the theory of turbulent flow. Rouse [183] gives a concise analysis of present knowledge in this work. The developments promise to be of value in the settling of discrete particles such as grit and in classification such as occurs in the separation of organic matter from grit in American type grit chambers.

Chemical Treatment

By 1940 chemical treatment became established as a common American practice in sewage treatment. The basic factors governing its application, the results which can be obtained and the costs involved have been well worked out. Hence the number of papers dealing with this subject has decreased. There is a swing from a predominance of reports on new installations and operation, to papers by research workers seeking better and less costly methods and chemicals. This is a normal trend for it is to the laboratory that chemical treatment must look for further progress.

Two very interesting papers of the year were those by Christianson and Lavine [35] and Hurwitz and Williamson.[101] The former authors undertook the study of those factors affecting the preparation of "activated" silicate solutions devised by Baylis for use as a coagulant aid. They found that the aging period could be decreased by raising the temperature to 180° F. after acidification and that the pH after acidifying had a marked effect on the time required for the solution to reach its maximum activity. For sewage coagulation they found that the silicate widened the zone in which alum was effective, producing good results from pH 4.9 to 9.3. They report that very low dosages, 5 to 15 p.p.m. of silica, are required to produce the desired results. Excessive dosages retarded flocculation. B.O.D. reductions obtained by treatment with a fixed dosage of alum could be increased from 51.2 per cent to 73.5 per cent by the addition of 10 p.p.m. of silica. The results presented did not show the optimum results obtainable with alum.

A theoretical explanation attributes the "activity" of the silicate to polymerization of silica molecules and their interaction with positively charged aluminum oxide particles.

Hurwitz and Williamson [101] used "activated" silicate and copperas for sewage coagulation in a pilot plant at the West-Side Chicago Works. Their carefully conducted experiments demonstrated that the silicate-copperas treatment could produce better results, as measured by B.O.D.

and suspended solids content of the effluent than did ferric chloride alone, ferric chloride and lime or chlorinated copperas. The cost of such treatment was found to be lower than the methods with which it was compared. The chemical prices used for comparison were those obtained by the Sanitary District of Chicago which are lower than those normally quoted. Recalculation of costs using prices more commonly paid shows that even greater savings than those claimed by the authors could be obtained by this method of treatment. The only objection to this method is the number of chemicals involved and the proper preparation of the silicate solution which is not too simple. The silicate-copperas treatment is of interest in that this is the first of any of the methods employing copperas that can yield decidedly superior results at low cost. The silicate overcomes the weakness of copperas treatment which is mainly failure to obtain a settleable floc.

Rudolfs [191] after discussing progress in chemical treatment to date, presented some results obtained in the laboratory and plant with two new chemicals. Aluminum hydroxy chlorosulfate was shown to produce better results than alum in both laboratory and plant tests. This chemical can be easily manufactured and the cost of coagulant at the plant where it was tried could be lowered by its use. This chemical is of exceptional interest because of the hydroxyl ions it contains. Many preparations containing colloidal forms of aluminum hydrates have been tried from time to time but none previous to this have shown promise of improving the results obtainable with alum. This product hydrolyzes more readily than alum but not as readily as do most aluminum hydrosols. Its improved coagulating power is probably due to this characteristic.

Ferri-gel, which is a compound of ferric chloride and a protein, was the other chemical discussed. This material has the property of forming rapidly an exceedingly heavy ball-like floc which will settle despite agitation. The sludge produced compacts very rapidly and can be dewatered without the use of additional chemicals. The dosage of ferric chloride required for clarification is reduced as much as 40 per cent. The product is less corrosive than ferric chloride and can produce equal clarification at lower cost and better results at equal cost. Rudolfs concludes that chemical treatment will take a firmer and more definite place in sewage treatment practice now that its accomplishments and limitations are well understood. He looks for further improvement in chemicals and equipment in the future and that perhaps with a better understanding of the function of the chemicals now used their value will be increased.

Treating a sewage containing wool scouring waste, Lumb and Barnes [142] found that a combination of sulfuric acid and alumino-ferric was an improvement over treatment with acid alone. Fifty, 100 and 150 parts per million of alumino-ferric lowered the acid dosage 104, 183 and 263 p.p.m., respectively. The total cost of chemicals under some conditions could be reduced and the pH of the effluent raised by the combined treatment. It is a well known fact that the acid treatment to

pH 4.5–6.0 will lower the alum dosage necessary for clarification and that with acid alone a pH of 3.0 will clarify sewage. This paper has shown that this relationship holds for sewage containing a large quantity of grease. The fact that alumino-ferric and acid will produce the same results at pH values as high as 4.8 as compared to pH 3.2 for the acid alone should be of importance both in preserving the equipment and producing a less objectionable effluent.

Discussing this paper before the Institute of Sewage Purification, Goldthorpe [142] calls attention to possible savings in lime, necessary for neutralizing of acid effluents prior to biological treatment, that could be effected by using alumino-ferric and acid rather than acid alone in treating grease-laden sewages. He states that such combined treatment would also permit the use of a small separate flow of domestic sewage for neutralizing the acid tank effluent. Investigations on how treatment of the sludge obtained would be effected by the use of alumino-ferric and how much of the precipitation was due to the sulfate ion, the trivalent ion and the alumina floc, respectively, were thought desirable. Goldthorpe believes the acid treatment changes the lime soaps to fatty acids, thereby releasing occluded particles in a form amenable to coagulation by the alumino-ferric.

Several new chemical treatment plants were under construction or starting operations in 1940. A plant at Albuquerque, N. M., is described by Neuffer [164] as having a design capacity of 5 m.g.d. This plant will employ chlorinated copperas and lime for clarification prior to treatment on trickling filters. A 6 m.g.d. plant at Oshkosh, Wisconsin, equipped for the application of any of the common coagulants is described by Frazier.[72] This plant will operate with chemicals up to a flow of 6 m.g.d. When storm-water raises the flow above this rate sedimentation alone will be practiced. The ability of chemical treatment to handle mixed sewage and industrial waste flow was demonstrated by Heist.[89] Located at Circleville, Ohio, this installation is called upon to treat a volume of strawboard waste three times the volume of domestic sewage and other wastes combined. Satisfactory results have been obtained using 750 pounds per m.g. of alum.

Trickling Filters

During the year many smaller sized sewage treatment plants were constructed which included trickling filters. A relatively larger installation comprising 16 units, 176 ft. in diameter (48 m.g.d.) was put into operation at Dallas, Texas.[48] Principal attention along new lines has continued toward higher average rates of filtration, stage filtration and recirculation of filter effluent. A considerable number of smaller filters of shallow type, 3 to 4 ft. deep, have been reported as under construction or in operation.

Theory. Levine [136] states that sewage coming in contact with the biological films on the filter media has its colloidal and finely suspended substances agglomerated into suspended particles, soluble substances

being diffused into the films while the agglomerated matter may be adsorbed to the films. He suggests that the adsorbed agglomerated matter may be degraded by enzymic action and acted upon similar to the soluble substances when the filter is operated at low rates, whereas they are removed mechanically as suspended particles when the filter is operated at higher rates. Thus, by high rate filtration it is possible to conserve the biological activities of trickling filters for action on soluble sewage matter and remove and dispose of the agglomerated matter by sedimentation and digestion. He further considers the filter as comprising strata of different biological activity and that anything which would tend to maintain these zones of biological activity would be conducive to optimum filter efficiency. He proposes to prevent the agglomerated matter reaching the lower strata by interposing a settling tank. Also he provides the primary filter with backwashing facilities. Fischer [67] discussing "Biofiltration" proposes that continuous passage of sewage and recirculated effluent at high rates through a filter causes a uniform action throughout the filter bed. He also considers the filter as serving to coagulate the colloidal matter and agglomerate the very fine particles in much the same way as in the chemical precipitation process or in the first stages of the activated sludge process.

Wilson and McLachlen [242] arrived at the conclusion that carbonaceous matter is oxidized to carbon dioxide to a much greater extent in filter beds than in the activated sludge process. In contrast to the production in an activated sludge process of approximately 10 per cent of total carbon input as carbon dioxide in the effluent air, this study showed a production of 8.5 to 48.2 per cent carbon input as carbon dioxide in the effluent air of a filter bed.

Insect Life in Biological Filters. On the basis of experience gained with enclosed filters at Germiston, South Africa, Murray [160] reports that enclosing a filter results in increased fly breeding due to the more uniform temperature maintained. The author questions the opinion that high rate filtration prevents excessive fly breeding by drowning them. The bodies and wings of *Psychoda* are not wetted with water and the surface tension of the water is sufficient to support them on the surface of the water. It is impossible to drown the flies with even large quantities of soap solution.

The life-history and ecology of *Lumbricullus lineatus mull.* was reported by Reynoldson [175] who previously had pointed out the role played by this organism in the unloading of the filter bed. Lloyd, Graham and Reynoldson [139] extended the systematic study of the insect life in the filter bed to include the habits, life cycle, occurrence and number of larvae and pupae of the most commonly found insects, such as *Psychoda siverini, Psychoda alternata, Spaniotoma minima, Spaniotoma perennis, Metriocnemus longitarsus* and *Metriocnemus hirticollis* as well as *Lumbriculles lineatus.*

Loading. No definite answer is yet available to the important question of the loading which should properly be applied to a trickling filter. Fischer [67] expressing the loading in lb. B.O.D. per cu. yard of filter

media per day, believes that the capacity of a filter for removal of B.O.D. is not yet fully understood. He refers to data showing B.O.D. removals of 5.23 lb./cu. yd./day (8,450 lb. per acre foot) for beet sugar wastes with 1,650 p.p.m. B.O.D., and 15.4 lb./cu. yd./day (25,000 lb. per acre-foot) for distillery wastes with 20,000 p.p.m. B.O.D. These amounts appear to be extreme. Levine [136] states that B.O.D.'s up to 3,000 p.p.m. have been effectively treated and removals of 4,000 to 6,000 lb. of B.O.D. per acre-foot are feasible.

Keefer and Kratz [121] report experimental results showing B.O.D. loadings from about 1,000 to 4,500 pounds per acre foot daily with removals of 72 per cent or about 3,300 pounds per acre foot daily. These tests were made by dosing a small section of the Baltimore filter bed at rates ranging from 6.5 to 30.0 m.g.a.d. with an average 5-day B.O.D. of about 150 p.p.m. as applied to the filter. Porges, Miles and Baity [173] using recirculation on a batch basis, report 90 per cent reduction in B.O.D. by a 4-foot depth filter after five hours recirculation, equivalent to about 10,300 lb. per acre-foot.

Conventional Filters. Research along this line has been overshadowed by the attention to high rate, stage, and recirculation studies. Gilcreas and Sanderson [82] report a study of the time required for a newly constructed sewage trickling filter to reach maximum efficiency. Settled domestic sewage dosed on to a filter at about 400,000 gallons per acre daily required 40 days for complete oxidation of nitrogenous compounds, about 50 days for total development of the fauna and flora, and 60 days for maximum reduction of carbonaceous organic matter. The test was started in April which may account, in part, for the long time requirements. Dixon [48] reports that in the large Dallas trickling filter installation each filter unit has a guaranteed uniform application when operating between 700 and 2,200 gal. per min., and that by adjusting orifices the rate can be increased to 3,200 gallons per minute and allow capacity for two-stage treatment which can be arranged for by closing two motor operated sluice gates. Also by operating return pumps recirculation may be obtained. Thus this relatively large plant may be operated as a conventional filter with straight gravity flow through sixteen filter units, or as two-stage treatment or with recirculation of effluent up to 100 per cent of the sewage flow at the will of the operator. Funk [75] reports a trickling filter designed for a rating of 2 m.g.a.d. followed by a sand filter to treat cannery wastes to protect goldfish breeding ponds, this design being selected in preference to either two-stage high rate or high rate with recirculation methods. The design includes piping arrangements to permit future provision of recirculation of filter effluent. Allison [1] reports improvements in trickling filter operation by chlorination for slime control which increased B.O.D. removal from 82.5 per cent up to a peak of 97 per cent, and increased the settleable solids removal sufficiently to make the effluent satisfactory for an oil refinery water supply.

The enclosing of trickling filters by covering with concrete domes is of interest particularly for the colder areas. Foster [71] describing the

dome enclosures for the two filters, 150-ft. in diameter, at Hibbing, Minn., states "Domes were provided for these filters primarily to prevent ice formation." Also he says the enclosures prevent interference by high winds and reduce the fly and odor nuisance. At the village of Excelsior [17] on Lake Minnetonka a filter 54-ft. in diameter, was put into operation provided with a blower with 3,000 c.f.m. capacity for aeration of the filter and an exhaust fan in the center of the conical dome for ventilation.

The journal *Public Works* has presented a series of articles summarizing the design of trickling filters, in which are included illustrations of design, various filter media, and other characteristics of filter design, construction and operation.

High rate, Enclosed, Aerated, Heated, Stage and Recirculated Filters. Further investigations on the advantage of enclosing a filter were reported from Johannesburg, South Africa, by Wilson and Hamlin.[241] The main advantage of enclosing a filter was the conservation of the heat and the consequent maintenance of as high a rate of efficiency in the winter time as in the summer. An open filter could treat experimentally the same quantity of sewage in the cold months as in the warm months when the applied sewage was warmed to 80° F. Experiments further showed that the efficiency of purification was increased by maintaining a bed temperature up to 95° F. but at 100° F. purification and nitrification seriously diminished. Experiments with the artificial introduction of carbon dioxide into the filter showed that although high concentrations were deleterious, concentrations such as can be ordinarily found in the beds were not harmful. Ventilation of a filter for the purpose of sweeping out carbon dioxide was not necessary.

Stage filtration has been tried out in service with and without recirculation, but usually with provision for higher rates of sewage application. Levine [136] has presented the results of operation of both experimental and full scale plants in which two stages of filtration are used. The primary filter comprises a shallow filter of fine material designed to be backwashed when needed. A settling tank follows both the primary and the secondary filters. A plant built in 1929 for the Decker Packing Company at Mason City, Iowa, and a similar plant built in 1937 at West Fargo, N. D., show overall reduction of B.O.D. or 94.3 per cent and 95 per cent, respectively. After six years of operation and laboratory studies modifications have been suggested in the Decker plant including deepening the washable filter to 6 feet, increasing the rate of application to at least 6 to 8 m.g.a.d. and decreasing the dosing cycle to two minutes or less.

Fischer [97] shows three types of two-stage treatment—(*a*) with the primary and secondary filters placed between the primary and secondary sedimentation units; (*b*) with both sedimentation units placed between the primary and secondary filters, and (*c*) with the primary sedimentation following the primary filter and the secondary sedimentation following the secondary filters. In all cases recirculation is included.

A B.O.D. removal of 90 to 95 per cent is anticipated with a well nitrified effluent, high in D.O. and low in suspended solids. Jenks [112] describes a small filter plant for Lakeport, Cal., with capacity for 250,000 gallons per day, including two-stage filtration, each filter 3 ft. deep and 36 ft. in diameter. A description of a two-stage plant built for Liberty, N. Y.,[12] and the results of a short period of operation showing B.O.D. reductions ranging from 85 per cent to 97 per cent appeared in *Public Works*.[13] This plant also includes a magnetite effluent filter and final contact tank for chlorination.

The Water Pollution Research Board [232] investigated the possibility of applying the treatment developed for milk wastes to sewage. The method consisted of applying the sewage to two filters in series and changing the order of application to the beds at intervals of one or two weeks. The experimental plant was constructed at the Minworth plant of the Birmingham area, and consisted of four beds of 115 to 118 ft. diameter and 6 to 7 ft. deep supplied with rotary distributors and different types of filtering media. Preliminary results showed that the application of settled sewage at the rate of 70 Imp. gal. per cu. yd. per day during the winter months did not give satisfactory results (B.O.D. in settled effluent greater than 20 p.p.m.). Better results were obtained during the spring. To overcome the difficulty in operating the rotary distributors, which would not revolve at a steady speed in a strong wind at lower rates of flow than the distributors were designed for, small sails were rigged at the ends of the two arms.

The reduction of the strength of sewage applied to a filter bed by recirculating the filter effluent has been used in several installations. Eldridge [38] described the conversion of a conventional filter into a high-rate filter with recirculation for the treatment of milk wastes at Perrington, Michigan. He reports a removal of 77.1 per cent of suspended solids and 90.6 per cent of B.O.D. as compared to about 60 per cent removal of B.O.D. when operating previously as a conventional filter. The B.O.D. of the influent was 537 p.p.m. and of the final effluent 46 p.p.m. The operating procedure produces a recirculation of five times during the day and once every 47 minutes during the night. Funk [75] described a plant for the treatment of cannery wastes, with piping included to provide future recirculation should operating experience warrant. Cannery waste with a 5-day B.O.D. as high as 3,000 p.p.m. (10 per cent of samples) is combined with domestic sewage with a resultant 5-day B.O.D. of 600 to 850 p.p.m. and 90 per cent of tests showing less than 1,200 p.p.m.

Promotion of the system of sewage treatment termed "biofiltration" has continued. The Dorr Company gives a list of 25 plants built or under construction during 1940 including one plant for a sewage flow of 6.75 m.g.d., one for 3.0 m.g.d. and the others for flows of 10 m.g.d. or smaller. Fischer [67] has described the general design and operation procedures and has given a limited amount of operating data.

Activated Sludge

Theory. Williams [239] in a historical review of theories of the mechanism of the activated sludge process came to the conclusion that no evidence that definitely excludes either the physical or biological factors has been fully substantiated. The evidence according to the author is in favor of a mechanism involving both factors. The relative importance of each factor is not yet apparent, but the division of the process into clear-cut stages involving physical changes in one stage and biological changes in another, is unwarranted. It is more than likely that one form of action is partly or entirely dependent on the other, though one factor may tend to dominate during one particular period.

Lumb [141] made a study of the suspended solids balance in the purification of sewage by activated sludge under laboratory conditions operated for a period of 13 months. The results showed that almost 100 per cent of the suspended and colloidal matter removed was recovered as activated sludge.

Barritt [19] studied the respiration of activated sludge under starvation conditions with constant aeration for a period of 25 days at different temperatures. Continuous aeration had little effect on the volume of sludge. The loss in weight of sludge due to respiration was greater during the first three days of aeration than subsequently. During the early period of aeration temperature did not have an effect on the relative amounts of organic matter destroyed by respiration. Subsequent loss by respiration was small, being greatest at 30° C. The sludge, after aeration for three weeks, was placed in flasks, one exposed to daylight and the other kept in the dark. The carbon dioxide given off was measured. Less carbon dioxide was given off when the sludge was exposed to daylight than when it was kept in the dark. The author believes that exposure of sludge in the aeration tanks to light would account for low loss in weight due to increased photosynthetic activity of certain flagellates.

Sawyer [196] in a study of four activated sludges possessing widely different characteristics, found that in all cases, dissimilar sludges fed on a given sewage acquired similar characteristics within three weeks. On certain diets a sludge which nitrified poorly became a good nitrifier and on other diets, good nitrifiers lost the ability and became essentially non-nitrifiers. The same author [197] observed that the loss of nitrifying power by activated sludge at low temperature depends upon the relative rates at which the organisms responsible for stabilizing both carbonaceous and nitrogenous matter grow. Rapid growth of the organisms responsible for the stabilization of carbonaceous matter is favored by lower rates of oxidation at low temperature and by the ability of sludge to hold available, at all times, a large food supply by adsorption and coagulation of sewage solids. The growth of nitrifying organisms is hindered by the slow rate of oxidation of ammonia nitrogen at low temperature and by the inability of the sludge to adsorb and hold available, appreciable quantities of ammonia nitrogen. At low tempera-

tures, the proportion of nitrifying organisms in the sludge diminishes and the nitrifying ability of the sludge decreases accordingly.

Ingols [103] reported that the activity of sludge is dependent upon the concentration of oxidation-reduction enzymes. The rate of activity of these enzymes is affected by the temperature, the amount of oxygen supplied, the pH of the medium and the type of food. Dickinson [46] believes that the adsorption of substances by activated sludge is controlled by enzymes. He considers floc to be made up of an inorganic nucleus surrounded by a layer of enzymatically active material. Dickinson [47] also studied the changes in oxidation-reduction potential within the sludge floc. Using a special electrode made by allowing activated sludge to grow and completely cover a bright platinum electrode, he found that the addition of sewage to aerated sludge resulted in a relatively rapid fall in potential of the bio-electrode with respect to a bright platinum electrode. Then a fairly constant level maintained for a long period was followed by a slow rise to the initial potential level. It was necessary to prolong aeration for some time after complete clarification of the sewage to attain the initial potential level. This stage was probably mainly reactivation.

Barritt [18] suggested that the protozoan fauna takes an active part in the direct removal of organic matter in solution and does not live chiefly by ingestion of bacteria. He found that the production of a gelatinous matrix by *Zooglea ramigera* is independent of the composition of the nutrient solution and is not stimulated by the addition of sugar. This organism cultivated in liquid culture medium grows in a dispersed form without a gelatinous matrix.

Heukelekian and Littman [92] studied the carbon and nitrogen transformations in mixtures of sterile sewage and pure culture zoogleal sludges. They found removal of suspended organic carbon was followed by removal of organic carbon in solution. This period of biological assimilation was accompanied by an increased rate of evolution of carbon dioxide. The sludge increased in amount by the adsorption of suspended organic carbon and by the synthesis of bacterial protoplasm. Ammonia nitrogen was assimilated by the sludge but nitrification did not occur. The carbon-nitrogen ratio of the pure zoogleal sludge was about 4.7 to 1. They believe that the zoogleal bacterium, *Zooglea ramigera*, is of primary importance in natural activated sludge and that nitrifying bacteria, protozoa and higher filamentous organisms are secondary.

Mihaeloff [149] takes the view that activation is the result of microbial action which coagulates and oxidizes organic matter and cites the constant presence of filamentous organisms in activated sludges from various sources as evidence. He believes that the larger the amount of microbial filaments, the more rapid is the settling rate of sludge.

In a study of the conditions affecting the distribution of nitrogenous compounds during treatment of sewage by the activated sludge process, Corbet and Wooldridge [40] found that the amount of ammonia nitrogen adsorbed on sludge was greatest shortly after the addition of fresh

sewage and decreased as the treatment proceeded. The amount adsorbed at any time was small. On non-nitrifying sludge, the decrease in ammonia was accounted for by an increase in organic nitrogen. When potassium nitrite or nitrate was added to a non-nitrifying sludge, a rapid loss of nitrogen gas occurred. No indication of any intermediate compound was found. With nitrifying sludge, a large proportion of the ammonia was converted to nitrate with intermediate formation of nitrite and hyponitrite. When potassium nitrite was added to the sludge, the concentration of nitrite remained nearly constant during aeration until all the ammonia had been converted to organic nitrogen in the sludge. Then the nitrite was oxidized to nitrate. When the carbon-nitrogen ratio of the sewage was changed by daily feeding of glucose, the ratio in the sludge itself was not affected. The addition of glucose inhibited nitrification because, in the presence of excess carbonaceous material, the ammonia was utilized to form insoluble nitrogenous compounds in the sludge. Wooldridge and Corbet [245] found that under sterile conditions, continuous aeration of activated sludge-sewage mixtures, containing added nitrite and ammonia nitrogen, did not result in loss of nitrogen. The study indicated that the loss of nitrogen was not caused by chemical reactions involving nitrite or by reactions between amino acids and nitrites but that under aerobic conditions, the loss of nitrogen was due to the action of micro-organisms or their enzymes upon nitrate.

Shibata [201] found that when a mixture of activated sludge and sewage was aerated for 189 hours, as might be expected, the pH decreased, the turbidity of the liquor increased, the volume of settled sludge decreased and the dissolved oxygen reached a saturation value of 96.3 per cent. Sludge disintegrated by prolonged aeration was reactivated by aeration with sewage in two or three days. Activated sludge mixed with garbage liquor required a longer period of aeration for purification than did sludge with sewage. Shibata believed that the additional time was needed to reduce the particles of garbage to the colloidal state.

Williams [240] observed the effect of bubbles of various gases on mixtures of activated sludge and sewage. He found that when air, oxygen, hydrogen and nitrogen were passed through sewage for six hours without sludge, about the same amount of organic carbon was removed by each gas. In the presence of activated sludge, the rate of removal of carbon by air and oxygen was greatly increased, but only a small removal was obtained with hydrogen and nitrogen.

Rokuro and Jinnosuke [180] studied the decomposition of phenol by activated sludge and found that the phenol was oxidized directly to carbon dioxide and water without the formation of any intermediate products.

The effect of sugars on the activated sludge process has been studied by several investigators. Ruchhoft, Kachmar and Moore [186] found that glucose is removed from solution much more rapidly by activated sludge than by domestic sewage, pure cultures of *Bact. coli, Bact. aerogenes, Sphaerotilus natans* or zoogleal sludge. The rate of glucose

removal by activated sludge is a function of the quantity of sludge present and after the first hour, the removal rate follows the Freundlich adsorption equation. Glucose was removed more slowly than the carbonaceous organic material of synthetic sewage but more rapidly than the nitrogenous material. Heating the sludge for ten minutes at 35° C. had no effect on the rate of removal but ten minutes at 45° C. reduced the rate and ten minutes at 55° C. practically destroyed the ability of the sludge to remove glucose. Lowering the pH for 20 minutes to 5.2 before the addition of glucose retarded the removal slightly. Lowering the pH to 2.8 for 20 minutes practically destroyed the glucose removal mechanism for several hours but raising the pH to 11.0 for 30 minutes, followed by neutralization, had little effect. For optimum removal of glucose, aerobic conditions and a proper nutritive balance are necessary. Ruchhoft, Kachmar and Placak [187] found that with normal activated sludge the rate of removal of glucose from solution was 5 to 7 times the rate of its decomposition and carbon dioxide formation. Zoogleal sludge removed glucose about three times as fast as it was able to oxidize it to carbon dioxide. The addition of 1,000 p.p.m. of glucose to normal activated sludge did not increase the short-time oxygen requirements of the sludge-feed mixture to as great an extent as did 500 p.p.m. of peptone. This is probably explained by the difference in metabolism of these two substances by the activated sludge. Glucose removal was found to be the result of biological metabolism following adsorption and not simple adsorption upon the surface of the floc. Dissimilation products, besides carbon dioxide, could not be found.

Working with lactose, Jenkins and Wilkinson [111] found that sugar was removed at a high rate during the first hour of aeration. Small amounts of lactic acid were formed in the early part of aeration but disappeared in 24 hours. After a few weeks, sludge treated with lactose became extremely dense and formed short, thick, well-defined clumps which were dark brown in color. The sludge did not bulk. The dominant organism was the fungus *Pullularia pullulans*. The rate of disappearance of lactose was influenced by the carbon-nitrogen ratio. The fat content of sludge fed with a carbon-nitrogen ratio of 150:1 increased from 0.6 to 5.8 per cent and the nitrogen content decreased from 4.68 to 1.14 per cent. When the ratio of carbon to nitrogen was 1:10, the fat content remained low and the total nitrogen increased from 4.68 to 5.2 per cent.

Bulking. Considerable progress has been made in laboratory studies of bulking. Henkelekian and Ingols [91] were able to produce bulking experimentally by diluting the concentration of oxygen in the air used with nitrogen. Using quantities of oxygen comparable to those supplied in plant practice, bulking was readily produced. They found that with constant sewage load and concentration of sludge, the rate of bulking depends on the quantity of air or its concentration in the gas mixture. With constant sewage load and quantity of air, the bulking becomes worse as concentration of solids in the aeration liquor increases. A highly oxidized sludge bulks less readily than one poorly

oxidized and the addition of 10–20 p.p.m. of nitrate nitrogen prevents bulking caused by oxygen deficiency. Ingols and Heukelekian [104] found that bulking occurs when sludge fed with sugar, calcium butyrate, peptone, glycerine or calcium propionate is agitated with a limited amount of oxygen. The authors believe that in an activated sludge plant, a deficiency of oxygen is more apt to cause bulking than any particular ingredient of normal domestic sewage.

Lackey and Wattie [133] state that it is possible to produce experimental bulking of activated sludge by heavy doses of sugars or mixtures of nitrogenous and carbonaceous compounds. In such bulking, the predominant organism is the filamentous bacterium, *Sphaerotilus natans* Kutzing. They were able to isolate only one species and its cultural characteristics have been constant. However, they found morphological differences in field collections from which some of the isolations have been made. The organism grows abundantly in solutions of sugar if a suitable source of nitrogen is present. Inorganic nitrogen is readily used but only two of several amino acids, alanine and asparagin have promoted good growth. Peptone has proved a good source of nitrogen. No substance which is common or apt to occur normally in sewage has been found to stimulate *Sphaerotilus* to excessive growth. Chlorine is the cheapest and most readily available toxic substance to control its growth.

Littman [138] who studied the carbon and nitrogen transformations in the purification of sewage by the activated sludge process, found that sludge containing *Sphaerotilus* did not grow well in sterile sewage devoid of carbohydrates. The sludge containing the *Sphaerotilus* had a solids concentration of 757 p.p.m. and removed a maximum of 46 per cent turbidity and 56 per cent B.O.D. in a four-hour aeration period. A slow, limited removal of suspended organic carbon was observed but most of the carbon removed was from solution. The sludge containing *Sphaerotilus* was white and fluffy and was about three times as great in volume as an equivalent amount of zoogleal sludge.

Berg [23] believes that at certain periods bulking at San Antonio is caused, in part, by digester supernatant liquor and that 1,000 pounds of B.O.D. from digester supernatant liquor has a far greater effect on the activated sludge than 1,000 pounds of normal sewage B.O.D. The digester liquor seems to have a lasting poisonous effect on the activated sludge.

At the North Side plant in Chicago, Palmer [165] reports that bulking is caused generally by high percentage of volatile solids rather than by underaeration or the presence of filamentous growths.

Operation. Sawyer [197] pointed out that the use of low concentrations of solids in aeration tanks results in the production of sludges with high volatile solids content and high activity as measured by the base rates of oxygen utilization. Because of the high activity, the solids must be removed rapidly from final settling tanks and kept in contact with dissolved oxygen to maintain them in proper condition. High concentration of solids in aeration tanks produces sludges with

lower volatile solids and lower base rates of oxygen utilization. These solids become more compact and may be kept for longer periods without aeration than sludge with high volatile solids.

Berg [23] has attempted to determine some definite mathematical relationship between the concentration of activated sludge suspended solids and the suspended solids in the primary effluent. A preliminary study indicated that the ratio of pounds of suspended solids in the return sludge per day to the pounds of suspended solids per day in the primary effluent should be between 8 and 10. Higher ratios seemed to give poorer results.

Edwards [55] reported that at Wards Island chlorination of return sludge with an average of 1.8 p.p.m. improved the settling characteristics of the aeration tank liquor about 35 per cent as measured by the sludge index. At Tallmans Island, excess activated sludge could be concentrated satisfactorily when the sludge was chlorinated sufficiently to maintain at least 1 p.p.m. residual in the overflow. Based on values from the Wards Island and Tallmans Island plants, he found that the concentration of solids in the excess activated sludge and the sludge index (Donaldson) decreased as the volatile matter increased.

Bloodgood [26] believes that the sludge index, as commonly determined, is a measure of sludge condition and not plant condition. He pointed out that the sludge index of a particular sludge varies with the solids concentration. To obtain comparable results with the sludge index, some standard solids concentration should be used.

Effluent Filtration

Additional plants using effluent filters were installed in 1940. Magnetite filters were placed in operation following high rate trickling filters at New Ulm, Minn., Sonoma, California, and Liberty, New York; following plain sedimentation at Woodbridge, New Jersey, and Rock Island, Illinois; and for polishing the activated sludge effluent at the Ley Creek Plant, Syracuse, New York. A sand effluent filter was installed for final treatment at Carlstat-Rutherford, N. J., following chemical precipitation and trickling filter treatment.

The trend in design of magnetite filters has been toward downflow circular filters with finer magnetite. Comparative parallel box filter tests with 3 in. depth of magnetite have indicated approximately 35 per cent removal of suspended solids filtering through 1.3 mm. and 70 per cent removal through 0.4 mm. size. Only 10 to 15 per cent improvement in removals was obtained by increasing the thickness of the filter bed from a depth of 3 in. to 6 in. of the various grades of magnetite tested. Tests at Woodbridge, N. J., Liberty, N. Y., and Ley Creek, N. Y., have indicated that the pollution of the effluent during cleaning was reduced to a minimum by the 3-level arrangement of a positive backhead between the effluent weir and the washwater weir. This was accomplished by sealing the wash chamber against the head over the filter bed. Filters are now either installed in separate structures or on the outside

periphery of clarifiers. At Santa Fe Springs, California, two units have been installed for treating oil field wastes with the magnetite filters surrounding circular Dorr flocculators with no intermediate settling. The wastes from the gravity oil separators will be chemically treated, flocculated and applied directly to the magnetite filters.

Veatch [226] reported a year's operating results for Denver with magnetite filter removals averaging 16.5 p.p.m. suspended solids and 15.7 p.p.m. B.O.D. but noted that, due to slimy growths, the efficiency of the filters fell off considerably during the last part of the year. Solids and B.O.D. reaching the filter were 86.7 p.p.m. and 49.2 p.p.m., respectively.

Rudolfs [188] mentions the use of magnetite filters for activated sludge and trickling filter effluents when a high degree of clarity is desired. He also notes that several sand strainers are performing good work on plain settled sewage, and that screens covered with 1/4 in. to 1/2 in. coke at Niagara Falls are removing 20 to 33 per cent of the suspended solids from raw sewage instead of the usual 12 per cent by rotary plate screens.

Streander [209] outlines the importance of thoroughly washing the sand in the operation of sand effluent strainers. With improved washing, sand filters in New Jersey are operating satisfactorily at filter rates less than 1 gal. per sq. ft. per min. Modified sand filters 28 in. deep of the rapid backwash type are operating with about a 4 ft. loss of head at a full size plant in Wuppertal, Germany. These filters improve the removal of 35 per cent of the suspended solids by sedimentation, to 60 per cent by sedimentation and filters. These filters operate at 0.5 gal. per sq. ft. per min. and have 1 to 2 mm. sand. Experimental work at Wuppertal indicated that such filters ahead of activated sludge made possible a 50 per cent saving in aeration time. Six-inch depth of approximately 1 mm. sand are used in the effluent filters at South River, Sayreville, Raritan and Somerville, N. J. Operation has been at normal design rates of 0.65 gal. per sq. ft. per min. to peak hourly rates of 1.7 gal. per sq. ft. per min. Removals by the filter have averaged about 50 per cent of the suspended solids reaching the filters. Suspended solids influent to the filter amounted to 100 to 150 p.p.m. after plain settling and 50 to 60 p.p.m. after chemical precipitation. Increase of suspended solids in filter effluent during washing was noted. About 50 per cent removal of suspended solids at a 2 gal. per sq. ft. per min. filter rate was accomplished with a Laughlin sand filter in tests at Atlantic City. This filter consisted of a mechanical surface cleaner which removed the dirt accumulation in the first half inch and a bottom pipe and water jet cleaner which expanded and cleaned the sand supported on the screen. This bottom cleaner has recently been replaced by a subdivided bed with means for admitting backwash water, below the supporting perforated plate screen. The backhead water is introduced at each section by means of a pump through a sliding valve connection.

Final effluents [13] of 4.4 p.p.m. suspended solids and 8.7 B.O.D. are

reported for magnetite filters used as a final polish on biofiltration plant effluent at Liberty, New York. These results were obtained at average filter rates of 2.0 and maximum of 2.7 gal. per sq. ft. per min. The B.O.D. removal through the filter amounted to 49 per cent and the suspended solids removal 67 per cent.

A summary of magnetite filter operation at the Minneapolis-St. Paul Sanitary District [151] shows filter influent of 78 p.p.m. and filter effluent of 56 p.p.m. suspended solids at average filter rates of 2.5 gal. per sq. ft. per min. with daily averages as high as 5.4 gal. per sq. ft. per min.

Chlorination

Chlorination is represented in sewage literature largely by reports on operation and operating results. There is a large field and a real need for more fundamental research, particularly in some of the newer applications of chlorine. Such studies would be amply justified by improvements in operation and by economy of chlorine.

Chlorine for Disinfection. In a review of operating experiences at the new Buffalo plant, Velzy, Johnson, and Symons [227] mention variations in chlorine demand of this sewage. The average chlorine dosage is approximately 5,600 lb. per day, but may be as low as 3,500 lb. in winter and as high as 8,000 lb. in summer. The daily maxima and minima demands are higher and lower than these values. On one occasion the chlorine demand reached a rate of 63,000 lb. per day for a few hours. Sewage odors are controlled by chlorination and ventilation but, even though a low residual is maintained, there is some loss of chlorine to the air in the conduits. Vapors arising from the chlorinated sewage have resulted in condensation in the ventilating system. Analysis of the crystals precipitated from this condensed vapor indicates almost pure ammonium chloride.

Variations of chlorine demand with daily fluctuations of sewage concentration are discussed by Griffin [84] who cites a number of typical examples in detail. All of these illustrate that chlorination at a fixed rate results in long intervals of over- or underdosage. Manual variation of chlorine dose accomplishes only an approximation of ideal conditions. Automatic feed of chlorine in proportion to flow of sewage also leaves much to be desired, since a flow change of 2 to 1 may be accompanied by a change in chlorine demand of 8 or 10 to 1. Two new methods of sewage chlorination provide greater efficiency in meeting this problem. Programmed step-by-step chlorination, to maintain a different dosage rate at preselected intervals throughout each 24 hour period, is demonstrated as following the requirement curve fairly well. The new method of chlorination by potential control depends upon an electrode system which controls the dosage rate of chlorinators. A predetermined potential may be selected to maintain a residual or subresidual dosage. Charts show this to represent the ideal method of chlorine control, in that such operation meets the dosage variation corresponding to demand, daily flow, storm flow, and other unusual con-

ditions. Klegerman [128] cites a number of other instances of the wide flow and chlorine demand variations disclosed by sewerage investigations. He notes that the potential method should provide not only ideal control of dosage but substantial chlorine economies as well.

The Covina, California, sewage treatment plant includes both biological and chemical treatment processes because odor control, a high degree of effluent quality, and flexibility are essential. According to Koebig [150] odor control and flocculation are accomplished by means of ferrous chloride and ferric chloride generated by means of a universal type chlorinator and Scott-Darcey apparatus. Disinfection of final effluent is handled by means of a separate chlorinator. These units are flexible so that any of the solutions can be applied at several vital points in the plant. The raw sewage, supernatant liquor return, secondary and final sludge returns may be treated with chlorine or ferrous chloride. This plant has operated satisfactorily and economically, the effluent being used for irrigation. At Corpus Christi, Tex., Allison [1] reports settled trickling filter effluent to be purchased by an oil refinery for condenser cooling water. This effluent is treated with chlorine for control of condenser slimes and appears to be made entirely suitable for the purpose.

Pearse [167] reviews a report on proposed sewage treatment for the city of Toronto, and Mohlman [152] notes that an election has approved plans to build the preliminary part of the plant. This will consist of sludge removal and digestion with effluent chlorination in order to protect bathing beaches and the water supply from Lake Ontario. The Ontario Minister of Health will approve this construction only as the initial stage of a complete treatment plant which must be constructed not later than four years subsequent to the first stage of the disposal works.

Prechlorination and Odor Control. The use of prechlorination at a sewage treatment plant receiving canning wastes is mentioned by Bernhardt.[25] When domestic sewage alone is treated, the effluent has a chlorine demand of 4.5 to 6.2 p.p.m., but this demand is increased by the addition of canning wastes to a figure of 15 to 32 p.p.m. Prechlorination is reported to reduce odors about the plant and to assist in sedimentation. The dose, or degree of chlorine demand satisfaction, is not given. Describing operation of the Richmond-Sunset sewage treatment plant of San Francisco, Benas [22] notes that chlorine is added in proportion to flow, both for odor control and for disinfection. Prechlorination is reported to require at least 30 lb. of chlorine per m.g. to prevent odors, while postchlorination feed is at the rate of 60 lb. per m.g. from 8 A.M. to 12 P.M. and 30 lb. per m.g. from 12 P.M. to 8 A.M.

Control of odors from the enclosed Asbury Park, N. J., plant by chlorinating the vented gases is described by Strahan.[207] According to Dixon [48] raw sewage reaching the Dallas, Texas, plant is confined in airtight enclosures. After screening and grit removal, spent gases collected from the preaeration and aerochlorination units are directed into a stack for washing and further treatment if needed. Chlorinators

are provided to produce chloride of iron, chlorinated copperas, or for adding chlorine to the grit channels in order to control odors.

Chlorine for Grease Removal. The present status of aerochlorination, as a method of increasing the removal of grease from sewage, is reviewed by Faber.[64] Theory and plant scale operation of such treatment is discussed as well as studies on removal of wool grease from industrial waste. Eddy and Fales [54] describe the design of aerochlorinating tanks to be installed in the Boston sewage treatment plants. These will provide a detention of 3 to 4 minutes at average flow, the introduction of air at 0.02 cu. ft. per gallon rate, and chlorine at 2 to 3 p.p.m. At Dallas, Texas, the new sewage treatment plant, as described by Dixon,[48] is equipped with aeration and aerochlorination for removal of grease. Released scum is swept by water sprays to a scum box from which it is automatically removed at time-clock-controlled intervals.

Chlorine in Activated Sludge. At the Wards Island activated sludge plant, chlorine was applied to return sludge to prevent bulking and to maintain the desired sludge index. Edwards [55] has noted that chlorine is generally believed to be most effective in combating bulking caused by filamentous microorganisms, having been successfully used for this purpose at a number of plants. Bulking at Wards Island is caused mainly by high volatile solids but occasionally by filamentous growths. For six months, two aeration batteries, each treating an average of more than 50 m.g.d. of sewage, were operated as nearly the same as possible, except that an average of 1.8 p.p.m. of chlorine was added to the return sludge of one battery. The settling characteristics, as measured by the sludge index, were about 35 per cent better in the battery using chlorine than in the control battery. Then bulking in the control battery made necessary the chlorination of return sludge in both batteries. Over a period of eight months, with an average chlorine treatment of about 2.5 p.p.m., the sludge index in both batteries averaged about 0.75 (Donaldson index), the same as for the chlorinated battery during the previous six months period. Filamentous bacteria have not been present in objectionable quantities during chlorination. Care must be taken to add the proper amount of chlorine, as too little has no effect and too much produces a decidedly milky appearance, the result of breaking down the floc. This observation may apply to the results found by Bloodgood [26] at Indianapolis, where the application of chlorine was reported to indicate no benefit when tried on one of two plants operated as nearly as possible the same.

Chlorination of return sludge at the Mansfield, Ohio, activated sludge plant is reported by Turner.[223] *Sphaerotilus* is ever present in the raw sewage and appears to multiply rapidly in the activated sludge. Chlorination of return sludge at a 10 p.p.m. rate controlled bulking, though as high as 20 p.p.m. has been required at times. Chlorine has also been used to supplement air when a blower was down for repairs.

Chlorine in Sludge Thickening. Thickening tanks at the Tallmans Island activated sludge plant are provided with chlorinators to treat

the supernatant liquor, the purpose being to prevent bulking of sludge during its detention in the tanks. Chlorine may be added near the center of the tank with the incoming sludge or near the surface in the supernatant liquor. According to Edwards,[55] for satisfactory thickening, sufficient chlorine must be added to maintain at least 1.0 p.p.m. residual in the overflow. The amount of chlorine required depends upon the condition of the sludge and the monthly average used is about 30 p.p.m. Results indicate that the concentration of solids depends more upon the volatile content of the sludge than upon the place where the chlorine is added, but addition of chlorine at the center of the tank gave better control of residual. Shapiro[198] also provides limited data on this installation which indicates that sludge of only 0.5 per cent solids has been concentrated to one-sixth of its original volume without difficulty.

Anderson[3] reports that, in warm weather, chlorine is used for thickening thin activated sludge from final settling tanks at the Rockville Center, N. Y., plant. A better concentration results by adding from 90 to 100 p.p.m. of chlorine solution to the wasted sludge and decanting the supernatant.

General Uses. Miljevic[150] and others describe the use of chlorine for controlling filter flies and filter pooling. Heavy dosage of low night flows to provide a high residual seems to be an accepted procedure. Riker[176] notes that foaming of a separate sludge digestion tank occurs when pretreatment of sewage with chlorinated iron is stopped at the end of the summer. In a round table discussion, Vermette[228] and others describe successful application of chlorine for a variety of purposes at a number of sewage treatment plants. Data given by Gibbons[81] on the effectiveness of a chlorinated organic compound (Benoclor-3) for control of vegetation in lakes and ponds is of interest.

Operation. Symons and Kin[212] provide a multiple nomograph for determining chlorine demand or dosage from given p.p.m. and sewage flow. This eliminates much calculation where the chlorine demand determination is made frequently. Weber[234] discusses improvements in the Annapolis, Maryland, plant which provide better mixing of chlorine applied to raw sewage. This has resulted in correlation between chlorine applied and chlorine residuals—a condition not formerly true. It also prevents loss of chlorine from the treated sewage and resultant corrosion of metal fixtures. Johnson and Jablon[114] describe a simple chlorine deficiency alarm which should be of value in preventing interruption of continuous chlorination at small plants.

In a paper on maintenance of the Allentown, Pa., sewage treatment plant, Krum[132] notes that the three manually operated vacuum chlorinators are given complete overhauling periodically. Equipment is dismantled, the cast iron base painted, and reassembled with such new parts as are found necessary to keep it in satisfactory condition. By this means, a spare apparatus is maintained for immediate service, and operators are familiarized with the function of all parts of the equipment in case of trouble.

Hartz [87] points out a number of safety considerations dealing with gases at sewage treatment plants. While a proper type of cannister mask is adequate for working in an atmosphere containing chlorine gas, consideration must be given to the conditions of use. If workmen must enter enclosed spaces where there may be an oxygen deficiency, then either hose masks or self-contained oxygen breathing apparatus should be available. He suggests that the location of the nearest inhalator should be known, in the event of emergency need for such equipment. It should be noted that Jones [115] recommends the use of oxygen-carbon dioxide mixture as preferable to oxygen for use in inhalators when treating cases of chlorine gassing. A report on 60 gas cases treated with the oxygen-carbon dioxide mixture (oxygen 93 per cent, carbon dioxide 7 per cent) indicates that this treatment relieves the distressing early symptoms. Frequently a community fire or police department has such equipment for its emergency work, and this may be available to the sewage plant.

Sludge Digestion

General information on sludge digestion is given in the excellent books by Keefer [120] and Imhoff and Fair,[102] while recent advances are briefly discussed by Mohlman [154] and Rudolfs.[188] British practice is outlined by Watson,[233] and Jenkins.[109]

Sibata [200] reports on the digestion of seeded garbage mixed with clay, in which liquefaction took place at a pH value below 7.0 with little or no methane or hydrogen production. Boiled soybean or starch, similarly seeded, gave considerable hydrogen. Fuel oil yields on the distillation of the residues after digestion were higher where the combustible gas yields were low.

Keefer and Kratz [122] present data on the chemical treatment of digester overflow liquor. 300 to 400 p.p.m. of ferric chloride gave best B.O.D. and suspended solids reduction. High speed mixing of the chemicals for short periods was desirable. High solids removals were obtained at pH values of 4.0 to 11.0. B.O.D. removals were best at a pH of 4.0.

Smith and Studley [202] give results of pilot plant tests where two 2-stage digestion systems were operated in parallel. In one system where the primary tank was stirred, a solids loading of 12 lb./cu. ft./mo. was attained without foaming as against 4.5 lb./cu. ft./mo. where there was no stirring in the primary unit. The temperature of the stirred primary unit was then raised from 85° to 130° F. and the loading increased to 38 lb./cu. ft./mo. without foaming.

Design. Design data on the sludge digestion tank at Dallas, Texas, are given by Dixon,[48] at Hibbing, Minnesota, by Foster,[71] at Muncie, Ind., by Burger,[31] at Gary, Indiana, by Howson,[98] at New Haven by Emerson,[62] at Albuquerque by Wheeler,[237] at Pueblo, Colo., by Veatch,[225] at Darien, Conn., by Bogert,[27] at Springfield, Mass., by Burger,[30] at Des Moines, Iowa, by American City,[4] at Seattle, Wash., by Sylliassen,[211] and at Rock Island, Illinois, by Consoer and Townsend.[41] At the Rock

Vol. 1
1941

Island and Gary plants the digesters are designed to handle combined garbage and sewage sludge.

A flexible arrangement of a heating system where gas engines, building heaters and digester heating coils are interconnected is shown by Frazier.[73] Eggertson [56] describes the method of pre-heating sludge and scum before pumping to the digester at the Raritan (N. J.) Township plant. Nagel [161] outlines the safety features of the Imhoff tank reconstruction at Dayton, Ohio. Langford [134] gives precautions to follow in the design of digester gas collection equipment. In *American City* [5] details are given of the gas collection and heating system at Greenwich, Conn.

Eliassen [59] presents some very useful monographs for calculating the size of digesters using the old rule of thumb cu. ft. per capita basis and the more scientific solids detention method.

Operation. Operation of the Richmond-Sunset plant at San Francisco is given in an article by Benas.[22] Velzy, Johnson and Symons [227] give operating experiences at Buffalo, where supernatant liquor is sprayed on the surface of the scum to soften the scum layer.

Experiences at Lansing, Mich., with the digestion of garbage with raw and activated sludge are described by Wyllie.[246] Particular attention is called to the necessity of providing a means of removing bones, eggshells and fruit pits from the garbage before it is added to digesters; otherwise segregation of this material in the sludge withdrawal lines occurs. The effect of the garbage in giving a poorer quality overflow liquor is also stressed. Cleary [37] discusses the digestion of garbage with sewage sludge, and states that digesters would have to be doubled in order to handle all the garbage as well as the sludge of a municipality. Operating results of the two-stage system at Grand Forks, N. D., are given by Riley,[177] and at the Barston Works of Birmingham, England, by Hewitt.[94] Anderson [2] describes his digester operation experiences at Rockville Center, N. Y. Corrosion of gas lines, gas engine operation and digester maintenance are discussed. The reasons for a slight explosion in the chamber where the gas collection equipment is housed, are also outlined.

A round table discussion of foaming in sludge digestion tanks is presented in *Municipal Sanitation*,[181] wherein a number of plant operators discuss methods of control. Lime addition was of help in some cases. In others, a temporary reduction in solids loading was beneficial. A round table discussion of sludge digestion tank operations is given in *Sewage Works Engineering*.[182] This is an excellent compilation of actual operating procedures followed at a number of representative plants. Points discussed are methods of feeding raw sludge, disposal of overflow liquor, sludge mixing, tanks, temperatures and heating, and insulation, etc. Ten good rules for digester operation are given by Reybold.[10] Important points stressed are frequent addition of small quantities of raw sludge to the digester, preparation of the digester for shock loads and winter storage, and the avoiding of depletion of seed sludge.

Patents. Streander [210] shows a digester design wherein circulation of liquid is assisted by a central draft tube. Heat is applied below the bottom opening of the draft tube. Fischer [68] covers a two-stage digestion system in which thermophilic digestion is carried out in the first stage and mesophilic digestion in the second stage. Downes [51] describes a two-stage digestion system with the primary units superposed over the secondary tank. Petersen [168] shows a tank rotating on a horizontal axis for the mixing of sludge undergoing digestion. Durdin [53] covers a digester equipped with a gas holder in which there is a screen in the lower part that normally submerges solid matter in the tank. Potts and Wigley [174] describe a process of stabilizing sludge by the action of molds and fungi. Breuchaud [29] shows a multiple hearth unit for the stabilization of organic matter, wherein anaerobic action is carried out in the first part and aerobic action in the second part. Roeder [178] covers the aerobic thermophilic digestion of dewatered raw sludge treated with stabilized material ahead of the dewatering step.

Plant Records. Seven years' operation records of Grand Rapids, Mich., are presented in *American City.*[6] Complete data from Winnipeg, Canada, for the year ending December 31, 1939, are given in THIS JOURNAL.[243] A brief summary of the operation of digestion tanks at Cleveland is given by Ellms [60] in his 1939 Annual Report. In his 1939 Annual Report, Cohn [38] gives results of the Imhoff tank operation at Schenectady, N. Y.

Need for Further Study. In view of the interesting pilot plant results on thermophilic-mesophilic two-stage digestion at Los Angeles, further work along this line at other plants on a full plant scale would be well worth while.

There is still need for correlation of digestion tank operating results obtained at different plants over long periods, to better evaluate the various factors that have an influence on digestion.

SLUDGE DISPOSAL

Most developments during 1940 in sludge disposal have rotated around vacuum filtration and incineration, which appear to continue their popular trend for the larger plants.

Buffalo, New York,[227] finds cotton flannel the most satisfactory filtering cloth tried for vacuum filtration of digested primary sludge. The teasel on the flannel appears to be a factor in its favor. Plain steel wire at a relative narrow spacing of 1½ inches has increased the life of the cloth, which averages 200 to 225 hours.

Calcium carbonate incrustation in the filter monel metal supporting screens has been satisfactorily removed with a 5 to 10 per cent muriatic acid solution. The filters were subjected to this bath for about 10 hours. The same solution has been used to remove incrustations in pipe lines and in the filtrate pumps. Flower [70] at Cleveland cleans filter supporting screens in 4 hours by coating an unused filter cloth with rubber latex, suspending this cloth under the filter drum and filling the

bag so formed with muriatic acid so that the bottom section is submerged. He does not state the strength.

About 1.2 cu. ft. of gas has been required at Buffalo for each pound of dry solids burned, when the volatile solids in the sludge cake is around 40 per cent. When scum (top sludge) and bottom sludge are burned together the higher volatile content tends to over-heat the furnaces and water is sprayed in the drying tower. This procedure suggests a method of ridding digesters of excessive scum at other plants where the piping arrangements permit and the scum is soft enough to flow or be pumped.

Grit was burned for several hours alone and was mixed with equal parts of sludge during one whole month. Sand in the sludge (not grit as added to the sludge) has caused abrasion of fans, cage mills, ducts, etc. At elbows and bends in the fuel lines (feeding powdered dry sludge) wear has been excessive and a wear back made of a steel box, filled with concrete, and clamped to the pipe has proved effective, inexpensive, easy to construct and easy to replace.

Lynch and Milliken [143] report that winter chemically-precipitated raw sludges at Auburn, New York, have a greasy appearance and a gritty composition, these properties clogging the filter cloths and causing a build up of partially dewatered sludge in the filter vats. Grit removal is inadequate, again showing the need for sufficient grit handling facilities at all sewage plants.

Chemical doses for sludge conditioning are determined by estimating the solid content from the specific gravity of the sludge. The relation of specific gravity to solid content is based on experience. The Buchner funnel test is employed in the laboratory for filterability of the conditioned sludge.

Division bars of brass on the Conkey filters have been replaced with half round soft wood held with finishing nails at a net saving of $6.50 in material and 20 hours of labor per cloth change. Removal of the preheater at Auburn has eliminated escaping smoke and gases in the Nichols Herreshoff sludge incinerator.

Elmira [143] reports a welcomed change from anhydrous ferric chloride to liquid. A change at this plant from batch to continuous feed of ferric chloride has resulted in a considerable saving. Lime is still added to a batch of the raw sludge. The incorporation of patented valves in the oil and air lines to oil burners for the sludge incinerator so that the oil pipe is closed when the pressure drops in either line prevent the formation of oil products and subsequent charring. This has been a problem at many plants.

Denise [143] also feels that liquid rather than anhydrous ferric chloride will prove easier to handle, cheaper and be easier on the equipment at Greece, New York. A change from air diffuser tubes to a mechanical agitator in the sludge conditioning tank is giving far superior mixing.

Weber [235] at Annapolis has substituted elutriation of digested sludge with ferric chloride coagulation for filtration conditioning with marked

benefits over ferric chloride and lime treatment. Benefits include savings in chemical cost, labor, power and filter cloth. Successful filter runs have been made on elutriated sludge with alum alone.

At Cleveland [76, 78] the costs of vacuum filtration for 1939 were $5.97 and $4.92 per ton of dry solids filtered at the Westerly and Southerly plants, respectively. Both handle digested sludge. Incineration costs on the same basis were $5.10 and $3.86, respectively. These are some of the first cost figures published on digested sludge filtration for a long operating period.

Faber [34] has presented some interesting data on chemicals, yields, per cent of solids, life of cloth and treatment of sludge in connection with the vacuum filtration of sludge. Of 46 vacuum filter plants, 85 per cent use ferric chloride for conditioning.

Jones [116] urges caution in the release of data on conditioning of sludge, unless there is assurance that time and mass effect of results have been sufficient to render true decision. In a summary of current opinion on present practices he also emphasizes accuracy in volume measurements and in sampling if a true evaluation of all factors involved in dewatering and conditioning is to be realized. The results of filtration at recently completed plants might well be studied, he recommends, and coordinated in a committee report by the Federation.

In a report on the cost of sludge disposal at the Michigan City activated sludge sewage treatment plant Jones [126] states that in a period somewhat over 2½ years digested sludge averaging 7 per cent solids was delivered to open beds at a total direct cost per dry ton of $1.54. The cost of delivering sludge of somewhat lower solids content to artificially constructed lagoons was $1.34 per dry ton. These costs, it should be kept in mind, do not include sludge cake removal.

Rudolfs and West [103] presented an interesting report on the properties of raw sludge affecting its discharge through pipe at the Elizabeth Valley Joint Meeting sewage treatment plant. Here sludge is pumped 4,400 feet through a 24-inch force main for barging to sea. Two years of study show an increase in loss of head with an increased dry solids content or decreasing sludge temperature. The temperature of the sludge exerted a greater influence on the head than the solids content. The studies also showed an increased rate of sludge flow with a higher ash content.

A total of 54,088 dry tons of sludge was dumped at sea during 1939 from New York City's sewage plants, principally from Ward's Island, at an operating and maintenance cost of $2.20 per million gallons of sewage or $2.55 per dry ton of solids.[49] Three sea-faring ships each holding 55,000 cu. ft. of sludge make the 68 mile round trip in about 6½ hours. The three vessels cost $1,500,000 and each carries a crew of 18 men including a cook and mess boy. Besides New York City, this method of sludge disposal is now limited to Passaic Valley, Elizabeth and Providence. New Haven at its East Street plant discontinued

barging in 1940 with the installation of vacuum filters and a sludge incinerator.

Re-discovery of sludge drying with alum and results obtained at Aurora, Illinois, are of interest. Sperry [204] made an initial trial with one pound of chemical to 85–90 gallons of sludge with shortened drying time. Liquid application with a very short mix releases the carbon dioxide in the digested sludge and results in a thinner cake than untreated wet sludge applied to a similar depth. The greatest benefits occur from alum in the first 24 hours. Alum treated sludge is less affected by rain. Alum treatment is of especial benefit with poorly digested sludge or sludge containing much grease such as scum.

Agricultural Utilization. Van Kleeck [224] points out the dangers in the use of raw sludge, compares analytically sludges, manures and commercial fertilizers and advises the potential user of digested primary sludge to weigh the cost of manure in his community as a rough index of the value of local sludge. Methods of applying sludge, amounts to use for various crops, fortification of sludge and the results from its use are cited.

Rudolfs [190] stresses the "fertility" value of sewage sludges in contrast to their fertilizing values. The growth promoting substances in sludge have a definite sales appeal for sewage plant superintendents. The article contains data on the chemical constituents and growth promoting substances to be found in sludges and gives methods for applying and fortifying sludges. Sludges improve the soil and will continue to do so, he says, if acidity (caused largely by the break-down of the greases and fats present in sludge) is checked by judicious applications of lime to the soil every 3 or 4 years. The omission of this simple remedy accounts for the good results with sludge for the first few years followed by injury to plant growth by the accumulating acidity.

Experiments on the manurial value of sewage sludge from septic tanks was reported by Cranfield.[42] Application on experimental plots of sludge from septic tanks fortified with artificial fertilizers containing nitrogen, phosphorus and potassium were compared with manure on equal weight basis similarly fortified. It was concluded that under favorable conditions sewage sludge may be as effective as manure but if conditions were adverse militating against rapid decomposition, then manure may have an advantage over sludge. To get good results adequate dressing with artificial manure is recommended. The residual effect of the sludge may carry over for a second year's crop.

The preparation of manure from town refuse by composting was reported by Tripp [222] from England. The refuse after sorting and pulverizing is inoculated. It is subjected to aerobic and anaerobic fermentation for 16 days in cells where the temperature rises to 170 to 175° F. The dry matter in the manure varied from 63.9 to 74.4 per cent and nitrogen in dry matter from .97 to 1.42 per cent. This manure when applied to kale and sugar beets gave higher yields than farmyard manure on the basis of equivalent nitrogen applications.

Mechanical Developments

Although it does not appear that outstanding mechanical developments in the sewage field took place during 1940, even a casual reading of the literature cannot fail to impress one with the steady growth of mechanization of sewage treatment and improvements in the mechanisms. Several interesting articles were published on the research which led to the development of some equipment.

The new sewage treatment at Gary, Indiana,[78] has many interesting mechanical features. One of these is the ventilation of the rack room through a filter protected connection to the suction side of the blowers for the aeration tanks. Three out of five large sewage pumps are direct connected to gas engines which are automatically throttled by the sewage level in the suction channel. These installations are designed to work efficiently over a range from 15 to 25 m.g.d. discharge. Since the engines are located on the first floor of the administration building great care was taken to minimize vibration and noise. The concrete engine pads are mounted on vibration dampeners. Piping has flexible connections and double flexible couplings are installed between the engines and the pumps. Acoustical tile has been used on the ceilings of the pump and blower rooms. Double doors and a double framed and double glazed observation window are provided between the office hallway and the blower room.

Since Gary is a steel center it is not surprising, but interesting to know, that approximately seven miles of steel pipe in sizes up to 60 in. diameter were used in the plant. Sizes smaller than 6 in. are galvanized. Sizes larger than 6 in. are of black steel ½ in. thick. All buried piping is bituminous coated and wrapped. The interior of air piping was given a rust protecting high temperature resisting paint.

Garbage to be ground at this plant will be dumped into a hopper from which it will be carried to the grinders by belt conveyor from which bones, silver ware, cans and some of the other materials which have been bothersome elsewhere may be picked out.

Emerson [62] reports that recent developments in materials and methods for under water work made feasible a 4850 ft., 36 in. diameter underwater connecting sewer at New Haven, Conn. This eliminated the necessity of one sewage treatment plant which had been contemplated in a comprehensive plan of several years ago for three plants. The leakage in this line was reported to be less than five gallons per day per inch diameter per mile.

An existing plant was enlarged and one new plant built at New Haven.

The sludge filters are completely enclosed in a sheet aluminum ventilating hood piped to the air intake of the incinerator to control odors from the filtration of raw sludge. An annular space in the incinerator chimney takes the discharge from the vacuum pumps.

Specifications for the sludge incinerator limited the combined cost of fuel oil and power to $1.50 per ton of dry solids, with oil at 5¢ per gal-

lon and power at 1.5¢ per kw. hr. Fly-ash content of gases to base of chimney is not to exceed 0.75 grains per cu. ft. of gas at discharge temperature.

The new Bond Island sewage treatment plant at Springfield, Mass.,[30] incorporates the latest improvements in mechanization. These include detritors for grit removal and washing, comminutors, aerated influent channel to sedimentation tanks, automatically controlled sludge pumps, spherical, pressure gas holder, gas pressure boosters and compressors in a separate gas control building, vacuum filtration of elutriated digested sludge, and flash drying and incineration of sludge cake. Incinerator ash is pumped to a low area for disposal as fill.

Fuhrman [74] reviewed the uses of sludge gas with particular attention to power production. A comprehensive list of engine installations indicates that they have been installed rapidly in small as well as large plants. The table lists a total of 22,170 horsepower, 20 per cent connected to pumps, 35 per cent to blowers and 45 per cent to generators. Fuel requirements vary from 8400 B.t.u. per brake horsepower hour for the 1200 H.P. engine at Washington, D. C., to 14,500 for a 45 H.P. engine at Ontario, Cal. A common guarantee figure is 10,000 B.t.u. with gas at 600 B.t.u. per cubic foot. In some installations the investment has been saved in two or three years. In one or two rare cases the use of an engine has been discontinued because of noise or cost. The use of an early installation at Rockville Center, L. I., was discontinued because of noise and the low cost of municipally produced current.

The estimated savings at Washington, D. C., is $13,000 annually which could be increased to $23,000 by installing another 1500 H.P. gas engine, a 750 H.P. Diesel and severance of the utility lines. These estimates include both fixed and operating charges. In 1939 the 1200 H.P. engine operated 95 per cent of the time and produced over 95 per cent of the total power. Recoveries from the engine were estimated as electrical energy 23 per cent, jacket water 30 per cent, exhaust 12 per cent and losses as electrical and heat 35 per cent. This would indicate an overall efficiency of 65 per cent.

Hecking [58] estimates a 20 per cent loss from the potential power in gas to the driven unit when electric current is generated and used instead of direct drive. He estimates that 100,000 population should produce sufficient gas for the continuous operation of a 150 H.P. engine.

One advantage of engine-generator drive is indicated in installations at Albuquerque,[164] Fort Dodge [140] and Oshkosh [72] each of which has arrangements with the local utility to draw from, or furnish power to their lines. At Oshkosh utility power is utilized through the generator acting as an induction motor to start the engine. Fort Dodge has a 25 year contract with the utility company to buy or sell power at 0.85¢ kw. hr.

Dowling [50] has given an interesting explanation of the development of rotary positive blowers from a machine originally designed for water power. This type of blower might well be called a positive volume

blower since the volume remains practically the same for constant speed regardless of the outlet pressure. This feature is utilized for metering the output. A recent development is a dual compartment blower giving three different capacities at one speed or six with dual speed drive. Fisher and Hillman [69] describe the development of a combined flocculation and sedimentation tank called a "clariflocculator." The flocculator occupies a central well in a circular clarifier. Inlet is at the center, agitation is produced by moving V-shaped vertical paddles. The flocculated sewage passes directly through the bottom into the clarifier with little agitation. Kivel,[127] Tark and Gilbert [217] and Nichols [163] have written of the development of the modern mechanical devices for the automatic removal and washing of grit.

Some progress has been made in the problems of corrosion, erosion and abrasion of metals used in sewage treatment. A symposium on this important matter was conducted [215] at which the resistance properties of nickel, aluminum and copper alloys and rubber linings was discussed. Cox [215] reported that studies were underway at Newark, N. J., where gas contains 100–300 grains of hydrogen sulfide per 100 cu. ft. These tests are on the nickel-copper alloys, "monel" and "ni-resist." Burr [215] stated that for sludge gas, copper tubing has shown scaling and pitting, red brass was little attacked while "admiralty" metal was scarcely attacked beyond a little blackening over a period of several years in one test. He suggested "admiralty" metal for heat exchanger tubes. Considerable erosion or abrasion of metal parts in the sludge handling equipment at Buffalo [227] has been bothersome. This has taken place in bars of the flash dryer, fan blades and casing. This effect is apparently due to very fine sand in the sludge. Experiments are being carried out to find an economical and satisfactory solution of the problem. In one case a steel box filled with concrete has been clamped to the outside of a bend in a fuel line. This has proved effective, inexpensive, easy to construct, and to replace.

Material used for ladies' stockings would hardly seem suitable for any use in a sewage treatment plant yet brushes made of "nylon" bristles are reported at Milwaukee [11] to outwear those made of hog bristle for cleaning the fine screens. Although higher in first cost they appear to be more economical because of at least 50 per cent longer life.

New Aids to Practice

Each year sewage works operators, engineers and equipment manufacturers contribute new aids to better performance and economy of plant operation and sewerage service. The following developments, representing refinements and in some cases innovations in practice, command a special place in this review. Set apart in this fashion these practical developments acquire individuality which otherwise might be overlooked in a panoramic picture of progress.

Departing from conventional practice in building filter bed inclosures of reinforced concrete, Jenks [113] is using corrugated iron sheets

in two California plants with a resulting saving in cost of 20 per cent. The corrugated iron plates are of the type normally used for culvert construction. In addition to economy of construction the use of this material has the merit of quick and easy assembly, thus recommending its employment in disposal works urgently needed in army camps and centers of industrial expansion. According to Jenks the use of these thin iron sheets has probable limitations—in beds of diameters greater than 50 ft. the curvature of the inclosure would be so flat as to necessitate some means of stiffening the sheets against bulging. It has been found very satisfactory, however, for beds of 36 and 45 ft. diameter and 3 ft. in depth.

One way to cut the cost of treatment plant construction was demonstrated at Liberty, N. Y., where a magnetite filter and chlorine contact tank were combined in a single structure.[7] This eliminated the need for extra tanks and resulted in a more compact design.

Substantial economy in cost as well as improvement in hydraulic characteristics resulted from a model study of a backwater gate structure built in Detroit.[99] The test, using a scale model 1/24 of full size, showed that a six channel structure, originally proposed, was inferior to a smaller, simpler and less costly four channel arrangement. Here again was demonstrated the desirability of wider use of model studies as an adjunct of design procedure.

New information on the flow of sludge in pipes resulted from studies made at the University of Illinois.[16] In the pumping of sludge it has been assumed that the common hydraulic formulas for flow of water may be used provided that the velocity is sufficient to insure turbulent flow. But the Illinois investigation indicates that this method is only an approximation of the true condition. Viscosity and plasticity are important factors, and it is considered evident that sewage sludge and clay slurries are true plastics. Conclusions presented are, in brief, as follows: (*A*) Sludges such as mixes of clay and water used in deep well boring, sewage sludges, sludges from water softening plants and other similar aqueous suspensions of fine particles, obey the fundamental formula for the flow of a true plastic; (*B*) for sludge flowing in a pipe a critical velocity is encountered as the velocity of flow is increased—below the critical point the flow is laminar, while above it the flow is turbulent; (*C*) further research as to the factors affecting turbulent flow in pipe is desirable, as the common hydraulic formulas for flow of water are not applicable to the flow of sludge.

A sludge-carrying tractor with specially fitted "saddle bag" bins is the answer to economical cleaning of drying beds, according to reports from Sperry.[8] A removal cost of 14.5 cents per cu. yd. is cited as against 48.6 cents using the narrow gage track and car system originally installed at the plant. Equipment consists simply of a standard tractor fitted on each side with No. 8 gage sheet metal dumping bins of 3 cu. yd. capacity, and it is similar in construction to a machine previously built by the Springfield (Ill.) Sanitary District. When not

transporting sludge, the tractor has a score of other uses around the plant, such as clearing snow, trimming sludge piles, moving grit, etc.

A "vacuum cleaner" for septic tanks, which is useful also for removal of sludge from tanks, can easily be made in the plant workshop, according to the department of water supply and waterworks at Salt Lake City, Utah.[135] This ingenious homemade device employs a 550 gal. airtight tank mounted on an old auto truck, a 10 gal. auxiliary tank, a few check valves and some hose. Air in the 550 gal. tank is sucked out by means of a tube that goes in the tank to the inlet manifold of a truck motor. When the truck is operated, a vacuum is thereby created in the tank; then a 3 in. hose connected with the tank is dropped into the sludge, a quick acting valve is opened, and the sludge immediately flows upward into the tank. The operation continues until the tank is almost full, after which it is emptied and is then ready for use again.

The idea of putting a laboratory on wheels is not new, but the design and equipment of mobile units employed by the U. S. Public Health Service on the Ohio River survey, introduces some novel features.[9] The mobile unit consists of two elements—a trailer containing complete laboratory facilities, and a tow car. The latter is a dual purpose accessory; it not only provides motive power for the trailer but also serves as a means for rapid collection of samples. Thus the laboratory can be located in the center of an area under study for a period of one or more weeks, during which the towing car collects samples within a 40 mile radius. The total cost of this mobile field laboratory including the tow car, equipment and six months' supplies is given as $3,671. The experience gained by the Public Health Service in designing and operating these units should be of considerable value to state health organizations and sanitary districts who have frequent need of mobile laboratory equipment.

A simple but effective scheme for removing floating grease and scum from settling tanks which lack mechanical equipment for doing this job is to use a water spray.[137] At Cleveland's Westerly plant some 1,360 Link-Belt spray nozzles have been installed on Imhoff tanks for this purpose. The water spray is made to strike the surface of the tank at an angle thus imparting motion to the floating material. The nozzles are located at intervals so that the material is kept moving until it reaches a scum trough at the end of the tank.

Rubber balls covered with a chain netting were made available this year for use in sewer pipe cleaning.[139] The chain-inclosed ball, which comes in various sizes, is first inflated with air so that it will float through the pipe and thus scrape the upper surfaces and also remove major obstructions. Then it is filled with water and permitted to roll along the pipe invert as a final cleaning measure.

Some new facts on ventilation of sewers, pointing to the usefulness of simple ducts in manholes for aeration, were made available by studies of the U. S. Bureau of Mines.[118] Among other things, these investigations showed that natural ventilation by means of openings in manhole covers increases as the area of the openings are increased, and

that wind velocity across the openings has a marked effect on ventilation; a 50 per cent increase in ventilation was noted when the velocity of the wind increased from zero to 10 m.p.h.

A method whereby sludge drying on sand beds can be speeded up by the simple expedient of applying heat to the bed was described by Phillips.[169] A grid system of 3/4 in. pipe was installed just below the sand surface of the bed, and excess hot water from the digester heating system was circulated through the pipe. It was reported that 43 per cent more dry solids could be handled than was heretofore possible on the same beds without heat.

Industrial Wastes

European work on industrial waste treatment has been diminished by the war, and the literature is meagre and difficult to obtain. In this country, however, interest still remains at a high level, and more attention has been devoted to the treatment of wastes in conjunction with domestic sewage.

General. The developments of 1939 were reviewed by Mohlman [155] in a paper published early in 1940, which contains a number of things not widely reported in the literature. Among these are the German work on wastes from coal hydrogenation and fatty acid synthesis. The wastes from the latter process contain 5,000 to 10,000 p.p.m. of fatty acids. The low B.O.D. reduction obtained in the treatment of sulfite wastes by the Howard process is also mentioned. The same author [153] has described the work of the Sanitary District of Chicago in classifying and studying the individual wastes making up the 89 m.g.d. of industrial waste received at the District's sewage plants.

The Annual Report of the Division of Sanitary Engineering of the Maryland State Health Department for 1940 contains a resumé of the industrial waste problems handled by the Department in the past few years. It is of general interest as an indication of the wide variety of problems encountered in an industrial state. The general aspects of the industrial waste problem have also been discussed by Knowlton.[129]

A symposium of the Institute of Sewage Purification (Eng.) on pre-treatment of trade effluents [15] discussed the principles of pre-treatment, specifically chromate wastes, acid wastes, cyanide wastes, metallic wastes, and oil and grease wastes. Quantitative determination of the objectionable constituents of these wastes, and limitation of the amounts allowed to be discharged, also came under discussion.

Beet Sugar Waste. Construction of a plant for treating beet sugar wastes has been described by Eldridge.[57] The plant consists of a revolving screen, grit chamber, coagulation tanks with 20-minute detention, and settling tanks with 90-minute detention. Sludge is sent to a drying pond. The plant was intended to receive flume, beet washer, battery wash and pulp press waters, and to coagulate them with Steffens waste. During the first operation period no Steffens waste was available; plain sedimentation yielded an effluent with 201 p.p.m.

B.O.D. (30.3 per cent reduction). After normal operation was established, using Steffens waste as a coagulant, an effluent of 264 p.p.m. B.O.D. was obtained, corresponding to a 71.3 per cent reduction for the mixture including the Steffens waste.

Cannery Waste. Treatment of cannery waste in the sewage plants of New York State is discussed by Ryan.[194] A table of analyses of cannery wastes is included. Ryan states that the most difficult wastes are corn, pea, tomato and beet, in the order named. He concludes that canning wastes can and should be treated with domestic sewage, if proper screening is provided and an adequate ratio of sewage to waste is maintained. However, the activated sludge process is not suited for treating mixtures of sewage and cannery waste. Ryan advocates the use of activated carbon for reducing the odors of waste solids and ensilage juice, and the treatment of screenings dumps with bleaching powder.

Reports on the treatment of wastes from citrus juice canning plants have been issued by the Texas State Department of Health.[218] The waste from the peel bins contains the bulk of the B.O.D. and should be separated and carried to waste land. Grinding the peel in hammer mills will reduce the amount of this liquid drainage from the peel bins. The floor-washing wastes may be treated by chemical precipitation with alum and lime to reduce their B.O.D. from 1,700 to 1,200 p.p.m.; this effluent, mixed with the cooling waters and other weak wastes, gives a final waste containing about 115 p.p.m. B.O.D. The chemical cost of such treatment for the average plant was about $1.00 per day. It was also found possible to treat the wastes by activated sludge or trickling filters, either alone or mixed with domestic sewage.

Coal Washery Water. Results of investigations dealing with the flocculation of coal washery water are reported by Yancey et al.[247] Starchy materials such as potato starch, wheat flour and cornstarch were found to be effective as flocculants for coal. The maximum effectiveness of these materials was over a short range of concentration. Electrolytes were effective flocculants over a wider range, but the concentration necessary to produce good flocculation was much higher than with the starchy materials. Flocculated coal slurries filtered much faster than unflocculated ones.

Gas Plant Waste. In experiments on treatment of phenol wastes on trickling filters, Eldridge [57] found complete removal of 20 to 30 p.p.m. of phenol in single-stage filtration, and of 180 p.p.m. in two-stage filtration. When the work was repeated using gas plant scrubber liquor containing 1,932 p.p.m. of phenol, it was found that other toxic materials accumulated in the filter, necessitating dilution of the waste in the ratio of 1 to 64. For such wastes, trickling filter treatment would be prohibitive but it might be suitable for wastes containing low phenol concentrations.

Milk Plant Waste. Following practice abroad the use of the activated sludge process for treating milk waste at dairies in Somerset, Pa., and New Bremen, O., is discussed by Montagna.[157] The plants differ from the usual activated sludge plant in that the waste is treated

with lime to pH 8 to 9, mixed, and given primary sedimentation with recirculated primary sludge. The casein sludge from the tank, amounting to about one per cent of the total waste volume, is disposed of by transporting to waste land by tank truck. The effluent from the primary tank is aerated with activated sludge for about 24 hours, the lactic acid produced lowering the pH to 7.6–7.8. The air used amounts to 2.8 cu. ft. per gallon of waste. Secondary sedimentation follows, and all sludge from the secondary tank is returned to the aeration tank. The average B.O.D. of the influent waste is 545 p.p.m., that of the effluent 7.4 p.p.m., a reduction of 98.4 per cent. The maximum B.O.D. of the influent is 1,800 p.p.m., that of the effluent 16.5 p.p.m. Each plant treats about 50,000 gallons of waste per day. The construction cost for each plant was $12,000 and the operating cost is reported to be $3.00 per day.

Mallory [144] has described a "package delivery" plant for treating milk wastes, consisting of two factory fabricated steel tanks designed to treat the wastes by the "oxidized sludge" process. This process consists of fine screening, aeration with activated sludge, clarification, coagulation with unspecified chemicals, and secondary clarification. Reductions in B.O.D. of 94.5 to 99.2 per cent are claimed. The prefabricated units make for economy in construction and rapid installation for small plants.

Eldridge [57] converted a low rate trickling filter at a milk plant into a high-rate recirculating filter, operating at a gross rate of 16 m.g.a.d., and a net influent rate of 3.4 m.g.a.d. The low rate plant had given a B.O.D. reduction of 60 per cent; the reconstructed plant gave an average reduction of 90.6 per cent, on the basis of an average influent B.O.D. of 537 p.p.m., and an effluent B.O.D. of 46 p.p.m.

The report of the British Water Pollution Research Board [232] for 1939 contains an account of experiments on the treatment of whey washings from a cheese factory by two-stage trickling filters and by activated sludge. The two-stage filters, operating at 160 gal. (Imp.) per cu. yd. of filter medium, produced from whey washings of 270 p.p.m. B.O.D., an effluent of 70 p.p.m. B.O.D. The activated sludge process, using a 36-hour aeration period, handled washings of 660 p.p.m. B.O.D., and produced an effluent containing 60 p.p.m.

Disposal of milk waste on land by irrigation or by spraying (artificial rain) is described by Christophersen.[36] The "tank process," in which the water is subjected to successive fermentations in a series of tanks, is recommended as a preliminary to agricultural utilization of the waste.

Nichols [162] describes the treatment of dairy waste by chemical precipitation with alum and sterilization by hypochlorite. The usual alum dose is 25 to 35 grains per gallon; sufficient hypochlorite is added to produce a chlorine residual of 2 to 3 p.p.m., and the waste is settled in fill-and-draw tanks holding one day's discharge. Sludge is dried on cinder filters. A weak milk waste had its B.O.D. reduced from 846

p.p.m. to 119 p.p.m. by this process, and a strong waste from 1980 to 534 p.p.m.

Oil Well Brines and Oil Refinery Waste. In California, according to Humphreys and Rawn,[100] brines from producers in adjacent fields are collected, given the necessary treatment to remove oil and suspended solids, and carried to the ocean in pipe lines of considerable length. At one of these central treatment plants a special two-compartment sedimentation and skimming tank is used. The effluent from the tank passes downward through an excelsior filter. The treatment removes 95 per cent of the 1,000 p.p.m. of oil contained in the waste, and practically all of the suspended solids. The entire plant, including the outfall, cost $750,000, and has a capacity of 4 m.g.d. Operation and maintenance costs are $25 per m.g. and fixed charges $50 per m.g.; from this may be deducted the $20 per m.g. realized from the sale of the recovered crude oil for road or fuel oil.

Gibbons [80] shows what small quantities of petroleum products will produce taste and odor difficulties in water supplies. For example, No. 2 heating oil can be detected by the hot odor test in dilutions of 1 to 12,000,000. Gibbons discusses the removal of these tastes and odors.

Packinghouse Waste. The treatment plant of Armour and Co. at West Fargo, described by Howson,[97] treats 700,000 g.p.d. of packinghouse waste with an average B.O.D. of 1000 p.p.m. Treatment takes place in the following steps: screening, grit removal, grease flotation, flocculation, primary settling, primary filtration on trickling filters equipped for both air and water washing, secondary settling, secondary filtration on conventional trickling filters, final settling, and cascade aeration prior to discharge to the stream. The sludge is lagooned without digestion. Most interesting is the performance of the primary filters: dosed at 6 m.g.a.d., or 5,000 to 6,000 lb. of B.O.D. per acre-foot, they remove 3,000 to 4,000 lb., reducing the B.O.D. of the effluent waste to 250 to 350 p.p.m. The secondary filters may be operated in parallel or in series. The plant has consistently bettered the 95 per cent B.O.D. removal upon which the design was based.

Paper Mill Waste. The Howard process for treating sulfite pulp mill wastes, as installed at the Marathon Paper Co., Rothschild, Wisconsin, is the subject of a number of papers. The details of the process are given by Howard,[96] who claims a B.O.D. reduction of approximately 80 per cent, and describes the utilization of the precipitated lignin. A study of the Howard process effluent by Warrick [231] showed a 43.5 per cent decrease in the potential hydrogen sulfide generating power of the waste. Warrick also found that the results obtained depended to some extent on the types of wood and cooking procedures used in the paper mill. The greatest percentage of the total oxygen demand of the waste was exerted by its carbohydrate content. Warrick found B.O.D. reductions of 31 to 45 per cent to be the best obtainable from the process. River water was used as dilution water, since the standard dilution waters proved unsatisfactory for the waste. Keeth [123] discussed the use of the precipitated lignin as fuel. Pressing of the material reduced

the moisture content to 50 per cent. The press-cake, when mixed with 15 per cent of coal, was burned in boilers equipped with stokers. A recovery of 64 per cent of the available heat was indicated.

The chemistry of lignin and its utilization is discussed by Harris [86] in a paper which summarizes recent research, and shows the relationship of the structure of the lignin molecule to the commercially useful materials produced from it. The production of tanning materials, iron-removing compounds for water, vanillin, and other materials is taken up.

In experiments on the purification by activated sludge of mixtures of sewage and sulfite waste liquors, Sawyer [195] found that satisfactory results were obtained with sewage containing 6 per cent or less of Howard process effluent, and 10 per cent or less of raw calcium-base sulfite liquor. Higher percentages produced sludges too heavy to be kept in suspension by normal aeration, due to precipitation of calcium carbonate. Magnesium-base sulfite liquor produced bulking sludges. The importance of adding nitrogen and phosphorus in assimilable form to dilution waters used for determining the B.O.D. of mixtures containing high proportions of sulfite waste was demonstrated. Failure to add these necessary nutrients, according to Sawyer, accounts for the claims of high B.O.D. removals by the Howard process.

German investigators, according to Fink and Lechner,[66] are using sulfite wastes for growing yeast which is dried and used at cattle fodder.

The use of magnesium instead of calcium as the base of sulfite cooking liquor facilitates recovery and re-use of chemicals; operation of the process on a pilot plant scale is described by Tomlinson and Wilcoxson.[220] Descriptions of a number of recent patents on the disposal of paper mill wastes, particularly sulfite wastes, will be found in TAPPI, sections 276 to 278 of the *Paper Trade Journal* for 1939.

Experiments on the flocculation of white waters, described by Poor,[171] showed that the best results were obtained with fatty acid soaps in conjunction with alum. The amount and character of the filler contained in the white waters had a considerable effect on their flocculation.

Spulnik *et al* [205] studied the specific effects of raw waste sulfite liquor on plant growth and soil properties. It was found that waste sulfite liquor in concentration below 80 tons per acre was not toxic to sunflowers. It increased carbon dioxide production in the soil, organic decomposition and the microbiological population of the soil.

Textile Wastes. Experiments by Porges, Miles and Baity [172] have shown that direct addition of sulfur dye wastes to activated sludge in amounts as low as 0.5 per cent by volume will retard digestion. Digestion of sludge produced from sewage-dye waste mixtures is also inhibited, but the effect per unit of dye waste is not as great as that obtained by direct addition. The inhibiting effect of the dye waste may be minimized by using sludges acclimated to the waste as seeding material, and by increasing the quantity of seeding sludge used per unit of

fresh sludge. Production of hydrogen sulfide and colloidal sulfur was noted during digestion of the dye-waste treated sludges.

An anonymous article in the *Surveyor* [14] describes the history of grease recovery from wool-scouring waste at Bradford, the English wool center. Wide fluctuations in the price obtained for the recovered grease are noted, with especially favorable prices in war time. Progress in the production of higher quality greases has widened the market.

A British patent granted to Jones, *et al* [117] recovers grease and soap from wool scouring wastes by using soluble salts of metals such as calcium to form insoluble soaps. Gaseous carbon dioxide and coagulants such as bentonite or alum are added, and the mixture is filtered. The filtrate may be re-used in scouring. The precipitate is extracted with benzene to recover grease, which is further purified by extraction to separate the true grease and the soaps.

Recovery of tin compounds from silk weighting liquors by filtration through activated alumina, solution of the adsorbed tin by sodium sulfide, and ultimate conversion of the tin to tin-chloride is described by Downie.[52]

Phillips [169] has found that kier liquors may be digested in the same manner as sludge, and will produce 4 to 5 volumes of a gas similar to sludge gas per volume of liquor. The B.O.D. of the liquor is reduced by 80 to 90 per cent in the process. It is planned to dispose of kier liquors at Durham, N. C., by piping them directly to the digesters of the sewage plant.

Tannery Waste. A detailed study of chrome tanning waste at a tannery in Waukegan, Ill., has been made by Harnly, Wagner and Swope.[85] The wastes are treated by sedimentation only, and the sludge is used to fill an adjacent marsh. A small portion of the waste, consisting of highly colored spent vegetable tanning extract, is lagooned on an old sludge bed, which removes the color by chemical action and filtration; the decolorized effluent is added to the general plant waste.

The strongly alkaline beam house waste, constituting about 75 per cent of the total flow, precipitates practically all of the chromium in the spent tanning liquor; the final waste is not toxic. The treatment process as described reduces the average suspended solids from 1,050 p.p.m. to 162 p.p.m., and the B.O.D. from 335 to 202 p.p.m. The lower B.O.D. of chrome tanning waste, as compared with that of vegetable tanning waste, does not appear to be due to the presence of toxic substances. Experiments on coagulation of the waste with ferrisul showed that 20 to 25 p.p.m. would yield an effluent 50 per cent lower in suspended solids than that obtained by sedimentation alone. Equations are developed for computing total and suspended solids, nitrogen, and B.O.D. in the wastes, in terms of the quantity of hides in process.

Treatment of waste from a sheepskin tannery on a pilot plant scale is reported by Eldridge.[57] The methods tried included plain sedimentation and lime precipitation; both fill-and-draw and continuous-flow methods were used. Eldridge recommended the fill-and-draw lime precipitation, using 14 lb. of lime per 1,000 gallons of waste. The sus-

pended solids were reduced from 1,980 p.p.m. to 497 p.p.m., and the B.O.D. from 1,630 to 823 p.p.m. The sludge volume was 5.3 per cent of the total waste volume, and the sludge contained 3.9 per cent of solids by weight. It was found that the breaks and fleshing machine wastes could be treated separately with 1.25 gallons of sulfuric acid per 1,000 gallons of waste, aerated, and skimmed to recover about 31 lb. of grease per 1,000 gallons. The commercial value of the process was not determined.

Winery Wastes. Hodgson and Johnston [95] have made a study of winery wastes, which included operation of a pilot plant, and final design of a pre-treatment plant to remedy the difficulties caused by these wastes at the Glenelg activated sludge plant of Adelaide, Australia. The wastes, consisting mainly of spent liquors and residues from final alcohol recovery by distillation, were found to amount to 200 to 250 (Imperial) gallons of waste containing 4,200 p.p.m. B.O.D. per ton of grapes processed. On the basis of the pilot plant experiments, the final treatment comprised the following steps: precipitation with about 1,200 p.p.m. of lime, flocculation, sedimentation, dilution of settled waste with plant effluent, adjustment of pH to 7.0–8.0 with acid, and treatment of the liquid on trickling filters in two stages, with a humus tank after the first stage. The effluent of the second stage is sent to the aeration tanks of the activated sludge plant, to be treated with the domestic sewage of the city. Because of the possibility of odor nuisances, covered sedimentation and flocculation tanks, and enclosed, forced-ventilation trickling filters were specified. The pilot plant experiments indicated that an effluent not exceeding 60 to 80 p.p.m. of B.O.D. could be produced, which would not be harmful to the activated sludge plant. Construction of a separate sewer from the winery to the pretreatment unit, located at the sewage plant, was avoided by providing storage at the winery, and discharging the winery wastes into the main sewer during the early morning period of low sewage flow. The resulting mixture of waste and sewage goes directly to the pretreatment plant.

Effect of Industrial Wastes on Sewage Treatment

General. Admission of industrial waste to sewers has received considerable attention in England. Garner [77] and Dart [44] have discussed the principles governing such admission as derived from the Public Health Acts of 1936 and 1937. Local authorities are directed to admit trade waste to the sewers at the request of the manufacturer, but are empowered to make rules covering period, rate, and quantity of discharge, temperature and pH value, exclusion of injurious wastes, and payment for admission. The legislation confers on manufacturers a prescriptive right to discharge, without payment, wastes equal in quantity and composition to those discharged into the sewers at any time during the year ending March 3, 1937. This provision has been a source of dissension and discussion. The City of Manchester [145] has had prepared a review of methods proposed and in use for assessing

charges for the handling of industrial wastes. Manchester is considering dividing wastes into three classes, A, B, and C, according to the difficulty of handling and treatment, and making a flat charge per 1,000 (Imperial) gallons of 2, 3 and 4 pence, respectively.

McKee [147] has described the ordinance put into effect by the Borough of Middlesex, N. J., governing the acceptance of industrial wastes in its sewers and sewage plant. A plant manufacturing glazed fruit was required to pre-treat its wastes by sedimentation, addition of lime to pH 7.0, and chlorination to 1 p.p.m. residual. A motion picture developing concern, with a waste having a chlorine demand of 5,000 p.p.m., was required to maintain a pH of 7.0, and a chlorine residual of 1.0 p.p.m. The plant subsequently reduced its high consumption of chlorine by recovering the sodium thiosulfate in the waste. A plant manufacturing Paris green and calcium arsenate was required to reduce the arsenic content of the waste to an amount which would not interfere with digestion. It was shown by experiment that digestion was stimulated by 0.05 g. of calcium arsenite in 400 ml. of mixed fresh and digested sludge, while 0.25 g. had no effect, and 1.25 g. retarded digestion. Paris green markedly retarded digestion in amounts as low as 0.05 g. in 400 ml. mixed sludge. This requirement was met by installing a filter press, and the recovery of the arsenic sludge was subsequently found to be profitable. The plants pay the borough at the rate of $33 per m.g. for disposing of their waste, in addition to fulfilling the pretreatment requirements.

The sewage plant at Greensboro, N. C., was designed to handle domestic sewage and textile wastes. After operating for six months on domestic sewage alone, textile wastes were admitted. This, according to Mengel,[148] necessitated a number of changes in the operation of the plant. The practice of adding excess activated sludge to the primary tank had be to abandoned, and the excess sludge pumped to the digesters separately from the primary sludge. Re-aeration of the return sludge was found necessary, and air consumption increased in the aeration tanks. The amount of ferric chloride required for sludge conditioning prior to filtration increased by 8 to 20 per cent, and the equipment for handling the filter cake was redesigned. At one time, excessive dumping of kier liquor raised the pH in the secondary tanks to 11.5, resulting in a cloudy effluent. The condition was remedied by treatment with acid. Close co-operation between the municipality and the textile plants is indicated as a necessity to prevent recurrence of such conditions. Other desirable changes indicated were a 50 per cent increase in primary tank and digester capacities, and provision for pH control of the influent, and for the thickening of excess activated sludge.

Activated Sludge. At the Glenelg activated sludge plant, according to Hodgson and Johnston,[95] the high carbohydrate content of untreated winery wastes, present to the extent of one per cent by volume in the sewage flow, resulted in the conversion of the activated sludge to something closely approaching a pure culture of filamentous organisms within one or two weeks. Sludge indices went as high as 500 to 600,

with complete breakdown of the plant. All conventional methods of controlling the growth of the filamentous organisms failed, and the only remedy was the construction of a pre-treatment plant to remove 75 to 80 per cent of the carbohydrates from the winery wastes. This plant is described in the section on industrial wastes.

Sedimentation. In discussing the paper of Ryan,[194] Bernhardt [25] described difficulties encountered at Fredonia, N. Y., where the flow of cannery wastes was at times double the sewage flow. Poor maintenance of screens in some of the canning plants resulted in accumulation of cannery solids on the bar screens of the sewage plant, and in an unsatisfactory effluent. Lime is applied to the Imhoff tanks two or three times per week during the canning season, at the rate of 100 lb. per dose. Prechlorination is also employed at this time. The maintenance of cannery screens is discussed.

Trickling Filters. Jenkins and Hewitt,[110] in an experimental study of the effect of chromium compounds in sewage on the operation of trickling filters, found that 1 p.p.m. of chromium in the form of potassium chromate had a slight effect, 10 p.p.m. appreciably reduced the quality of the effluent, and 100 p.p.m. reduced nitrification by 66 to 78 per cent, and produced an effluent containing twice as much organic matter as the effluent from the control filter. Heavy deposits of solid matter were noted in the upper part of the filter receiving 100 p.p.m. of chromium.

Stream Pollution

Foreign research in stream pollution has suffered considerably because of the war; a condition which is probably due to continue for some time. Less material is available because peace time work is out of joint and through failure to receive published material from blockaded countries. This effect is not yet apparent on American studies but will doubtless become so as more personnel and funds are diverted into national defense work. In contrast with a probable decrease in funds spent for pollution abatement, there is to be expected a sharp rise in the amount of industrial pollution due to increased production and the construction of new industrial plants.

National legislation for stream pollution abatement seems temporarily shelved with the failure of the Senate and House conferees to reach an agreement on their respective bills. The Congress did, however, authorize the Ohio and Potomac River compacts on July 1st. When finally ratified by all of the states concerned, these compacts should greatly facilitate and stimulate pollution abatement in their respective basins.

Shaw [199] has reported in some detail the work of the California Fish and Game Division in the control of pollution in that state. California laws pertaining to this division restrict pollution control to those substances deleterious to fish, plant or bird life and require proof of damage except for pollution by petroleums, acid, sawdust and certain specific types of factory wastes. The pollution control unit, charged

with enforcement of these laws, varies from eight to ten men. A large number of pollution cases have been settled by cooperative correction of conditions, but 210 cases have been prosecuted during the past five years with fines totalling $35,625.

In a progress report on chemical treatment of lakes and streams, the Wisconsin Committee on Water Pollution [244] discussed the origin and control of swimmers itch which was in all observed instances found to be due to penetration into man's skin of the larvae of schistosome flukes (flatworms). Control measures considered most feasible were: Control of the intermediate host, the snail, by chemical treatment with copper carbonate in some instances or by physical removal of snails in others; restriction of bathing in infested waters; destruction of the schistosome cercariae by vigorous rubbing with a towel immediately after bathing. They found that hard waters could be safely dosed with 80 p.p.m. of copper sulfate without serious danger to fish life. Inasmuch as the eggs of these flukes are excreted by mammal and avian hosts, the possible dispersion of infestation through sewage pollution becomes an interesting problem.

Improvement in the bacteriological quality of water in the Niagara River following the installation of intercepting sewers and sewage treatment at Buffalo, was studied by Symons and Simpson.[213] Treatment and disinfection of Buffalo sewage reduced the inflowing coliforms by 98.5 per cent and total bacteria by 97.5 per cent. Reductions in bacteria in the Niagara River below Buffalo averaged 97 per cent for coliform bacteria and 84 per cent for total bacterial counts. Bacterial after-growth following chlorination was not strongly evident and heavy peak loads at downstream filtration plants were eliminated. Symons and Torrey [214] have also published an analysis of the Buffalo River covering these same periods. Coliform organisms in this river were reduced 75 per cent and the B.O.D. 57 per cent. However, D.O. depletions in the Buffalo River during warm weather were not eliminated.

Thomas [219] has presented an extension of his "slope method" of analysis of B.O.D. results which is applicable to curves containing a positive lag and to the nitrification stage of B.O.D. curves. Application of this formulation to B.O.D. curves of sewage gave second stage reaction velocity constants 20–30 per cent of those for the first stage. Probable errors in computing second stage demands were thought to range from 15 to 65 per cent as against 5 to 25 per cent in calculating first stage demands.

Gallaher [76] reported oxygen depletion with resultant destruction of fish in the lower Fox River caused by the concentration by wind and subsequent decomposition of floating algae near the outlet of Lake Winnebago, the head of this river. Goudey [83] found measurements of solar ultra violet radiation to be more effective in forecasting algae growths than either water temperature or hours of sunshine.

Jones [119] has noted the absence of normal biological life in a Wales stream polluted by discharge from old zinc mines. He attributed this

to the zinc content of the stream water which averaged 0.7 to 1.2 p.p.m. The water also contained from a trace to 0.05 p.p.m. of lead.

Williams [238] has summarized the problems presented by salt water waste from oil fields in Texas. Disposal by dilution and by evaporation seriously threaten ground water supplies as these methods allow percolation into the absorption areas of ground water strata. Furnace evaporation pits leave unsolved the disposal of the crystal salt as refining of this salt to a saleable product has not been attempted. Pretreatment of the wastes by aeration, chemical treatment and filtration has made possible the continuous disposal of large quantities of salt water into a single injection well which may serve a hundred or more producing oil wells.

Young [248] has reported the effects of sewage treatment, industrial waste control, mine sealing and low flow augmentation upon the polluted surface water supplies of Western Pennsylvania. He found the downward trend of indices of pollution had recently been reversed but concluded that a uniform program for the completion of these pollution control measures was necessary to assure further improvements in river conditions.

The Interstate Sanitation Commission [106, 107, 108] has published an interesting series of reports on pollution in the New York City area. The first of these is a broad review tracing the history of the shellfish and fishing industries of that area and the effect of various factors, including pollution, upon these industries. While unrestrained exploitation caused the original decline of most species, recent conservation measures have not proven effective because most waters of this area are now unfit for fish life. Pollution abatement has already improved conditions to some extent and should, with proper conservation, restore fishing in the area. The second report of this Committee [107] deals with tides and currents and the basic causes of the hydraulic phenomenon observed in the tidal waters of this area. Chemical and bacteriological data and field and laboratory methods are included in the third section.[108]

Improvement in the sanitary condition of the Mississippi River following treatment of sewage from the Minneapolis-St. Paul Sanitary District is discussed in a report [151] from that District. In the section of river above the new treatment plant outfall, pollution has been largely eliminated, but below this point D.O. levels have averaged under 2 p.p.m. during the three months, July, August and September. Treatment of additional sewage and industrial wastes in plants now under construction is expected to improve this condition.

Eriksen and Townsend [63] have reported an extensive study of the pollution of Gray's Harbor, Washington, by sewage and sulfite pulp wastes. They found these wastes were shuttled back and forth on the average by 80 tidal cycles—42 days—before passing out to sea. Considerable stratification of fresh water was observed during high river stages of streams tributary to this harbor with the position of a given chloride gradient differing by as much as ten miles between winter high

and summer low flows. Fish deaths could be explained by D.O. depletions but existing concentrations of sulfite pulp waste were found experimentally to be a contributing factor in the susceptibility of fish to low concentrations of D.O. Sharp peaks in dissolved oxygen occurred when the local pulp mill, producing 260 tons of pulp per day, was closed down for short intervals and it was concluded from this and other evidence that fish deaths were due largely to the oxygen demand of the wastes from this plant.

BIBLIOGRAPHY

1. Allison, S. L., *Mun. San.*, **11**, 279 (1940).
2. Anderson, C. G., *Amer. City*, **55**, 68 (July, 1940).
3. Anderson, G. C., *Water Wks. and Sew.*, **87**, 44 (1940).
4. Anon., *Amer. City*, **55**, 42 (Dec., 1940).
5. Anon., *Amer. City*, **55**, 63 (Dec., 1940).
6. Anon., *Amer. City*, **55**, 66 (Sept., 1940).
7. Anon., *Eng. News-Record*, **125**, 402 (1940).
8. Anon., *Eng. News-Record*, **125**, 745 (1940).
9. Anon., *Eng. News-Record*, **124**, 858 (1940).
10. Anon., *Sew. Wks. Eng.*, **11**, 603 (1940).
11. Anon., *Sew. Wks. Eng.*, **11**, 611 (1940).
12. Anon., *Pub. Wks.*, **71**, No. 7, 28 (1940).
13. Anon., *Pub. Wks.*, **71**, No. 10, 16 (1940).
14. Anon., *Surveyor*, **97**, 27 (1940).
15. Anon., *Surveyor*, **98**, 209, 225 (1940).
16. Babitt, H. E., and Caldwell, D. H., Univ. Ill. Eng. Exp. Sta. *Bull.* 319 (1939).
17. Bardwell, E. E., *Pub. Wks.*, **71**, No. 5, 16 (1940).
18. Barritt, N. W., *Ann. Appl. Biol.*, **27**, 151 (1940).
19. Barritt, N. W., *Inst. Sew. Purif. Jour. and Proc.*, Part I, p. 109 (1939).
20. Beard, P. J., *Amer. Jour. Pub. Health*, **30**, 1077 (1940).
21. Bell, E. A., *Water Wks. and Sew.*, **87**, 163 (1940).
22. Benas, B., THIS JOURNAL, **12**, 81 (1940).
23. Berg, E. J. M., *Proc.* 21st Texas Waterworks and Sewage Short School, p. 102 (1939).
24. Berl, E., and Koerber, W., *Ind. Eng. Chem. Anal. Ed.*, **12**, 245 (1940).
25. Bernhardt, C. J., THIS JOURNAL, **12**, 105 (1940).
26. Bloodgood, D. E., THIS JOURNAL, **12**, 1085 (1940).
27. Bogert, C. L., *Mun. San.*, **11**, 82 (1940).
28. Bosch, W. C., and Brown, B. B., *Jour. Opt. Soc. Am.*, **29**, 466 (1939).
29. Breuchaud, J. R., U. S. Pat., 2,222,651 (Nov. 26, 1940).
30. Burger, A. A., *Amer. City*, **55**, 43 (1940).
31. Burger, A. A., *Mun. San.*, **11**, 85 (1940).
32. Butterfield, C. T., *Jour. Bact.*, **39**, 527 (1940).
33. Casey, A. C., and Aymond, B. J., *Science*, **91**, 17 (1940).
34. Chlorine Institute, *Sew. Wks. Eng.*, **11**, 555 (1940).
35. Christinson, C. W., and Lavine, I., *Trans. Amer. Inst. Chem. Eng.*, **36**, 71 (1940).
36. Christophersen, J., *Molkerei-Zeitung*, **54**, 245 (1940).
37. Cleary, E. J., THIS JOURNAL, **12**, 1098 (1940).
38. Cohn, M. M., *Ibid.*, **12**, 1126 (1940).
39. Conn, H. J., and Conn, J. E., *Jour. Bact.*, **39**, 99 (1940).
40. Corbet, A. S., and Wooldridge, W. R., *Biochem. Jour.*, **34**, 1015 (1940).
41. Consoer, G. O., and Townsend, D. W., *Eng. News-Record*, **125**, 221 (1940).
42. Cranfield, H. T., *Empire Jour. Exp. Agric.*, **7**, 319 (1939).
43. Crawford, A. B., and Frank, A. H., *Civil Eng.*, **10**, 495 (1940).
44. Dart, R., *Surveyor*, **97**, 145 (1940).
45. Datzko, V. G., *Jour. Applic. Chem.* (Russ.), **13**, 384 (1940); also British Chem. and Parm Abst. B, p. 766, Oct. (1940).

46. Dickinson, D., *Jour. Soc. of Chem. Ind. Trans. and Comm.*, **59**, 78 (1940).
47. Dickinson, D., *Jour. Soc. Chem. Ind. Trans. and Comm.*, **59**, 257 (1940).
48. Dixon, R. M., *Water Wks. and Sew.*, **87**, 245 (1940).
49. Donaldson, W., *Water Wks. and Sew.*, **87**, 583 (1940).
50. Dowling, D. L., *Water Wks. and Sew.*, **87**, 440 (1940).
51. Downes, F. A., U. S. Pat. 2,195,408 (April 2, 1940).
52. Downie, C. C., *Silk and Rayon*, **13**, 962 (1939).
53. Durdin, A. C., Jr., U. S. Pat., 2,202,772 (May 28, 1940).
54. Eddy, H. P., Jr., and Fales, A. L., THIS JOURNAL, **12**, 1011 (1940).
55. Edwards, G. P., THIS JOURNAL, **12**, 1077 (1940).
56. Eggertson, T., *Proc.* N. J. Sew. Wks. Assn., **25**, 200 (1940).
57. Eldridge, E. F., Mich. Eng. Exp. Sta. *Bull.* **87** (1939).
58. Eldridge, E. F., *Sew. Wks. Eng.*, **11**, 599 (1940).
59. Eliassen, R., *Mun. San.*, **11**, 235 (1940).
60. Ellms, J. W., THIS JOURNAL, **12**, 625 (1940).
61. Ellsworth, S. M., *New England Jour. of Med.*, **55**, 222 (1940).
62. Emerson, C. A., *Sew. Wks. Eng.*, **11**, 483 (1940).
63. Eriksen, A., and Townsend, L. D., Washington State Pollution *Bull.* No. 2 (June, 1940).
64. Faber, H. A., THIS JOURNAL, **12**, 313 (1940).
65. Fair, G. M., *Ibid.*, **12**, 1033 (1940).
66. Fink, H., and Lechner, R., *Zeitschrift Spiritsindustrie*, **62**, 251 (1939).
67. Fischer, A. J., *Water Wks. and Sew.*, **87** (1940).
68. Fischer, A. J., U. S. Pat. 2,190,598 (Feb. 13, 1940).
69. Fischer, A. J., and Hillman, A., THIS JOURNAL, **12**, 280 (1940).
70. Flower, G. E., *Water Wks. and Sew.*, **87**, 528 (1940).
71. Foster, C., *Ibid.*, **87**, 115 (1940).
72. Frazier, R. W., *Sew. Wks. Eng.*, **11**, 324 (1940).
73. Frazier, R. W., *Ibid.*, **11**, 598 (1940).
74. Fuhrman, R. E., THIS JOURNAL, **12**, 1087 (1940).
75. Funk, J. B., *Mun. San.*, **11**, 245 (1940).
76. Gallaher, W. U., *Jour. Amer. Water Wks. Assn.*, **32**, 1165 (1940).
77. Garner, J. H., *Surveyor*, **97**, 315 (1940).
78. Gascoigne, G. B., *Proc.* 25th Ann. Meeting of N. J. Sew. Wks. Assn., p. 82 (Mar., 1940).
79. Gehm, H. W., *Proc.* Penn. Sew. Wks. Assn. (1940).
80. Gibbons, M. M., *Jour. Amer. Water Wks. Assn.*, **32**, 465 (1940).
81. Gibbons, M. M., *Water Wks. and Sew.*, **87**, 231 (1940).
82. Gilcrease, F. W., and Sanderson, W. W., THIS JOURNAL, **12**, 73 (1940).
83. Goudey, R. F., *Eng. News-Record*, **124**, 525 (1940).
84. Griffine, A. E., THIS JOURNAL, **12**, 307 (1940).
85. Harnly, J. W., Wagner, F. R., and Swope, H. G., *Ibid.*, **12**, 771 (1940).
86. Harris, E. E., *Ind. and Eng. Chem.*, **32**, 1049 (1940).
87. Hartz, N. W., THIS JOURNAL, **12**, 147 (1940).
88. Hecking, J. F., *Ibid.*, **12**, 132 (1940).
89. Heist, E. F., *Sew. Wks. Eng.*, **11**, 330 (1940).
90. Heukelekian, H., and Heller, A., *Jour. Bact.*, **40**, 547 (1940).
91. Heukelekian, H., and Ingols, R. S., THIS JOURNAL, **12**, 694 (1940).
92. Heukelekian, H., and Littman, M. L., THIS JOURNAL, **12**, 260 (1940).
93. Heukelekian, H., and Schulhoff, H., *Sew. Wks. Eng.*, **11**, 592 (1940).
94. Hewitt, C. H., *Surveyor*, **98**, 163 (1940).
95. Hodgson, H. J. N., and Johnston, J., THIS JOURNAL, **12**, 321 (1940).
96. Howard, G. C., *Chem. and Met. Eng.*, **46**, 618 (1939).
97. Howson, C. E., *Water Wks. and Sew.*, **87**, 217 (1940).
98. Howson, L. R., *Sew. Wks. Eng.*, **11**, 413 (1940).
99. Hubbell, G. E., *Eng. News-Record*, **124**, 645 (1940).
100. Humphreys, W., and Rawn, A. M., *Water Wks. and Sew.*, **87**, 341 (1940).
101. Hurwitz, E., and Williamson, F. W., THIS JOURNAL, **12**, 562 (1940).
102. Imhoff, K., and Fair, G. M., "*Sewage Treatment*," John Wiley and Sons (1940).

103. Ingols, R. S., THIS JOURNAL, **12**, 862 (1940).
104. Ingols, R. S., and Heukelekian, H., *Ibid.*, **12**, 849 (1940).
105. Ingols, R. S., and Heukelekian, H., *J. Ind. Eng. Chem.*, **32**, 401 (1940).
106. Interstate Sanitation Commission Report, New York City, Jan., 1939.
107. Interstate Sanitation Commission Report, New York City, Mar., 1940.
108. Interstate Sanitation Commission Report, New York City, Apr., 1940.
109. Jenkins, S. H., *Public Works, Roads and Transport Congress* (Dec., 1939), London.
110. Jenkins, S. H., and Hewitt, C. H., *J. Soc. Chem. Ind. Trans.*, **59**, 41 (1940).
111. Jenkins, S. H., and Wilkinson, R., *J. Soc. Chem. Ind. Trans. and Comm.*, **59**, 125 (1940).
112. Jenks, H. N., *Sew. Wks. Eng.*, **11**, 595 (1940).
113. Jenks, H. A., Personal Communication to E. J. Cleary (Dec., 1940).
114. Johnson, H. O., and Jablon, F. M., *Water Wks. and Sew.*, **87**, 135 (1940).
115. Jones, A. T., *J. Ind. Hyg. Tox.*, **22**, 233 (1940).
116. Jones, F. W., THIS JOURNAL, **12**, 1106 (1940).
117. Jones, G., and McGregor and Sons, Ltd., British Pat. 508,371 (1939).
118. Jones, G. W., Miller, W. E., and Campbell, J., *Bull.* R. I. 3496, U. S. Bureau of Mines (Feb., 1940).
119. Jones, J. R. E., *Ann. Appl. Biol.*, **27**, 368 (1940).
120. Keefer, C. E., "Sewage Treatment Works," McGraw-Hill (1940).
121. Keefer, C. E., and Kratz, H., Jr., THIS JOURNAL, **12**, 477 (1940).
122. Keefer, C. E., and Kratz, H., Jr., *Ibid.*, **12**, 738 (1940).
123. Keeth, G., *Trans. Amer. Soc. Mech. Eng.*, **61**, 679 (1939).
124. Kempf, E. J., and Soule, M. H., *Proc. Soc. Exp. Biol. and Med.*, **44**, 431 (1940).
125. Killeffer, D. W., *Ind. Eng. Chem.*, **33**, 9 (1941).
126. Kirkpatrick, J. W., THIS JOURNAL, **12**, 341 (1940).
127. Kivel, W. A., and Lund, N. B., *Water Wks. and Sew.*, **87**, 176 (1940).
128. Klegerman, M. H., THIS JOURNAL, **12**, 315 (1940).
129. Knowlton, W. T., *Sew. Wks. Eng.*, **11**, 435 (1940).
130. Koebig, A. H., Jr., THIS JOURNAL, **12**, 895 (1940).
131. Kramer, S. D., Gilliam, A. G., and Milner, J. G., *Pub. Health Repts.*, **54**, 1914 (1939).
132. Krum, H. J., THIS JOURNAL, **12**, 143 (1940).
133. Lackey, J. B., and Wattie, E., *Ibid.*, **12**, 669 (1940).
134. Langford, L. L., *Ibid.*, **12**, 128 (1940).
135. Lazenby, A. J., *Eng. News-Rec.*, **124**, 801 (1940).
136. Levine, M., THIS JOURNAL, **12**, 1062 (1940); also *Proc.* 25th Ann. Meeting N. J. Sew. Wks. Assn., 27 (1940).
137. *Link-Belt News*, Jan., 1940. See also *Eng. News-Rec.*, **124**, 398 (1940).
138. Littman, M. L., THIS JOURNAL, **12**, 685 (1940).
139. Lloyd, L. L., Graham, J. F., and Reynoldson, T. B., *Ann. Appl. Biol.*, **27**, 122 (1940).
140. Lovell, T. R., *Sew. Wks. Eng.*, **11**, 492 (1940).
141. Lumb, C., *Surveyor*, **98**, 256 (1940).
142. Lumb, C., and Barnes, J. P., *Surveyor*, **98**, 239 (1940). Discussion in *Surveyor*, **98**, 274 (1940).
143. Lynch, J. T., Milliken, H. E., McInerney, G. J., and Denise, W. D., THIS JOURNAL, **12**, 919 (1940).
144. Mallory, E. B., *Water Wks. and Sew.*, **87**, 102 (1940).
145. Manchester, England, River Dept., Annual Report for Year Ending March 31, 1939.
146. McCalla, T. M., *Jour. Bact.*, **40**, 23 (1940).
147. McKee, W. J., *Proc.* 25th Annual Meeting, N. J. Sewage Wks. Assn., p. 183, 1940.
148. Mengel, C. W., *Civil Eng.*, **10**, 267 (1940).
149. Mihaeloff, S., *Jour. Pharmacie et de Chemie*, **30**, 13 (1939).
150. Miljevic and others, *Mun. San.*, **11**, 92 (1940).
151. Minneapolis-St. Paul Sanitary District, Seventh Annual Report (1939).
152. Mohlman, F. W., THIS JOURNAL, **12**, 182 (1940).
153. Mohlman, F. W., *Proc.* 25th Annual Meeting, N. J. Sewage Wks. Assn., p. 106, 1940.
154. Mohlman, F. W., *Water Wks. and Sew.*, **87**, 47 (1940).
155. Mohlman, F. W., *Ibid.*, **87**, 93 (1940).

156. Mom, C. P., and Schaeffer, C. O., THIS JOURNAL, **12**, 715 (1940).
157. Montagna, S. D., *Ibid.*, **12**, 108 (1940).
158. Mueller, E. F., *Ind. Eng. Chem. Anal. Ed.*, **12**, 171 (1940).
159. Müller, R. H., *Ibid.*, **12**, 10, 571 (1940).
160. Murray, K. A., *Sewage Purification*, **2**, 21 (1940).
161. Nagel, W. B., Report, Ohio Conf. Sew. Treat., **13**, 104 (1939).
162. Nichols, C. M., *Proc.* 25th Annual Meeting, N. J. Sewage Wks. Assn., p. 67, 1940.
163. Nichols, R. D., *Water Wks. and Sew.*, **87**, 190 (1940).
164. Neuffer, H. C., *Sew. Wks. Eng.*, **11**, 346 (1940).
165. Palmer, J. R., *Proc.* 13th Annual Ohio Conference on Sewage Treatment.
166. Paul, J. R., Trask, J. D., and Cullotta, S. C., *Science*, **90**, 258 (1939).
167. Pearse, L., THIS JOURNAL, **12**, 181 (1940).
168. Petersen, K., U. S. Pat. 2,198,727 (April 30, 1940).
169. Phillips, C. M., *Proc.* 25th Annual Meeting, N. J. Sewage Wks. Assn., p. 58, 1940.
170. Pomeroy, R., *Water Wks. and Sew.*, **81**, 33 (1940).
171. Poor, E. N., *Paper Trade Jour.*, **110**, TAPPI Sect. 143 (1940).
172. Porges, R., Miles, H. J., and Baity, H. G., THIS JOURNAL, **12**, 601 (1940).
173. Porges, R., Miles, H. J., and Baity, H. G., *Ibid.*, **12**, 956 (1940).
174. Potts, C., and Wigley, C. G., U. S. Pat. 2,206,851 (July 2, 1940).
175. Reynoldson, T. B., *Ann. Appl. Biol.*, **26**, 782 (1939).
176. Riker, I. R., *Mun. San.*, **11**, 92 (1940).
177. Riley, K. W., *Pub. Wks.*, **71**, 12 (1940).
178. Roeder, G. H., U. S. Pat. 2,209,613 (July 30, 1940).
179. Rogers, H. T., *J. Soc. Chem. Ind.* B, **59**, 34 (1940).
180. Rokuro, A., and Jinnosuke, C., *Mitt. Mediz. Akad. Kioto*, **27**, 389 (1939).
181. Round Table, *Mun. San.*, **11**, 25 (1940).
182. Round Table, *Sew. Wks. Eng.*, **11**, 520 (1940).
183. Rouse, H., U. S. Dept. of Agr. Soil Conservation Service, July 1939.
184. Ruchhoft, C. C., and Moore, W. A., *Ind. Eng. Chem., Anal. Ed.*, **12**, 711 (1940).
185. Ruchhoft, C. C., Ettinger, M. B., and Walker, W. W., *Ind. and Eng. Chem.*, **32**, 1394 (1940).
186. Ruchhoft, C. C., Kachmar, J. F., and Moore, W. A., THIS JOURNAL, **12**, 27 (1940).
187. Ruchhoft, C. C., Kachmar, J. F., and Placak, O. R., *Ibid.*, **12**, 485 (1940).
188. Rudolfs, W., *Mun. San.*, **11**, 57 (1940).
189. Rudolfs, W., *Eng. News-Record*, **125**, 706 (1940).
190. Rudolfs, W., *Water Wks. and Sew.*, **87**, 575 (1940).
191. Rudolfs, W., THIS JOURNAL, **12**, 1051 (1940).
192. Rudolfs, W., and Heinemann, B., *Ibid.*, **12**, 18 (1940).
193. Rudolfs, W., and West, L. E., *Ibid.*, **12**, 60 (1940).
194. Ryan, W. A., *Ibid.*, **12**, 99 (1940).
195. Sawyer, C. N., *Ind. and Eng. Chem.*, **32**, 1469 (1940).
196. Sawyer, C. N., THIS JOURNAL, **12**, 3 (1940).
197. Sawyer, C. N., *Ibid.*, **12**, 244 (1940).
198. Shapiro, R., *Water Wks. and Sew.*, **87**, 44 (1940).
199. Shaw, P. A., THIS JOURNAL, **12**, 947 (1940).
200. Shibata, S., *J. Soc. Chem. Ind.*, Japan, **42**, Sep. binding 338 (1939).
201. Shibata, S., *J. Soc. Chem. Ind.*, Japan Suppl. Bind., **42**, 257 (1939).
202. Smith, H. G., and Studley, H. G., THIS JOURNAL, **12**, 745 (1940).
203. Sorgato, I., *Chim. e l'Ind.*, **22**, 1 (1940).
204. Sperry, W., *Pub. Wks.*, **71**, 28 (1940).
205. Spulnik, J. B., Stephenson, R. E., Caldwell, W. E., and Bollen, W. B., *Soil Sci.*, **49**, 37 (1940).
206. Stone, R. W., White, A. G. C., and Fenske, M. R., *Jour. Bact.*, **39**, 91 (1940).
207. Strahan, J., *Mun. San.*, **11**, 142 (1940).
208. Strawinski, R. J., and Stone, R. W., *Jour. Bact.*, **40**, 461 (1940).
209. Streander, P. B., *Water Wks. and Sew.*, **87**, 351, 422, 493 (1940).
210. Streander, P. B., U. S. Pat. 2,188,647 (Jan. 30, 1940).

211. Sylliassen, M. O., *Civil Eng.*, **10**, 575 (1940).
212. Symons, G. E., and Kin, S. R., *Water Wks. and Sew.*, **87**, 547 (1940).
213. Symons, G. E., and Simpson, R. W., *J. Amer. Water Wks. Assn.*, **32**, 1529 (1940).
214. Symons, G. E., and Torrey, W. L., THIS JOURNAL, **12**, 586 (1940).
215. Symposium, *Water Wks. and Sew.*, **87**, 83 (1940); also *Mun. San.*, **11**, 148 (1940).
216. Synder, R. F., *Sew. Wks. Eng.*, **11**, 16 (1940).
217. Tark, M. B., and Gilbert, J. J., *Water Wks. and Sew.*, **87**, 186 (1940).
218. Texas State Department of Health, Bureau of Sanitary Engineering. Reports on Citrus Wastes (1940).
219. Thomas, H. A., THIS JOURNAL, **12**, 504 (1940).
220. Tomlinson, G. H., and Wilcoxson, L. S., *Paper Trade Journal*, **110**, TAPPI Section 209 (1940).
221. Trask, J. D., Vignec, A. J., and Paul, J. R., *Proc. Soc. Exper. Biol. Med.*, **38**, 147 (1938).
222. Tripp, E. H., *Chem. and Ind.*, **58**, 1102 (1939).
223. Turner, J. R., *Water Wks. and Sew.*, **87**, 527 (1940).
224. VanKleeck, L. W., *Pub. Wks.*, **71**, No. 6, 20 (1940).
225. Veatch, F. W., *Eng. News-Record*, **124**, 24 (1940).
226. Veatch, F. M., *Mun. San.*, **11**, 8 (1940).
227. Velzy, C. R., Johnson, J. W., and Symons, G. E., THIS JOURNAL, **12**, 907 (1940).
228. Vermette, F., *Sew. Wks. Eng.*, **11**, 569 (1940).
229. Viehl, K., *Zeitschrift F. Hyg. und Infekionskrankheiten*, **122**, 135 (1940).
230. Vitek, Coll, *Czech Comm.*, **7**, 537 (1935); also *Chimie et Industrie*, **29**, 215 (1933).
231. Warrick, L. F., Joint Report, Wisconsin State Committee on Water Pollution, State Board of Health, and Green Bay Metropolitan Sewerage District, 1938–39.
232. Water Pollution Research Board, Report for Year Ended June 30, 1939.
233. Watson, D. M., *J. Inst. Civil Eng.* (Eng.), Dec., 1939.
234. Weber, C. G., *Water Wks. and Sew.*, **87**, 309 (1940).
235. Weber, C. G., *Proc.* of the 14th Ann. Conference of the Maryland-Delaware Water and Sewerage Association (1940).
236. West, E. S., and Christianson, J., *J. Bio. Chem.*, **132**, 681 (1940).
237. Wheeler, W. W., *Eng. News-Rec.*, **123**, 842 (1940).
238. Williams, B. F., *Water Wks. Eng.*, **93**, 1165 (1940).
239. Williams, E., *Sewage Purification*, **2**, No. 5, 125 (1940).
240. Williams, E., *J. Soc. Chem. Ind. Trans. and Comm.*, **59**, 39 (1940).
241. Wilson, H., and Hamill, E., *The Inst. of Sewage Purification, Jour. and Proc.*, Part I, 39 (1939).
242. Wilson, H., and McLachlan, J. A., THIS JOURNAL, **12**, 557 (1940).
243. (Greater) Winnipeg Sanitary District, *Ibid.*, **12**, 628 (1940).
244. Wisconsin Committee on Water Pollution Progress Report, State of Wisconsin, July, 1939.
245. Wooldridge, W. R., and Corbet, A. D., *Biochem. Jour.*, **34**, 1026 (1940).
246. Wyllie, G. F., THIS JOURNAL, **12**, 760 (1940).
247. Yancey, H. F., Zane, R. E., Wood, W., and Cannarella, J. T. H., *Bull.* R. I. 3494, U. S. Bureau of Mines, 1940.
248. Young, C. H., *J. Amer. Water Wks. Assn.*, **32**, 1867 (1940).
249. Zobell, C. E., *Biol. Bull.*, **78**, 388 (1940).
250. Zobell, C. E., and Stadler, J., *J. Bact.*, **39**, 307 (1940).

CHEMICAL COAGULATION OF SEWAGE*

XII. IRON SALTS AND LIME

By Harry W. Gehm

Associate, Dept. of Water and Sewage Research, New Brunswick, N. J.

To date numerous plant and laboratory scale trials with various coagulants have been made. Such trials have been stimulated by competing chemical manufacturers and by engineers desirous of determining what chemical or combination thereof will produce satisfactory and economical results at particular plants. On examination of the results of such studies it is evident that some chemicals work better on a particular sewage than do others. This is due to variations in character of sewage such as age, strength, septicity, kind and amount of dissolved matter, and in some cases the presence of industrial wastes. No general laws can be set down as to comparative coagulating power of different chemical reagents. Nevertheless, if a number of sewages react in a similar manner general facts, subject to variation under peculiar conditions, can be determined.

Methods

It is the purpose of this paper to demonstrate the relative effectiveness of the processes of chemical treatment of sewage employing iron salts. Since industrial wastes cause the greatest variations in effectiveness of different chemicals their presence was avoided by selecting sewages of mainly domestic origin and containing little if any of other types of waste. The methods employed were similar to those discussed in former papers of this series (1, 2), except where otherwise stated. The chemicals used were of technical grade and special compounds such as chlorinated copperas were prepared.

Procedure

The iron compounds commonly used for coagulating sewage are ferric chloride, ferric sulfate, and chlorinated copperas (3). Untreated copperas has been used in conjunction with lime and aeration (4), but this process did not gain headway due to the poor settling characteristics of the floc formed. Laboratory trials have been made with iron sols of various types (5). These compounds proved to be of more theoretical than practical interest. Much attention has been given to the preparation of ferric coagulants from the action of chlorine on iron, particularly in the southwest where the ferric salts demand a high price (6, 7, 8). The solution of iron by electrolyzing the metal itself was the basis of several patents but this procedure has proven too

* Journal Series Paper, N. J. Agricultural Experiment Station, Dept. Water and Sewage Research, New Brunswick, N. J.

costly. Ferrites have also been tried on a laboratory scale, but their high alkalinity and sodium content limit their practicability.

In comparing the relative coagulating ability of iron salts only the three most used compounds were employed. The relative clarifying power of ferric chloride, ferric sulfate and chlorinated copperas were determined over a pH range from 2.5 to 10.0. The pH adjustments were made with sulfuric acid and lime. When acid was used it was added after the coagulant, and lime, before coagulant addition. These procedures have been shown to produce the best results with iron salts (9). Six different domestic sewages were treated over the pH range with a dosage of iron which would give practically complete clarification at the optimum pH values. The dosage employed in all cases was 10 p.p.m. on the iron basis. Another series of tests was made to determine the relative degree of clarification obtainable by graduated dosages of the three coagulants without pH adjustment.

Iron Salts

Comparisons with pH adjustment are shown in Fig. 1, where the curves obtained for six sewages are presented as averages. The trends



Fig. 1.—The relative clarifying power of three iron compounds.

of the data obtained were sufficiently similar to allow averaging. Ferric chloride yielded somewhat better clarification than the other two compounds, with the exception of the results in pH ranges 5.0 to 7.0 and 2.5 to 3.0. In the former range ferric sulfate was slightly better while in the latter little difference between the three chemicals was noticeable. However, clarification by the small coagulant dosage was not great in the 5.0 to 7.0 pH range and the comparison of graduated coagulant dosages without adjustment (Table I) is probably better. Here the

pH was between 6.5 and 7.0 and inspection of the data shows that ferric chloride gave the best clarification. In general the order of effectiveness of the three chemicals was ferric chloride, chlorinated copperas and ferric sulfate.

TABLE I.—*Clarification Obtained by Equal Dosages of Three Ferric Salts*

Sewage	P.p.m. Iron	Ferric Chloride	Chlorinated Copperas	Ferric Sulfate	P.p.m. Turbidity Remaining Greater Than with $FeCl_3$	
	P.p.m. Turbidity Remaining				Chlorinated Copperas	Ferric Sulfate
Highland Park	5	58	67	73	9	15
	10	29	25	34	4	9
	15	5	9	20	4	11
Madison-Chatham	10	93	105	111	11	18
	15	44	49	53	4	9
	20	15	23	27	8	12
Morristown	15	51	63	64	12	13
	20	23	35	39	12	16
	25	5	18	19	13	14
South River	25	121	146	158	25	37
	30	36	42	49	4	13
	35	14	19	24	4	10
Princeton	5	142	161	160	19	18
	10	110	143	136	33	26
	15	39	55	48	16	9
Plainfield	10	71	72	84	1	13
	15	50	58	69	8	19
	20	33	36	47	3	14
				Average	10	16

Mixtures of the salts were also compared as to clarifying value. Ferric sulfate, ferric chloride and chlorinated copperas were first applied alone in concentrations of 20, 25, and 30 p.p.m. of iron and the degree of clarification measured. Solutions of equivalent strength (on the iron basis) of ferric chloride and ferric sulfate in equal proportions, ferric chloride and chlorinated copperas, and ferric sulfate and chlorinated copperas, were prepared. Portions of these solutions were applied to the sewage in the same dosages (on the iron basis) as used with the single salts alone.

The clarification was measured in each case. The data obtained are presented in Table II. It does not appear from these figures that combinations of these salts exceed to any measurable extent the clarifying power of a single salt when the iron content is used as the basis for their addition.

TABLE II.—*Clarifying Activity of Mixed Ferric Salts*

P.p.m. Iron	20	25	30
	Turbidity Remaining		
Ferric Chloride	60	36	10
Ferric Sulfate	63	48	23
Chlorinated Copperas	62	36	15
Ferric Chloride and Ferric Sulfate	54	38	15
Ferric Chloride and Chlorinated Copperas	68	32	10
Ferric Sulfate and Chlorinated Copperas	61	34	15

In order to determine if the anions of the salts were responsible for the differences in the clarifying power of the iron salts, titration curves on sewage were made employing 0.1 N solutions of sulfuric and hydrochloric acids. It was thought that possibly the chloride ion was more effective in reacting with the sewage materials, thus effecting coagulation. If this assumption is correct differences in the titration curves with the two acids might be shown.

Five samples of sewage were titrated electrometrically with both acids. As the results were similar in every case one typical result is shown in Fig. 2. Practically no difference in the titration curves obtained with the two acids are observed as far as pH changes are concerned.



FIG. 2.—Titration curves of sewage with hydrochloric and sulfuric acids.

Since the acids themselves have definite clarifying power the question of the relative effect of sulfuric and hydrochloric acids in equivalent quantities arises. To determine the relative effects dosages of both acids were added to separate samples of the same sewage, so that pH values of 6.8, 6.0, 5.0, 4.0, 3.0 and 2.0 were obtained. The samples were flocculated, settled and the turbidity remaining measured.

The results were plotted as shown in Fig. 3. Examination of this graph reveals the fact that hydrochloric acid is more effective in clarifying sewage than sulfuric acid.



FIG. 3.—Relative clarifying power of hydrochloric and sulfuric acids.

IRON SALTS AND LIME

It is well known that the amount of ferric coagulants is reduced when lime is also used. Fig. 4 shows the possible reduction of iron salts by application of lime. This curve represents the average results obtained for fourteen different sewages. Relatively small quantities of lime (20 to 40 p.p.m.) did not effect appreciable reduction (4 p.p.m.) of $FeCl_3$. After a pH of 8.0 was reached, small additional quantities of lime effected a considerable reduction. Forty p.p.m. more of lime accounted for 10 p.p.m. lower iron dosage. Increases of lime over a total of 80 p.p.m. allowed a further reduction of but 2 p.p.m. of iron.

Whether the effectiveness of lime in clarifying sewage is due to the calcium or the hydroxyl ion has not been demonstrated. The experiments described below were conducted to study this question.

Liter portions of sewage were treated with increasing dosages of calcium hydroxide so that a series of pH values ranging from 7.0 to 10.5 was obtained. A similar set of liter samples were treated with sodium hydroxide to give the same range of pH values as obtained with



FIG. 4.—The clarification of sewage with lime and ferric chloride.

the calcium hydrate. All samples were flocculated, settled, and the degree of clarification measured by the turbidity remaining in the supernatant. This procedure was repeated with three different sewages.

The average of the four series of results are graphically shown in Fig. 5. No appreciable degree of clarification was obtained with sodium



FIG. 5.—The clarification of sewage with sodium hydroxide as compared to calcium hydroxide.

hydroxide. At high pH values (10.0 and above) a small degree of dispersion took place. With the calcium hydroxide the sewage clarified to a considerable degree. The clarification increased in general as the lime dosage increased. The hydroxyl ion alone, therefore, is not the factor involved in clarification of sewage.

The same procedure was repeated using combinations of caustic soda and ferric chloride covering a pH range of 7.0 to 10.0. Two dosages of ferric chloride were used, namely 5 and 15 p.p.m. of iron. As shown in Table III no additional clarification resulted from the use

TABLE III.—*Effect of NaOH on Clarification with Ferric Chloride*

Adjusted with NaOH to pH	P.p.m. Iron ($FeCl_3$)	
	5	15
	P.p.m. Turbidity	Remaining
7.0	80	59
7.6	83	55
8.1	86	54
8.5	80	59
9.0	86	60
9.6	84	56
10.0	83	65

of caustic soda with either dosage of ferric chloride. Neither did any noticeable degree of dispersion result from the application of the caustic.

The effect of the calcium ion was then investigated. A sample of sewage was divided into four series of six one-liter aliquots. In each series the liter samples were treated in order with 0, 20, 40, 60, 80 and 100 p.p.m. of Ca as calcium chloride. To one series 5 p.p.m. of Fe as ferric chloride was added, to the second 10 p.p.m., to the third 15 p.p.m., and to the fourth, 20 p.p.m. The samples were flocculated, settled, and turbidity determined on the supernatants.

The clarification curves resulting from the addition of calcium chloride (illustrated in Fig. 6) show definitely that calcium chloride aids in the clarification of sewage when added in conjunction with an iron salt.

Sodium chloride does not act in the same manner as calcium chloride. This is demonstrated by the data presented in Table IV. It is noted that as much as 500 p.p.m. of sodium chloride did not effect clarification to any appreciable extent.

It has been stated that the clarifying effect of lime used in conjunction with iron salts was due to the precipitation of calcium carbonate (4). The activity of the calcium chloride which could not precipitate as calcium carbonate led us to make the following experiment.



FIG. 6.—The clarification of sewage with calcium chloride and ferric chloride.

A sample of sewage was divided into five aliquots of one liter each. Lime as calcium was added in the form of lime water at dosages of 0, 10, 20, 30 and 40 p.p.m. The sewages were flocculated and settled, and samples of the supernatant withdrawn. The pH and calcium content were determined on these samples.

TABLE IV.—*Effect of Sodium Chloride on Clarification with Ferric Chloride*

	P.p.m. Iron ($FeCl_3$)				
		0	5	10	15
P.p.m. Sodium Chloride	0	138	75	42	10
	50	142	72	38	15
	100	132	68	37	10
	200	128	78	45	10
	300	142	70	43	10
	500	140	74	39	15

The results of the analyses showed that increases in the p.p.m. calcium remaining in the supernatants were in direct proportion to the amount added. Table V serves to illustrate this point. It will be noted that in every case practically all the calcium remained in the supernatant rather than precipitated in the sludge.

TABLE V.—*Calcium Content of Sewage After Treatment with Lime and Settling of the Sludge*

pH	Calcium Added	Calcium in Supernatant (Found)	Maximum Possible Calcium
	P.p.m.	P.p.m.	P.p.m.
7.2	0	43	43
7.7	10	51	53
8.3	20	66	63
8.8	30	71	73
9.1	40	79	81

DISCUSSION

A comparison of the clarifying power of the three common ferric salts employed in sewage treatment over a pH range of from 2.0 to 10.0, using lime and sulfuric acid for pH adjustment, showed that in general the effectiveness of the three compounds on the iron basis was similar. Ferric chloride appeared to be somewhat better than ferric sulfate in clarifying power and the activity of chlorinated copperas was intermediate, except in the pH range of 5.0 to 7.0 where it gave the best results. Theoretically, its clarifying power should lie between the two other compounds as it is either a mixture of ferric sulfate and chloride or a compound containing both anions $\left(\mathrm{Fe}\begin{matrix}\diagup\!\!\diagup \mathrm{SO_4} \\ \diagdown \mathrm{Cl}\end{matrix}\right)$.

At some plants chlorinated copperas has not produced as good results as the other two salts. The reason is probably that the copperas was not chlorinated in the proper manner and oxidation was not complete. The reaction between copperas and chlorine is not completed as rapidly as was formerly believed.

The difference between the clarifying power of the iron salts has been shown to be due to varying clarifying power of the anions employed. Hydrochloric acid gave a greater degree of clarification than sulfuric acid, although no differences in the pH values were produced with equivalent amounts of the acid. This is contrary to findings with pure colloidal suspensions dispersed in definite agents. Under such conditions greater coagulating power is ascribed to the sulfate ions.

The difference is not difficult to understand when the material dealt with is considered. It has been shown (10) that in sewage coagulation the dispersion medium plays a more important role than the dispersed material. The observations made with sewage are not contradictory to the theory, as the anions evidently act on the dissolved material, which determines the coagulability of the dispersed particles.

The addition of lime with an iron salt was studied in an effort to determine the mechanism of action of the lime. Measurements of clarification of sewage at pH values from 7.0 to 10.5, obtained by the addition of calcium as compared to sodium hydroxide, showed that sodium hydroxide failed to clarify while calcium hydroxide showed strong clarifying properties. It is clear, therefore, that merely changing the

pH value or making the material alkaline does not cause clarification. It appears then that the hydroxyl ion alone does not promote clarification.

It was believed that the sodium present might have acted as a dispersing agent, neutralizing the coagulating power of the hydroxyl ion. This does not appear to be true because it was shown that neutral sodium salts have neither dispersing nor coagulating properties for sewage when added in concentrations up to 500 p.p.m. with and without addition of ferric chloride.

That calcium chloride itself has little clarifying power was also demonstrated. This salt was effective in aiding clarification when used in conjunction with ferric chloride. These results seem to indicate that the calcium in the form of a neutral salt can act to change the character of the dispersion medium. The action of lime is probably twofold: Some of the calcium reacts with the dispersion medium allowing a reduction in the amount of iron salt necessary for clarification; some of the calcium becomes itself a clarifying agent at high pH values. It is clear that in the case of lime the hydroxyl ion may play a role.

Conclusions

1. The iron salts commonly used in sewage clarification are effective over the pH range 2.0 to 10.0.

2. Ferric chloride, chlorinated copperas and ferric sulfate is the general order of effectiveness in clarifying sewage although differences are not great.

3. The chloride ion is more effective for clarifying sewage in the acid pH range, which may account for the differences in effectiveness of ferric chloride and ferric sulfate.

4. The action of lime in lowering the coagulant demand appears to be due to the action of the calcium ion on the dispersion medium and its own clarifying power in the presence of hydroxyl ions.

References

1. Rudolfs and Gehm, *This Journal*, 8, 195 (1936).
2. Rudolfs and Gehm, *Ibid.*, 8, 204 (1936).
3. Enslow, *Civil Eng.*, 5, 234, 1933.
4. *This Jour.*, 7, 997, 1935.
5. Elder and Stahl, *Ind. Eng. Chem.*, 31, 925, 1939.
6. Yaffee, *Mun. San.*, 9, 298, 1938.
7. Scott, *This Jour.*, 7, 506, 1935.
8. Whedbee and Zeller, *Bul. 5*, Tex. Eng. Exp. Station.
9. Gehm, *This Jour.*, 9, 450, 1938.
10. Gehm, *This Jour.*, 11, 738, 1939.

Plant Operation

VARIATIONS IN THE CHLORINE DEMAND OF BUFFALO SEWAGE

By G. E. Symons, R. W. Simpson and S. R. Kin

Chief Chemist, Associate Sanitary Chemist and Assistant Sanitary Chemist, Buffalo Sewer Authority

More than two years have passed since the beginning of sewage chlorination at the Buffalo Treatment Works. During this time, studies begun in the construction period (1, 2, 3) were continued. Throughout this period of operation, the effectiveness of chlorination of Buffalo sewage has been studied and reported in papers on the reduction of bacterial pollution of the Niagara River (4, 5). It appears warranted at this time to make a study of the data that have been collected on the chlorine demand of sewage itself. This paper which covers the data collected in 27 months of chlorination is the first in a new series of sewage chlorination studies which were inaugurated with the beginning of sewage treatment at Buffalo. Additional papers will cover the subject of chlorine dosage control, the effectiveness of chlorination in the reduction of bacteria in sewage, the determination of chlorine demand and the estimation of coliform bacteria in chlorinated effluents.

In considering the results of any study of this kind, the effects of the physical plant and its operating schedules and conditions must be taken into account. For example, at Buffalo the sewage is pumped by one or more of six vertical centrifugal pumps of 550 h.p., each having a capacity of 120 to 140 m.g.d. Two of the pumps have two speeds and at low speed can pump from 80 to 100 m.g.d. The actual pumping rate depends on the total dynamic head.

The effect of this physical factor is shown in the record charts of the metered flow through the plant for, with an interceptor which allows some reservoir capacity, it is possible to use one pump for a long period of time independently of the variation in the flow into the interceptors. This reservoir capacity has a damping effect on the flow peaks and makes normal variations gradual. For this reason any study of chlorine demand must take into account the fact that although the flow does follow the normal curve for a sewage treatment plant, it is relatively constant throughout the day and any significant changes in pumping rates are step-wise by the capacity of either a low or high speed pump.

Another factor to be considered in interpreting the chlorine demand of Buffalo sewage is the relatively short run from the outskirts of the city to the treatment works. The total time of flow through the interceptors is not over five to six hours, with the major portion of the sewage flow reaching the treatment works in three to four hours. Al-

though the interceptor has a capacity equivalent to approximately five hours, the rate of pumping under normal operating conditions is such that actual storage is relatively small. Thus the sewage arrives at the plant relatively fresh. With the absence of sulfates in the city water supply there is little or no hydrogen sulfide present in the sewage and, as has been reported heretofore (2), the chlorine demand is therefore relatively low in comparison with that of many other cities.

Still another reason for the low chlorine demand is the high dilution of the sewage. This derives from a high per capita pumpage and flow equivalent to approximately 200 g.c.d. Although this results in low chlorine demand in p.p.m., the total demand is not necessarily low when the total flow is considered. A third reason for somewhat lower demands than observed elsewhere may be due to the technique used in the Bird Island Laboratory for determining chlorine demand. The spot plate technique, which has been reported heretofore (1, 2), apparently gives results slightly lower than the technique of the present standard method (6). Inasmuch as the Bird Island Laboratory method of determining chlorine demand maintains a chlorine dosage control that effects practically complete reduction of coliform bacteria in the sewage, it is our opinion that the use of this method was warranted in making these studies.

It is doubtful that the results of these studies are strictly applicable to the sewage existing in any other city or treatment works. On the other hand, the statistical study of over 20,000 chlorine demand tests made at hourly intervals for twenty-seven months has produced some very interesting data. From these studies, it appears in a general way that the chlorine demand of Buffalo sewage varies with a number of factors; the time of day, the temperature of the sewage or season of the year, storm and runoff effects, industrial effects, and the day of the week. The following discussion presents our findings on the effects of these various factors.

Technique of Studies

The technique of the investigation was to tabulate, for statistical study, the hourly determinations of chlorine demand made by the routine laboratory sampler analyst. Samples were tested for chlorine demand within fifteen minutes after their collection. No changes were made in the Bird Island Laboratory spot plate test (1) for the determination of chlorine demand. It should be noted here that it has been found quite satisfactory to use tap water instead of distilled water for making the chlorine reagent solution. This appears to be feasible so long as the mineral salts, particularly the alkalinity of the water, are not great.

The reading accuracy of the chlorine demand test appears to be 0.1 ml. of reagent, equivalent to 0.3 to 0.5 p.p.m. Therefore, it has not been deemed feasible to report the chlorine demand in p.p.m. to more than one decimal place.

In tabulating and plotting the data to ascertain the various effects, it became evident that in order to develop the normal trend of the chlorine demand of Buffalo sewage, it was necessary to eliminate all effects of storms and industrial peak loads from the basic tabulations. Quite obviously it was neither possible nor desirable to eliminate the effects of normal industrial loads because they constitute a normal portion of the demand. There were, on the other hand, a great many times when the demand suddenly increased out of all proportions to normal expectancy and these effects were attributed to waste load discharges from industries and were termed industrial peak loads.

Variations in Chlorine Demand

Effect of Compositing and Standing.—It has been previously reported (2) that the proper chlorine demand of sewage could not be determined from a composite sample and that the true chlorine demand of the sewage must be determined from a series of hourly tests, weighted properly for the effect of flow. As a further test of the effect of compositing and standing of samples on chlorine demand, comparative studies were continued for several months on both raw and chlorinated effluent samples. The results of this study are shown in Table I. Except in one month, in the case of raw sewage, the chlorine demand of the composite sample was always less than the average chlorine demand of the fresh sewage. The extent of this difference was from +6 to −25

Table I.—*Comparison of Chlorine Demand of Daily Composite Samples with the Weighted Average of 24 Hourly Tests.* Results in p.p.m.*

Month	Raw Sewage			Chlorinated Effluents		
	Weighted Avg. C.D. of Hourly Samples	C.D. of Daily Comps.	% Diff.	Weighted Avg. C.D. of Hourly Samples	C.D. of Daily Comps.	% Diff.
1938						
Sept.	5.8	4.8	−17.3			
Oct.	7.8	7.3	− 6.4			
Nov.	7.0	5.6	−20.0			
Dec.	6.6	5.8	−12.1			
1939						
Jan.	4.8	5.1	+ 6.2			
Feb.	4.7	4.0	−14.9			
Mar.	4.7	3.5	−25.5			
April	4.3	3.6	−16.3	1.0	1.9	110
May	5.6	4.5	−19.6	.5	2.1	320
June	6.2	5.3	−14.5	1.1	2.7	145
July	6.1	4.9	−19.7	1.0	2.6	160
Aug.	5.9	4.5	−23.7	.6	2.1	250
Sept.	6.6	5.4	−18.2	1.0	2.8	180
Avg.	5.85	4.9	−16.2	0.87	2.37	172

* Results include storm and industrial loads.

per cent, with an average of —16 per cent. In short, compositing and refrigeration of sewage samples apparently decreases the chlorine demand by about one-sixth.

In the case of chlorinated effluents where the demand of the effluent is 1 p.p.m., or less, it appears that the chlorine demand of the composite sample increases from two to four fold, with an average somewhere between. These data serve to confirm the contention that all tests should be made on fresh sewage samples.

Effect of Temperature.—In Table II the monthly average data on chlorine demand in p.p.m. are tabulated with the monthly average sewage temperatures for the period of study. These data are plotted in

TABLE II.—*Variation in Chlorine Demand (p.p.m.) with Sewage Temperature (excluding effects of storms and industrial peak loads)*

Month	1938		1939		1940		Average	
	Temp. °F.	Avg. C.D. Hourly Samples p.p.m.	Temp. °F.	Avg. C.D. Hourly Samples p.p.m.	Temp. °F.	Avg. C.D. Hourly Samples p.p.m.	Temp.	C.D. p.p.m.
Jan.			47.3	4.6	48.7	5.1	48.0	4.9
Feb.			46.7	4.4	46.6	4.8	46.7	4.6
Mar.			45.8	4.4	45.5	4.3	45.7	4.4
April			47.9	4.0	48.5	4.0	48.2	4.0
May			56.3	5.2	54.8	4.9	55.6	5.1
June			66.1	5.8	64.2	5.8	65.2	5.8
July			72.0	5.7	69.5	5.8	70.8	5.8
Aug.	75.2	5.8	74.7	5.7	72.5	5.9	74.1	5.8
Sept.	71.0	5.8	70.8	5.9	68.4	6.3	70.1	6.0
Oct.	65.0	7.2	65.4	5.8	64.2	7.0	64.7	6.7
Nov.	57.5	6.8	58.8	6.5			58.2	6.7
Dec.	50.2	6.9	52.8	5.8			51.5	6.4
Avg. for 27 Mo.							59.5	5.6

Fig. 1. One of the most interesting observations about these results is that the chlorine demand in p.p.m. lags behind the sewage temperature. In other words, the demand rises after the temperature begins to fall and falls after the temperature begins to rise. This might be considered an anomoly and some considerations should be given as to the reasons for it. In the first considerations the factor of flow will be omitted.

It is to be noted that the chlorine demand in p.p.m. is apparently representative of the general strength of the sewage as it varies with the temperature because the p.p.m. of 5-day B.O.D. and suspended solids of the sewage follows very similar curves to that of the chlorine demand.

There are certain effects to be observed, namely that during the summer months there is apparently a flattening off of chlorine demand, followed by peaks in the late fall. An inspection of the tabulated data indicates that there is a similar recurring trend of the chlorine demand

at certain seasons, e.g., January, February, and March group together; April, in both years, was the minimum; May shows an increase; June, July, August, and September appear to be on a plateau; October, November, and December represent the high of the year although, actually, during December the daily data show a decrease.

It was not possible to tabulate and plot the total chlorine demand in pounds per day (excluding rain and industrial peak effects), but a calculation was made based on median flow data (approximating the dry weather average) and the demand in p.p.m. These total demand results confirmed the lag effect, but the minimum occurred in May instead of April and there was a tendency toward a gradual increase from May to December with a decrease toward a minimum in January, followed by increases in February and March (the latter due to high flows from melting snows).



FIG. 1.—Variations in temperature and chlorine demand of sewage by months.

There are two possible explanations for this apparent lag in chlorine demand behind temperature. First, during the early spring months, February and March particularly, normal flows are quite high and the sewers and interceptors may be washed relatively clean of sewage solid depositions. The flow decreases following that period and the chlorine demand of the sewage decreases due to a deposition of some of the sewage solids. Secondly, the bacterial activity in the sewage is at its lowest during the winter months and begins to increase with the rise in temperature. This activity may also take place in the solids which are deposited during the lower flows of late spring and early summer, with the result that decomposition products are introduced into the sewage, thereby increasing the chlorine demand in the late summer and fall. Sewer slime growths may also be important in this seasonal effect.

Hourly Variations.—After giving full consideration to temperature and seasonal effects, it appeared that any tabulation to determine the hourly variations of chlorine demand must be made in accordance with the seasons as given above. An average hourly demand would not be indicative of actual operating conditions and would be of little or no value in the determination of the dosage control under the various seasonal temperature conditions. The data in Table III show the average

TABLE III.—*Hourly Variations in Chlorine Demand by Seasons*—Results in parts per million*

Hour	Average Jan.–Feb.–March	April	May	Average June–July–Aug.–Sept.	Average Oct.–Nov.–Dec.	Average Jan.–Dec. inclusive
8:00 a.m.	3.6	3.1	3.9	4.4	5.0	4.2
9:00	3.7	3.0	4.1	4.5	4.9	4.3
10:00	4.1	3.5	4.4	5.1	5.5	4.8
11:00	4.6	4.0	4.9	5.5	6.1	5.3
12:00 m.	5.2	4.6	6.0	6.4	7.2	6.2
1:00 p.m.	5.3	5.1	6.6	6.6	7.5	6.4
2:00	5.3	4.9	5.8	6.9	7.5	6.4
3:00	5.2	4.8	5.6	6.8	7.5	6.4
4:00	5.3	4.8	5.5	6.9	7.7	6.5
5:00	5.6	4.7	6.0	6.9	7.7	6.5
6:00	5.6	5.0	5.8	6.9	7.9	6.6
7:00	5.4	4.6	5.7	6.7	7.8	6.6
8:00	5.2	4.6	5.7	6.7	7.5	6.4
9:00	4.8	4.5	5.6	6.5	7.1	6.1
10:00	4.8	4.0	5.3	6.2	6.9	5.8
11:00	4.5	3.8	5.2	5.8	6.5	5.5
12:00 p.m.	4.7	3.6	5.2	5.8	6.6	5.6
1:00 a.m.	4.4	3.5	5.0	5.5	6.4	5.4
2:00	4.3	3.4	4.8	5.6	6.3	5.3
3:00	4.1	3.4	4.7	5.5	6.1	5.1
4:00	3.9	3.4	4.5	5.3	5.9	5.0
5:00	3.6	3.3	4.2	4.9	5.5	4.6
6:00	3.5	3.1	3.9	4.6	5.5	4.4
7:00	3.4	2.8	3.8	4.3	5.2	4.2
Average	4.6	4.0	5.1	5.8	6.6	5.6

* Excluding storm flows and industrial peak loads.

hourly chlorine demand in p.p.m. for the five seasons mentioned, considering that April is a season of minimum demand and May is unlike any other time of the year because it immediately follows the minimum demand and does not reach the average demand of the summer months. These data are plotted in Fig. 2 and, as indicated above, exclude the effect of storm and industrial peak loads. It should be borne in mind that these data are in p.p.m. and therefore do not take into account the effect of flow on total chlorine demand. They are, however, useful in formulating a set of curves for the control of chlorine dosage. These will be discussed in a subsequent paper.

Certain definite trends are to be observed from the curves in Fig. 2. There is a general increase in chlorine demand between the hours of

8:00 A.M. and 12:00 M. to 1:00 P.M. from January until June. During the months when the sewage is cold or just beginning to warm up, there is a drop in chlorine demand after the 1:00 P.M. peak, followed by an increase at 5:00 to 6:00 P.M. Thereafter the chlorine demand decreases at a relatively constant rate until the end of the fiscal day at 7:00 A.M. In the summer and late fall months, when the chlorine demand is higher, there is no definite decrease after the first peak, but the demand tends to remain relatively constant throughout the afternoon, or rise to a peak about 6:00 P.M.



FIG. 2.—Hourly variations in chlorine demand by seasons—(excluding storms and industrial peak loads).

It may be argued that since only a two-year period is covered, the choice of April and May as separate seasons is unwarranted because there are too few data. On the other hand, it appears from Fig. 1 that April is definitely the month of minimum chlorine demand (in p.p.m.) and that May is definitely between the minimum demand and the summer demand. The probability is that the data for these two months indicate a general tendency.

For that matter, it is quite probable that at the end of five years of study when these summaries are to be revised and the data re-averaged, the general trend of these curves will remain relatively the same, but the individual tendencies may vary somewhat.

The effect of the volume of sewage flowing at any particular time on the total chlorine demand of sewage in pounds per day is indicated in Fig. 3, for a typical month of August, 1939. It is apparent from these dry weather data that the pumping schedule for sewage at the Buffalo plant does have a damping effect on the flow curves. Because of this, the hourly variation in the total demand is not as great as might be expected in some plants (7). Averages of the hourly rates of flow of

sewage are not available and it is therefore not possible to show the effect of the hourly flow variation on the hourly total demand rate in the various seasons listed in Table III.

Using the data in p.p.m., shown in Table III, however, and the median flows for the various months, it was possible to estimate the average total demand in pounds per day for these seasons. (Note: The median flow has been found to approximate the dry weather average.) From these calculations, it appears that the difference between total demand in the months of January, February, and March, and the total demand of April was much less than the difference in p.p.m. Also, in May as mentioned above the total demand was the minimum for the year, although the chlorine demand in p.p.m. had increased over the previous months.



FIG. 3.—Hourly variations in D.W. flow and chlorine demand in p.p.m. and lb./day for typical month—Aug. 1939.

These calculations likewise indicate that the total demand in pounds per day in the summer months was but little more than that of January, February and March, although the demand in p.p.m. was 1.2 p.p.m. higher. These differences between total demand and demand in p.p.m. are best shown, perhaps, by comparing the percentage relationships of the various seasons with the average demand in p.p.m. and in pounds, as shown in Table IV.

Daily Variations.—In Table V are listed the average data for each day of the week. These data present observations both including and excluding storm flows and industrial peak loads. These data are plotted in Fig. 4. The effect of storm and industrial peak loads was equivalent to approximately 0.3 p.p.m. on the daily average.

TABLE IV.—*Comparison of Chlorine Demand by Seasons on the Basis of p.p.m. and Pounds Per Day. Data in Per Cent.*

On Basis of p.p.m.

	Jan.–Feb.–Mar.	April	May	June–July–Aug.–Sept.	Oct.–Nov.–Dec.
% of Yearly Avg.	82	71	91	103	118
% of June, July, Aug., Sept.	79	69	88	100	114
% of Oct., Nov., Dec.	70	61	82	77	100

On Basis of Lb. Per Day

	Jan.–Feb.–Mar.	April	May	June–July–Aug.–Sept.	Oct.–Nov.–Dec.
% of Yearly Avg.	99	96	86	102	117
% of June, July, Aug., Sept.	97	95	85	100	114
% of Oct., Nov., Dec.	85	82	74	87	100

TABLE V.—*Variation in Chlorine Demand by Days Results in parts per million. Average of 27 months*

Day of Week	Avg. of All Data	Avg. Excl. Storm Flow and Industrial Peak Loads
Sunday	4.8	4.7
Monday	5.9	5.6
Tuesday	6.2	5.9
Wednesday	5.9	5.6
Thursday	5.9	5.6
Friday	6.2	5.9
Saturday	6.2	6.0
Average 7 days	5.87	5.61
Average Excl. Sunday	6.84	6.55

It appeared that the Sunday chlorine demand (p.p.m.) was approximately 70 per cent of the average demand for the remainder of the week, and, as was observed in experimental studies (2), Tuesday appeared to be a high day. There was an apparent decrease on Wednesday and Thursday, followed by an increase on Friday and Saturday. These data would then appear to give the effects of normal industrial operation during the week. On the basis of total pounds of demand, the Sunday chlorine demand was equivalent to approximately 59 per cent of the average for the other six days since the flow on Sunday is approximately 85 per cent of the flow for the remainder of the week.

Effects of Storm Flow.—Although it was easy to remove the storm effect data from the general averages, it was not so easy to estimate the exact effect of storms themselves. This was true because a rain storm might occur during the time of day when there was a normal



FIG. 4.—Daily variation in chlorine demand.

expected rise of chlorine demand and this normal rise might augment the peak due to the sudden flushing of the sewers. On the other hand, the normal demand might offset the falling off of the chlorine demand with the higher dilution due to rain flows after the sewers had been flushed. A study of the one hundred twenty-six days on which rain occurred at various hours of the day produced the average data shown in Table VI. On the basis of these data, it appears that for the first two hours after a rain has started (usually when the pumping rate is increased by a second pump), the chlorine demand rises. This is followed by a drop to what may be considered a normal demand.

TABLE VI.—*Effect of Storm Flows on Chlorine Demand of Raw Sewage*

	Parts per million
Before storm	5.3
First hour	6.0
Second hour	6.8
Third hour	5.7
Fourth hour	6.0
Fifth hour	6.0
Sixth hour	5.8

In cases where rains continue over a long period of time, from eight to twenty-four hours, the demand is usually considerably less after the first few hours. In cases of sudden sharp showers, the demand may increase greatly during the first hour and return to normal within an hour or two. On the average, the effect of storm flows was to raise the daily average chlorine demand by 0.2 p.p.m. Considering that due to rainstorm runoff the average flow is 22 m.g.d. higher than the dry weather flow, this would indicate that the effect of storms was to increase the daily average total demand by approximately 360 lb. per day.

The greatest effect of any storms observed was to increase the daily average chlorine demand for any single month by 0.4 p.p.m. This occurred during the normal dry weather months. The greatest effect toward decreasing the demand was observed in the cold months when there was a normal high flow. In this case, in one month, the daily average demand for the month was decreased by 0.5 p.p.m. due to storm water.

Industrial Effects.—As indicated above, there appears to be a normal industrial load which varies as the days of the week. But there were at least three hundred thirty-eight times during the twenty-seven months when the chlorine demand at a single hour suddenly increased above the normal demand for that time of day and season of the year. The effects of these industrial peak loads are shown in Table VII, Parts A and B. In Part A is shown the frequency and time of the peaks. On Saturdays the number of peaks was greatest for any single hour and the majority of these peaks occurred at noon with a smaller number at 11:00 A.M. and 1:00 P.M. Totaling the number of times that these peaks occur at various hours indicates that there is a definite rise to a maximum between 10:00 A.M. and 2:00 P.M. followed by a recurring tendency to a maximum between 5:00 P.M. and 9:00 P.M., and a rapid decrease thereafter. There were very few peak industrial effects observed after midnight.

It is not so easy to explain the source of these peaks, but from previous studies it would appear that they may be due to sudden discharges of strong waste loads from the city's industrial section which is about three and one-half hours flow time from the treatment works.

It is possible that these tendencies toward maxima may indicate approximately definite dumping times of waste loads. The spread of these tendencies over several hours is probably due to the natural streaming effects in the sewers and the damping effect of the interceptor reservoir capacity.

The effects of these loads on the normal demand are shown in Part B of Table VII. The average demand before the peak hour, the demand during the peak, and the demand for the two succeeding hours thereafter, together with the average for the days of the peak are listed for each day of the week.

On the average, the demand was practically doubled although there were several days when the demand increased four and five fold. The highest demand ever observed was 63 p.p.m. The general effect of

TABLE VII.—*Effects of Industrial Peak Loads on Chlorine Demand of Raw Sewage*

Part A—Frequency and Time of Peaks

Hour	Sundays	Mondays	Tuesdays	Wednesdays	Thursdays	Fridays	Saturdays	Total
8:00 A.M.								0
9:00				1			1	2
10:00		4	1		2	4	1	12
11:00		4	7	2	6	2	5	26
12:00		8	5	3	9	8	15	48
1:00 P.M.		9	7	1	10	3	6	36
2:00		8	5	9	8	4	1	35
3:00		7	6	4	4	2	2	25
4:00		4	5	3	2	4	1	19
5:00		4	4	3	1	6	1	19
6:00		9	5	7	3	2	1	27
7:00		6	9	4	7	8	1	35
8:00		2	7	4	1	4	1	19
9:00		1	1	3	1	4	1	11
10:00		1	2			1		4
11:00		1	2		1			4
12:00		2	1	2		1		6
1:00 A.M.		1	3					4
2:00			1					1
3:00		1						1
4:00								0
5:00			1	1				2
6:00				1				1
7:00			1					1
Total	0	72	73	48	55	53	37	338

Part B—Effect of Peak Load on Demand

Before peak p.p.m.	6.6	6.9	6.7	6.5	6.8	6.4	6.7
Peak hour p.p.m.	13.2	14.8	14.6	12.9	14.2	13.4	13.8
First hour after peak p.p.m.	8.4	7.6	7.5	7.4	7.4	7.3	7.6
Second hour after peak p.p.m.	7.5	7.6	6.9	6.8	7.3	7.0	7.3
Avg. for day of peak p.p.m.	5.7	6.0	5.7	5.8	6.1	6.1	5.6

these peaks was to raise the daily average demand by approximately 0.1 p.p.m. This was equivalent to 110 lb. per day on the total average flow. On the individual days in question when peaks occurred, the effect was to raise the demand from 0.3 to 5 p.p.m. or more. Not only are these facts interesting from a strictly observational standpoint, but they also indicate the need for special chlorine dosage control at such times.

DISCUSSION

The presentation of these data and results is not complete without some discussion of the comparison of the analytical results and their

indications with the experimental work which was carried on during the construction of the treatment works project and which lead to the continuation of these studies.

On the basis of these published preliminary and field studies on the chlorine demand of sewage (2), the senior author prepared a report (8) estimating the probable total chlorine demand and variations therein of Buffalo sewage as it might be expected to be received in the treatment works. It is interesting to note that in this unpublished report it was "concluded that the average chlorine demand will be between 57 and 60 lb. per million gallon or approximately 6,000 lb. per day on a dry weather flow of 105 m.g.d. excluding rain effects." The present studies indicate a dry weather flow of approximately 113 m.g.d. and a total demand of 5,970 lb. or approximately 53 lb. per m.g.

The preliminary studies upon which these predictions were based involved studies made in July, August, November, and February, and from those studies it was impossible to determine the trend during the week but it was observed (8) that the total Sunday demand was approximately 58 per cent of the average for the other days in the week and that the maximum demand occurred on Tuesdays. In the present studies it appeared that the highest demand occurs on Tuesdays, Fridays, and Saturdays, and that on the basis of total pounds per day the Sunday chlorine demand appears to have been 59 per cent of the average demand for the remainder of the week.

It was predicted (8) that the minimum would occur about 6:00 A.M. and the maximum between 12:00 M. and 1:00 P.M. Actually the minimum occurred at 8:00 A.M. and the maximum at 1:00 P.M. or later, depending upon the season of the year. It was also expected that occasional maxima of 25 p.p.m. would occur. This has been borne out in the studies of the industrial peak loads which are generally less than that figure although one maximum demand was recorded at two and one-half times that value.

On the basis of a lower estimated flow than actually occurred it was estimated that the average demand would be approximately 7 p.p.m., whereas on a 10 per cent higher flow, it was found to average 5.6 excluding storm flows and varied between 4.0 and 6.6 on monthly averages. It was estimated that the variation in chlorine demand during a dry weather day would be from 30 to 225 per cent of the average. This was found to be approximately correct although on the average the normal variation was from 70 to 130 per cent during the day. Single peak loads of 800 to 1000 per cent of the average for a single day occurred infrequently.

The preliminary studies indicated (2) that the cold weather chlorine demand would be approximately 65 per cent of the warm weather demand. It was assumed at that time that the cold weather demand would prevail from January through April and the warm weather results the remainder of the year. On the basis of the studies reported herein it appears that the cold weather demand is from 70 to 80 per cent of the warm weather demand as regards concentration in p.p.m., but as re-

gards total demand in pounds the cold weather demand is from 85 to 95 per cent of the warm season demand with the transition month between cold and warm seasons having the lowest total demand.

Previous studies (2) included an attempt to determine the chlorine demand per capita and the results of the study of the sewage of a district not containing industrial plants indicated that the average per capita demand was approximately .0047 lb. per capita per day. On the basis of the present studies it was indicated that the per capita of demand for Buffalo was 0.01 lb. per capita per day excluding storm and industrial peak load effects, or 0.011 lb. per capita per day including all sewage flows. Whether this high per capita demand can be entirely attributed to industrial wastes cannot be ascertained from a study of the data collected.

The study of 126 storms indicated that the data available from the early preliminary studies, though lacking in completeness, were correct in indicating that the "chlorine demand in p.p.m. of combined sewage and storm water is not materially less than that of dry weather sewage and during the early runoff is usually higher" (2). The data of these present studies show increases in p.p.m. of chlorine demand during the first and second hour of the storm flow. Therefore it is readily to be seen that since this demand occurs with flow increases of 200 to 300 per cent, the total chlorine demand rate in pounds per day rises precipitously.

In the published summary of the laboratory and field studies (2), it was pointed out that "two criticisms of the analytical results might be raised. First, that the data presented covered only four short periods at different seasons and might not be representative. Secondly, that the results as determined in the laboratory probably are not strictly transferable to plant operation."

The fact that the results of 27 months' study in the sewage treatment works are not greatly different from the predicted results based on those four short periods indicates that it is possible, by proportional sampling and judicious choice and weighting of the sewers to be sampled and analyzed, to utilize preliminary studies as a basis of plant capacity design.

In accordance with the findings of preliminary studies that up-sewer chlorination was not necessary at Buffalo due to lack of sulfates in the sewage and consequent lack of hydrogen sulphide, no further studies were made on the subject.

Summary and Conclusions

In reviewing the analytical work of these studies and interpretations thereof certain factors become evident.

1. The chlorine demand of sewage is dependent on local conditions of sewage strength, chemical composition and sewage flow. For water low in sulphates, where the rate of flow is maintained relatively constant by pumping, following a relatively short sewer run, the chlorine demand

of the sewage in p.p.m. is not high. In the case of Buffalo the dry weather demand is approximately 5.6 p.p.m. equivalent to 53 lb. per m.g.

2. The determination of chlorine demand on composite samples of raw sewage or chlorinated effluents does not give a true demand of the sewage when compared to the average of 24 hourly tests. It is generally from 12 to 25 per cent low in raw sewage and is high in the case of chlorinated effluents by 100 to 300 per cent.

3. The chlorine demand of Buffalo sewage in p.p.m. rises and falls with the temperature but lags behind it, for the demand continues to rise after the temperature begins to fall and vice versa. The total chlorine demand, in pounds per day, also lags behind the temperature but the effect of volume changes the characteristics of the curve somewhat.

4. The chlorine demand in p.p.m. during an average day varies from 70 to 130 per cent of the average, but a single day's variation may be much greater. Minimum demands occur at 7:00 A.M. to 9:00 A.M. and maximum demands at noon and after, reflecting the normal industrial and domestic life of the city.

If the pumpage in the Buffalo Treatment Works were at a less constant rate and more nearly reflected the actual hourly variation in sewage flow, it is quite probable that the chlorine demand rate in pounds per day, if plotted by hours, would show a much wider variation than do the data in p.p.m.

5. Generally speaking there is little difference in the average demand during the week although Monday, Wednesday, and Thursday appear to be somewhat lower than the other days and the demand on Sunday, both in pounds per day (59 per cent) and p.p.m. (70 per cent) is considerably less than the average for the remainder of the week.

6. Storm flow and runoff effects do not greatly increase the concentration of chlorine demand although there is a tendency to increase during the first two hours of a storm runoff. On the other hand, the total chlorine demand rate per day increases by several fold during these hours due to the increased flow occurring.

7. Normal industrial loads on the sewers may not be strictly recognized as such, but at times peak loads occur. On the average, the peak is approximately double the normal demand for that or the previous hour and these effects have usually disappeared within two hours. There appear to be two periods in the day when peak loads occur, between 10:00 A.M. and 2:00 P.M., and between 5:00 P.M. and 9:00 P.M.

8. The per capita demand of Buffalo sewage is 0.01 lb. per day, excluding storm effects. This is slightly more than twice the value reported for strictly domestic sewage (2). For purposes of designing capacity for chlorinating machines, it is apparent that this per capita demand or the total demand in pounds per day is more important than the p.p.m. of chlorine demand.

9. The compilation of these data has shown the variability of the chlorine demand of Buffalo sewage and the need for control of chlorine

dosage to meet these variable factors. The data have also furnished the basis whereby a system of chlorine dosage control could be developed.

REFERENCES

1. G. E. Symons, "A Modification of the Chlorine Demand Test and the Orthotolidine Test for Residual Chlorine in Sewage," *This Jour.*, 9, 569–78 (1937).
2. G. E. Symons, G. E. Terhoeven and Wm. L. Torrey, "Laboratory and Field Studies on Chlorine Demand of Sewage," *Water Works and Sewerage*, 85, 789–95 (1938).
3. G. E. Symons, R. W. Simpson and Wm. L. Torrey, "Reduction of Bacteria in Sewage by Chlorination," *Water Works and Sewerage*, 85, 983–89 (1938).
4. G. E. Symons and R. W. Simpson, "Bacterial Pollution of the Niagara River, Part I," *J. A. W. W. A.*, 31, 1156–70 (1939).
5. G. E. Symons and R. W. Simpson, "Bacterial Pollution of the Niagara River, Part II," *J. A. W. W. A.*, 32, 1529–46 (1940).
6. *Standard Methods* for the Examination of Water and Sewage, 8th Edition.
7. A. E. Griffin and G. A. Campbell, "Problems and Progress in the Chlorination of Sewage," *This Jour.*, 12, 307–20 (1940).
8. G. E. Symons, "The Estimation of the Chlorine Demand of Buffalo Sewage," Unpublished Report, Buffalo Sewer Authority, June, 1938.

PUBLIC HEALTH ASPECTS OF SEWAGE TREATMENT IN DETROIT *

By W. M. Wallace † and Arthur B. Morrill ‡

† *Supt. of Filtration, Detroit Dept. of Water Supply and* ‡ *Engineer of Sewage Treatment, Detroit Sewage Treatment Plant*

The discharge of untreated sewage into watercourses is objectionable for many reasons. A certain reason may be of the utmost importance in one situation and insignificant in another. Thus the objects of sewage treatment may and should vary with the situation. Oxygen depletion in streams, decomposing sludge banks, floating oil and grease, damage to fish and game, bacterial pollution of water supplies and bathing beaches, tastes and odors in water supplies, odor nuisance, and injury to shellfish industries are some of the results of sewage discharge that have made sewage treatment necessary.

In America, and even more so in England and Germany, treatment plants have generally been built to remedy gross pollution, as such situations naturally demanded first attention. The public health was usually endangered, but in most cases it is safe to say that sewage treatment would not have come, at least for many years, if there had not also been conditions offensive to sight and smell or damage of some other kind. So public health has until now usually been secondary, and sometimes decidedly unimportant, as the real reason for adopting treatment.

The sewage disposal problem at Detroit is most unusual. Among all the large cities in the United States, and most of the small ones, there is probably no case, with the single exception of Buffalo, where such an enormous quantity of pure flowing water is available for disposal by dilution. The flow in the Detroit River is very uniform and is never less than 300 times the average sewage flow from the city. This situation is to be contrasted with those at Chicago and Indianapolis, for example, where the flow of diluting water is often less than the flow of sewage.

The result of this has been to make the nuisance aspects of sewage discharge less important at Detroit, increasing the relative importance of the public health aspects. Reduction of biochemical oxygen demand of the sewage, which has sometimes been taken as a general measure of the success of sewage treatment, is of no practical importance at Detroit. The objectives of the Detroit plant are to eliminate visible nuisance, sludge banks, floating oil and grease due to the discharge of sewage from the city and to reduce as much as possible the discharge of sewage bacteria.

The principal treatment of the sewage proper is in sedimentation tanks which are designed to give 1½ hours detention at average flow

* Presented at the 69th Annual Meeting of the American Public Health Assn., Detroit, Mich., Oct. 11, 1940. Released by courtesy of the Engineering Section of the A. P. H. A.

and remove 55 per cent of the suspended solids, which is believed to be quite sufficient for the conditions. Results for the first six months of operation indicate that the actual removal will be somewhat greater than was contemplated.

The tank effluent is treated with chlorine before discharge into the river through a tunnel more than a mile long. The chlorine demand has averaged between six and seven parts per million and the plan has been to dose at a rate somewhat in excess of the demand found, so as to be reasonably sure of a residual in the final effluent, in spite of sudden variations in the chlorine demand. Because of lack of sampling facilities, which will soon be provided, it has not been possible to determine directly the actual residuals and bacterial kills obtained. Laboratory samples, treated with the same chlorine dose as the plant effluent and given the same contact time as it receives in passing through the effluent conduit, have shown an average reduction of coliform bacteria of over 99 per cent. This is probably a better result than that obtained by the plant, because of difficulty in following there the rapid fluctuations in chlorine demand.

The estimated cost of chlorine, for the first year of operation, is about 20 per cent of the total operation and maintenance budget, showing the unusual importance of disinfection in the plant scheme. The actual chlorine demand is proving to be less than was expected, and as other costs have been closer to estimates, the actual cost of chlorine for the year will probably amount to nearer 10 per cent of the total budget.

One of the most obvious public health effects of sewage treatment at Detroit will be a decrease in the bacterial load on water purification plants taking their raw water from the Detroit River below the city. There are two of these on the American side of the river, one supplying about 30,000 people and the other about 4,000. It does not appear that Detroit pollution has had any effect in increasing the load on water plants on the Canadian side of the river.

The bacterial load on the two American plants has been serious. The larger plant, for which better data are available, has its intake located about one-third of the way across the river and so has missed most of the pollution from Detroit sewers. Because of the positive velocity of flow in the river at all times, the pollution passes down the river much faster than it works out from the shore. In spite of the fact that its intake is located in a relatively clean part of the river, the average coliform index for the five years, 1934 to 1938, inclusive, was 19,900 per 100 ml. The corresponding average index for the month of August was 63,000.

Considering Streeter's suggested standard of 5,000 per 100 ml. as an upper limit of pollution for water to be safely handled by a modern, well-operated purification plant, it is apparent that the figure represents a heavy overload on the plant in question.

Direct observations have been made of the bacterial condition of the river but interpretation of the results is complicated by the fact that other sewage effluents and some untreated sewage are being discharged

at and below Detroit. It is not yet possible to say to what extent the remaining bacterial pollution is due to the Detroit effluent and to what extent to other sources.

The best available information is in regard to the Trenton Channel of the river, that is the part of the flow between Grosse Ile and the American shore. It is an interesting fact that this channel, carrying only 23 per cent of the river flow, carries probably more than 95 per cent of all coliform bacteria in the river, certainly more than 95 per cent of all those of American origin. Good longtime-average bacterial results on the improvement of conditions are not yet available and longtime results are necessary because of the seasonal variation in bacterial numbers. The average coliform count at the Wyandotte water intake, for example, was formerly six times as great in August as in February. Preliminary figures indicate that the bacterial pollution of the American half of the river has been decreased at least 75 per cent and that this percentage will increase as the remaining untreated sewage from Detroit and other communities is diverted from the river, as a better method of sampling makes closer control at the Detroit plant possible, and as the smaller plants adopt chlorination.

The Detroit River, from Lake St. Clair to Lake Erie, is about 27 miles in length. Because of sewage discharge, largely from the city itself, bathing has for many years not been considered safe at any point on the American shore for the entire length of the river. Much of this shore is a potential playground for a population of two million but the bathing possibilities have been nearly destroyed by sewage discharge. How soon and to what extent sewage treatment will make bathing in the river safe is a question for sanitarians. There can be no doubt however that the intercepting, settling and disinfecting of Detroit sewage is a long step in the right direction.

Nearly all of the sewage discharged into the Detroit River and its tributaries on the American side is now treated. Treatment of most of it has started within the past year so its effects are only now becoming apparent. It is certain however that the river will be much more attractive for recreational use and such use is certain to increase. It has been limited in the past by offensive conditions rather than by actual public health hazards, although a certain amount of health danger was involved. For such recreational uses as picnicking on the banks or on islands in the river, and for boating, the degree of sewage treatment now provided will practically eliminate public health risk and will doubtless mean an actual public health gain through recreation.

There is one respect in which sewage treatment is unsatisfactory at Detroit and in most other cities where bacterial pollution is a factor. This is brought about by the discharge of diluted sewage from the stormwater overflows of combined sewer systems during heavy rains. Where the purpose of sewage treatment is to avoid nuisance, such discharge has not been particularly serious. The most objectionable conditions are due to extremely low flows in the receiving streams, and such low flows almost never exist at the time of stormwater overflow. The dry

weather sewage is much diluted if there is any considerable amount of rain, so that in biochemical oxygen demand, for example, the untreated sewage at a time of heavy storm may be better than the settled effluent during dry weather.

With regard to bacterial pollution, however, the conditions are quite different. The drainage area of the Detroit River is so great that its discharge is only very slightly affected by any local storm and not much affected by any cause whatever. In cases of extreme downpour the combined sewers may discharge at full capacity for hours, with the total rate being perhaps 25 or 50 times the volume of dry weather sewage flow. Since the sewage treatment plant is able to handle only about two times the dry weather flow, it means that perhaps 95 per cent of all sewage bacteria must be discharged without disinfection into the river. Whereas the concentration of bacteria, per unit volume, is apt to be much less in the case of a heavy rain, the total bacterial discharge is certainly greater.

Thus any bacterial protection that is secured by sewage treatment to the present extent is almost entirely lost during an extremely heavy rain. As this condition affects the safety of downstream water supplies, it must now be met by extreme vigilance at water treatment plants during such periods. The first Detroit water filtration plant was formerly exposed to such a situation. Special care and increased chlorine dosages were necessary during heavy storms to guard against increased chlorine demand or heavier bacterial pollution because of stormwater discharge.

The effect on recreational use of the stream is less serious. Stormwater pollution will disappear from the upper reaches of the river within a few hours after discharge from the overflows ceases. In twenty-four hours the effect will probably have disappeared from the entire length of the river. Since recreational use will naturally be much limited during actual storm conditions, there will be relatively small hazard from this cause. If it is found that bathing is safe in the lower river at most times but unsafe for a day or so after heavy storms, it may be necessary to post bathing beaches to warn of unsafe conditions. Notices are now issued through newspapers to show whether skating is available in public parks and there seems to be no practical reason why a similar system could not be used for bathing beaches. Doubtless for weeks on end, in hot summer weather, it will not be necessary to limit bathing, so that most of the advantages of unlimited bathing conditions could be obtained with very little risk.

A complete remedy for this situation of storm weather discharge is not easy to foresee. It may seem fanciful to suggest that it will eventually be found practicable to chlorinate stormwater discharges. The cost of chlorine will be relatively unimportant, for the total amount of rain water involved is usually less than the total amount of dry weather sewage discharged. The difficulty is due to the fact that the discharge is at scattered points, at very high rates, and for relatively short times. The difficulty then lies in securing adequate equipment at moderate cost

and getting either automatic operation or immediate attendance when a stormwater discharge starts. Available equipment for applying chlorine is certainly much too expensive to be considered for this field. The carefully made equipment available is too good for the job, that is, it involves expensive construction and careful control which is very desirable in water treatment but could well be dispensed with for occasional treatment of stormwater sewage.

In some cases, as where the discharge of sewage is through stormwater pumping stations, the question of attendance for stormwater chlorination would not be difficult. In other cases it is difficult to see how any practical arrangement could be developed. Possibly investigation would show that automatic equipment might be perfected. At least it is clear that this is a field of sewage treatment which present methods do not cover and the results are, to that extent, unsatisfactory. It is to be hoped that more attention will be given to this question in the future.

In conclusion, it may be said that sewage treatment is fully as much a matter of decent, municipal housekeeping as it is a matter of public health. Advocates have been inclined to exaggerate the health aspect, knowing well that it is generally easier to secure funds for a project if the question of health appears important. It is a doubtful proceeding to urge a false reason, even for a good project, and in the long run it appears that the cause of public health will be retarded by such action.

Communities adopting sewage treatment should understand the real reasons for their action and that when this action is to eliminate nuisance, rather than to safeguard health, no improper emphasis should be placed on the health aspect.

In the case of Detroit, the sanitary value of the improvement is obvious. The Detroit River, even before any sewage treatment was undertaken, was still in sufficiently good condition so that it was used as a source of water supply, with or without treatment. It is too much to expect that the river can ever be restored to its original condition of purity. As a result of sewage treatment, however, the load of sewage contamination has been vastly reduced, to such an extent that treatment for water supply purposes is reasonably easy and safe. For other purposes than water supply the treatment adopted has practically eliminated the objectionable conditions due to sewage contamination.

Stream Pollution

THE NATURAL PURIFICATION OF RIVER MUDS AND POLLUTIONAL SEDIMENTS *

By Gordon M. Fair, Edward W. Moore, and Harold A. Thomas, Jr.

Harvard Graduate School of Engineering, Cambridge, Mass.

I. Benthal Decomposition—General Concepts

Much of the suspended matter poured into streams and other regional drainage channels by natural runoff, the runoff from sewered areas, and the discharge of water-carried wastes from household and industry settles to the bottom of sluggish river reaches, backwaters, lakes, reservoirs and mill ponds to form river muds and pollutional sediments. The bottom deposits that are built up in a given receiving water fluctuate in depth, composition and location: (1) with the character and amount of waste matter entering the body of water; (2) with changing hydrographic conditions; and (3) with the rate and nature of decomposition prevailing during different seasons of the year. It is the purpose of this series of papers to discuss (1) the processes of natural purification by which river muds and pollutional sediments are stabilized and (2) the effects of this natural purification upon the supernatant waters.

Significance of Benthal Decomposition in the Sanitary Economy of Receiving Waters.—The organic débris included in river deposits is subject to decomposition, the processes of decomposition being transferred by sedimentation from the flowing waters to the pollutional carpet spread, sometimes to considerable thickness, upon the bottom of the stream. In this *benthal* or bottom environment, decomposition proceeds in a manner that is at variance with that obtaining in the flowing water. To distinguish it from the *aerobic* stabilization of organic matter that is dissolved or suspended in well-aerated water and from the *anaerobic* decomposition prevailing in sludge digestion tanks, this process of decomposition is called *benthal* decomposition.

River muds and pollutional sediments are decomposed by the life activities of numerous different organisms. Worms, mollusks and insect larvae burrow and delve in the bottom deposits, and large numbers of bacteria and protozoa find their sustenance in the organic débris. If the water overlying the sediments contains dissolved oxygen, aerobic conditions will prevail at the surface of the deposits, but oxygen will penetrate into the mud only as deeply as the balance between oxygen diffusion and oxygen consumption will permit. Ordinarily, the downward diffusion of oxygen is not sufficiently vigorous to maintain aerobic conditions below

* Presented at the Thirteenth Annual Meeting of the New York State Sewage Works Association, New York City, January 17, 1941.

the superficial layers. There is, however, (1) an upward diffusion of products and residues of anaerobic decomposition and (2), accompanying the consolidation of deposits with time, an upward displacement of the liquid contained in the interstices of the sediments. Such vertical transport is a very important element in benthal decomposition since many of the substances reaching the sludge-water interface are capable of consuming oxygen or otherwise affecting the quality of the supernatant water. Within all but the uppermost mud strata, the available supply of dissolved oxygen is quickly exhausted, and anaerobic decomposition must of necessity become established. In deposits of measurable thickness, therefore, decomposition is forced to proceed in part aerobically and in part anaerobically, *i.e.* benthally. The picture is further complicated by the activities of living organisms like the sludge worms that ingest subsurface mud and deposit their fecal pellets upon the surface or that otherwise, by burrowing operations, bring subsurface mud to the sludge-water interface. Wherever decomposition is active, furthermore, the gases liberated by decomposition accumulate as bubbles that overcome the frictional and surface-tension forces in the sludge voids, break through the surface and rise through the supernatant water. In escaping through the deposits, these gas bubbles may stir up the sediment, expose new surfaces of mud to the water, and create a path for the liquid products of decomposition to pass out of the sludge into the receiving water. When decomposition becomes very active, sludge particles are gas-lifted into the water and may rise to its surface to form unsightly islands of floating sludge.

All of these phenomena of anaerobic activity may be observed while the supernatant water contains dissolved oxygen. In heavily polluted streams, however, sludge activity may be raised to the point where the dissolved-oxygen content of the flowing water becomes depleted by the high and rapid oxygen demand of putrescent sludge banks. Anaerobic conditions will then penetrate into the flowing water in the same manner as if the stream was transporting too heavy a flowing pollutional load. During periods of bottom scour, when much of the sediment is carried away by the flowing waters, aerobic conditions are generally maintained, because scour is normally associated both with high river stages, *i.e.* high oxygen supply, and with the colder months of the year, *i.e.* high oxygen solubility and low oxygen demand. In standing bodies of water that are sufficiently deep to establish a zone of stagnation by thermal stratification, anaerobic conditions will generally prevail in the bottom waters and bottom sediments.

The interest of sanitary engineers in the decomposition of river deposits centers on the effects of decomposition upon the quality of the supernatant water. These are broad and varied. In a heavily polluted water that serves primarily as a sewage receiver or carrier, the most important consideration is probably the effect of decomposing sludge banks upon the oxygen balance with which the nuisance question is so intimately associated. In a more normal water that receives only small amounts of municipal or industrial waste waters and serves as a source of process

water for industries or of drinking water for industrial or communal supply, the effect of decomposing deposits is broader in scope. Increases in suspended solids or turbidity, in color, iron and organic matter, and in odors and tastes become of importance. Changes in hydrogen-ion concentration and other attributes that affect the purification of water must be taken into account, also changes in the fertility of the water in relation to undesirable plankton growths.

Not all of the manifold aspects of the problem are discussed in this series of papers, which is confined more particularly to the analysis of certain experimental investigations conducted in the authors' laboratory.

Composition of River Muds and Pollutional Sediments.—The sediments of rivers are composites of particulate organic and inorganic impurities that have been thrown down and impounded, generally over relatively long periods of time associated with stream flows too low to prevent sedimentation of suspended solids or to move deposited solids downstream by bottom scour. The sediments of lakes and other standing bodies of water are similarly constituted but only in so far as differences in hydrographic conditions permit. The composition of river muds and pollutional sediments, as actually laid down, depends upon many factors: (1) the primary source of the pollutional (decomposable) solids; (2) the amount of natural silt that is carried down with the pollutional solids; (3) the flocculating properties of the receiving water (notable, in particular, in sea or brackish water); (4) the removal of certain constituents by washing, or natural elutriation; (5) the hydraulic selection of deposited particles as a result of differential sedimentation; and (6) the compacting of the sediment under its own weight.

The composition of a number of different types of muds and pollutional sediments is shown in Table I in order to exemplify their general properties and variability. It is seen that the percentage of dry solids in the wet sediments varies in a general way from 10 to 40% and that from 10 to 30% of the total solids are volatile. The high value of 83% of volatile matter belongs to a sewage sludge studied by Baity (1) as collected from plain sedimentation tanks, *i.e.* without the addition of inert or weighting solids. Usually, the discharge of sewage into a stream will lay down sludge deposits that have from two to eight times the solid content and from one-half to one-sixth the proportion of volatile matter of sludge that is collected by primary tanks in sewage-treatment works. Factors responsible for these differences have been enumerated before and are reflected within the series of benthal deposits shown in Table I by the low solids content and high volatile content of the lake deposit in particular.

The proportion of organic nitrogen in the volatile solids of river muds is not unlike that of sewage solids. Dissolution of organic nitrogen, therefore, appears to be of the same order of magnitude as that of the remaining organic substances. The proportion of iron, on the other hand, seems to be larger in benthal deposits than in sewage sludges. Actual values must be expected to vary with the amount of iron in the receiving water itself and with the selective presence of iron in the material deposited. The B.O.D. of deposited solids depends largely upon the character of the

TABLE I.—*Composition of Benthal Deposits*

	Sewage Sludge	Sludge Deposit	River Muds	River Mud	River Muds	Lake Mud
	(1)	(2)	(3)	(4)	(5)	(6)
Analyst	Baity	Authors	McGowan et al.	Authors	Rudolfs	Allgeier et al.
Reference	(1)	—	(2)	—	(3)	(4)
Origin of deposit	Sewage treatment works		English Rivers	New England Stream	Connecticut River	Lake Mendota
Dry Solids—% of sediment	8.5	11.25	16.6 to 39.7	17.4	—	9.6
Volatile Solids—% of dry solids	83.0	13.85	11.0 to 17.1	24.2	—	27.4
kg. per sq. m.	0.07 to 2.8	0.19 to 3.8	0.15 to 2.2	4.5	10 to 20	—
Organic Nitrogen (N)—% of volatile solids	4.5	4.5	1.3 to 5.1 *	4.2	2.1 to 4.9	—
Iron (Fe)—% of volatile solids	—	5.0	7.9 to 15.8	4.8	—	—
B.O.D. (5-day, 20° C.)—grams per kg. of volatile solids	173	331	16 to 111	47.7	40.9 to 110	—

* Total nitrogen—probably mostly organic.

organic matter and the age of the sediment. Freshly settled solids are found to exert a 5-day, B.O.D. comparable to that of fresh sewage sludge (from 300 to 500 grams of oxygen per kg. of volatile matter). In older deposits, all gradations of B.O.D. below this value may be encountered. B.O.D. values below 40 grams per kg. of volatile matter, however, appear to be unusual. This may mean either that there is a residual B.O.D. that cannot be released in the benthal environment or that the rate of decomposition is extremely slow in its later stages, and so escapes our analytical techniques.

Of the tests that are well established in sanitary analysis, the B.O.D. test might seem to reflect most directly the decomposability of benthal deposits. Interpretation of 5-day results is complicated, however, by two factors that are related to the shift in conditions of decomposition from benthal (partly anaerobic) to strictly aerobic ones when samples of sludge solids are suspended in dilution water. These factors are: (1) the rapid, chemical or immediate oxygen demand exerted upon substances present in the sludge as a result of the preceding anaerobic decomposition and (2) the time lag before aerobic decomposition has become well established. To a certain extent, these are compensating effects, but their existence casts additional shadows upon the otherwise already questionable habit of generalizing widely from the 5-day, 20° C., B.O.D. test. Moreover, the significance of short-time oxygen demand results is sometimes further obscured by difficulties inherent in the analytical determination of dissolved oxygen in suspensions of muds, which, as shown by Ruchhoft and

his coworkers (5), may lead to anomalies in the evaluation of immediate oxygen demand.

The two samples of material studied by the authors are identified as a sludge deposit and a river mud in columns 2 and 4 of Table I. The sludge deposit was employed in a series of experiments, begun in 1938, dealing with the effect of depth upon benthal decomposition and referred to, in this paper, as "depth" studies. The river mud was used in a series of experiments, begun in 1935, dealing with the effect of temperature upon benthal decomposition and referred to in this paper as "temperature" studies. The sludge deposit consisted of fresh sewage solids mixed with inorganic matter in such proportions as to approximate in its gross chemical constitution natural sediments that had been laid down in a heavily polluted stream. The sewage solids were collected during the late summer from the upper story of an Imhoff tank at Natick, Mass. The sewage from this community contains only a small amount of industrial waste. Preliminary experiments had demonstrated that it was not possible to keep fresh sewage solids, representing in excess of 2.5 to 3.0 kg. of volatile matter per sq. m. of benthal surface, at the bottom of carboys unless inert materials were added to weight the sludge. This observation may explain in part the relatively low percentages of volatile matter found in natural sludge banks. A mixture of fine sand, passing a sieve with 40 meshes to the inch, and diatomaceous earth, in a ratio to the sand of 1 to 5 by weight, was added to the sewage solids together with an amount of lime sufficient to adjust the reaction of the sludge to a pH of 7.0. By these means, the total-solids content of the sludge was raised from 2.65 to 11.25%, and the proportion of volatile-solids was decreased from 64.4 to 13.85% of the total dry weight. A small amount of iron, present in the admixed materials, increased the percentage of iron slightly above that occurring naturally in the fresh sludge.

The river mud was collected in the fall of the year from a New England stream draining an upland valley and receiving in addition to natural run-off with its included surface wash—largely mineral matter and vegetable débris—some industrial wastes as well as a small amount of sewage. Gas bubbles rose from the natural deposit when it was disturbed.

Course of Benthal Decomposition.—The benthal environment, as has been explained, gives free play to both aerobic and anaerobic activities; mutually stimulating and mutually retardant. Much remains to be learned about the interlocking mechanisms by which benthal decomposition proceeds. Three salient stages are readily distinguished, however, when benthal decomposition is observed in the laboratory: (1) intensive fermentation; (2) gradual consolidation; and (3) quiescent stabilization. The various manifestations of sludge activity associated with these three stages may be outlined schematically as follows:

BENTHAL DECOMPOSITION

I. Period of intensive fermentation. Fermentation may be so vigorous as to occasion the escape of large portions of the sediment into the supernatant water.
   A. Physical manifestations.
      1. Effervescent fermentation and rapid evolution of gases (CO_2 and CH_4)
      2. Unstable equilibrium, internal agitation, and flotation of solids.
      3. Release of hydrogen sulphide and similar putrefactive odors.

B. Biochemical manifestations.
1. Lowered pH values, production of organic acids, and reduction of nitrates, sulphates, and the like.
2. Presence of a large, active bacterial population. Uniformly high gelatin (20° C.) counts and rapid decrease in coliform organisms.
3. Rapid reduction in B.O.D. of organic solids.
4. Uniformly high benthal oxygen demand with frequent surcharges due to the release of readily oxidized interior fluids and the ebullition of gases.

II. Period of gradual consolidation. Consolidation may control the rate of transport of oxidizable materials to the sludge-water interface.

A. Physical manifestations.
1. Marked retardation of gas production.
2. Slow but persistent subsidence of the sediment with accompanying increase in sludge density.
3. Creation of a definite surface zone, gray in color, into which materials originating in the anaerobic interior of the deposit escape and in which they are subjected to aerobic stabilization.

B. Biochemical manifestations.
1. Recovery of pH values to magnitudes obtaining in the supernatant water. Release of ammonia and soluble nitrogenous compounds to this water.
2. Development of an active, varied protozoan population and gradual evolution of a specialized bacterial population that is capable of oxidizing a widely diversified number of compounds, including ammonia and nitrites.
3. Slow but measurable decrease in B.O.D. of organic solids.
4. Continuance of a relatively high rate of benthal oxygen demand.

III. Period of quiescent stabilization.

A. Physical manifestations.
1. Cessation of consolidation.
2. Gradual expansion of the light-colored surface zone. Deposition of ferric iron as a brownish red surface film that is sometimes slick and glistening. This film may be relatively impervious and retard or prolong subsequent benthal oxidation.
3. Blackening of lower layers and acquisition of a distinctive tarry odor.

B. Biochemical manifestations.
1. Gradual decrease in bacterial population and activity. Establishment of higher forms of life, including worms and insect larvae, upon and within the deposit. The burrowing operations of these larger organisms may honeycomb the sediment and increase diffusion processes from and to the interior.
2. Nearly sustained values for the B.O.D. of the organic solids indicative of the exhaustion of anaerobic decomposition.
3. Reduced but still measurable benthal oxygen demand.

Experimental Procedures.—It is evident that the progress of benthal decomposition can be traced in many different ways. Interpretation of benthal decomposition in engineering terms requires, however, that the yardsticks employed shall either measure the effect of river muds and pollutional sediments upon the supernatant water in terms of changes in water quality or that they shall evaluate in over-all terms the amount of stabilization of the sludge itself that is accomplished. Experimental procedures must be adapted to these requirements. Among the methods reported in the literature, there are three that have yielded quantitative results. For purposes of identification, they will be referred to in this paper as the methods of Adeney (6), Rudolfs (7) and Baity (1).

As employed by McGowan, Frye and Kershaw (2), the apparatus devised by Adeney (Fig. 1) is a simple form of respirometer in which the loss of oxygen from an atmosphere overlying a sample of mud is measured as a difference in pressure and change in volume, the release of carbon

dioxide being prevented by adding magnesium hydroxide to the mud. That there is no opportunity for products of decomposition to be washed away by supernatant water is the most obvious defect in this arrangement. The oxygen demands measured are, however, closely akin to what seem to be more naturally benthal demands.

To investigate the progressive stabilization of sludge banks, Rudolfs (7) placed sludge in carboys that were left open to the air, the supernatant liquid being withdrawn from time to time and replaced by tap water. The B.O.D. (5-day), pH, and volatile-matter content of the sludge were determined. The conditions of test, here created, appear to be quite unlike those encountered in many receiving waters, particularly streams, in which a residual concentration of dissolved oxygen is continually present in the supernatant water and a delicate and precise balance between the,



FIG. 1.—Adeney's apparatus for measuring the rate of absorption of oxygen by river mud (6). This is a manometric respirometer. Bottles *A* and *B* are similar. To work the apparatus, *B* is partially filled with a known volume of mud to which a little magnesium hydroxide has been added and a similar volume of distilled water is poured into *A* which acts as a standard pressure bottle. Oxygen absorption reduces the pressure in *B*, and the volume of water that rises into the graduated portion of the tube *ab* at any given time, and the height of it above the zero mark give the means of calculating the volume of oxygen absorbed during the period of observation.

more or less supplementary, processes of anaerobic and aerobic fermentation within the sediment is continually maintained. The partial or temporary absence of the aerobic factor may reduce the amount of overall stabilization that is effected and confine the conditions of decomposition to those obtaining in deep sludge deposits or sediments that lie within the zone of stagnation of deep lakes and reservoirs. As shown later, this does not mean that the rate of anaerobic decomposition is necessarily slower than that of benthal decomposition, only that the amount of material that can be decomposed anaerobically may be smaller than the amount that can be decomposed benthally. Benthal oxygen demand is not measured directly, by Rudolfs' method, and the mistake must not be made of interpreting the progressive reduction in the 5-day B.O.D. of the

sludge as being equal to the demand that the sludge would have exerted upon the oxygen supply of the supernatant water.

In Baity's method (1), samples of sludge or sediment are placed at the bottom of stoppered glass carboys through which a continuous, controlled flow of water is maintained. Progress of decomposition is evaluated by determining measurable and significant changes in the composition of the water passing over the deposit. Benthal oxygen demand, for example, is calculated from the depletion in dissolved oxygen suffered by the flowing water. Under favorable conditions, changes in the sediment itself can be observed by withdrawing samples of the deposit for analysis; otherwise sampling must be confined to the beginning and end of the test. The principal objections to this apparatus are (1) the difficulty of balancing flow against oxygen depletion or other changes in water quality so as to make possible the measurement of all of these factors with adequate precision and (2) the great demands made upon the observer's time in operating the equipment and performing the necessary tests. The conditions encountered in a flowing stream, however, appear to be happily simulated without the interference of changing hydrographic elements, wide fluctuations in temperature, and the fortuitous addition of fresh sediment.

The methods employed by the authors in the studies reported in this paper followed essentially along the lines established by Baity. A sketch of the apparatus is shown in Fig. 2. Departures from Baity's design



FIG. 2.—Apparatus for measuring the rate of benthal oxidation and the rate of gas evolution. This is a continuous-flow respirometer.

included: (1) improvements in regulating flow and temperature; (2) modifications of the piping system to eliminate, so far as possible, the interruption of flow by entrapping gases in the tubes; and (3) provision for collecting and measuring gases that are released by the sediments during decomposition. The water supplied to the carboys (warmed, if necessary,

with an electric knife-edge heater to eliminate supersaturation with oxygen) was first held for about a day in a large storage tank that served to equalize the temperature of the water and render its oxygen content uniform; the water passed next through a sand filter, to remove iron that might be present in granular or flocculent form, and finally through a sand trap. The water was delivered to the surface of the sediment through a glass tube so shaped as to force the flow to take a spiral course towards the outlet at the top of the bottle.

Rate of flow and drop in the dissolved-oxygen content of the water in its passage over the sediments were measured daily, the flow being adjusted to establish measurable differences in the oxygen content of the incoming and outgoing water. In the "depth" studies, to be reported in Section III of this paper, the dissolved-oxygen gradient ranged between 0.5 and 3.5 p.p.m., the lowest recorded dissolved-oxygen content of the outgoing water being 3.6 p.p.m. in a single day's run. The average detention period of the water in the carboys lay between one and two days. In the "temperature" studies, to be reported in a later section of this series of papers, the dissolved oxygen gradient was generally lower than that observed in the "depth" studies, ranging from 0.5 to 2.0 p.p.m., and the dissolved oxygen content of the outgoing water was usually 6 to 8 p.p.m., only once falling as low as 4.0 p.p.m. The detention period in these experiments was 4 to 16 hours. No attempt was made to vary the concentration of oxygen in the water overlying the sediment. Baity's observation (1) that the oxygen demand of deposits of sewage sludge is independent of the oxygen concentration of the supernatant water was confirmed during the routine performance of the authors' tests. The conclusion may be drawn that the rate of benthal oxygen demand is not controlled by the rate of diffusion of oxygen from the water into the deposit but by the rate of diffusion and transport of oxidizable substances from the interior of the deposit into the surface zone. Although the maximum depth for which this was observed was 10 cm., there appears to be no reason to suspect that deeper deposits will not behave in much the same way, since all but the superficial layers of sediments become completely anaerobic and upward transport of oxidizable substances is increasingly retarded with depth.

The record of benthal oxygen demand was supplemented by the following observations:

1. Quantities of nitrogen and iron in various forms, disappearing from the mud or appearing in the water.
2. Long-time or short-time B.O.D., volatile-matter content and fuel value of the deposit at the beginning and end of the experiment and at such intermediate times as practicable.
3. Volume and composition of gases liberated in the course of decomposition of various depths of sediment (in the "depth" studies only).

Where sludge activity is high—in warm weather and during the deposition of fresh solids, for example—the supernatant water must be expected to take up some of the oxygen-demanding substances that leach, or other-

wise escape, from the deposit. In streams, the flowing pollutional load may be increased in this way and the oxygen reserve of the flowing water drawn upon for some time and distance below the area of sludge deposition. The substances that pass through the surface zone may also be expected to exert an immediate, or chemical, oxygen demand in addition to their B.O.D. Accordingly, the effluent of the carboys was tested for ammonia and B.O.D. In the "depth" studies in which fresh sewage solids were employed, the recorded increase in ammonia and B.O.D. was significantly large for about the first month. After that, differences became too small to be measurable. In the "temperature" studies, in which a natural river mud was used, no consistent measurable increase in B.O.D. of the effluent water was found at any time after the first day or two of the experiment. Measurable increases in ammonia, nitrite and nitrate, however, were observed for about two months.

Since benthal decomposition is a vertically integrated aerobic-anaerobic process, the two phases of the process were isolated, for purposes of comparison, by subjecting separate samples of sediment to stabilization by essentially aerobic and essentially anaerobic processes. The progress of aerobic decomposition was followed by B.O.D. dilution methods, that of anaerobic digestion by capturing and analyzing the gases of decomposition and determining the salient changes occurring in the composition of the digesting solids. Benthal decomposition may be expected to merge (1) with aerobic decomposition when sediments are laid down in layers so thin that oxygen can penetrate into them sufficiently fast to satisfy the oxygen requirements of the bacteria and other living organisms of decay, and (2) with anaerobic decomposition when sediments are laid down in stagnant pools in which the waters in contact with the sludge are devoid of oxygen.

II. Rates of Benthal Decomposition

The rate of decomposition of organic matter by microörganisms depends generally upon two factors: (1) the amount of decomposable matter in the substrate; and (2) the availability of this decomposable matter for the life and reproduction of bacteria and other microbes. During the course of stabilization of an organic deposit, both amount and availability of the food supply diminish progressively. The quantity of organic matter decreases as a consequence of its utilization by bacteria as a source of energy and growth. This is an obvious fact of which account is taken in all formulations of biochemical reactions. Less obvious is the circumstance that, due to the selective action of successive generations of microörganisms, the more available food is attacked first, leaving the less readily available compounds for subsequent destruction. As a result, the rate of decomposition is subject to continual deceleration.

If, as in the key portions of the present studies, decomposition is measured by observing the rate of benthal oxidation, *i.e.* the amount of oxygen withdrawn in a given interval of time from the supernatant water by aerobic activities and oxidation reactions within the superficial layers of sludge deposits, the observed rates of oxygen utilization will decrease

persistently (1) due to the combined effect of reduced quantity and selective availability of food supply and (2) due to the physical barriers imposed upon biochemical oxidation in the course of time by reduced rates of diffusion and transport of oxidizable substances into the surface zone: restrictions of availability that are markedly influenced by the process of consolidation (see Appendix to Part III).

Mathematical Formulation of the Progress of Decomposition.—In the mathematical formulation of certain biochemical changes that are confined (1) to short periods of time, (2) to the influence of a relatively few genera of bacteria and other microörganisms, and (3) to a relatively stable environment, it is possible to neglect, without appreciable error, changes in the availability of the organic substrate. In these circumstances, as shown by Phelps (8) for short-time aerobic biochemical oxidations, for example, the changes that accompany decomposition may, to a useful degree of approximation, be formulated in terms of a simple unimolecular equation. Here the rate of decomposition is assumed to depend solely upon the amount of organic matter remaining to be decomposed, and the availability of the substrate is presumed to be constant regardless of its physical condition and state of selective decomposition. It is obvious that this simple formulation is only a first approximation of the progress of benthal oxidation or the rate of stabilization of sludge deposits. So varied are both the chemical and physical environments during the slow course of benthal decomposition that the postulation of constant availability of food supply would lead to significant discrepancies between observed and fitted values. In order to adjust mathematical formulation to theory as well as measurement, while recognizing the fundamental usefulness of the unimolecular conception of reaction velocity, the simple unimolecular formulation may be elaborated to take into account the deterioration in the availability of the food supply in the course of time. This modification will be shown to correspond closely to experience.

If y = the amount of material decomposed or the oxygen demand exerted in time t;
L = the ultimate amount of decomposable material or ultimate oxygen demand;
k = the reaction velocity constant, reflecting the initial availability of the substrate, and depending upon the type of organic matter present and the condition of the physical environment (mineral matter, specific gravity, and depth of the deposit);
and a = the coefficient of retardation, depending upon the type of organic matter present and the condition of the physical environment,

then the requirement that the rate of decomposition, dy/dt, shall be proportionate to the amount of material remaining to be decomposed, $(L - y)$, and to the availability of this material, which decreases with time, may be expressed by the following relation:

$$\frac{dy}{dt} = \frac{k}{1 + at}(L - y). \qquad (1)$$

Integration then yields the equation:

$$y = L[1 - (1 + at)^{-k/a}]. \tag{2}$$

In equation (1) the factor $(L - y)$ represents the amount of decomposable or oxidizable matter remaining in the substrate at any given instant, and the factor $k \div (1 + at)$ is a measure of the availability or rate at which a unit weight of remaining decomposable or oxidizable matter is stabilized. This rate factor decreases with time for positive values of a. When $t = 0$, $k \div (1 + at) = k$. The parameter k, therefore, measures the initial rate of reaction or availability. When $t = 1 \div a$, $k \div (1 + at) = \frac{1}{2}k$ and the reaction velocity has been cut in half after this period of time. When $a = 0$, the formulation becomes identical with the simple unimolecular equation:

$$\frac{dy_u}{dt} = k_u(L_u - y_u) \tag{1a}$$

and

$$y_u = L_u(1 - e^{-k_u t}), \tag{2a}$$

where the subscript u distinguishes between the constants and variables of the two formulations. For purposes of comparison, equations (2) and



FIG. 3.—Course of decomposition traced by the retardant unimolecular curve. When the coefficient of retardation $a = 0$, $k/a = \infty$ and the retardant curves merges with the simple unimolecular curve. These curves facilitate the estimation of the proportion of decomposition completed in a given time.

(2a) have been plotted in dimensionless form in Fig. 3. Here increasing values of k/a depict, in a general way, the influence of the coefficient of retardation upon the progress of decomposition. Since equation (2) takes

into account the decrease in rate of decomposition due to the reduction of availability as well as amount of remaining food supply, it may suitably be named the "retardant unimolecular equation." In order to fit the equation to observed values, a least-squares procedure, based on the differential form of the equation, has been developed (see Appendix to Part II of this paper). By means of this procedure it is possible to generalize the observed values of y and t in terms of the parameters L, k, and a.

It is not the opinion of the authors that this retardant form of the unimolecular equation represents the ultimate refinement in the analysis of long-time processes of decomposition. They do believe, however, that it provides an adequate and mathematically not inconvenient description of the stabilization of organic deposits while satisfying the requirements of the theory of the active processes as well as experimental findings.

If we are interested in the time needed to accomplish a given proportion of the ultimately expected amount of benthal decomposition, equation (2) may be solved for t as follows:

$$t = \frac{1}{a}\left[\left(1 - \frac{y}{L}\right)^{-a/k} - 1\right]. \qquad (2b)$$

For decomposition 50, 90 and 99 per cent completed, y/L equals 0.5, 0.9 and 0.99 and t is given by the following expressions:

Decomposition 50 per cent completed in time $t = 1/a(2^{a/k} - 1)$, $(2b_1)$

Decomposition 90 per cent completed in time $t = 1/a(10^{a/k} - 1)$, $(2b_2)$

Decomposition 99 per cent completed in time $t = 1/a(100^{a/k} - 1)$. $(2b_3)$

Mathematical Analysis of the Studies of the Royal Commission on Sewage Disposal.—Before discussing the authors' experiments on benthal decomposition, for which the mathematical methods just presented were developed, these methods will be tested against the recorded, but unformu-

TABLE II.—*Character of English River Muds* (*2*)

Sample No. and Date of Collection	Source	Depth of Mud—cm.	Total Solids—% of Wet Sediment	Volatile Solids—% of Total Solids	5-Day, 18° C., B.O.D.—Grams per kg. Volatile Matter	Total Nitrogen—N—	Total Iron—Fe—
						% of Volatile Solids	
304 10-12-1910	River Anker below Nuneaton Outfall	1.4	23.7	15.3	32.5	4.44	8.10
306 10-13-1910	River Avon above Coventry Outfall	1.2	24.6	11.7	13.4	4.11	8.81
308 10-13-1910	River Avon below Coventry Outfall at Bubbenhall	0.5	16.6	17.1	86.5	4.60	10.88
309 10-13-1910	River Avon below Coventry Outfall at Rock Spinney	1.2	22.2	12.8	102	5.09	14.31
123k 11-24-1910	South Delph above Lincoln Outfall	3.0	53.2	11.0	36.4	1.32	15.80
128k 1 -1 -1911	Canal below Berkhamsted Outfall	0.7	39.7	11.2	—	2.37	7.89

lated, results of three authoritative sanitary institutions: the Royal Commission on Sewage Disposal (2), the New Jersey Agricultural Experiment Station (7), and the Chicago Sanitary District (9).

Of classical importance are the studies of English river muds by McGowan, Frye and Kershaw (2) in which six samples of sediments of different origin, age, and depth were held at 18° C. in the Adeney apparatus



FIG. 4.—Course of oxygen demand exerted during decomposition by five English river muds. From observations by McGowan, Frye, and Kershaw (2) for the Royal Commission on Sewage Disposal. The observed points are fitted by retardant unimolecular curves.

(6), shown in Fig. 1. The properties of these muds are summarized in Table II, and the oxygen demands observed during 650 to 750 days, or about two years, when the demands were still active, are plotted in Fig. 4.

Analysis of the results yields the retardant unimolecular parameters of benthal oxygen demand listed in Table III and needed for the solution of equation (2). The retardant unimolecular curves calculated by means of these parameters have been drawn in Fig. 4. Agreement between ob-

served and computed values is seen to be excellent over the entire range of experience. For purposes of comparison, the calculated simple unimolecular parameters, equation (2*a*), are added to Table III. The magnitudes of k_u, it will be noted, are consistently larger than those of k and the magnitudes of L_u consistently smaller than those of L. In line with theoretical considerations, these differences produce poorer agreement between observed oxygen demands and those computed by the simple unimolecular equation. For sake of clarity, however, the simple unimolecular curves are not shown in Fig. 4.

TABLE III.—*Mathematical Parameters of Benthal Decomposition of English River Muds*

Sample No.[1]	Approximate Depth—cm.	Volatile Matter—kg. per sq. m.	Specific Gravity[2]	Mathematical Parameters				
				Retardant Formulation			Simple Formulation	
				k[3]	a[3]	L[4]	k_u[3,5]	L_u[4]
304	1.4	0.570	1.12	0.00132	0.000333	378	0.00148	329
306	1.2	0.390	1.13	0.00244	0.00120	206	0.00269	174
128k	0.7	0.381	1.23	0.00295	0.00183	178	0.00396	136
308	0.5	0.153	1.08	0.00362	0.00188	418	0.00433	341
123k[6]	3.0	2.2	1.28	0.00523	0.00101	185	0.00534	177

[1] The results recorded for sample 309 are so irregular that they have not been included in this table.

[2] Estimated from average values for the density of volatile constituents and ash.

[3] On daily basis.

[4] Grams of oxygen per kg. of volatile solids initially present.

[5] This value is 2.303 times the magnitude of the reaction velocity constant as calculated by Phelps [8] and others from a modification of formula (2a): $y_u = L_u(1 - 10^{-k_u t})$.

[6] Sample shaken during decomposition; conditions of test not comparable with other samples.

While the English observations were carried out on muds that were too different in character to permit strict quantitative comparisons between them, it is evident that the reaction velocity constant, k, and the coefficient of availability or retardation, a, decrease with increasing depth of mud or, more significantly, with the areal concentration of volatile matter.* The decrease in both k and a is to be expected, because benthal oxidation can take place only in the superficial layers of mud and the rate of reaction is reduced and increasingly retarded as vertical diffusion and transport of oxidizable materials from the interior of deposits to their surface are hampered by increasing depths. The values of k and a for the deep sample No. 123k are out of line with the rest because the potential influence of depth was eliminated by shaking the sample. The lack of trend in L with depth is explainable, since Table II shows that the different samples, as collected were nowhere near alike in composition or state of stabilization.

Perhaps the most striking evidence of the behavior of pollutional sediments, revealed by this mathematical analysis of a more than thirty-year old record of river muds, is the slow rate at which benthal oxidation

* Reasons for employing in place of depth the concept of areal concentration of volatile matter, which is expressed in Tables I and III in kg. per sq. m., will be given in Section III of this paper.

takes place in comparison with known rates of biochemical oxygen demand of organic materials that remain in suspension or solution in receiving waters. While a value of $k_u = 0.23$ is an accepted average for the rate of B.O.D. of polluted water incubated at 20° C., the initial rate of benthal oxidation of English river muds was approximately 1 to 5 per cent of this magnitude. This means that the same proportion of ultimate oxidation is accomplished only in a very much longer period of benthal exposure: months or years against days or weeks.

A better understanding of this element of time can be gained by substituting the values of the parameters a and k into equation (2*b*). Certain results are shown in Table IV. To some extent all of these findings anticipate those of the authors. It will become evident, however, that the conclusions so far reached gain in significance as they are implemented, rationalized or confirmed by the results of the authors' experiments which are yet to be discussed.

TABLE IV.—*Time Required for Benthal Oxidation of English River Muds*

Sample No.	$\frac{1}{a}$ [1]	$\frac{k}{a}$	Years to Reach Stated Completion [2]		
			50%	90%	99%
304	8.2	3.96	1.6	6.5	18
306	2.3	2.03	0.93	4.8	20
128k	1.5	1.61	0.81	4.8	25
308	1.5	1.93	0.63	3.3	15
123k [3]	2.7	5.18	0.39	1.5	3.9

[1] Years elapsing before reaction velocity has been cut in half.

[2] The time required for 50, 90 and 99 per cent completion of the 20° C. B.O.D. of polluted water is ordinarily 3, 10 and 20 days respectively.[8,10]

[3] This sample was shaken.

Mathematical Analysis of the Studies of Rudolfs and Mohlman.—The experiments of McGowan, Frye and Kershaw (2) were performed in such a way as to evaluate, within limits, the benthal oxygen demand that may be expected to be exerted by river muds that are decomposing under relatively peaceful conditions of stream flow and sludge activity. In a broad sense, benthal oxygen demand, under these conditions, is a compound measure of the trend towards ultimate stabilization and so is governed, in its rate, by the velocity of the slowest constituent activity or combination of activities. The controlling processes in benthal oxidation appear to be those by which oxidizable substances are moved from the lower (anaerobic) to the upper (aerobic) layers of sludge (see Appendix to Part III).

The progressive reduction in the 5-day, 20° C., B.O.D. of sewage sludge or river mud stored under the conditions described by Rudolfs (7) and Mohlman (9) (see Part I) must not be confused with benthal oxygen demand. While the results of such tests do not measure the amount of oxygen that must gradually be abstracted from the receiving water, they do measure the fundamental, but not necessarily controlling, rate of natural purification of river muds and pollutional sediments. Paradoxical

as it may seem, this fundamental rate of sludge stabilization—in all but very thin pollutional films—is fixed largely by the rate of anaerobic activity. How this rate compares in magnitude with that of benthal oxygen demand may be found by a mathematical analysis of Rudolfs' and Mohlman's results. The published data can be fitted quite precisely by a retardant unimolecular equation (Fig. 5), or less precisely by the simple unimolecular equation. As indicated in the thumbnail sketch included in Fig. 5, equations (2) and (2*a*) must be reoriented to suit the mirrored and



FIG. 5.—Progressive reduction in 5-day B.O.D. of stored sewage sludge and mud, observed by Rudolfs (7) and Mohlman (9). The observed points are fitted by retardant unimolecular curves.

inverted position of the curves of progressive reduction in 5-day B.O.D. Adjustment of equations (2) and (2*a*) to the new axes of reference (see Fig. 5), by substitution in these equations of $L = y_0 - L_i$ and $y = y_0 - y_i$, yields the following modified relations:

$$y_i = L_i\left[1 + \left(\frac{y_0}{L_i} - 1\right)(1 + at)^{-k/a}\right] \qquad (2c)$$

and

$$y_{iu} = L_{iu}\left[1 + \left(\frac{y_0}{L_{iu}} - 1\right)e^{-k_u t}\right]. \qquad (2d)$$

Here y_0 is the initial 5-day B.O.D. of the sludge, y_i the 5-day B.O.D. after time t, and L_i the residual 5-day B.O.D. apparently remaining after anaerobic decomposition has been completed. Fitting these equations to Rudolfs' and Mohlman's results, establishes the magnitudes of the parameters shown in Table V.

Examination of Table V and comparison of its figures with those of Tables III and IV shows that the fundamental rate of sludge stabilization is relatively much higher than that of benthal oxidation. The ratios of the respective reaction velocity constants are of the order of 5 to 10, and the ratios of the respective coefficients of retardation are of the order to 2 to 5. This means that the times required to reach a given proportion of the ultimate amount of decomposition are expressed conveniently in months instead of years. We shall not be surprised to find that the fundamental rate of sludge stabilization is substantially the same as the rate of anaerobic gasification of unseeded sewage solids, which is about one-tenth that of well-seeded sewage solids. Corroborating figures will be presented later in this series of papers.

TABLE V.—*Mathematical Parameters of, and Time Required for, Sludge Stabilization.* From Measurements by Rudolfs (7) and Mohlman (9)

	y_0 [1]	Mathematical Parameters				
		Retardant Formulation			Simple Formulation	
		k [2]	a [2]	L_t [1]	k_w [2,3]	L_{tw} [1]
Rudolfs [4]	526	0.0126	0.0060	70	0.0105	96
Mohlman	380	0.0181	0.0078	94	0.0122	102
	$\frac{1}{a}$ [5]	$\frac{k}{a}$	Months to Reach Stated Completion			
			50%		90%	99%
Rudolfs [4]	5.5	2.1	2.1		10.9	43.3
Mohlman	4.2	2.32	1.5		7.2	26.6

[1] 5-day, 20° C. B.O.D. in grams per kg. of volatile solids.

[2] On daily basis.

[3] This value is 2.303 times the magnitude of the reaction velocity constant as calculated by Phelps and others.

[4] Results of study employing intermittent decantation of supernatant liquid.

[5] Months elapsing before reaction velocity has been cut in half.

Taken by itself, measurement of the decreasing putrescibility of sludge deposits records, in addition to the fundamental rate of sludge stabilization, the potential oxygen requirements of the deposit in terms of its 5-day B.O.D. at a specific time. These requirements are set in motion, however, only in unusual circumstances, for example, when bottom sediments are lifted into the supernatant water. The rate of oxygen demand of these materials should then approach that normally anticipated by Phelps (8) and Theriault (10) for the biochemical oxygen demand of polluted waters. The amount of oxygen actually used up will vary with the time that elapses before the sludge solids are reprecipitated. Among causes for sludge rise are: (1) the gas-lifting of solids in warm weather and (2) flood scour. Of these, the warm-weather rise of bottom deposits is obviously

the most immediately significant occurrence. The chemical oxygen requirement of the sludge may also be of importance in this connection. It should be emphasized again that the difference between the initial 5-day B.O.D. (y_0) and the final 5-day B.O.D. (L_i) of the deposit is not the amount of oxygen ordinarily abstracted by river muds and pollutional sediments from the water that flows or lies above them. Benthal oxygen demands are ordinarily much smaller, and benthal periods of oxidation are ordinarily much longer.

III. Effect of Sludge Depth upon Rate of Decomposition

Although the present section of this paper bears the heading "Effect of Sludge Depth," the simple linear measurement of depth, when taken by itself, does not differentiate adequately between the conditions of existence that obtain within pollutional sediments. Sludge depth is not constant but decreases due to consolidation of the deposit under its own weight (see Appendix to Part III) and destruction of organic matter as the deposit ages. Depth, moreover, does not reflect such important factors as the amount of organic matter present, the density of the sediment and the content of total solids. A better general yardstick of what we wish to express by the term depth is the areal concentration of volatile matter, m, in a sludge deposit. By this is meant the weight of organic or volatile solids accumulated beneath a unit area of benthal surface or sludge-water interface. This measure may be expressed conveniently in kg. of volatile solids per sq. m. in the metric system or in lb. per sq. ft. in the English system of measurement (see Tables I and III). Areal concentration of volatile matter is simple of determination and definite in meaning. Although not a unique measure, it does reflect the potential intensity of decomposition, and the authors have found it to be the most consistent and satisfactory single parameter of the conditions that are otherwise characterized only roughly by depth.

A limited amount of information on the effect of sludge depth upon rate of decomposition has been derived in Part II from a mathematical analysis of the results obtained by McGowan, Frye and Kershaw (2) for the benthal oxidation of a heterogeneous group of English river deposits. Additional information is available in a 35-day study of a sewage sludge carried on by Baity (1). It is the hope of the authors that the experiments to be recorded in this section of this paper will constitute a further contribution to our knowledge of the natural purification of river muds and pollutional sediments and their effects upon the quality of the waters that override them.

Experimental Procedures.—The apparatus employed is shown in Fig. 2 and has been described in Section I of this paper. The general properties of the sludge studied are summarized in Table I which shows that the mixture of sewage solids and inert materials that was prepared was representative of a freshly deposited pollutional sediment, with a 5-day B.O.D. per kg. of volatile solids comparable to that of fresh sewage solids. Different amounts of the mixture were measured into five carboys (Fig. 2)

TABLE VI.—*Observed Cumulative Benthal Oxygen Demand of Sludges of Varying Depth*
Grams of oxygen per kg. of volatile solids initially present

Temperature: 20 to 25° C. Surface Area of Sludge: 526 sq. cm.

Time in Days		Carboy No.				
		I	II	III	IV	V
10		11	27	16	40	20
30		34	77	90	170	132
50		55	105	146	261	243
70		68	131	188	312	292
90		78	149	215	352	332
120		94	175	252	407	384
160		109	198	290	461	435
200		124	214	316	496	467
250		135	232	336	547	502
300		144	245	354	581	540
350		154	257	370	614	572
400		163	268	386	642	605
450		169	274	400	667	635
Areal Concentration of Volatile	*Initial*	3.77	1.38	0.513	0.188	0.188
Matter (kg. per sq. m.)	*Final*	1.37	0.640	0.261	0.101	0.102
Depth of Deposit (cm.)	*Initial*	12.2	5.4	2.7	1.5	1.5
	Final	8.2	4.1	2.4	1.34	1.35
	Mean *	10.2	4.75	2.55	1.42	1.42
Specific Gravity	*Mean* †	1.143	1.113	1.078	1.051	1.051

* ½ (depth at 3 days + depth at 450 days).

† Computed from density of materials added and mean depth:

$$1 + 0.001185 \frac{\text{Total solids (grams)} - \text{Volatile solids (grams)}}{\text{Depth (cm.)}}$$



FIG. 6.—Course of benthal oxidation of sludge deposits of varying depth, and course of aerobic B.O.D. of the material originally deposited. Retardant unimolecular curves are fitted to the observed points.

and two anaerobic digestion flasks. The amounts introduced into carboys I to IV were chosen so that the weight of volatile solids (198, 72.7, 27, and 9.9 grams) would decrease in approximately geometric ratio for the purpose of spacing the expected benthal oxygen demands more or less uniformly over the range covered by the tests. Carboy V contained the same amount of volatile matter as carboy IV (9.9 grams) but differed from the rest in that, during the first month of operation only, the influent pipe terminated four inches instead of one inch above the surface of the sludge. The slight discrepancies between the results obtained from these two carboys are believed to be due to this temporary variation.

The changes taking place in the deposits were evaluated in a number of different ways that may be grouped conveniently as follows:

1. Measurement of (*a*) the oxygen absorbed from the supernatant water and the gases released by the sludge; (*b*) the aerobic oxygen demand, or long-time B.O.D., of the sludge at the beginning and end of the test; and (*c*) the volume and composition of the gas liberated during anaerobic digestion of the sludge.
2. Measurement of (*a*) the loss of nitrogen from the deposit; (*b*) the changes in its iron content; and (*c*) the reduction in its fuel value.

Only the first group of observations will be discussed in the present section of this paper.

Results.—The chronology of the benthal oxygen demand exerted in 450 days by the five depths of sludge is listed in Table VI and plotted in Fig. 6. Fitting retardant and simple unimolecular equations to these data, yields the mathematical parameters shown in Table VII and the retardant curves of best fit drawn in Fig. 6. Calculations of the time required to complete 50, 90, and 99 percent of the ultimate benthal oxygen demand are recorded in Table VIII.

TABLE VII.—*Mathematical Parameters of Benthal Oxidation of Sludges of Varying Depth*

Carboy No.	Mean Depth cm.	Initial Areal Concentration of Volatile Matter kg. per sq. m. (m)	Mathematical Parameters				
			Retardant Curve			Simple Curve	
			k [1]	a [1]	L [2]	k_u [1,3]	L_u [2]
I	10.2	3.77	0.00628	0.00240	196	0.00674	172
II	4.75	1.38	0.00726	0.00245	309	0.0101	260
III	2.55	0.513	0.00750	0.00301	447	0.0103	377
IV	1.42	0.188	0.00762	0.00373	758	0.00869	641
V	1.42	0.188	0.00764	0.00369	710	0.0102	587
Long-time, 20° C. B.O.D. of Initial Sludge.....			0.1212	0.0791	818	0.103	715

[1] On daily basis.

[2] Grams of oxygen per kg. of volatile matter initially present.

[3] This value is 2.303 times the magnitude of the reaction velocity constant as calculated by Phelps and others.

TABLE VIII.—*Time Required for Benthal Oxidation and Areal Oxygen Demand of Sludge Deposits of Varying Depth*

Carboy No.	Mean Depth cm.	$\frac{1}{a}$ [1]	$\frac{k}{a}$	Years to Reach Stated Completion			Areal Oxygen Demand	
							Total	Initial Rate
				50%	90%	99%	L_s [2]	y_{s_0}' [3]
I	10.2	1.1	2.61	0.33	1.6	5.5	739	4.65
II	4.75	1.1	2.96	0.30	1.3	4.2	426	3.09
III	2.55	0.91	2.49	0.29	1.4	4.9	227	1.70
IV	1.42	0.73	2.04	0.29	1.5	6.3	142	1.08
V	1.42	0.74	2.07	0.29	1.5	6.1	134	1.02
Long-time 20° C. B.O.D. of Initial Sludge.....		0.035	1.53	0.020	0.12	0.67	—	—

[1] Years elapsing before reaction velocity has been cut in half.
[2] $L_s = Lm$ = Grams of oxygen per sq. m. of sludge surface.
[3] $y_{s_0}' = kLm$ = Grams of oxygen per sq. m. of sludge surface per day.

On the whole, there is remarkable agreement between the authors' results and those of McGowan, Frye and Kershaw (2). Comparable values of k, a, and k_u, however, lie nearer the second decimal than the third,

TABLE IX.—*Observed and Fitted Long-time B.O.D. of Sludge Before and After 450 Days of Benthal Decomposition and After 495 Days of Anaerobic Decomposition*

Temperature: 20° C. Demand: Grams of oxygen per kg. of volatile solids initially present.

Time—Days	Original Deposit	Carboy No.							Anaerobic Sample [3]
		I [1]	I Upper	I Lower	II	III	IV	V	
2	195	21	19	24	19	9	6	7	63
4	290	38	37	40	27	19	9	14	143
6	376	51	46	55	42	31	14	18	204
8	434	65	54	77	55	43	19	23	235
10	463	76	62	92	66	52	21	28	277
15	501	119	126	111	89	71	28	35	344
20	602	139	151	127	103	81	33	43	386
30	677	—	—		—	—	41	50	428
50	738	—	—		—	—	—	—	455
75	768	—	—		—	—	—	—	—
L [2]	818	160	157	164	145	135	50	61	456
First-Hour Demand [3]	13	6	4	7	4	4	3	4	16
Total	831	166	161	171	149	138	53	65	472

[1] Average of values for upper and lower layers of sludge proportioned according to the volatile-solids content of these layers (0.512 of upper + 0.488 of lower).
[2] Calculated from retardant unimolecular curve of best fit for original deposits and for simple unimolecular curve for the remainder.
[3] Part of this amount, although small, may be due to interference of suspended matter with the dissolved-oxygen test (5). The azide modification with potassium fluoride to reduce interference by ferric salts was employed.

and comparable values of L and L_u are appreciably larger. The ratio k/a ranges between 2 and 3 as against 1.6 and 4. Most of these differences can probably be accounted for by the freshness of the sludge used by the authors and the variable age and origin of the English river muds. Age appears to decrease both the rate of decomposition and its potential amount. The time required to reach a significant degree of completion, however, remains a matter of months or years rather than days or weeks.

Comparing the simple with the retardant parameters in Table VII, we note, as in the analysis of the English studies, that the magnitude of L_u is smaller than that of L, and the magnitude of k_u is larger than that of k. For all but carboy I, indeed, the value of L_u falls short of the mark actually reached in 450 days. Also there is no consistent variation in k_u with depth.

Variation of L with Depth.—All of the mathematical parameters of decomposition are seen to vary systematically with depth. Most striking, perhaps, is the rapid decrease in the ultimate benthal oxygen demand, L in grams per kg. of volatile matter, with increasing depth or areal concentration of volatile matter. There can be little doubt that anaerobic decomposition plays a larger part as deposits become deeper and decom-



FIG. 7.—Observed variation of (1) ultimate, areal demand of benthal oxygen, (2) initial, areal rate of demand, and (3) half-life areal rate of demand with areal concentration of volatile matter (depth characteristic).

posable substances are farther removed from the sludge-water interface. Much of the potential oxygen demand is then destroyed anaerobically and escapes from the sludge in the form of methane. It must be expected, therefore, that the benthal oxygen demand, L, of deep deposits will

approach a lower limiting value which is exerted by those residues that are not decomposed anaerobically. Well-digested sewage sludge, for example, still possesses a B.O.D. of 150 to 250 grams of oxygen per kg. of volatile



FIG. 8.—Volume of gas released by sludge deposits of varying depth, decomposing benthally. Observations were initiated 20 days after the start of the tests. The course of anaerobic gasification of the material originally deposited is shown for purposes of comparison. The curves are fitted by eye.

solids, and the lower limiting benthal demand of deep sludge deposits may well be of this order of magnitude. This statement is supported by the observed long-time biochemical oxygen demands of the deposits after 450 days of benthal decomposition (Table IX). The B.O.D. of the residues is

seen to vary from about 60 grams per kg. of volatile solids for the shallowest samples to about 170 grams per kg. of volatile solids for the deepest one.

In spite of decreasing values of L, however, the total oxygen requirements of deeper deposits are greater than those of shallow ones because of



FIG. 9.—Decrease of ultimate oxygen demand, L, initial rate of demand, k, and coefficient of retardation, a, with areal concentration of volatile matter (depth characteristic). Straight lines facilitate estimation of the magnitudes of L, k, and a.

the larger amount of decomposable matter present. The daily oxygen demands, too, are greater even though the reaction velocity also becomes smaller with depth. The ultimate areal oxygen demands, calculated for the authors' results, are shown in Table VIII and traced in Fig. 7. The ultimate areal, or surface, demands for oxygen, $L_a = Lm$, are here expressed in grams of oxygen per sq. m. of sludge-water interface.

That anaerobic decomposition does become ascendant with depth can be seen also from Fig. 8, a record of the volume of gas liberated during benthal decomposition. Unfortunately, collection of this gas was not instituted until 20 days after the beginning of the tests. The preceding happenings, therefore, are quantitatively unknown. Excepting carboy I, gas production per unit weight of volatile matter initially present is seen to have increased with depth. The peculiar behavior of carboy I may be due to this very fact. For purposes of comparison, observations of the gas produced during strictly anaerobic decomposition of the deposit are included in Fig. 8. The rapidity of gas production and small volume collected are somewhat unusual, but it is probable that the admixture of inert materials and lime are responsible for this situation. The high B.O.D. of the digested sludge (Table IX) is a necessary corollary. The proportion of methane in the gas from all sources was close to 70 per cent.

If anaerobic conditions establish the lower limit of benthal oxygen demand, a full aerobic environment similarly fixes the upper limit. The course of the fully aerobic oxygen demand, or long-time B.O.D. of the fresh sludge used by the authors, was followed for 75 days by the "dilution method." Observed values are listed in Table IX and a fitted curve, based upon the retardant parameters included in Table VIII, is shown in Fig. 6. The ultimate B.O.D. of 818 grams per kg. of volatile matter is seen from Table VII to exceed the highest benthal oxygen demand (smallest depth) by about 60 grams per kg. of volatile matter and the lowest benthal oxygen demand (largest depth) by over 500 grams per kg. of volatile matter. Discussion of these relationships will be continued in a later section of this series of papers.

Variation of k and a with Depth.—As shown in Table VII and Fig. 9, the reaction velocity constant, k, decreases only slowly with depth, while the coefficient of retardation, a, is reduced more rapidly. The magnitude of both of these parameters of benthal oxidation is only a small percentage of the magnitude of the corresponding parameters for the B.O.D. of polluted waters. This is understandable when one considers the differences inherent in the respective environments. The rate of B.O.D. is a direct measure of the life activities of the organisms responsible for aerobic decomposition, while the rate of benthal oxygen demand is influenced, in addition, by the physical processes of diffusion and consolidation. No direct comparison can be made between the benthal oxidation and anaerobic decomposition observed in these tests, because of the unusual behavior of the anaerobic sample. Ordinarily one would expect the rate of anaerobic gasification to be somewhat more rapid than that of benthal oxidation, but much would depend upon so-called seeding effects. The rate of anaerobic gasification is a fundamental rate in the same sense as the rate of change in 5-day B.O.D. observed by Rudolfs and Mohlman (k = 0.0126 and 0.0181 respectively).

The influence of depth upon the daily oxygen requirements of sludge deposits is included in Table VIII and Fig. 7. These requirements are a function of reaction velocity as well as ultimate oxygen demand. They are conveniently expressed in grams of oxygen per sq. m. of sludge-water

interface per day. Two rates of areal, or surface, oxygen demand are presented in Fig. 7: (1) the maximum areal rate, which obtains at the start of benthal oxidation, and (2) the half-life areal rate * which is reached after 50 per cent of the ultimate benthal oxygen demand has been exerted. Examination of equation (1) will show that the initial areal rate, y_{s_0}', and the half-life areal rate, $y_{s_{\frac{1}{2}}}'$, must equal:

$$y_{s_0}' = kLm, \qquad (1b)\ \dagger$$

$$y_{s_{\frac{1}{2}}}' = \frac{kLm}{2^{1+a/k}}. \qquad (1c)\ \ddagger$$

The time when the half-life of the deposits has been reached ranges between 3 and 4 months (Table VIII). Intermediate rates are included in Fig. 10 which will be discussed in connection with the generalization of the experimental results. The areal, or surface, rates of oxygen demand are particularly useful concepts of benthal oxidation, because they can be translated directly into the amounts by which the dissolved-oxygen content of the supernatant water will be reduced in flowing over the bottom sediments. It follows directly from the simple relations of the metric system, for example, that each square meter of sludge surface will lower the dissolved-oxygen content of a flow of one cubic meter of water per day by y_s' parts per million. In the English system of units, correspondingly, each acre of sludge surface will remove y_s' parts per million of dissolved oxygen from approximately 1 m.g.d. of water.§ Whether y_s' is the initial, half, or any other rate of demand depends upon the particular circumstances.

This discussion of the effect of depth upon the initial rate of benthal oxidation would not be complete without reference to the pioneer studies of Baity (1). The initial benthal demands observed by Baity may be expressed in grams of oxygen per sq. m. of benthal surface per day and tabulated as follows:

Depth—cm	0.5	1.0	1.5	2.0	4.0
Areal concentration of volatile matter (m)—kg. per sq. m.	0.355	0.710	1.06	1.41	2.82
Initial rate of benthal oxygen demand (y_{s_0}')—grams of oxygen per sq. m. per day	1.84	2.89	3.45	3.77	5.17

Comparison of these rates with the ones recorded in Table VIII will show that they are approximately 30 per cent greater. In the absence of significant differences in temperature, this discrepancy may be due to variations in the character of the organic matter, but it is more probably

* Not to be confused with the half-rate at time $t = \frac{1}{a}$.

† For $t = 0$ and $y = 0$, $y' = \frac{dy}{dt} = kL$ and $y_{s_0}' = kLm$.

‡ For $\frac{y}{L} = 0.5$ in equation (2), $(1 + at) = 2^{a/k}$, and for $(L - y) = 0.5$ in equation (1),

$$y' = \frac{dy}{dt} = \frac{kL}{2^{1+a/k}} \quad \text{and} \quad y_{s_{\frac{1}{2}}}' = \frac{kLm}{2^{1+a/k}}.$$

§ More exactly, 1.07 m.g.d.

the result of the lower density and consequently greater mobility and benthal exposure of the sewage sludge studied by Baity. The initial



FIG. 10.—Decrease of rate of benthal oxygen demand in time and with areal concentration of volatile matter. Straight lines facilitate estimation of rates at given times and areal concentrations of volatile matter (depth characteristic).

density of this sludge is estimated from its analysis (Table I) to have been about 1.01, whereas the sludge deposit prepared by the authors had an estimated mean density of 1.05 to 1.14. It is evident that areal concen-

tration of volatile matter falls short of being completely descriptive of the "depth factor" and that some other measure will have to be introduced when sufficient information has accumulated to permit its identification.* At the same time, it is clear that the discrepancies between Baity's results and those of the authors would become greatly exaggerated if comparisons were based upon depth itself. At a depth of 4 cm., for example, the areal concentration, m, of the sludge studied by Baity was 2.82 kg. per sq. m. and the initial rate of benthal oxygen demand, y_{s_0}, was found to be 5.17 grams per sq. m. The corresponding values interpolated from the authors' findings would be $m = 1.05$ kg. per sq. m. and $y_{s_0} = 2.55$ grams per sq. m. On this basis, therefore, Baity's values would be about 100 per cent greater than those of the authors, rather than 30 per cent.

Mathematical Generalizations.—The information collected by the authors on the relation between sludge depth and rate of benthal oxidation can be generalized in a number of different ways both within and outside the immediate mathematical framework of the retardant unimolecular equation. Remaining immediately within this framework, the variation of the parameters k, a, and L with the depth measure, m, can be formulated empirically as follows:

$$k = 0.0078e^{-0.0571m}, \tag{3a}$$

$$a = 0.0024 + 0.0021e^{-2.57m}, \tag{3b}$$

$$L = 355m^{-0.449}. \tag{3c}$$

Here, m is measured in kg. of volatile matter per sq. m., k and a are on a daily basis, and L is given in grams of oxygen per kg. of volatile matter. The relationships were derived by straight-line plotting of L, k and $(a - 0.0024)$ against m as shown in Fig. 9.

Going outside the immediate framework of the unimolecular equation, there are at least two generalizations that will relate the authors' observations of benthal oxygen requirements to sludge depth. The first of these follows from a straight-line (double-logarithmic) plotting of the information shown on natural scales in Fig. 7. For areal concentration of volatile matter in kg. per sq. m., the empirical equations that have been derived take the following form:

Ultimate benthal oxygen demand (grams of oxygen per sq. m. of sludge): $L_s = 355m^{0.551}$, (4a)

Initial rate of oxygen demand (grams of oxygen per sq. m. daily): $y_{s_0}' = 2.45m^{0.485}$, (4b) †

Half-life rate of oxygen demand (grams of oxygen per sq. m. daily): $y_{s_t}' = 0.91m^{0.516}$. (4c)

* One might speculate that the rate of demand varies inversely as the square of the sludge density.

† A similar generalization of Baity's observation gives the equation

$$y_{s_0}' = 3.2m^{0.485}.$$

Equation (4*a*) is seen to equal equation (3*c*) multiplied by m. Since the oxygen demand must be satisfied by the supernatant water, the rates of demand, as explained before, also evaluate directly the rates at which oxygen is withdrawn from the water, provided these rates are stated in p.p.m. of dissolved oxygen per cu. m. of water per sq. m. of sludge, or p.p.m. of dissolved oxygen per m.g.d. of water per acre of sludge. Formulated:

P.p.m. of oxygen removed from supernatant water = Rate of benthal oxygen demand (y_s') × acres of sludge surface ÷ million gallons of flow per day.

The second generalization that lies outside the immediate framework of the retardant unimolecular equation is more ambitious in that it embraces time as well as rate of benthal oxidation and areal concentration of volatile matter. This generalization proceeds from a differentiation of equation (2) which results in the following variant of equation (1):

$$y' = \frac{dy}{dx} = \frac{k}{(1 + at)^{k/a+1}} L. \tag{1d}$$

In this equation, the value of the fraction is substantially constant for a given value of time, t. Since equation (3) shows that L varies as some power of m, equation (1*d*) may be reduced to the following approximate relations:

$$y' = Am^{-v} \tag{5a}$$

and

$$y_s' = Am^{1-v}. \tag{5b}$$

If m is expressed in kg. of volatile matter per sq. m. of sludge surface, y' is the rate of benthal oxygen demand in grams daily per kg. of volatile matter, and y_s' is the corresponding areal rate of benthal oxygen demand in grams daily per sq. m. of sludge surface. Equations (4*b*) and (4*c*) are seen to represent special cases of equation (5*b*). Selecting specific values for the time, t, a series of straight lines on double logarithmic paper is obtained, as shown in Fig. 10. The intercepts, A, and slopes, v, of these lines decrease in magnitude with the age of the deposits, t. This decrease can be formulated,* but this is not sufficiently useful to be emphasized here. Baity's results are included in Fig. 10 and are seen to be parallel to, though 30 per cent higher than, the corresponding results of the authors for $t = 0$.

Sample Calculation of Benthal Oxygen Demand.—A sample calculation involving the use of many of the equations and figures will acquaint the reader with their relative merits and significance. Such a calculation must of necessity be confined to the special conditions of benthal decomposition that have been discussed so far in this paper. In practice, these conditions could be matched, for example, in a millpond fed by a stream that is not protected against pollution during the winter months because of seasonal (summer) operation of treatment works or tradewaste discharge. If such a pond covers an area of 10 acres and decomposable

* $A = 0.11 + 2.3e^{-0.0090t}$,
$v = 0.393 + 0.122e^{-0.0103t}$.

matter accumulates to a depth of about 2 in. during the winter, what are some of the characteristic benthal oxygen requirements to be expected at the onset of warm weather, assuming the deposited sludge contains 82 per cent of water and 15 per cent of the residue on evaporation is lost on ignition?

The specific gravity of such a deposit may be estimated to be about 1.11,* yielding an areal concentration of volatile matter,

$$m = 2 \times 2.54 \times 0.18 \times 0.15 \times 1.11 \times 10 = 1.5 \text{ kg. per sq. m.}$$

To evaluate k, a, and L, substitute this value of m in equations (3) or enter Fig. 9 with it.

a. $\log k = \log 0.0078 - 0.0571 \times 1.5 \times 0.4343 = 0.8549\text{–}3$
and $k = 0.00716$; checked in Fig. 9.

b. $\log (a - 0.0024) = \log 0.0021 - 2.57 \times 1.5 \times 0.4343 = 0.648\text{–}5$
and $a = 0.0024 + 0.00004 = 0.00244$; checked in Fig. 9;
or $\frac{k}{a} = 2.93$.

c. $\log L = \log 355 - 0.449 \log 1.5 = 2.4711$
and $L = 296$; checked in Fig. 9.

These values may be substituted in equation (2), in order to find the oxygen demand at any time, t, and in equation (1) or (1*b*) if the rate of demand at any time, t, is wanted.

d. For $t = 200$ days, equation (2) states that
$y = 296[1 - (1 + 0.00244 \times 200)^{-2.93}] = 0.682 \times 296$,
and $y = 202$ grams per kg. of volatile matter.

This result can be checked in Fig. 3 for $kt = 0.00716 \times 200 = 1.432$ and $\frac{k}{a} = 2.93$. The areal demand for oxygen, therefore, is

$$y_s' = 202 \times 1.5 = 303 \text{ grams per sq. m.}$$

e. The rate of demand at 200 days, as given by equation (1), is

$$y' = \frac{0.00716}{1 + 0.00244 \times 200} (296 - 202) = 0.00497 \times 94,$$

and $y' = 0.467$ grams per kg. daily.

The areal rate, therefore, is

$$y_s' = 0.467 \times 1.5 = 0.70 \text{ grams per sq. m. daily.}$$

f. The ultimate areal demand for oxygen is

$L_s = Lm = 296 \times 1.5 = 444$ grams per sq. m. of sludge surface.

g. The initial, or maximum, areal rate of demand is

* Specific gravity = 25,000 ÷ [250 × % water + % solids (2.5 × % volatile + % mineral)].

$y_{s_1}' = kLm = 0.00716 \times 444 = 3.18$ grams per sq. m. per day, or $3.18 \times 8.92 = 28.4$ lb. per acre per day. As shown by Imhoff and Fair (11), this rate of demand would probably exceed the rate of atmospheric reaeration of the pond under normal circumstances. If 20 m.g.d. of water flow through the pond, the concentration of dissolved oxygen in the water will be lowered, in the absence of reaeration, by $3.18 \div (20 \div 10) = 1.59$ p.p.m. at the outset of decomposition.

h. The half-life areal rate of benthal oxidation is given by equation (1*b*):

$$y_{s_1}' = \frac{3.16}{2^{1.341}} = 1.25 \text{ grams per sq. m. per day,}$$

and the time elapsing before it is reached is obtained from equation ($2b_1$):

$$t = \frac{1}{0.00244}(2^{0.341} - 1) = 110 \text{ days.}$$

i. According to equation ($2b_2$), decomposition will be completed 90 per cent in

$$t = \frac{1}{0.00244}(10^{0.341} - 1) = 490 \text{ days.}$$

As explained in the statement of the problem, the results listed under *f* and *g* have a meaning only because deposition is not continued after the onset of warm weather. The possibilities of evaluating the effects of continuous deposition will be considered in a later section of this series of papers.

2. To find the answers listed in 1 *f*, *g* and *h* more quickly but also more approximately, except for L, we can use equations (4), as follows:

f. $\log L_s = \log 355 + 0.551 \times \log 1.5 = 2.647$;
and $L_s = 444$ grams per sq. m. of sludge surface.
g. $\log y_{s_0}' = \log 2.45 + 0.485 \times \log 1.5 = 0.4747$;
and $y_{s_0}' = 3.0$ grams per sq. m. per day.
h. $\log y_{s_1}' = \log 0.91 + 0.516 \times \log 1.5 = 0.0498$;
and $y_{s_1}' = 1.1$ grams per sq. m. per day.

These values can also be read directly from Fig. 7.

3. Figure 10 can be used to approximate the results listed in 1*g* or 2*g*, and particularly for the purpose of finding the rate of oxygen demand at 100, 200 or 400 days or, by interpolation, at intermediate values (see also 1*c*).

g. For $t = 0$, read $y' = 20$ grams per kg. of volatile matter and find $y_s' = 2 \times 1.5 = 3.0$ grams per sq. m. of sludge surface per day.

e. For $t = 200$ days, read $y' = 0.45$ grams per kg. of volatile matter and find $y_s' = 0.45 \times 1.5 = 0.68$ grams per sq. m. of sludge surface per day.

The answers given are naturally circumscribed by the extent of the information so far available. It is to be hoped that it will be possible to place greater reliance upon calculations such as these, as the work of other experimenters and practitioners carries our knowledge farther. At the

present time, the results given only indicate roughly the order of magnitude of benthal oxygen requirements.

Summary of Parts I to III and Conclusions

The natural purification of river muds and pollutional sediments is an important, often poorly understood, and inadequately controlled factor in the regimen of water courses and other bodies of water. Depending upon flows and currents, more or less of the pollutional load that is imposed upon water by the discharge of natural or man-made drainage is thrown to the bottom where it undergoes benthal decomposition and interacts in various and sundry ways with the supernatant water. About 30 per cent of the organic, decomposable, or oxygen-demanding, matter in raw sewage, for example, may be precipitated to form river muds or pollutional sediments. The amount of work to be done in stabilizing these substances, therefore, may reach a considerable proportion of the total that a receiving water is called upon to do. Whether or not this shift in locus of biochemical activity is of benefit or detriment to the receiving water must depend upon circumstances.

As shown in Parts I to III of this discussion of the natural purification of river muds and pollutional sediments, benthal decomposition must be expected to fluctuate widely in character, quantity and rate. Depth of deposit, or areal concentration of organic matter, as shown in Part III, may of itself align benthal stabilization with processes akin to the aerobic decomposition of flowing pollutional matters at the one extreme, or with processes akin to anaerobic sludge-digestion at the other. With reference to oxygen requirements, aerobic processes make the greatest demands per unit weight of decomposable matter, both in quantity and rate, while anaerobic processes make the least. Aerobic processes, in the very nature of things, however, are associated with thin and hence light layers of sludge, while anaerobic processes are maintained in thick and hence heavy sediments. The overall effect is a product of (1) rate of reaction, (2) amount of oxygen required for ultimate stabilization of a unit weight of decomposable matter, and (3) the weight of decomposable matter. We cannot overlook the possibility that the building of sludge banks may, under certain circumstances, be one of nature's ways of solving the problem of pollution and natural purification in the most efficient and least damaging manner.

As to the quantity of oxygen required, the upper, aerobic, limit appears almost to approach a value of weight for weight of volatile solids (kg. of oxygen per kg. of volatile matter, for example), while the lower, anaerobic, limit lies at about 10 per cent of this value. The rate at which this demand is initially exerted, in turn, seems to approach, at the upper, aerobic limit, the rate of the B.O.D. of polluted waters—*i.e.* 20 per cent of the ultimate demand is exerted in the first day—while the lower, anaerobic limit lies well below the rate of digestion of unseeded sewage solids—*i.e.* well below 1 per cent of the ultimate demand is exerted in the first day. Between these quantities and rates are arrayed the various conditions of

benthal activity that produce some of the values recorded in connection with the studies of the authors and other workers. These are ultimately tied up with depth, and the rate of areal oxygen demand is shown to vary approximately as the square root of the areal concentration of volatile solids. In addition to areal concentration of volatile matter, however, specific gravity of the solid matter, permeability, and elastic properties of the deposit are shown to be important in determining the rate and eventual magnitude of benthal oxidation.

Rates of decomposition are seen to be variable in time, decreasing in such manner, as the deposit ages, that they are halved about every three months. This retarding factor has been recognized in the mathematical formulation of the progress of decomposition and establishes the "retardant unimolecular curve" as a curve of good fit. Methods of applying it to experimental data and simple field situations have been outlined.

The influence of temperature upon the reactions that have so far been considered will be taken up in a later section of this series of papers. Presentation of the problem of continuous deposition of solids awaits this discussion. Effects of benthal decomposition on the quality of the supernatant water, other than oxygen requirements, are also left for later treatment.

References

1. H. G. Baity, "Studies of Sewage Sludge." Unpublished Thesis. Harvard University (1927); and *This Journal*, **10**, 539 (1938).
2. G. McGowan, C. C. Frye and G. B. Kershaw. "Results of Stream Observations, 1909 to 1912." Royal Commission on Sewage Disposal, 8th Report, Appendix, 148 (1913).
3. Willem Rudolfs, "Relation between Biochemical Oxygen Demand and Volatile Solids of the Sludge Deposits in the Connecticut River." *This Journal*, **4**, 317 (1932).
4. R. J. Allgeier, W. H. Peterson, C. Juday and E. A. Birge. "The Anaerobic Fermentation of Lake Deposits." Internationale Revue der Gesamten Hydrobiologie und Hydrographie, **26**, 444 (1932).
5. C. C. Ruchhoft, and W. A. Moore. "Determination of Biochemical Oxygen Demand and Dissolved Oxygen of River Mud Suspensions." Industrial and Engineering Chemistry, **12**, 711 (1940).
6. E. A. Letts and W. E. Adeney. "Pollution of Estuaries and Tidal Waters." Royal Commission on Sewage Disposal, 5th Report, Appendix VI, 438 (1908).
7. Willem Rudolfs, "Stabilization of Sewage Sludge Banks." Industrial and Engineering Chemistry, **30**, 337 (1938).
8. E. B. Phelps, "The Disinfection of Sewage and Sewage Filter Effluents." U. S. Geological Survey Water Supply Paper 229, 74 (1909).
9. F. W. Mohlman, "Oxygen Demand of Sludge Deposits." *This Journal*, **10**, 613 (1938).
10. E. J. Theriault, "The Oxygen Demand of Polluted Waters." Public Health Bulletin 173, 135 (1927).
11. Karl Imhoff and G. M. Fair. "Sewage Treatment." John Wiley & Sons, New York, 304 (1940).
12. H. A. Thomas, Jr. "Analysis of the Biochemical Oxygen Demand Curve." *This Journal*, **12**, 504 (1940).

Appendix to Part II

Least Squares Fitting of the Retardant Unimolecular Equation.—In applying the theory of probability to observed data, in order to obtain the parameters of the retardant unimolecular equation of best fit, the general method of approach parallels that found successful for equations

of the simple unimolecular type in which the mathematical treatment is based upon the differential form of the equation (12). The differential form of the retardant equation is written as follows:

$$\frac{dy}{dt} = y' = \frac{k}{1 + at}(L - y) \qquad (A)$$

or

$$y' + ay't = kL - ky. \qquad (B)$$

The rate (y') may be calculated from the given values of y and t as follows:

$$y' = \frac{(y_i - y_{i-1})\dfrac{t_{i+1} - t_i}{t_i - t_{i-1}} + (y_{i+1} - y_i)\dfrac{t_i - t_{i-1}}{t_{i+1} - t_i}}{t_{i+1} - t_{i-1}}. \qquad (C)$$

Since it may be safely assumed that there is no appreciable error in the measurement of time, t, the lefthand side of equation (B) may be treated as a dependent function varying linearly with the independent variable y. The least squares criterion requires that the sum of the squares of the residuals, $R = kL - ky - y' - ay't$, be a minimum; that is

$$\Sigma R^2 = \Sigma(kL - ky - y' - ay't)^2 = \text{a minimum}. \qquad (D)$$

Therefore

$$\frac{\partial \Sigma R^2}{\partial (kL)} = 2\Sigma R \frac{\partial R}{\partial (kL)} = 0$$

and since

$$\frac{\partial R}{\partial (kL)} = 1,$$

$$\Sigma R = nkL - k\Sigma y - \Sigma y' - a\Sigma y't = 0, \qquad (E)$$

where n is the number of sets of observations y', y and t. Equation (E) provides the first one of three normal equations each of which is obtained by differentiating equation (D) with respect to one of its three parameters (kL, k, and a). Thus by applying the conditions $\frac{\partial \Sigma R^2}{\partial k} = 0$ and $\frac{\partial \Sigma R^2}{\partial a} = 0$, the remaining equations may be obtained as follows:

$$kL\Sigma y - k\Sigma y^2 - \Sigma yy' - a\Sigma yy't = 0, \qquad (F)$$

$$kL\Sigma y't - k\Sigma yy't - \Sigma y'^2 t - a\Sigma(y't)^2 = 0. \qquad (G)$$

Equations (E), (F) and (G) involving the quantities Σy, $\Sigma y'$, Σy^2, $\Sigma yy'$, $\Sigma yy't$, $\Sigma y't$, $\Sigma y'^2 t$, and $\Sigma(y't)^2$ calculated from the measured quantities y, y', and t provide the three conditions necessary for the determination of the parameters k, L, and a.

Summarizing, the steps in the least squares procedure are:

I. Given $(n + 2)$ sets of experimental points y versus t, compute the n corresponding values of y' by means of equation (C).

II. From the n sets of values of y, y', and t, calculate the sums Σy, $\Sigma y'$, Σy^2, $\Sigma yy'$, $\Sigma yy't$, $\Sigma y't$, $\Sigma y'^2t$, and $\Sigma(y't)^2$.

III. Substitute the sums obtained in II in equations (E), (F) and (G). Solve these equations simultaneously for the parameters k, L, and a, of the retardant equation of best fit.

Appendix to Part III

Consolidation of Deposits and Upward Diffusion of Oxidizable Substances.—Two processes have been suggested by which the soluble oxidizable organic and inorganic substances that are found as the end products of anaerobic decomposition are transported from the interior of the deposit to the surface, or interfacial, zone of oxidation. These are the processes of consolidation and diffusion.

During consolidation of the deposit, an upward displacement of fluid through the interstices of the deposit is created by the internal excess hydrostatic pressure, h, that is due to the weight of the upper layers of sludge being partly carried by the fluid contained in the interstices. When upward flow relieves this pressure, the weight of the upper layers is transferred to the solid particles of the deposit. After this state has been reached, upward flow ceases and the deposit has become completely consolidated. The resulting decrease in depth of deposit is proportional to the total amount of flow that has taken place. The mathematical formulation of the process of consolidation proceeds from the well-known differential equation of hydrodynamics for streamlined flow in the unsteady state:

$$\frac{\partial h}{\partial t} = p^2 \frac{\partial^2 h}{\partial x^2}, \qquad (a)$$

where h = the excess hydrostatic pressure within the deposit at time t, and depth x below the surface,

and p^2 = a constant depending upon the permeability and the elastic properties of the deposit. ($p^2 = E_p k_p$; where E_p is the bulk modulus, and k_p the coefficient of permeability of the deposit.)

Taking into account the fact that the initial distribution of the excess hydrostatic pressure, h, throughout the depth of the deposit is triangular, with a value of zero at the top, equation (a) integrates into the following expression for the percentage of consolidation:

$$P = 100\left[1 - \frac{32}{\pi^3}\sum_{n=1}^{n=\infty}\frac{(-1)^{n-1}}{(2n-1)^3}e^{-(2n-1)^2Kt}\right], \qquad (b)$$

where P = the per cent of the ultimate amount of consolidation (either settlement or flow) that has occurred up to time t,

and K = a constant depending upon the total depth of deposit D; $K = \frac{\pi p^2}{4D^2}$.

In the process of diffusion, an oxidizable organic compound is transported upward because of a gradient in the concentration of the compound that is created between the interior of the deposit and the surface zone where oxidation is taking place. In this process, depth and specific gravity of the deposit remain essentially unchanged and no flow occurs through the interstices, the movement of oxidizable products being limited to the slow process of molecular diffusion. Formulation of this process stems from the same differential equation that applies to the process of consolidation—as do all processes that depend fundamentally upon thermodynamic principles. Consequently the relation controlling the concentration, C, of a given dissolved constituent may be written as follows:

$$\frac{\partial C}{\partial t} = j^2 \frac{\partial^2 C}{\partial x^2}, \qquad (c)$$

where C = the concentration of a given dissolved substance at any time t and depth x below the surface

and j^2 = the coefficient of diffusion, depending, among other things, upon viscosity of the interior fluid and size of molecules being diffused.



FIG. 11.—Progress of consolidation, diffusion, and retardant unimolecular decomposition, showing similarity of pattern in time.

Taking into account the fact that the initial concentration of the dissolved substance is rectangular, being constant at all depths below the surface, the diffusion that has occurred at any time may be expressed as follows:

$$P' = 100\left[1 - \frac{8}{\pi^2}\sum_{n=1}^{n=\infty}\frac{1}{(2n-1)^2}e^{-(2n-1)^2K't}\right], \qquad (d)$$

where P' = the per cent of the ultimate amount of diffusion taking place in time t; in other words, the per cent of the total amount of dissolved substance that has entered the surface zone of oxidation at time t

and K' = a constant depending upon depth of deposit, D; $K' = \frac{\pi^2}{4}\frac{j^2}{D^2}$.

Equations (b) and (d) have been plotted in Fig. 11, and it may be observed that they are in close agreement with the course of decomposition delineated by the retardant unimolecular equation plotted in this figure. A similarity may also be observed between the general shape of these theoretical curves and the actual curves of benthal oxidation presented in the body of this paper (Figs. 4 and 6). It is probable that both processes occur successively and that the oxidation actually accomplished depends upon the sum of their individual effects.

Industrial Wastes

CHEMICAL PRECIPITATION OF SULFUR DYE WASTES ON A PILOT PLANT SCALE*

By Ralph Porges, Robert K. Horton, and Harold B. Gotaas

Special and Assistant Investigators for The Textile Foundation, Washington, D. C.; and Assistant Professor, Department of Sanitary Engineering, School of Public Health, University of North Carolina

The application of laboratory results to plant operation is a factor often neglected. Various problems arise during plant operation which are entirely overlooked or are insignificant in the laboratory. For instance, such matters as odor concentration and the feasibility of batch or continuous operation are problems that must be decided with equipment larger than that necessary for laboratory studies. Laboratory experimentation permits adequate control, but the question arises as to whether the results so obtained can be duplicated by the plant operator working on a large scale. These difficulties may be overcome, in part, by correlating laboratory data to studies made on a pilot plant scale.

The processing wastes from textile mills are voluminous and when composited may exert a five-day 20° C. B.O.D. of approximately 500 p.p.m. or more. Under such conditions of compositing, the entire waste must receive special treatment, although the greater portion of the volume of the composite waste comes from wash waters which have negligible pollutional qualities. Under specific conditions, the strong and highly colored wastes can be separated from the wash waters. In this way, the wash waters can be discharged into domestic sewers without placing an undue burden on the domestic sewage treatment process, while only the concentrated discharges will have to be handled by industrial waste treatment processes. Although the cost of treating strong discharges is very high, it may be advantageous to treat the small volume of strong waste at a high unit cost rather than a large volume of composite waste at a low unit cost. With this objective in view laboratory studies on the precipitation of textile wastes have been reported (1). Many coagulants were employed to precipitate different types of wastes, including concentrated processing liquors. These studies indicated problems that may arise, some of which are stated below. The solving of these problems is important for the successful operation of a plant treating strong sulfur wastes.

Sulfur dye waste is most economically precipitated by strong acids; however, the production of malodorous hydrogen sulfide, which has toxic properties, should not be overlooked. Color removal is extremely sensitive to the chemical coagulant dosage; and hence proper control

* This research project was carried out under joint sponsorship of the University of North Carolina and The Textile Foundation.

of the amounts of reagent and close pH adjustment are of importance. Chemical precipitation of concentrated wastes produces large volumes of sludge; and since the ultimate problem of any treatment process is the disposal of sludge, large sludge volumes aggravate this problem. It appears that efficient operation is difficult but may be attained through adequate plant control.

Apparatus and Material

A 4,000-gallon detention tank outside the dye house was used as a storage tank for the collection of the waste obtained from the dyeing machines. A drain line from this storage tank was connected to a pump that fed a siphon box in which the liquid was maintained at a constant head by a float valve. The siphon from this box was so arranged as to discharge the liquid either into a hydraulic-jump mixing device or to a mixing chamber containing a mechanical stirrer. Chemicals were added into the mixing device either by a constant head floating siphon or from a constant discharge bottle (2). When lime or copperas were added, air agitation kept the material in suspension. The flocculator consisted of a downward flow circular tank of 12-gallon capacity, equipped with a mechanically operated, variable speed, spirovortex mixer. The settling tank had a total capacity of 95 gal. of which 17 gal. was the volume within the sloping bottom and hopper. The volume of the hopper bottom was assumed to be the sludge capacity; while the remaining 78 gal. was the volume or capacity used as a basis for the calculation of all theoretical detention periods. The inlet trough contained bottom outlets thus causing downward flow. Equal distribution over the width of the tank was assured by a constant head of liquid over these bottom orifices. The supernatant liquor from the tank was discharged over the outlet weir to the waste line. The sludge was withdrawn from within a hopper in the center of the sloping bottom and was piped to sludge-drying sand beds (3). In addition, a series of 8-in. vitrified tile pipes filled with 6 in. of gravel covered with sand to a total depth of 18 in., were also used as sludge drying beds. The apparatus is shown diagrammatically in Fig. 1*a* and 1*b*.

The waste has been described in detail in a previous paper (1). The pigment consists of a sulfur compound and is usually applied onto the cloth with the addition of a solution agent, sodium sulfide. The waste contains the pigment, sodium sulfide, salt, a small amount of caustic soda, and other chemicals in minor amounts. Although the waste varied considerably during the period of experimentation, the analysis averaged approximately as follows:

Color	Deep blue black
Total alkalinity	18,000 p.p.m. as $CaCO_3$
Phen. alkalinity	10,000 p.p.m. as $CaCO_3$
B.O.D.	10,000 p.p.m. (5 day, 20° C.)
Total solids	9%
Volatile solids	23% of the total solids
pH	11.2





FIG. 1*a*, 1*b*.—Schematic presentation of pilot plant for the precipitation of textile wastes.

Since the materials in the dye bath are in solution, the suspended solids content of the waste is very low.

Procedure

The waste was pumped from the dyeing machines to the storage tank immediately after the processing of each roll of goods. After sufficient waste was accumulated, it was mixed and stored preparatory for use. The waste was pumped to the constant-head siphon box at which point a sample was taken for laboratory tests in order to determine the chemical dosage. Chemicals in convenient concentrations were added from the discharge siphons to the waste at the mixing device. All flows were adjustable.

An inclined channel involving a hydraulic jump was used at first for the mixing device. This method of mixing was discontinued because the froth which occurred at the jump ran over the sides of the channel. A mixing chamber with a mechanical stirrer was substituted. The mixture was flocculated and then settled; the effluent was discharged over a weir. The resulting sludge was drawn to sand beds to observe dewatering characteristics.

In these studies, the following tests were made on the indicated materials:

1. Raw waste: pH, total solids, alkalinity, B.O.D., color.
2. Flocculator effluent: pH, suspended solids, settling characteristics.
3. Sludge: pH, suspended solids, total solids, filtrability, sludge index.
4. Effluent: pH, color, suspended solids, B.O.D.

All analyses were performed according to *Standard Methods of Water and Sewage Analysis*. The hydrogen-ion concentration was determined by means of a Coleman glass-electrode electrometer. Filtrability of samples was determined by filtering in an 11 cm. Buechner funnel through No. 202 Reeve-Angel, rapid filtering paper. In all cases, 100 ml. samples were dewatered by maintaining a vacuum of 22 in. of mercury.

Results

Typical results obtained by the treatment on pilot plant scale of sulfur black dye wastes have been summarized in Tables I, II, and III. Table I shows flow characteristics and other pertinent data of the waste and coagulants used in these studies; Table II presents the characteristics of the effluents; while Table III gives data pertaining to the characteristics of the resulting sludges obtained with the coagulants.

In these studies, sulfuric acid was the first coagulant used for the precipitation of the dye waste. Frothing was violent in the mixing channel at the hydraulic jump. This froth, which was produced by all coagulants, was very persistent and foamed over the channel. Hydrogen sulfide was evolved in such large quantities at the point of mixing that it was uncomfortable to remain in the immediate vicinity

TABLE I.—*Coagulant, Waste, and Flow Data*

Coagulant		Sulfur Dye Waste		Coagulated Waste		
Name	Grains per Gal. of Waste	B.O.D.	Color	Rate of Flow g.p.m.	Detention Time in Minutes	
					Flocculator	Settling
H_2SO_4	926	13,600	100,000	0.56	21.0	140
$Fe_2(SO_4)_3$	2,043	11,000	100,000	0.32	37.5	245
$Ca(OH)_2$ and $Fe_2(SO_4)_3$	241 1,850	5,600	100,000	0.83	14.5	94
$FeCl_3 \cdot 6H_2O$	2,035	8,000	100,000	1.07	11.3	74
$FeSO_4 \cdot 7H_2O$	2,840	8 000	100,000	0.62	19.5	125
$Ca(OH)_2$ and $FeSo_4 \cdot 7H_2O$	701 2,435	8,000	100,000	Batch Process		

of the pilot plant. Bulking of the sludge over the effluent weir made it impossible to operate continuously. However, the final sludge dewatered rapidly and formed a dry cake.

Aluminum sulfate (filter alum) produced results similar to those obtained with the use of acid. Large amounts of hydrogen sulfide were evolved, and the filtrability of the sludge was good.

Ferric sulfate (ferrisul) coagulated the waste without odor formation but again settling of the sludge was poor. In one case, the waste was allowed to settle over night and the sludge compacted to about 50 per cent. The following morning continuous operation was started, but, after 3.5 hours operation, the sludge bulked over the effluent weir. Sludge drawn to the sand beds to a depth of 10 in. gave a cake about 3 in. thick in five days and, in spite of heavy rains, it appeared satisfactory for removal. The dried sludge had a total solids content of 22.5 per cent. It is not necessary to dry this material to as high a degree as sewage sludge since readily decomposable matter and humus is absent. The poor settling qualities of the precipitated waste are evidently due to the high suspended solids content. A representative sample of the tank mix showed over 2.2 per cent suspended solids while settled sludge had 4.5 per cent suspended solids.

TABLE II.—*Effluent Characteristics from Treatment Shown in Table I*

Coagulant	pH	Color		B.O.D.		Suspended Solids P.p.m.	Remarks
		Residual	Removal Per Cent	Residual P.p.m.	Removal Per Cent		
H_2SO_4	4.1	300	99.7	2,960	78.2	273	Not filtered
$Fe_2(SO_4)_3$	8.4	1,000	99.0	1,000	89.0	43	
Lime and Ferrisul	8.6	900	99.1	1,100	80.5	16	
$FeCl_3$	8.4	1,100	98.9	1,100	80.5		
$FeSO_4$	9.0	1,200	98.8	800	90.0		
Lime and Copperas	7.1	600	99.4	1,500	81.0		Batch Process

Lime was then used in conjunction with ferric sulfate in an attempt to improve results. However, no improvement was evident, as may be noted in Table II. Sludge obtained from the conjugated lime-ferrisul treatment was applied onto the tile filters in depths of 4.6, 9.2 and 13.8 in., corresponding to 1, 2, and 3 gal. dosages. All sludges cracked overnight, that from the 4.6 in. dose being removable. All sludges were removable on the fourth day; the total solids of the dry samples being 43.1, 28.9, and 25.4 per cent for the 4.6, 9.2, and 13.8 in. depths, respectively. Poorer results were obtained in drying the sludges with the tile filters than with the larger sand beds as the tile filters protected the sludges from sun and wind.

An effort was made to operate continuously by constantly withdrawing sludge. Ferric chloride was used as the coagulant. It was impossible to prevent the rising of the sludge blanket although 50 per cent of the total flow was drained to the sand beds.

Continuous operation was then tried with the use of copperas, but, likewise, did not prove feasible. Difficulty arose in the filtering of the copperas sludge. Effluent from the flocculator applied to the sand beds drained through the filter in a few minutes, but the sludge was not retained and the filter effluent was highly colored. Copperas sludge after flocculation forms a very fine floc that can be retained by sand filters only after the formation of a sludge mat. Since previous laboratory results showed that flocculation may be detrimental (1), another filter was dosed with the waste obtained from the mixing chamber. In this case the sludge was retained and the filter effluent showed good color removal. Evidently, mixing in the flocculator may break up the floc and result in poor filtration.

Lime was then added together with copperas to aid in the formation of a good floc. Dewatering results showed marked improvement. Copperas-lime sludge was applied to three of the tile filters to depths of 4.6, 9.2, and 13.8 inches. The sludge remaining from the 4.6 in. depth dried overnight and left a removable cake. Sludges from the other two filters cracked overnight but were not removable until the fifth day. Unfortunately, rain was plentiful and interfered with the sludge drying tests; hence, one would expect dry weather to improve the drying results.

Discussion

The treatment of strong wastes, such as concentrated sulfur black dye liquor, necessitates close control of all variable factors to obtain economical operation. Maximum color removal is obtained within narrow limits of coagulant dosages and any variation in the flow of strongly alkaline or acid wastes or in the dosage of the relatively concentrated coagulants will upset the chemical balance for optimum precipitation. Since a holding tank is necessary to composite the variable strength sulfur dye wastes, and since difficulties arise in accurately controlling the flow rates of both the waste and the chemical coagulant when using

continuous operation, it appears that the batch process is the more satisfactory method for treating strong, concentrated wastes. The holding tank may be used as a settling tank and the proper amount of coagulant may be added to a known volume of known-strength waste.

The large sludge volumes that occur with these wastes present another difficulty. Optimum precipitation of sulfur dye wastes was shown to depend, according to laboratory tests (1), upon mixing, flocculating, and the proper addition of chemicals, especially if settling of the sludge is to be considered. Similar results were obtained in the pilot plant studies. A short rapid mix, followed by little or no flocculation forms the most compact sludge.

TABLE III.—*Sludge Characteristics from Treatment Shown in Table I*

Coagulant	pH	Suspended Solids P.p.m.	Dewatering Time Seconds (Buechner Funnel Test)	Sludge Index	Remarks
H_2SO_4	5.1		55		
$Fe_2(SO_4)_3$	8.6	45,490	45	22	Settled to 50 per cent
Lime and Ferrisul	8.9	22,590	99	44	
$FeCl_3$	8.5	21,570	45	47	
$FeSO_4$	9.1	7,780	58	128	
Alum	5.1	12,148	70	82	

In Table III are given values for the sludge index of this coagulated waste. The index used is that as defined by *Standard Methods* and is equal to the volume occupied by one gram of sludge. Even though some settling occurred in the half-hour time interval required in making a sludge index analysis, the values given in the table were calculated on the assumption that no settling occurred, and that the sludge volume was equal to the total volume of waste. In the case of activated sludge, a sludge index of 100 or less shows a satisfactorily settling material. This is in accordance with Donaldson (5), whose index was equal to a hundred times the reciprocal of the present index, and who found that in general a sludge index of less than 1.0 indicated an undesirable condition from the standpoint of sludge bulking. Hence, it is seen that even without any settling a quite compact sludge is present.

The addition of coagulating salts increases the weight of the resulting sludge over that obtained by the use of acid alone, as may be noticed in Table IV. Although the increase varied from 82 to 128 per cent in weight, no great difference in the rate of settling in one hour was noticed. Overnight settling showed greater variation, although not so much as would be expected. With the waste used in this experiment, sludge settled overnight to 50 per cent of the total volume. Advantage may be taken of this fact when holding tanks are used to composite the daily waste. The batch can be precipitated and settled overnight, and a swinging effluent line may be used to withdraw the supernatant liquor.

It may be possible, provided a holding tank is used to composite the waste, to treat a given volume continuously. The chemical dosage may then be arranged to precipitate the given waste. A good mixing, followed by filtration should prove satisfactory, since it appears from the results that flocculation may not be necessary and that settling is unsatisfactory. Settling can be practiced only in cases where the necessary inclusion of rinse waters dilutes the waste, because the coagulated solids settle rapidly in dilute wastes where there is little or no effect of compaction. Hence, settling may be practical when the coagulated waste contains less than 6000 to 8000 p.p.m. suspended solids.

TABLE IV.—*Per Cent Increase in Weight of Sludge Produced by Various Coagulants—Acid Sludge Considered as Unity*

Coagulant	Per Cent Increase in Weight of Sludge	Per Cent Sludge to Total Volume	
		1 Hour Settling	Overnight Settling
H_2SO_4	0	81.5	30.3
$Al_2(SO_4)_3$	114	95.0	54.5
$FeCl_3$	87	82.8	41.6
$Fe_2(SO_4)_3$	82	80.0	37.0
$FeSO_4$	128	89.0	58.3

In the case of strong wastes, filtration is very important since the maximum concentration of the sludge by settling is 50 per cent of the total flow. Dewatering is very rapid and no difficulties should be experienced. In view of the rapid filtration of the sludge, it appears possible, when treating strong concentrated wastes, to dewater the entire waste on vacuum filters or sand beds and eliminate the settling tank.

Acid and alum should not be used to precipitate sulfur dye waste unless special precautions are taken to remove the evolved malodorous and toxic hydrogen sulfide. The toxic effects are appreciable as the authors noticed the ill effects caused by the hydrogen sulfide even with the small quantities of waste treated. Control of odors is often overlooked in waste treatment. (At least one plant comes readily to mind where acid and alum used in the treatment of a waste containing sulfur dye liquor created a nuisance because of odors. It is not the best policy to prevent one nuisance and in doing so create another.)

Iron salts coagulate the sulfur wastes very satisfactorily without the production of odors. Evidently a non-volatile sulfide is formed. Lime used in conjunction with the coagulants may aid in the production of a floc.

Previous laboratory results predicted the present findings very closely (1). The main discrepancy was in the color removal data. Better results were obtained in the laboratory, which fact can be accounted for probably by the ability to control conditions more accurately. Possibly better results may be achieved on a large scale basis than on a pilot

plant basis, as control may be better in the former. Another consideration is that a composite dye waste discharged by a mill will not be quite so strong as the waste handled in this experiment because of the inclusion of the highly-colored, first rinse waters.

The large amounts of chemicals required for coagulation and the large sludge volumes produced indicate the interesting possibilities of recovering and re-using the coagulants and the dye. Preliminary studies on the re-use of sludges have been made. Acid precipitates the pure dye and excellent results are obtained on re-using the dye. The other coagulants interfere with the dyeing process but this difficulty is eliminated by removing the coagulants from the sludge. The reclaimed chemical coagulants can be re-used to precipitate more waste. Rudolfs and Kessener (4) describe a plant which treats textile waste and sewage, wherein the sludge is treated with acid to recover the alum. More economical treatment of those industrial wastes that require large amounts of coagulants is possible if recovery and re-use of materials is practiced. Should the hydrogen sulfide difficulty in acid precipitation be overcome, the acid treatment of the dye waste with the re-use of the precipitated dye may be an acceptable method of treating sulfur dye wastes. Some of these problems have been investigated and are being prepared for future presentation.

Summary

Pilot plant studies on the chemical precipitation of sulfur dye waste were inaugurated in order to correlate laboratory studies to plant operation and to determine the difficulties that may arise from large scale operation.

It appears that laboratory studies give a close indication of plant operation. Laboratory results may be slightly better than pilot plant studies because of the possibility of more accurate control. An example of this is color removal.

The fill-and-draw method of operation appears to be more feasible than continuous operation when precipitating strong wastes.

Continuous operation may be practical when treating a waste that has been diluted several times with wash water, as this type of waste will have less suspended solids and settling is satisfactory.

Acids and alum should not be used to precipitate sulfur wastes unless precautions are taken to control the hydrogen sulfide.

Iron salts such as ferrisul, ferric chloride, and copperas can be used with this type of waste without the evolution of hydrogen sulfide. Flocculation is detrimental to the copperas floc and must be kept to a minimum. Lime aids in the production of a floc with copperas.

Dewatering is important because of the large sludge volumes. Maximum sludge concentration was approximately 50 per cent. The high content of suspended solids of the treated liquor preclude further compaction. Filtering the entire coagulated mixture appears satisfactory, especially since dewatering is rapid.

The large chemical dosages required and the large volumes of sludge produced indicate that recovery of both the coagulant and the dye may be practical. Preliminary studies of the re-use of precipitated dye and the recovery of the coagulants confirm these indications.

ACKNOWLEDGMENT

The authors wish to express their sincere appreciation to Dr. H. G. Baity of the University of North Carolina for his cooperation in this work, and to Dr. Nandor Porges, By-Products Laboratory U. S. D. A., Ames, Iowa, for his helpful criticisms.

BIBLIOGRAPHY

1. Horton, Porges and H. G. Baity, "Chemical Precipitation of Textile Wastes and Studies of pH Control," *This Journal*, 9 (September, 1939).
2. E. F. Eldridge, "A Further Study of Milk Waste Treatment," *Mich. Eng. Exp. Sta., Bulletin* 77 (November, 1937).
3. M. S. Campbell, "The Disposal and Recovery of Textile Waste Liquors," *Textile Research*, 5 (November, 1934).
4. W. Rudolfs and H. Kessener, "Some New Developments in Sewage Treatment in Holland," *Water Works and Sewerage*, 86 (May, 1939).
5. W. Donaldson, "Some Notes on the Operation of Sewage Treatment Works," *This Journal*, 4, 48–59 (January, 1932).

Operators' Reports and Suggestions

W. D. Hatfield

249 Linden Place, Decatur, Ill.

SEWAGE PUMPING INSTALLATIONS AND MAINTENANCE *

By Newell L. Nussbaumer

This discussion approaches the subject of design more from the operator's standpoint than the engineer's, and calls attention to features which, if incorporated in the design, will facilitate proper operation. There is a great need, particularly in small plants, for cooperation between operators and engineers in preparing designs.

The cause for pumping in a sewer system or at a treatment plant is, of course, obvious: to lift sewage from a lower to a higher level to permit outfall to some final point of disposition.

For strictly sanitary or domestic sewage, the fluctuations in flow are not too great and can be reasonably calculated by the designer. When storm flow is also involved, the calculations cannot be as exact, the fluctuations are far greater, the maximum being possibly thirty times the dry weather flow. The third case is the worst, when storm flow is permitted to enter a sanitary system where neither the sewers nor the pumps were intended for such service. In such a case, a by-pass is probably the most frequent solution.

The New York State Department of Health now has some rather rigid requirements for pumping installations which are in the operators' interests, among which are the following:

(*a*) Main pump stations must have at least three pumps.

(*b*) With the largest pump out of service, the other two must be able to pump the maximum flow.

(*c*) Sizes should be proportioned to anticipated flows.

(*d*) Power should be available from two sources where electric power is subject to interruption.

(*e*) Secondary lift stations should have duplicate equipment.

(*f*) Screening devices should, in general, be placed ahead of the pumps.

(*g*) Pumps should be located in a dry well.

If these requirements are all observed, a very good start has been made towards a good pump station. However, there are many stations in this district which were built before these regulations were in force.

* Presented at Meeting of Western New York Section, New York State Sewage Works Association, Dec. 14, 1940.

It is interesting to comment on some of these, and from the mistakes observed, formulate further principles of good practice.

A pumping installation to be inclusive should be considered jointly with such structures or equipment as affect the quality of sewage to be pumped, and the efficiency of the pumps themselves, which includes screen and grit removal facilities.

Basket screens and bar screens, located so as to be very difficult to clean, were frequently installed. These screens have two principal objections: They clog easily, often because the operator cannot clean the screen and dispose of the screenings without unusual exertion.

Therefore, let us say:

A bar screen, or other screening device, should be located to permit ready cleaning, and some easy way provided to dispose of screenings. Where the size of installation warrants the expense, mechanically raked screens with grinders, or a comminutor installation, is recommended.

A grit chamber ahead of pumps reduces wear on the pumps, particularly in a combined sewer system. However, if the invert elevation is rather deep in the ground, say twenty feet or more, the economics of additional wear on the pumps as against cost of the grit chamber installation should be studied. There are recent installations of both types near here which have been operated satisfactorily. When the grit chambers are placed after the pumps, the wearing rings on the pumps should be made of hardened steel, and water under pressure used in the stuffing boxes. It would be advisable when buying the pumps to inform the pump manufacturer of the conditions. Adequate facilities should also be provided for removing grit to a point of final disposal, such as craneways, or mechanical grit removal devices. In many of the older installations, the wet wells were designed too large, so that large quantities of grit and organic matter deposited in them. It is important that the velocity in a grit chamber be controlled by proportional weirs, a following Parshall flume, or other device.

From the grit chamber, sewage flow generally enters the pump wet well in which the pump suctions are located. Where three or four pumps, or more, are to be installed, probably the wet well should be divided into two sections which can be used jointly or separately to facilitate cleaning and repairs. The size of the wet well should be such as to permit pump operation without too frequent stopping and starting, and at the same time not provide a sedimentation basin. We have encountered several where the period of detention in the wet well was even greater than in the primary sedimentation tanks at the sewage treatment plant. The floor of the wet well should be sloped toward the pump suctions. If an operator has a well with a flat bottom, this can be corrected easily by installing a fillet of concrete. The wet well should also provide sufficient depth so the pumps will be primed at average pumping level in the wet well.

The pump operation will probably be controlled by a float switch operating from the levels in the wet well. This float tube should be located in such a way that the float and cable can be replaced if neces-

sary. A float and cable of non-corrosive material is advisable to avoid frequent replacements. It is quite helpful to an operator to have a wet well depth indicator near his control panel. This may be a part of the float switch, or a separate instrument.

Proper ventilation should be provided for a wet well to prevent condensation, and to remove foul odors and corrosive gases. There is one case nearby where oils and gasoline are frequently found in the entering sewage in objectionable amounts. In such cases, where an explosive mixture might develop, ventilating, or other equipment, should all be provided with explosion-proof electrical motors and starters. Adequate lighting should also be provided in a wet well and a safe means of access. Too frequently a narrow, steep, ladder, which is frequently wet and slippery, is the only means of descending to a screen platform.

The discussion of pumping equipment will be limited to centrifugal pumps as practically all sewage pumps in use in this district are of this type.

The major portion of present installations, except for a few of the larger plants, are all vertical, submerged pumps in a dry pit, driven through shafting by a motor located on the ground floor level of the pump station. In a number of cases, the shafting is twenty-five or more feet in length, requiring a large number of intermediate supports. Again, a fairly safe way to develop rules for good installations is to discuss the faults found in some of the older ones which have proved difficult and expensive to operate.

In some cases, the shafting has not been sufficiently rigid to prevent whip, or the bearings have worn to allow it. The bearings have been oil lubricated, and generally the oil applied too freely. The result is a well oiled pump room from top to bottom. There are several things which can be done to improve this kind of an installation:

(*a*) The motors can sometimes be lowered to a level above high water which is considerably below ground floor level, thereby reducing the shaft length.

(*b*) Grease lubrication can be substituted for oil lubrication. In this connection, it is further found to be more satisfactory to provide access for inspection to the point of lubrication, rather than a length of tubing with a pressure type grease fitting at some remote point.

(*c*) In some cases, heavier shafting of the Watson-Spicer or Dodge type can be installed with a reduction of points of intermediate support and number of intermediate bearings.

A clean-out hand hole should be provided in the pump or suction elbow so that clogging material can be removed.

Pumps should be located so that they will prime when starting. However, it may happen that due to turbulence in the wet well, or other reasons, the pump may become air bound or lose its prime. An air release valve should be provided at a high point in the casing to permit the release of air.

Gauges on the suction and discharge side of the pump are helpful in watching the operation, and may be the means of quickly indicating a clogging of the piping or falling off in efficiency of the pumps. An operator should have on hand a set of pump curves for the pumps under his care, so he may observe the pump operation for variations from intended performance.

Of course, a high efficiency is desired in a pump. However, this may sometimes be obtained at the expense of free openings and tight clearances so that a pump will clog more easily. A pump in sewage service should give steady and reliable operation primarily. If the pump must be removed from service, often due to characteristics producing high efficiency, then a less efficient but more reliable pump would be preferred.

Slow speed pumps, particularly in the larger sizes are desirable. To reduce the size of the motors and the cost, sometimes geared motors are used, which operate at several times the pump speed. It goes without saying that the pump should be designed for the proper heads, and the size chosen to conform with the anticipated flows. However, sometimes due to lack of knowledge, or an attempt to use an old pump for a new purpose, or the changing of the cycle of a motor without changing the pump impeller for the change in speed, or other reasons which may occur to you, an improper pump is installed. This pump, in the interest of economy, should be replaced with a proper unit.

In an effort to provide maximum flexibility of pump capacity with a minimum of units, and to eliminate the stopping and starting of the pumps, two speed or multiple speed motors are used so that after a pump is placed in operation, by increasing or decreasing the speed, its capacity can be altered to fit closely with the rate of flow.

Where a second source of power is required, a gasoline engine is frequently provided directly connected to the pump shaft through a right-angle gear drive unit so that either the motor or engine can be used by operating a clutch.

In other cases, a separate pumping unit is provided with a gas engine drive. On the Niagara Hudson system near Buffalo, the interruptions to service are so infrequent that generally a second source of power is not deemed necessary.

There is now an increasing tendency to use vertical lift, horizontal type pumps with some sort of vacuum priming. While there are not many in this district, some of the larger and more recent pumping installations are of that type. Examples are Gary, Indiana, and the Blue Plains plant at Washington, D. C. Situations where the suction lifts do not exceed 15 ft. are particularly adapted to this type of pump. The advantages are the ability to place the pumps and motors direct connected above high water, the reduction in space required at a lower level, greater ease in maintenance.

Ejectors are now also finding increased use where the handling of screenings would be difficult, and the heads are not high or the capacities

large. Very good performance can be expected under 30 ft. head and up to 350 g.p.m.

Piping to and from the pumps is important. The piping itself should be properly sized. Couplings in strategic locations should be provided to assist in dismantling the piping in case of repairs. No air pockets should be formed in the suction lines. A check valve of the non-slam type on the discharge side should be provided with free opening equal to the main pipe size. Gate valves should be placed in the suction and discharge lines to permit removing the pump from service without interfering with the other pumps. Adequate supports should be provided for the piping so that the load is not transmitted to the pumps.

Where the valve location makes operation difficult, special means such as chain falls, cat walks, or extension operating stems, should be provided to assist the operator in turning the valve, and an indicator should be provided to show the position of the valve opening.

A sump pump should be provided in the pump room to keep the floor dry. This pump can also be used to dewater the wet well in case of repairs, if the proper pipe connections are made.

We recommend that the pump room should be well ventilated, painted a light color which will reflect light, and can be easily cleaned, and should be well lighted. In addition, wall plugs should be located at convenient points for trouble light use or electric tool operation.

An operator should know the volume of flow pumped by his equipment. This knowledge can be secured in a number of different way. Two of the most common are the Venturi meter and the Parshall Venturi flume. Both have their advantages. The Venturi throat placed in a pipe line, particularly where adequate screening has not previously been provided, is very likely to clog particularly in the smaller sizes. If the lengths of pipe required ahead of the throat are such as not to give accurate measurement, and straightening vanes are used, they too will probably clog. The Venturi flume is a larger structure, is usually placed above ground, and to its advantage rarely clogs, but if such occurs, is readily cleaned. The recording of flows will probably be on an instrument mounted on or near the control panel. We recommend the type with recording, integrating, and indicating features so that an operator can secure information for making out reports, and readily check operation with a minimum of time and effort.

The control of pump operation is, of course, accomplished with the electrical control equipment. This is much more satisfactory, and frequently very little more expensive, if mounted on a panel where all the equipment and instruments can be together. Often, in smaller plants, the operator is not a skilled electrician. Operation is, therefore, safer in this type of plant by pushbuttons with indicating lights than the pulling of various starters and breakers. In case of trouble, a proper mechanic can be called to make the repairs. The panel is probably most convenient if located on the ground floor, with a good light, and not too close to a lane of common travel. Any high voltage equipment

should be safely screened off. The control room will present a pleasing appearance if finished with floor tile, and interior brick which will not require painting. The cost should not be excessive. Much time and expense in maintenance is saved with this type construction. If a building presents a pleasing appearance in the beginning, then there is a better chance of maintaining it in good condition in the future.

Safety protective devices and guards should be installed where needed such as around shafting at an intermediate floor. A telephone in the pump station is convenient in case of breakdown so the operator can make a report at once. Where a station is placed on automatic operation, some device should be provided so as to notify the proper parties in case of a failure. Lacking such a device, fairly frequent inspection should be provided. Overload and undervoltage protection should be provided for the motors. As a further protection, it is well to have the motor of such size that it will not be overloaded at any point in the pump curve by over 10 per cent.

Cranes, hoists, or other similar equipment should be provided, and access to openings allowed so that various items of equipment can be installed in the first place and removed later for repairs.

Where there are many small pipes in use, such as heating, hot and cold water, vacuum lines, etc., a schedule of colors for the pipes is helpful.

There are on the market now a number of special designs of pumps for particular circumstances. The mixed flow pump is a centrifugal pump particularly adapted for pumping large capacities at low heads with high efficiency. The screw propeller pump is a pump combining a feature to chew up rags and solids in the sewage before the flow enters the pump. There are now on the market several pumps with built-in vacuum priming systems.

In buying new pumps, it is advisable to specify that the unit shall have had a factory test, so that it is known that the various parts of the unit will fit together.

This discussion has outlined the major points considered in a pumping installation. Some operators have in their charge all of the facilities mentioned. Others have some, and would, no doubt, have better operation with the inclusion of those features which they lack. Some details in pump construction have been purposely omitted because the discussion of this paper is to be led by Mr. Allen Hopper of the Turbine Equipment Company whom I know is exceptionally well qualified to advise you on the details of construction.

Discussion

Mr. Hopper pointed out the advantages of wearing sleeves in the casing and on the impellers. These sleeves are readily replaced at little cost and materially increase the life of the pump. He further pointed out that the reason a customer frequently gets an unsatisfactory

pump is because the specifications are inadequate. Pump manufacturers are anxious to sell their pumps. When the selection is to be made on a price basis, they, of course, bid on their cheapest line, and omit all but the bare essentials, even though they have a more suitable pump, which over a period of years might prove more economical, even though the first cost is high.

The pump manufacturer would much prefer to sell the best pump for any particular situation. Therefore, it is urged that in taking bids for pumping equipment:

First: A fairly complete description be given under which the pump is to operate, and

Second: A description of the type of pump, together with drive and control equipment, be included.

Mr. Hutcheson—Operator in Charge-of-Plant, Newark, New York

Mr. Hutcheson inquired as to how far a description of the pump should go. His feeling was that if too much were included, the specifications would be limited to a comparatively few, or possibly only one manufacturer.

Mr. Hopper answered that the best way was to include, in general, only those points which involve good construction and without which a pump would not be considered satisfactory.

Mr. Youngs—Operator at Town of Tonawanda No. 2 Plant

The question was asked as to arrangement of piping on suction side of pump, particularly with regard to reduction in pipe size. The answer was to use an eccentric reducer to eliminate air pockets.

Mr. Velzy—Works Superintendent, Buffalo, New York

Engineers, when drawing specifications, particularly in regard to existing plant extensions where an operator is in charge, should consult with the operator regarding requirements and equipment to be supplied. He also advocates the periodic checking of all equipment operation.

SPRINGFIELD SANITARY DISTRICT'S ANNUAL REPORT FOR 1939

By C. C. Larson, *Chemist*

In 1929, the Springfield sewage plant was placed in operation. Ten years later, in the annual report, are shown photographs of the plant in 1929 and in 1939. Some of these are reproduced, herewith.

A nine year summary of data is shown in Table I, and Table II gives a log of important events.

TABLE I.—*Statistical Summary*

Yearly Totals	1931	1932	1933	1934	1935	1936	1937	1938	1939
Connected population	70,000	70,000	70,000	70,000	72,000	75,000	75,000	80,000	85,000
Population equivalent	67,975	74,268	66,700	72,525	62,104	74,166	79,362	70,373	74,717
Sewage treated—in million gallons	2,308	2,811	2,396	2,303	2,471	2,316	3,066	2,779	2,677
Air consumed—in million cubic feet	1,424	2,445	1,922	2,133	1,850	1,933	1,820	1,906	2,011
Solids added to digesters—in million pounds	2.25	3.27	2.77	3.50	3.10	3.99	4.70	3.82	3.81
Volatile solids added to digesters—in million pounds	1.40	2.00	1.78	2.25	1.93	2.64	3.09	2.39	2.50
Dry sludge produced—in tons (50% moisture)	1,025	1,475	1,178	770	959	1,114	1,075	1,470	1,182
Gas produced—in million cubic feet	14.86	13.79	14.82	19.66	18.36	22.35	20.12	21.37	22.58
B.O.D. in raw sewage—p.p.m.	187	168	152	181	128	188	151	159	170
B.O.D. % removal	67	90	91	91	94	92	91	91	91.6
Miscellaneous Factors									
Gas—in cubic feet per capita per day	.58	.54	.58	.77	.71	.83	.74	.73	.73
Gas—in cubic feet per million gallons of sewage treated	6,477	4,906	6,184	8,535	7,582	9,650	6,562	7,690	8,434
Gas—in cu. ft. per pound of solids added to digesters	6.62	4.22	5.36	5.61	6.04	5.60	4.28	5.60	5.92
Gas—in cu. ft. per lb. of vol. solids added to digesters	10.62	6.90	8.23	8.72	9.71	8.46	6.51	8.95	9.03
Per cent reduction of suspended solids in digesters	42.5	26.6	38.7	32.7	37.2	36.2	45.3	30.1	31.4
Per cent reduction of volatile solids in digesters	64.6	47.9	59.4	52.0	60.9	58.0	65.6	51.1	52.9
Suspended solids in raw sewage, lb. per capita per year	48.8	53.7	42.8	54.1	45.9	55.8	66.9	51.3	48.0
Suspended solids in pounds per million gallons of sewage	1,483	1,356	1,250	1,643	1,338	1,807	1,636	1,476	1,523
Cost—per million gallons of sewage treated	$14.45	$12.11	$12.61	$11.93	$12.16	$13.36	$11.91	$16.88	$15.90
Cost—per capita per year	$ 0.48	$ 0.53	$ 0.41	$ 0.39	$ 0.42	$ 0.41	$ 0.49	$ 0.59	$ 0.50

TABLE II.—*Log of Important Events*

Jan. 9. Established a new record for gas production; 114,400 cubic feet.

Jan. 25. Flooded our sunken garden with digested sludge in an effort to fertilize the grass. Am afraid we overdid it.

Jan. 30. Very heavy snowfall. All roads blocked.

Feb. 24. Due to poor gas production we were forced to turn in an electric blower for the first time in four months.

Mar. 1. A bad flash over on the electric switch board ruined several current transformers and caused serious damage to other equipment. There are too many automatic features about this board.

Mar. 6. Took first sludge of the season from the drying beds.

Mar. 12. High water in Spring Creek backed up into our main outfall. On the one occasion in ten years that we had use for the valve closing off the outfall it refused to close. Plant by-passed for 24 hours.

Apr. 15. One of the main drag chains in the Link Belt secondary tank broke and was replaced by a new chain. These chains have been in service 7½ years.

June 8. Activated sludge is behaving badly.

July 10. Sewage Works dedicated ten years ago today.

June 27. Burned out a bearing on large electric blower, due to failure of oil pump. Small electric blower back in service after flash over on March 1.

Aug. 1. Trustee J. A. Van Nattan resigned from Board and Roger E. Chapin was appointed to fill the vacancy.

Sept. 7. Activated sludge is very bulky and the sludge blanket rose to the weir crests of the secondary tanks today.

Sept. 18. Reduced flow to aerators to improve the activated sludge.

Sept. 20. Drew two beds of sludge using alum as an experiment.

Sept. 26. Drag chains in Link Belt Primary tanks No. 2 and 3 broke and were replaced by new chains. These chains have been in service 10 years.

Oct. 2. Switch board blew up again. This is getting to be a habit.

Oct. 8. Heavy rain today broke a 47 day drought. Needless to say it was welcome.

Nov. 9. Replaced main traction wheel on Dorr primary tank.

Nov. 20. Sludge index is down to 80 after a prolonged period of bulking.



General view of treatment works when placed in operation.

Same view after ten years.



Main building in 1929.



Main building, ten years later.

Editorial

A MORE USEFUL FEDERATION

The reorganization of the Federation is now well under way and the various member associations are considering the new Constitution and By-laws as they affect the local groups. The most important change to be considered by each local group relates to the classification of its members as active members of the Federation, whose dues will be three dollars per year in 1942. Each association is given the privilege of determining the number of its members who wish to continue to be active members of the Federation. They will receive all publications of the Federation and may serve on its Committees and vote in its elections. Affiliate members remain members of the local association, and pay their local dues, but are members of the Federation in name only.

Active members must therefore pay three dollars per year after 1941, in place of the $1.50 they are paying this year.

The Federation plans to offer considerably more service to active members than has heretofore been possible. Our new and capable Executive Secretary, Mr. Wisely, is bending every effort to make the Federation's services more valuable to the average plant operator. He is planning to broaden the Operators' Section in the SEWAGE WORKS JOURNAL, so that it will be of increased interest and value to the operator. He is soliciting information from operators all over the country as to their problems and experiences. He plans to visit as many meetings as possible in order to obtain first-hand information on operators' problems.

For several years the Federation officers have stressed the need for economic aid to the operators of small plants. State boards of health have been trying for years to raise the status, both technically and financially, of sewage works operators; local associations have also sought to improve the stability and economic independence of their operators; now the Federation will add its influence to standardize and equalize, as far as possible, the status of operators throughout the country.

The Federation plans to extend its committee activities and will publish, from time to time, reports of the Research, Standard Methods, and Sewage Works Manual Committees. Other committees might well be organized, possibly on Cost Data, Operators' Ratings, Annual Reports, and Maintenance of Sewerage Systems.

It is the intention to make the functions of the Federation so much more attractive to operators that they will be glad to pay the slight additional fee of $1.50 per year, in order to remain as active members, to whom all publications and benefits of the Federation will be available. It is too bad that in many parts of the country operators of small sew-

age works are paid so little that any expense beyond the necessities of life is a sacrifice. It is to be hoped that the concerted efforts of the Federation, the local associations, and the state departments of health will result in improved status and increased salaries for these men.

The Federation, as a more closely integrated organization, now faces a new duty, namely, to give consideration to the problems of defense and military development within the next few years. Sewage disposal is second only to water supply as a national public health problem, and the Federation should prepare to make its influence felt more strongly than heretofore in the country's defense plans.

In order to carry on the fine record of development of the Federation to date, officers of local associations should do everything possible to keep the members of their local associations in the Federation as active members. It will take time to demonstrate the value of the plans now under way to improve and enlarge the functions of the Federation, but in future years those who have remained with the Federation will not regret it.

F. W. Mohlman

Proceedings of Local Associations

IOWA SEWAGE TREATMENT CONFERENCE AND IOWA WASTES DISPOSAL ASSOCIATION

Twenty-second and Fourteenth Meetings, Respectively

Iowa State College, Ames, Iowa, November 7–9, 1940

The twenty-second Iowa Sewage Treatment Conference was held in Ames on November 7, 8, 9, 1940, under the auspices of the Iowa State College and the Public Health Engineering Division of the State Department of Health. One hundred and ten superintendents and operators of sewage works, municipal and sanitary engineers, and city officials were present from fifty-one municipalities.

The program opened Thursday morning, November 7, with Conference Director L. J. Murphy presiding. A. H. Wieters, Director of the Public Health Engineering Division of the State Department of Health, gave an interesting and informative discussion of the present sewage treatment situation in Iowa together with the trends and new developments in the field. The problem of handling and disposing of grit was discussed by Paul Winfrey, superintendent of the Des Moines Sewage Works, and Charles Wilson, superintendent of the Waterloo Sewage Works. The matter of "Eliminating Health Hazards at Sewage Treatment Works" was then discussed by Paul Houser, Assistant Engineer of the Public Health Engineering Division of the State Department of Health with a great deal of interest to everyone present.

The afternoon program opened with the presentation of a topic of general concern to Iowa Municipalities, "The Nuisance Liability of Cities," by Alan Loth, Attorney of Fort Dodge. The rest of the afternoon was devoted to a practical study of "Sewage Settling Tank Performance" led by Earle L. Waterman, Professor of Sanitary Engineering, State University of Iowa; "Sludge Digestion Tank Operation" by Charles D. Mullinex, Public Health Engineering Division, State Department of Health; and "Methods of Sludge Disposal" by John C. McIntyre, superintendent, Cedar Rapids Sewage Works.

An interesting discussion of "Mechanical Devices in Treatment" by C. P. Lewellen, of the H. R. Green Co., Cedar Rapids, B. K. Hartman, Link Belt Co., Chicago, and W. B. Marshall, Chain Belt Co., Milwaukee, opened the Friday morning program. This was followed by a talk on "Hydraulic Problems in Sewage Disposal" by W. E. Galligan, Civil Engineering Department, Iowa State College. Dr. Max Levine, Professor of Bacteriology and Sanitary Bacteriologist of the Engineering Experiment Station, then presented a scholarly paper on "The Role of the Trickling Filter in Sewage Treatment." Research tests on "The

Efficiency of Rotary Sewage Distributors" were discussed by Professor Earle L. Waterman with interest to the group.

"Sludge Gas Utilization" was the topic first on the list in the guided discussions of the afternoon. This was started by T. R. Lovell, Superintendent of the Fort Dodge Sewage Works, and Charles Wilson, Superintendent of the Waterloo Sewage Works. W. H. Wisely, Engineer-Manager of the Urbana-Champaign Sanitary District, then directed a lively discussion on "Nuisances—Flies, Weeds, Odors, Pooling." A common-sense, informative talk on "Maintaining Good Public Relations" concluded the afternoon program.

Saturday morning was devoted to a series of practical discussions on plant operation problems. W. H. Wisely directed the exchange of ideas on "Maintenance—Keeping the Plant in Operation" with real benefit to the group. The possibilities of "Garbage Disposal in Conjunction with Sewage Treatment" were presented by Professor B. A. Whisler of the Iowa State College Civil Engineering Department. Helpful ideas on "Landscape Treatment of Sewage Works" were brought out in an illustrated talk by Professor John R. Fitzsimmons of the Iowa State College Landscape Architectural Department. The Conference concluded with a round table discussion of "Sewage Plant Tests and Results" under the direction of George C. Ahrens of the Public Health Engineering Division of the State Department of Health.

The Fourteenth Annual Convention of the Iowa Wastes Disposal Association opened with a Dutch Lunch and Smoker, Thursday Evening, November 7, following the first day's sessions of the Iowa Sewage Treatment Conference.

The annual business meeting was called to order Friday afternoon, November 8, at 3:30 P.M., by President Elmer E. Dye. The reports of the Secretary-Treasurer were read and approved. Financial reports of the business of the Association during the past year were passed out to the members.

The proposed reorganization of the Federation of Sewage Works Associations was then introduced for consideration of the members. The two Iowa representatives to the Board of Control, Max Levine of Ames, and Earle L. Waterman of Iowa City, had both attended the October 5 meeting of the National Federation in Chicago, and they were asked to report. They explained the financial and business status of the Federation and gave the reasons for reorganization. Proposed changes in the Constitution and organization of the Federation were taken up and discussed item by item. The matter of a raise in Federation, and thus State, dues was discussed at length with many feeling that an increase might have a serious effect on the membership in the Association of representatives from the smaller communities. It was agreed that dues to these members should be kept as low as possible. On motion the Association voted to approve the proposed reorganization as contained in the new Constitution with revisions as suggested by Dr. Levine's Committee. The Executive Committee of the Iowa Wastes

Disposal Association was instructed by a second motion to revise the Constitution and By-laws of the State Association to conform to revised Federation requirements.

The Committee on Licensing, through T. R. Lovell, made a comprehensive report of its investigation of Licensing of Sewage Works Operators in other states. They stated that in general the results have been good. The report was highly commended, and upon motion the Committee was continued and asked to bring in definite recommendations on Licensing of Operators in Iowa Plants.

The selection of officers for the coming year then followed with the following being unanimously elected:

President	George C. Ahrens, Des Moines
Vice-President	T. R. Lovell, Fort Dodge
Director	Paul Winfrey, Des Moines
Director	R. G. Miller, Vinton
Representative to the Board of Control, Federation of Sewage Works Associations	Earle L. Waterman, Iowa City (To serve until reorganization of Federation)
Representative to the Board of Control, Federation of Sewage Works Associations	Max Levine, Ames (To continue as Iowa Association representative)

The business meeting then adjourned.

The annual dinner was held Friday Evening, November 8, at the Iowa State College Memorial Union. Guest speaker was Colonel E. B. Bush of Ames, who spoke interestingly on the topic, "Sanitation in and about Army Camps."

LINDON J. MURPHY,
Secretary-Treasurer

NEW YORK STATE SEWAGE WORKS ASSOCIATION

Thirteenth Annual Meeting, New York, N. Y., January 16–18, 1941

The thirteenth annual meeting of the New York State Sewage Works Association was held in New York City, January 16–18, 1941, with headquarters at the Hotel McAlpin. Over 300 members and guests were registered.

Professor M. L. Malcolm, Director of the School of Civil Engineering at Cornell University, Charles R. Velzy, Works Superintendent of the Buffalo Sewer Authority at Buffalo, and Lawrence L. Luther, Commissioner of Sanitation at Freeport, were elected to the Executive Committee for a period of three years. Mr. Herbert H. Wagenhals of

Syracuse was elected President and Mr. Robert C. Wheeler of Albany Vice-President. Mr. A. S. Bedell of the State Department of Health, Albany, was reappointed Secretary-Treasurer. Mr. J. C. Brigham and Mr. Arthur W. Eustance of Albany were appointed Assistant Treasurer and Assistant Secretary, respectively, for the ensuing year.

The program was arranged so that the members of the Sewage Works Association were able to attend all the Thursday sessions of the Sanitary Engineering Division of the A. S. C. E. And in like manner the members of the A. S. C. E. attended the technical sessions of the N. Y. S. S. W. A. on Friday and the joint inspection trip on Saturday.

At the general business meeting on Friday it was noted that the Association now has a membership of over 700 and that the Executive Committee had approved the formation of the Central New York Section, making a total of five local sections in the state. The reports of the activities of these sections and of the various standing committees were presented and considerable interest evinced.

At the technical sessions on Friday morning Mr. Earl Devendorf, Assistant Director of the Division of Sanitation of the New York State Department of Health, presented a paper on "Achievements in Sewage Treatment in New York State During the Past Decade." This paper gave a wealth of statistical and interesting construction data but time did not permit much discussion.

At the luncheon Messrs. George E. Symons and William L. Torrey of the Buffalo Sewer Authority were presented with the Kenneth Allen Memorial Award for 1940 for the most meritorious paper of a technical and research nature.

Mr. Nicholas Miljevic of Lackawanna was presented with a similar bronze plaque for the most meritorious paper covering the solution of certain operating problems at the City of Lackawanna sewage treatment plant.

Mr. C. George Andersen, the retiring President, was presented with a gold key bearing the emblem of the Association.

In the afternoon session Gordon M. Fair, Professor of Sanitary Engineering of Harvard University, presented a very scholarly paper on "The Effects of Sewage Sludge Deposits on the Quality of Streams," which aroused considerable discussion and is the forerunner of a series of studies. Following this, Charles R. Velzy, Works Superintendent of the Buffalo Sewer Authority, presented a paper on "Public Relations in the Construction and Administration of Sewerage Works," and Rodney E. Cook, Sanitary Engineer of the Suffolk County Department of Health, gave a paper on "Operating Experiences at the Riverhead Activated Sludge Sewage Treatment Plant."

In preparation for the inspection trip on Saturday, Mr. Richard H. Gould, Acting Deputy Commissioner of the Department of Public Works of New York City, spoke on "Present Status of Sewage Treatment in the Boroughs of Queens and Brooklyn," which was illustrated with many lantern slides.

Friday evening the members of the N. Y. S. S. W. A. and of the Sanitary Engineering Division of the A. S. C. E. enjoyed their usual annual banquet and were greeted very graciously by Frederick H. Fowler, President-elect of the A. S. C. E.

After the dinner the group listened spellbound to the experiences in the war zones of Europe as related by Robert C. Campbell, representing the Dorr Company in Holland, and S. R. Williams, representing the Worthington Pump and Machinery Company in France and Spain.

On Saturday a joint inspection trip was made by 130 persons in some 40 private cars and cars furnished by the city. This was a quick trip through the Midtown Tunnel, a comprehensive view of the marginal areas of Brooklyn and Queens, Owls Head Sewage Treatment Plant site, Shore Drive, Coney Island Plant, 26th Ward Plant site, Jamaica Plant, Cross Island Parkway, and Tallman's Island Plant.

Following luncheon at LaGuardia Airport a visit was made to the Pan-American Airways offices and hangar.

The Spring Meeting of the Association will be held in Niagara Falls on June 19–21, 1941.

A. S. BEDELL, *Secretary*

Federation of Sewage Works Associations

CONSTITUTION AND BY-LAWS

CONSTITUTION

ARTICLE I

Name

The name of this organization shall be the Federation of Sewage Works Associations, hereinafter designated as the Federation.

ARTICLE II

Objectives

The objects of this Federation shall be: The advancement of fundamental and practical knowledge concerning the nature, collection, treatment and disposal of sewage and industrial wastes; the design, construction, operation and management of treatment works; the study, promotion and encouragement of improved sanitation of waterways; the correlation and strengthening of regional and state sewage works associations or conferences within or without the United States of Americea; the publication of a journal; and other relevant activities.

ARTICLE III

Membership

The membership of the Federation shall consist of regional or state associations or conferences, either within or without the territory of the United States of America, hereinafter designated as Member Associations, whose objectives and constitutions are in harmony with the purposes of this Federation, and of individuals or corporations as specified in the By-Laws, subject to the conditions and limitations prescribed in the Constitution and By-Laws of the Federation.

ARTICLE IV

Organization

Section 1. The affairs of the Federation shall be conducted by a Board of Control (hereinafter designated as the Board), under such rules as the Board may determine, subject to the specific conditions of this Constitution and By-Laws.

Section 2. The officers of the Federation shall be a President, a Vice-President, a Secretary, a Treasurer, and an Editor.

Section 3. The Board shall consist of:

(*a*) The President of the Federation.
(*b*) The Vice-President of the Federation.
(*c*) The Treasurer of the Federation.
(*d*) One Director to be appointed by and to represent each Member Association.
(*e*) Six Directors-at-Large, of whom three are to be elected by the Executive Committee of the Sewage Works Division of the Water and Sewage Works Manufacturers' Association, and three by the Directors representing the Member Associations.
(*f*) The latest living Past President of the Federation.
(*g*) The Chairman of the Organization Committee.
(*h*) The Chairman of the Publications Committee.
(*i*) The Chairman of the Sewage Works Practice Committee.
(*j*) The Chairman of the Research Committee.

Section 4. After the Annual Meeting of October, 1941, the terms of office of the President, Vice-President, and Treasurer shall be one year, and the Directors three years, which terms shall start at the beginning of the last session of the Annual Meeting of the Board at which they are elected and continue until a successor qualifies. The Secretary and the Editor shall be appointed by the Board for the terms of office stated in the By-Laws. In the case of a vacancy in the office of President, the Vice-President shall act in his place for the unexpired term. In case the Vice-President cannot act, the latest living Past President shall do so. In the case of a vacancy in the office of Treasurer or of any Director-at-Large, the Executive Committee shall appoint an Active Member to fill such office for the unexpired term.

Section 5. The President, the Vice-President, and the Directors of the Federation will not be eligible for reelection for consecutive terms.

Section 6. The President of the Federation shall be the Presiding Officer of the Board.

Section 7. A quorum of the Board shall consist of a majority of its members. Absent members may vote by proxy, all such proxies being counted in determining a quorum.

Article V

Nomination and Election of Officers and Directors

Section 1. The annual meeting of the Board in 1941 shall be held in January. Thereafter, it shall be held on the first Saturday of October in each year, or such other day in October as may mark the closing of the Annual Convention of the Federation.

At the annual meeting the Directors representing the Member Associations shall meet under the Chairmanship of the President of the Federation and shall by a majority vote of all such Directors, elect a President, Vice-President, Treasurer, and one Director-at-Large. Absent Directors may vote by proxy. Any candidate so elected shall be an Active Member of some Member Association and shall signify willingness to serve. Any candidate elected as President or Vice-President shall at some time previous to such election have been a member of the Board of Control.

The President, Vice-President and Treasurer, elected at the meeting of the Board in January, 1941, shall hold office until the beginning of the last session of the meeting held in October, 1941. Thereafter, the terms of office shall be as provided in Article IV, Section 4, of this Constitution.

Section 2. One Director on the Board of Control to represent each Member Association shall be elected by each Member Association. Each Director so elected shall be an Active Member of the respective Member Association and in good standing at the time of his election.

After the annual meeting of October, 1941, the term of each Director so elected shall be for three (3) years beginning with the last session of the Board immediately following his election, excepting that the terms of Directors to be elected by the various Member Associations to take office in January, 1941, shall be as follows:

By lot at the January, 1941, meeting, the directors then taking office shall be divided into three groups, A, B, and C. Group A shall hold office until the beginning of the last session of the October, 1941, meeting. Group B shall hold office until the beginning of the last session of the October, 1942, meeting. Group C shall hold office until the beginning of the last session of the October, 1943, meeting. The three Directors-at-Large, elected by the Board, shall be divided among these groups as shall the three Directors representing the Water and Sewage Works Manufacturers' Association. As the term of office of each group expires, the term of office of their successors shall be as provided in Article IV, Section 4, of this Constitution.

In the case of any director, representing a Member Association, retiring for any cause before his term is completed, the governing board of the Member Association shall designate his successor, who shall serve for the unexpired portion of his term.

Article VI

Except as specifically mentioned herein, this Constitution shall take effect immediately upon its adoption by the Board of Control.

Article VII

Amendments

Amendments to this Constitution may be made by a two-thirds vote of the total membership of the Board, notice of the proposed amendment having been given to each member of the Board and to the Secretary of each Member Association not less than sixty days in advance of the meeting, at which the said amendments are to be voted upon.

BY-LAWS

Article I

Member Associations

Section 1. Any regional or state sewage works association or conference, or other organization whose objectives and constitution are in harmony with those of the Federation, may be granted membership in the Federation by a majority vote of the Board; provided, that the constitution of the applicant association or conference has been examined and certified by the Board as being in accord with Article III of the Constitution of this Federation; and provided further, that certification shall be made by the association seeking admission to membership that the Constitution and By-Laws of the Federation are accepted by it.

Section 2. Any Member Association may withdraw from the Federation at the end of any fiscal year by giving three months' notice of such intention, provided that the dues of such Member Association in the Federation are fully paid up to the time of withdrawal.

Section 3. Any Member Association may be excluded from this Federation, at the pleasure of the Board, for non-payment of dues, as hereinafter provided, or for any change in its constitution that may bring it into conflict with the Constitution or By-Laws of the Federation.

Section 4. Any change in the existing constitution or by-laws of a Member Association shall be reported in full to the Secretary of the Federation within thirty days after its adoption by said Member Association.

Article II

Classification of Members

Section 1. Membership of the Federation shall be composed of Member Associations, Honorary Members, Associate Members, and Sustaining Members. Membership of the Member Associations shall consist of Active Members and Corporate Members only.

Section 2. An Active Member shall be a superintendent, manager, operator, or employee of a sewage or industrial wastes system or treatment works; a professional engineer; a chemist, bacteriologist, biologist, or any qualified person professionally engaged or interested in the advancement of knowledge relating to the disposal or treatment of sewage and industrial wastes or improved sanitation of waterways. Present membership in any Member Association is to be taken as sufficient evidence that the individual is so qualified for as long as he continues to be a member in good standing.

Section 3. A Corporate Member shall be a Sewerage Board, Department or Commission; Sanitary District; Department of Public Works handling sewerage; National, State, District or Municipal Board or Department of Health; or other body, corporation or organization engaged or interested in at least one of the stated objectives of the Federation, and shall be entitled to one representative whose name shall appear on the roll of members and who shall have all the rights and privileges of an Active Member. This representative may be changed at the convenience and pleasure of the Corporate Member on written notice to the Secretary of the Member Association to which the Corporate Member is accredited.

Section 4. An Honorary Member shall be a person of acknowledged eminence in one or more fields of activity within the scope of the stated objectives of the Federation. Candidates may be nominated by any Member Association but can be elected only by a majority vote of the Board. There shall not be more than ten living Honorary Members at any time. No candidate for Honorary Membership shall be an elective or appointive member of the Board at the time of his nomination. Honorary Members shall be elected for life and shall receive, without cost, all the publications of the Federation that are distributed to its members.

Section 5. An Associate Member shall be a person, firm, or corporation engaged in the manufacturing or furnishing of supplies, materials, or equipment for the construction, operation, or maintenance of sewerage works and shall be elected by affirmative vote of a majority of the Board after consideration of written application duly made to the Secretary.

Section 6. A Sustaining Member shall be an individual or a corporation interested in the general objectives of the Federation.

Article III

Dues

Section 1. The dues established by Member Associations, as applied to their members, shall be as determined by the Member Association.

Section 2. (*a*) The dues paid by the Member Associations to the Secretary of the Federation shall be Three Dollars per annum for each Active Member in the Member Association on December 31st.

(*b*) For each Corporate Member the annual dues shall be Ten Dollars, payable to the Secretary of the Federation by February 1 of each year.

(*c*) For each Sustaining Member the annual dues shall be not less than Twenty-five Dollars, payable to the Secretary of the Federation by February 1 of each year.

(*d*) For each Associate Member the annual dues shall be Twenty Dollars, payable to the Secretary of the Federation by February 1 of each year.

(*e*) Corporate Members, Sustaining Members, or Associate Members whose dues remain unpaid on March 1 of any year may be dropped from membership on action of the Executive Committee.

(*f*) The dues for Member Associations outside the United States of America and its territorial possessions shall be greater than the amounts hereinbefore specified by an amount to be fixed annually by the Board as equivalent to the added cost for mailing the Journal to such associations as compared with the average cost for mailing to members residing within these limits.

(*g*) Active and Corporate Members of Member Associations, and Associate and Sustaining Members of the Federation, in good standing, shall be entitled to one copy each of all publications that are distributed by the Federation to its members.

Section 3. The fiscal year of the Federation shall begin on January first, and annual dues shall be collectible on that date and shall have been paid before February first. If the dues of any Member Association shall not have been paid by February first, fifteen days' notice of the dues in arrears shall be given to that association, after which time, if the dues remain unpaid, that association may be dropped from the rolls of the Federation on action by the Board, as provided in Article I, Section 3, of these By-Laws.

Section 4. Any member, newly elected before June 30, shall pay full dues and shall be entitled to all of the publications of the Federation that are distributed to its members during the year. Members elected after June 30 shall pay one-half the regular dues for that year, and shall be entitled to all of the publications distributed during the half year beginning July 1.

Section 5. In transmitting dues to the Federation, each Member Association shall forward with them a certified list of the names and correct mailing addresses of all members of all classes of the said association who are in good standing and are entitled to receive the Journal or other distributed publications of the Federation during the ensuing year.

Section 6. For the year 1941 dues for Active Members shall be at the rate of One Dollar and Fifty Cents per annum, as fixed under the previous By-Laws.

Dues for Corporate Members, Sustaining Members, and Associate Members for the year 1941 shall be at the rates fixed by these By-Laws.

Article IV

Duties of Officers and Directors

Section 1. The President shall have general supervision of the affairs of the Federation, and shall preside at all conventions of the Federation and meetings of the Board. In his absence, he shall designate a Presiding Officer to act in his stead at such conventions or meetings. The President shall be, ex-officio, a member of all committees.

Section 2. The Vice-President shall assist the President in the performance of his duties, and act in his stead when required.

Section 3. The Board of Control shall be the legal representative of the Federation, and as such shall manage its affairs subject to the conditions and limitations prescribed in the Constitution and By-Laws; direct the investment and care of funds of the Federation; make appropriations for specific purposes; appoint employees and fix their compensation; take measures to advance the interests of the Federation; and generally direct its business. The Board shall not incur indebtedness beyond the funds in the hands of the Treasurer and the Secretary. The Board shall hold a meeting during the Annual Convention. Other meetings shall be held at the call of the President, or on petition addressed to the Secretary and signed by ten or more members of the Board representing not less than seven Member Associations. Notice of all meetings shall be issued by the Secretary at least fifteen days in advance of such meetings to all members of the Board and to the Secretary of each Member Association.

At the Annual Meeting the Board shall appoint a Secretary to serve for a term of two years, and an Editor to serve for a term of three years, unless removed for cause by the Board.

Except as otherwise provided in the Constitution and By-Laws, all questions before the Board shall be decided by a majority vote.

Section 4. The Treasurer shall have charge of the funds of the Federation and custody of its investments, if any. He shall pay bills against the Federation when certified by himself and the Secretary. He shall make a report for each calendar year at the Annual Meeting of the Board, showing receipts from the Secretary and other sources, the expenditures, the investments and other assets, and the liabilities of the Federation. He shall make such other reports as may be required by the Board.

He shall be bonded at the expense of the Federation, and to an amount to be determined by the Board.

He shall perform such other duties as may be assigned to him by the Board.

Section 5. The Secretary shall be an Active Member and, under the direction of the President and the Board of Control, shall be the executive officer of the Federation. It shall be his duty to attend all conventions and meetings of the Board, prepare the business and duly record the proceedings thereof. He shall see that all monies due the Federation are carefully collected and without loss transferred to the custody of the Treasurer. He shall scrutinize all expenditures, shall certify to the accuracy of all bills and vouchers on which money is to be paid, and shall countersign checks drawn by the Treasurer against the funds of the Federation when such drafts are known by him to be proper and duly authorized by the Board. Once every three months he shall forward to each member of the Board a financial summary of receipts and disbursements, and at the annual meeting of the Board shall present a balance sheet of his books as of the 31st of December and as of the 30th of September preceding the meeting, together with a report of the activities of his office.

He shall have charge of the books and records of the Federation, including lists of members of the Federation and subscribers to the Journal. He shall have charge of the mechanical production and distribution of the Journal and other publications of the Federation, and shall handle all financial matters connected therewith.

He shall be bonded at the expense of the Federation, and to an amount to be determined by the Board.

He shall perform such other duties as shall be assigned to him by the Board.

The books of the Federation shall be audited annually at the expense of the Federation by public accountants to be appointed by the Board.

Section 6. The Editor shall be the literary agent of the Board and shall receive all manuscript copy and prepare it for publication. He shall have the authority to return to the author for correction, or to reject entirely, any manuscript which may be in bad condition, illegible, or clearly deficient in respect to composition, subject matter or supporting data, or otherwise conspicuously deficient or unfit for publication. He shall also have the authority to reject any manuscript which is designed to promote commercial interests. He shall be a member of the Publications Committee and of the Committee on Sewage Works Practice. Decisions of the Editor relative to rejection of manuscripts shall be subject to appeal to the Publications Committee.

Article V

Conventions of the Federation

The Annual Convention of the Federation shall be held at a time and place to be selected by the Board, preferably in the month of October. All conventions and meetings shall be conducted according to "Roberts Rules of Order."

Each member and guest present at any of the conventions of the Federation shall pay a registration fee of such amount as may be determined by the Executive Committte.

Article VI

Committees

Section 1. There shall be an Executive Committte of five members consisting of the President and four Directors. This committee shall be chosen by the Board at its annual meeting. The President of the Federation shall be Chairman, and the Secretary of the Federation shall act as Secretary of the committee. In the absence of the President, the committee shall choose a temporary Chairman from its members. The duties of this committee shall be to direct the administrative work of the Federation and carry out the policies of the Board between meetings of the latter. The Executive Committee shall present at the annual meeting of the Board a budget of estimated expenses of the Federation, including publications, for the ensuing year. On the adoption of the budget by a majority vote of the Board, the expenses of the Federation shall be limited, as far as may be practicable, within the amounts prescribed in the said budget. A quorum of the committee shall be three members.

Section 2. A General Policy Committee of seven members consisting of the latest living Past President, who shall serve as Chairman, three Directors and three Members-at-Large, appointed at the outset for terms of one, two, and three years, and thereafter for three-year terms, shall be appointed by the Board at its annual meeting. Three of the seven members of the committee shall be operators of sewerage systems or sewage or industrial wastes treatment plants.

The committee shall study and recommend to the Board upon matters of general policy affecting the well-being and usefulness of the Federation and its Member Associations; matters of public relations; the advancement of the professional and social status of members, and such other matters of similar nature as shall be referred to it by the Board.

Section 3. A Publications Committee shall be appointed by the Board at its annual meeting. It shall consist of the Editor and at least four additional Members-at-Large. Its Chairman shall be, ex-officio, a member of the Board. The Publications Committee

shall arrange the technical programs for the annual convention of the Federation and shall have general supervision of the publications of the Federation and of the performance of contracts and expenditures connected therewith. The committee shall prepare general rules which, after approval by the Board, shall control the preparation, presentation, acceptance and publication of papers and shall have general supervision of such other matters of similar nature as the best interests of the Federation may require.

Section 4. An Organization Committee of at least three Members-at-Large shall be appointed by the Board at the annual meeting, and its Chairman shall be, ex-officio, a member of the Board. The Organization Committee shall examine and report to the Board on applications for membership in the Federation and also shall serve in the encouragement of the formation of new regional or state associations or conferences eligible for membership, as well as serving in an advisory capacity in other matters of a similar nature as the best interests of the Federation may require.

Section 5. A Sewage Works Practice Committee Consisting of the Editor and at least four Members-at-Large shall be appointed by the Board at the annual meeting, and its Chairman shall be, ex-officio, a member of the Board.

Any resolution, report or publication which undertakes to establish, in the name of the Federation, professional or technical standards, shall be submitted to this committee, and it shall direct such matters on behalf of the Federation.

It shall give notice by publication to the membership of all such proposed standards and report its approval or disapproval of such to the Board.

It shall appoint such sub-committees as it may deem necessary properly to carry on its work.

Section 6. There shall be a Research Committee of at least five Members-at-Large. The Chairman shall be appointed by the Board, and the other members of the Committee may be appointed by the Chairman, by and with the consent of the President of the Federation. The Chairman shall be, ex-officio, a member of the Board.

The Research Committee shall be charged with the duty of stimulating and coordinating research work among the various Member Associations, and of cooperating with other organizations in the promotion of research work.

Section 7. The Board shall appoint such other committees as may be necessary to carry on the work of the Federation.

Section 8. The reports and recommendations of all committees of the Federation shall be subject to approval by the Board.

Section 9. Members-at-Large are Active Members who are not members of the Board.

Article VII

Publications

All publications of the Federation shall be issued under the direction of the Board and shall be copyrighted as far as is practicable and proper.

Article VIII

Amendments

The Board of Control may amend these By-Laws in any manner not inconsistent with the Constitution by the two-thirds vote of those voting at any meeting of the Board or by sealed letter ballot, provided that a copy of such proposed amendment has been mailed by the Secretary to each member of the Board and to the Secretary of each Member Association at least thirty days prior to such meeting or letter ballot.

Federation Affairs

FEDERATION OF SEWAGE WORKS ASSOCIATIONS

An important event in the history of the Federation of Sewage Works Associations occurred on January 15, 1941, in New York City, when the Federation was put on a sound and national footing.

The reorganization was carefully arranged and so constituted as to try to benefit all concerned.

The local sections are still the bulwark of the Federation but their more active participation in the entire Federation has been the aim of the new organization.

In order that all members of our organization may know what occurred at this historic meeting the minutes of meetings of the Board of Control, directors, and newly reorganized Board of Control are presented here, together with the new Constitution.

REPORT OF SECRETARY-TREASURER FEDERATION OF SEWAGE WORKS ASSOCIATIONS FOR THE YEAR ENDING DECEMBER 31, 1940

The past year has been a busy one for the Federation. The proposed Expansion and Reorganization was given official impetus by the appointment of a Committee, authorized at the January, 1939, Board Meeting, to consider methods for strengthening the Federation and to provide some plan for its further development. Its Progress Report was accepted by the Board at its January, 1940, meeting and the Committee continued.

At this same meeting it was decided to hold a Convention within a year. Committees were appointed to make necessary arrangements. An invitation was extended by the Central States Sewage Works Association, and after months of intensive planning and preparation the First Annual Convention of the Federation of Sewage Works Associations was held in Chicago on October 3–5, 1940. It was outstandingly successful and the details have already been published in the November, 1940, issue of Sewage Works Journal.

A feature of the Convention was the Business Meeting of the Federation on October 5, 1940, and the Special Meeting of the Board of Control held that evening and at which all Member Associations were represented except the two in England and the one in Argentina. Minutes of both meetings have been published in the November, 1940, issue of Sewage Works Journal, and relate the various matters considered. Possibly the most important was the approval of the Report proposed by the Committee on Expansion and Reorganization on Revised Consti-

tution and By-Laws, and a recommendation that the Board of Control at its January, 1941, meeting should adopt and declare these in effect.

William W. Buffum, the Federation's Business Manager from its inception, died on June 22, 1940. By letter ballot the Board of Control adopted an appropriate resolution, copies of which were sent to the family of the deceased and to The Chemical Foundation, and published in the July, 1940, issue of SEWAGE WORKS JOURNAL.

Mr. Arthur A. Clay, who succeeded Mr. Buffum as Treasurer and General Manager of The Chemical Foundation, was designated by The Foundation as the new Business Manager of the Federation and, by letter ballot, was elected to fill the unexpired term of Mr. Buffum as Member-at-Large on the Board of Control.

The Secretary, by questionnaire, received from Association Secretaries data classifying membership in their several groups. These,

	Gross Membership	Dual Mems.	Gross New Mems. and Re-instatements	Did not Renew	Membership	
					Increase	Decrease
Arizona S. and W. W. Assn.	28	—	17	14	3	—
California S. Wks. Assn.	280	1	60	46	14	—
Cent. States S. Wks. Assn.	503	6	77	85	—	8
Dak. W. and Sew. Wks. Conf.						
North Dakota	7	—	—	9	—	9
South Dakota	23	—	7	12	—	5
Federal S. Research Assn.	64	1	9	5	4	—
Ga. W. and Sew. Assn.	27	—	6	7	—	1
Iowa Wastes Disp. Assn.	44	1	13	6	7	—
Kansas W. and S. Wks. Assn.	21	—	6	20	—	14
Md.-Del. W. and S. Assn.	24	—	1	2	—	1
Michigan S. Wks. Assn.	136	—	28	42	—	14
Missouri W. and S. Conf.	10	—	3	13	—	10
New England S. Wks. Assn.	187	12	31	11	20	—
New Jersey Sew. Conf. Gr.	68	—	14	7	7	—
N. Y. State S. Wks. Assn.	629	21	96	66	30	—
N. Carolina S. Wks. Assn.	80	1	20	11	9	—
Ohio S. Wks. Conf. Gr.	106	—	13	17	—	4
Oklahoma W. and S. Conf.	1	—	—	3	—	3
Pacific NW. S. Wks. Assn.	80	—	23	9	14	—
Pennsylvania S. Wks. Assn.	213	9	30	22	8	—
Rocky Mt. Sew. Wks. Assn.	38	—	12	10	2	—
San. Engr. Div. of the Arg. Society of Engrs.	2	—	—	10	—	10
Sew. Div.-Tx. Sec., S.W.W.A.	28		13	12	1	—
Can. Inst. on Sew. and San.	123	2	9	9	—	—
Inst. of Sew. Purif.—Eng.	97	—	18	30	—	12
Inst'n of San. Engrs.—Eng.	54	—	1	3	—	2
	2873	54	507	481	119	93
	−54				−93	
	2819 Net Mems.				26 Incr.	

nearly complete, showed by far the greatest number classified as sewage works superintendents and operators. Next in order were municipal and consulting engineers, with equipment men in third place. Incidentally, it is worthy of note that this information, as well as routine correspondence, was received from the two English associations, both with headquarters in London; another bit of evidence of the invincible fortitude of our British colleagues.

At the close of 1940 there was a gross membership of 2,873, less 54 dual memberships, leaving a net total of 2,819, or an increase of 26 in the past year. Membership was not renewed by 481, which was 74 more than in the preceding year. Details are shown in the table on page 343.

Dues received by the Secretary-Treasurer and forwarded to the Business Manager totaled $3637.75 as against $3685.75, a decrease of $48.00. Petty cash expenditures of the Secretary-Treasurer for stamps and miscellaneous expenses amounted to $24.25. Dues received are detailed below:

	For 1938	For 1939	For 1940	For 1941	Total	Refund
Arizona S. and W. Wks. Assn.	(Paid dues direct to Business Manager)					
California S. Wks. Assn.			$ 423.00		$ 423.00	$1.50
Cent. States S. Wks. Assn.			745.50		745.50	
Dak. W. and Sew. Wks. Assn.			36.00	$16.50	52.50	1.50
Federal S. Research Assn.			79.50		79.50	1.50
Georgia W. and S. Assn.	(Paid dues direct to Business Manager)					
Iowa Wastes Disp. Assn.		$3.00	60.00	15.00	78.00	1.50
Kansas W. and S. Wks. Assn.			33.00		33.00	
Md.-Del. W. and S. Assn.			36.00		36.00	
Michigan S. Wks. Assn.		1.50	204.00		205.50	
Missouri W. and S. Conf.	(Paid dues direct to Business Manager)					
New England S. Wks. Assn.			264.50		264.50	1.50
New Jersey Sew. Conf. Gr.			102.00		102.00	
New York St. S. Wks. Assn.	$1.50	25.50	904.25		931.25	1.50
N. Carolina S. Wks. Assn.			118.50		118.50	
Ohio S. Wks. Conf. Gr.			159.00		159.00	
Oklahoma W. and S. Conf.	(Paid dues direct to Business Manager)					
Pacific NW. S. Wks. Assn.	(Paid dues direct to Business Manager)					
Pennsylvania S. Wks. Assn.		1.50	308.00		309.50	
Rocky Mt. Sew. Wks. Assn.			57.00		57.00	
San. Engr. Div. of the Arg. Society of Engrs.	(Paid dues direct to Business Manager)					
Sew. Div. Tx. Sec., S.W.W.A.			41.50	1.50	43.00	
Can. Inst. on Sew. and San.	(Paid dues direct to Business Manager)					
Inst. of Sew. Purif.—Eng.	(Paid dues direct to Business Manager)					
Inst'n. of San. Engrs.—Eng.	(Paid dues direct to Business Manager)					
	$1.50	$31.50	$3571.75	$33.00	$3637.75	$9.00

H. E. Moses,
Secretary-Treasurer.

FEDERATION OF SEWAGE WORKS ASSOCIATIONS

MINUTES OF THE ANNUAL MEETING OF THE BOARD OF CONTROL

Hotel Pennsylvania, New York City, January 15, 1941

The Annual Meeting of the existing Board of Control of the Federation of Sewage Works Associations was held at the Hotel Pennsylvania, New York City, on January 15, 1941. C. A. Emerson, Chairman, presided and convened the session at 3:30 P.M. The roll call indicated representation as follows:

Present in Person

Name of Affiliate	*Represented By*
California Sewage Works Association	Charles G. Hyde
Central States Sewage Works Association	W. W. DeBerard
Central States Sewage Works Association	George J. Schroepfer
Federal Sewage Research Association	F. J. Maier
Federal Sewage Research Association	A. P. Miller
Georgia Water and Sewage Association	Van P. Enloe
Georgia Water and Sewage Association	G. R. Frith
Iowa Wastes Disposal Association	Max Levine
Iowa Wastes Disposal Association	Earle L. Waterman
Maryland-Delaware Water and Sewerage Association	Harry R. Hall
Michigan Sewage Works Association	N. G. Damoose
Missouri Water and Sewerage Conference	George S. Russell
New England Sewage Works Association	F. W. Gilcreas
New Jersey Sewage Conference	Willem Rudolfs
New York State Sewage Works Association	Arthur S. Bedell
New York State Sewage Works Association	N. L. Nussbaumer
North Carolina Sewage Works Association	H. G. Baity
North Carolina Sewage Works Association	W. M. Piatt
Pacific Northwest Sewage Works Association	John W. Cunningham
Pennsylvania Sewage Works Association	C. A. Emerson
Pennsylvania Sewage Works Association	H. E. Moses
Member-at-Large	Arthur A. Clay
Member-at-Large	Linn H. Enslow
Member-at-Large	Charles G. Hyde
Member-at-Large	Wm. J. Orchard

Present in Person, Acting as Proxy

Name of Affiliate	*Represented By*
Arizona Sewage and Water Works Association	A. M. Rawn (for Phil J. Martin)
Arizona Sewage and Water Works Association	A. M. Rawn (for Bernard Schiller)
Dakota Water and Sewage Works Conference	Morris M. Cohn (for Lloyd K. Clark)
Dakota Water and Sewage Works Conference	H. E. Moses (for W. W. Towne)
Kansas Water and Sewage Works Association	F. W. Mohlman (for Earnest Boyce)
Maryland-Delaware Water and Sewerage Association	Harry R. Hall (for Abel Wolman)
Michigan Sewage Works Association	N. G. Damoose (for E. F. Eldridge)
Missouri Water and Sewerage Conference	George S. Russell (for W. Scott Johnson)

New Jersey Sewage Conference ..... Willem Rudolfs
(for Richard C. Smith)
Ohio Sewage Works Conference Group ..... M. W. Tatlock
(for Frank W. Jones)
Ohio Sewage Works Conference Group ..... M. W. Tatlock
(for C. D. McGuire)
Oklahoma Water and Sewage Conference ..... W. H. Wisely
(for H. J. Darcey)
Pacific Northwest Sewage Works Association ..... John W. Cunningham
(for W. P. Hughes)
Sewage Division, Texas Section, S. W. W. A. ..... Charles R. Velzy
(for V. M. Ehlers)
Sewage Division, Texas Section, S. W. W. A. ..... G. E. Symons
(for W. S. Mahlie)
Member-at-Large ..... Albert L. Genter
(for H. W. Streeter)

By consent, reading was dispensed with of the Minutes of the Special Meeting of the Board held at Chicago, Illinois on October 5, 1940, they having been printed in the November, 1940, SEWAGE WORKS JOURNAL.

Chairman Emerson and Secretary Moses each made brief verbal reports. Arthur A. Clay, Business Manager, who succeeded the late William W. Buffum, abstracted briefly his very comprehensive report on income and expenditures of the Federation for the year ending December 31, 1940, his report including a balance sheet as of December 31, 1940 and a tabulated statement of income and expenditures for the following periods: July 31, 1928 to December 31, 1939; January 1, 1940 to December 31, 1940; and July 31, 1928 to December 31, 1940. He reported a profit for 1940 of $1,368.52, exclusive of the excess of income over expenditures from the 1940 Convention of $1,449.83. This comprises a Journal operating profit of $768.37 and a 1940 profit on sale of copies of *Modern Sewage Disposal* of $600.15. On hand there are 389 copies of this publication and 5,304 copies of various back numbers of SEWAGE WORKS JOURNAL, these having an unestimated sale value.

On December 31, 1940, the assets of the Federation were $5,091.41, including cash in bank amounting to $3,588.01. The liabilities include accounts payable amounting to $1,389.69, advance subscriptions of $621.94, and suspense account of $4, leaving a surplus of $3,075.78.

In the tabular statement of income and expenditures for the year 1940, the actual printing and mailing cost of the Journal was shown to be $9,866.04; editorial, abstract and Secretary's office expense was $2,124.06; and the Business Manager's office expense was $278.37. Other expenses, including those in connection with the reorganization committee work, totaled $624.46.

It was pointed out that the actual printing and mailing cost of the Journal, aside from editorial and other necessary management expenses, amounted to approximately $3 for each member and nonmember subscriber.

Mr. Clay's verbal report was approved by the Board, which automatically constitutes approval of the written report, which written report has since been carefully examined and found to be correct.

On behalf of the convention committee, George J. Schroepfer, Chairman, presented the following report which, on motion and duly seconded, was accepted and ordered filed:

"Mr. Emerson: Jan. 15, 1941

Members of the Board of Control:

"With the First Annual Convention of the Federation of Sewage Works Associations some months behind us, and expressions of appreciation having been offered to all who played a part in its arrangements, the General Convention Committee considers its work completed.

"The report of the Committee presented at the annual meeting, and the statement in the recent issue of the SEWAGE WORKS JOURNAL, summarize the views of this Committee and constitute the record of this event.

"As a result of its contacts with a representative proportion of the membership both before and during the convention, and of its considerations since that time, the Committee makes the following recommendations:

1. That for the purpose of maintaining continuity and of taking advantage of the experience gained, one member of the general convention committee be retained on the committee to arrange for the next subsequent convention.
2. That the value of publicity continue to be emphasized, as was done in the 1940 convention, and that public relations constitute an essential part of the activities of the Federation.
3. That recognition of the highest type be accorded Mr. C. A. Emerson, Chairman of the Federation during this period, among other reasons, for his unselfish efforts in the interest of the Federation for more than a decade, which assumed still greater proportions during the past year. The Committee suggests as fitting recognition, that he receive the first honorary membership in the Federation.

"The Committee reiterates the statement in its report to the First Annual Convention that it is heartily in favor of the reorganization and revitalization of the Federation and its members pledge themselves individually to perform any additional service for which they may be called upon.

"For the opportunity of participating in the arrangements for the First Annual Convention, the Committee expresses its appreciation.

Respectfully submitted,
MORRIS COHN,
F. W. GILCREAS,
F. W. MOHLMAN,
WM. J. ORCHARD,
B. O. POOLE,
GEO. J. SCHROEPFER, *Chairman*"

Mr. Orchard presented the 1940 Convention Finance Committee report, which showed income from registration and sale of tickets of $2,600.50, and an advance from the Water and Sewage Works Manufacturers' Association of $1,500.00, or a total of $4,100.50. The total expenses amounted to $2,650.67, leaving a balance in the Finance Committee's bank account of $1,449.83. Upon motion made, seconded and carried unanimously, this report was accepted, and it was authorized that the Convention Finance Committee account in the Northern Trust Company of Chicago for the 1940 Convention, be certified by the proper resolutions which were in the hands of Mr. Orchard.

Mr. Emerson traced the history of the work done by the Committee on Reorganization and Expansion, stressing the large volume of correspondence, the number of committee meetings held, and the considerable work entailed. He then called on Mr. Orchard to read Item No. 8 of the report of the Committee on Motivation entitled: "Affiliate Members of Member Associations." This suggests a procedure for retaining the membership of low-income sewage works operators, a matter reported to be troubling nearly every Member Association, especially in anticipation of the increased dues contemplated under the revised Constitution and By-Laws. General discussion ensued, and finally by a motion which was seconded and carried, the matter was referred to the Executive Committee for further consideration and report, and then to be submitted to the Board for action by ballot.

Under the head of New Business, it was moved and seconded that the revised Constitution and By-Laws be adopted. These were distributed in printed form on October 16, 1940, by order of Chairman Emerson, to officers and members of the Board of Control and to members of the Committee on Reorganization and Expansion of the Federation, and to all secretaries, officers and directors of Member Associations of the Federation. After a prolonged discussion participated in freely by nearly all Board members present, the motion was unanimously carried and the suggested revisions of the Constitution and By-Laws were adopted.

Mr. Emerson stated that the Constitution and By-Laws just adopted provided for one Director for each Member Association. He asked the Secretary to call the roll to ascertain which of the two former representatives would remain on the Board as hold-over Directors. The list follows:

Arizona S. and W. W. Assn.	Phil J. Martin (A. W. Rawn, *proxy*)
California S. W. Assn.	Charles G. Hyde
Central States S. W. Assn.	Georgt J. Schroepfer
Dakota W. and S. W. Conf.	W. W. Towne (H. E. Moses, *proxy*)
Federal S. R. Assn.	A. P. Miller
Georgia W. and S. Assn.	Gilbert R. Frith
Iowa W. D. Assn.	Max Levine
Kansas W. and S. W. Assn.	Earnest Boyce (F. W. Mohlman, *proxy*)

Maryland-Delaware W. and S. Assn.	Harry R. Hall
Michigan S. W. Assn.	N. G. Damoose
Missouri W. and S. Conf.	George S. Russell
New England S. W. Assn.	F. W. Gilcreas
New Jersey S. Conf.	Willem Rudolfs
New York State S. W. Assn.	N. L. Nussbaumer
North Carolina S. W. Assn.	Wm. M. Piatt
Ohio S. W. Conf. Group	F. W. Jones (M. W. Tatlock, *proxy*)
Pacific Northwest S. W. Assn.	John W. Cunningham
Pennsylvania S. W. Assn.	H. E. Moses
Rocky Mountain S. W. Assn.	Chas. A. Davis
Sewage Div., Texas Sec., S. W. W. A.	V. M. Ehlers (H. E. Moses, *proxy*)

At the time of the Board meeting the following Member Associations had not furnished the names of their hold-over Directors:

Oklahoma Water and Sewage Conf.
Sanitary Engineering Division of Argentine Society of Engineers
The Can. Inst. on Sewage and Sanitation
The Inst. of Sew. Purif.—England
The Inst'n. of San. Engrs.—England

Article V, Section 1, Paragraph 2 of the new Constitution was read, this providing for the election of officers, and an invitation was extended by Chairman Emerson to the directors who retired from the Board and to all others present, to meet with the hold-over Directors at the meeting of the reorganized Board of Control immediately following the interim meeting for election of officers. He called upon the hold-over Directors to meet at once as an Election Committee, and stated that a meeting of the new Board of Control would convene as soon as the Election Committee report was ready.

Upon motion made, seconded and carried, the Board adjourned *sine die* at 4:51 P.M.

H. E. Moses,
Secretary-Treasurer

MINUTES OF A MEETING OF THE DIRECTORS OF MEMBER ASSOCIATIONS OF THE FEDERATION OF SEWAGE WORKS ASSOCIATIONS AS AN ELECTION COMMITTEE

Hotel Pennsylvania, New York City, January 15, 1941

This meeting was called to order by Mr. Emerson at 4:52 P.M., immediately following the meeting of the existing Board of Control, which had adopted the revised Constitution and By-Laws putting into effect this meeting. Mr. Emerson presided and explained the action of the Motivation Committee in preparing for this meeting, whose purpose was to effect organization under the revised Constitution and By-Laws. He then requested W. J. Orchard, Secretary of the Motivation Committee, to read the Committee's recommendation with reference to

the election of officers. This was done, and the following were recommended for election:

President: C. A. Emerson, New York City
Vice-President: A. S. Bedell, Albany, N. Y.
Treasurer: W. W. DeBerard, Chicago, Ill.

(The foregoing to serve from January 15, 1941, to election of their successors at the Board of Control meeting October 11, 1941.)

Director-at-Large: Langdon Pearse, Chicago, Ill. (Term expires October, 1941.)
Director-at-Large: Linn H. Enslow, New York City. (Term expires October, 1942.)
Director-at-Large: A. M. Rawn, Los Angeles, Calif. (Term expires October, 1943.)

By motion, seconded and carried, the report was accepted and the foregoing names were placed in nomination. There were no further nominations, and on motion which was seconded and carried, the nominations were closed. By *viva voce* vote these nominees were unanimously declared elected.

Upon motion the meeting then adjourned.

H. E. Moses,
Secretary-Treasurer

MINUTES OF A MEETING OF THE REORGANIZED BOARD OF CONTROL (WITH NEWLY ELECTED OFFICERS) OF THE FEDERATION OF SEWAGE WORKS ASSOCIATIONS

Hotel Pennsylvania, New York City, January 15, 1941

This meeting followed immediately after the meeting of the hold-over Directors under the new Constitution, which elected as officers to serve until October, 1941: C. A. Emerson, President; A. S. Bedell, Vice-President; and W. W. DeBerard, Treasurer.

Roll call was dispensed with in view of the preceding roll call to determine the hold-over Directors.

The action of the new Constitution (Article V, Section 2) pertaining to the election by lot of the length of service of the new Directors, was read. The question was raised about a three-year service on the Board of a Director of a Member Association who would be elected by that Member Association for only one year. It was pointed out that the Executive Committee would have to make some provision in the Member Association for a greater length of office for Directors, and that bringing the Member Associations' Constitution into a line with the new Federation Constitution would accomplish this.

The drawing by lot established tenures of office as follows:

The Institution of Sanitary Engineers—October, 1941
Pennsylvania Sewage Works Assn.—October, 1943
Michigan Sewage Works Assn.—October, 1943
Sanitary Engineering Division of the Argentine Society of Engineers —October, 1943
Georgia Water and Sewage Assn.—October, 1941
Maryland-Delaware Water and Sewerage Assn.—October, 1942
Kansas Water and Sewage Works Assn.—October, 1942
New York State Sewage Works Assn.—October, 1942
The Canadian Institute on Sewage and Sanitation—October, 1943
The Institute of Sewage Purification (England)—October, 1941
New England Sewage Works Assn.—October, 1942
Missouri Water and Sewerage Conference—October, 1942
Ohio Sewage Works Conference Group—October, 1942
Arizona Sewage and Water Works Assn.—October, 1943
New Jersey Sewage Conference—October, 1943
North Carolina Sewage Works Assn.—October, 1943
California Sewage Works Assn.—October, 1941
Central State Sewage Works Assn.—October, 1942
Dakota Water and Sewage Works Conference—October, 1943
Rocky Mountain Sewage Works Assn.—October, 1942
Sewage Division, Texas Section, S.W.W.A.—October, 1942
Pacific Northwest Sewage Works Assn.—October, 1941
Federal Sewage Research Assn.—October, 1941
Iowa Wastes Disposal Assn.—October, 1941
Oklahoma Water and Sewage Conference—October, 1941

Mr. Orchard, at the suggestion of Mr. Emerson, read the report of the Committee on Motivation in its entirety. The adoption of the report and its recommendations was made by items as numbered in the report, as follows:

Item 1—Cessation of support of The Chemical Foundation. "The Committee recommends the establishment of a central office and the employment of a part-time Executive Secretary immediately. This is necessary because the Chemical Foundation, from whose largess the Federation has greatly benefited in years gone by, has informed the Committee that it will be unable to carry on as it has in the past after March 31st, 1941." Adopted as read.

Item 2—Location of central office. Your Committee recommends establishment of a central office in the Chicago area not later than March 1, 1941. Adopted as read.

Item 3—Appointment of Executive Secretary.

A motion was made, seconded and carried that this item be adopted, reading as follows:

"3. *Appointment of Executive Secretary.*

"Your Committee recommends the appointment of Mr. W. H.

Wisely as Executive Secretary to work on a half-time basis until the October, 1941, meeting of the Board of Control. Your Committee recommends that Mr. Wisely be paid a salary not exceeding the rate of $2500.00 per annum for this half-time employment, plus expenses approved by the Executive Committee."

Item 4—Extension of Editorial service. "Your Committee recommends that the Executive Committee make arrangements with Dr. Mohlman to continue as Editor of the JOURNAL in co-operation with Mr. Wisely until the October, 1941, meeting of the Board of Control or at a time to be agreed upon by Mr. Wisely and Dr. Mohlman with the approval of the Executive Committee." Adopted as read.

Item 5—Place of 1941 Annual Meeting. Recommends that the October, 1941, Annual Meeting be held in New York City on October 9, 10 and 11. Discussion of this item brought forth an invitation from Mr. Nussbaumer to have the 1943 Convention of the Federation in the City of Buffalo, New York. Mr. Emerson ordered this invitation filed with the Secretary, and explained that the tentative setting of New York City as the place of the 1941 Convention at the October, 1940, Board meeting had resulted in voluminous committee work and the making of a great many arrangements. Invitations had been received for the 1941 and other Conventions from Tulsa, Cleveland, and many other cities. Item 5, it was moved, seconded, and carried should be adopted as read.

Item 6—Increasing scope of JOURNAL. "Your Committee feels that it is essential that there be every effort made to make the JOURNAL more attractive to and interesting for the average sewage works plant operator." Adopted as read.

Item 7—Budget for 1941 and indicated budget for 1942. Action temporarily deferred.

Item 8—Affiliate members of Member Associations. This item dealing with affiliates of Member Associations, will require an amendment of the By-Laws. It was moved, seconded and carried that this item be adopted as read and that the recommendation of the Committee on Motivation be submitted to the Executive Committee for study and prompt report to the Board of Control. The recommendation was as follows: "Your Committee recommends the amendment of Section 1, Article II of the By-Laws, 'Classification of Members,' to permit Member Associations to have affiliates for whom the Member Associations will make no payment to the Federation and which affiliates will not receive the JOURNAL. Your Committee recommends that the procedure adopted by the New York State Sewage Works Association be used by the Member Associations as a guide. Section 6, Article III, of the proposed Constitution of the New York State Sewage Works Association reads as follows: '*Affiliates.* Sewage plant operators in the Grade III or lower classifications and sewerage maintenance men in the

smaller communities *may* upon their specific request and with the approval of the Executive Committee become Affiliates of this association. Such Affiliates may become members of Local Sections of the N. Y. S. S. W. A., but shall not have voting privileges in the Parent Body and will not receive the publications of the Federation.' ''

Item 9—Contribution from Water and Sewage Works Manufacturers' Association. There was considerable discussion on this item, and it was finally decided that the offer of the Manufacturers was one in good faith, that they would gain by the arrangement as the Federation would gain and would do nothing to, as it were, "foul their own nest." A motion was made, seconded, and carried that Item 9 be adopted, reading as follows:

> "9. *Contribution from Water and Sewage Works Manufacturers' Association.*
>
> "Your Committee has received a proposal from the Water and Sewage Works Manufacturers' Association offering to contribute $5000.00 per year to the general funds of the Federation to be used as the Federation sees fit in advancing its interests. In return, the Manufacturers request the privilege of taking charge of the exhibits at the Annual Meetings of the Federation. Your Committee recommends the acceptance of this contribution from the Water and Sewage Works Manufacturers' Association on the basis indicated; that is, on a mutually agreeable basis to be worked out by the Executive Committee and the Manufacturers' Association."

Item 10—Incorporation of the Federation. Provides for incorporation in the State of Illinois as an association not for profit. Adopted as read.

Mr. Orchard interjected a remark at this point, stating that in view of the action on Item 9 as above, the Treasurer of the Federation had at his disposal, when he asks for it, $5000.00 from the Manufacturers' Association. He stated, further, that the Directors-at-Large designated by the Executive Committee of the Sewage Works Division of the Water and Sewage Works Manufacturers' Association were as follows:

Term expiring October, 1942—Mr. L. E. Rein, Pacific-Flush Tank Company

Term expiring October, 1943—Mr. Wm. J. Orchard, Wallace & Tiernan Co., Inc.

Term expiring October, 1941—Mr. D. S. McAfee, The Dorr Company, Inc.

A motion was made, seconded and carried that these Directors-at-Large be accepted.

The Board then proceeded to consideration of the budget, Item 7, of the Committee's report. This was read and explained by Mr.

Orchard, and it was moved, seconded and carried that the budget as drawn by the Committee be adopted.

On motion duly made and seconded, it was unanimously

RESOLVED, That the Federation, through its Secretary, tenders its sincere thanks to the Chemical Foundation for its help and co-operation in years past; and

FURTHER RESOLVED, That Chemical Foundation, Inc., be requested and authorized to continue its present relations and functions as Business Manager of the Federation until March 31, 1941, or until such earlier date as may be mutually agreed between the officers of Chemical Foundation, Inc., and the President and Treasurer of the Federation of Sewage Works Associations, at which time the Chemical Foundation is instructed to deliver to the aforesaid officers of the Federation with proper accounting, all books, records and funds of the Federation which may be in its charge and custody. Such accounting and delivery shall automatically relieve Chemical Foundation, Inc., of all responsibility to the Federation of Sewage Works Associations.

The recommendations of the Motivating Committee with respect to Committee Memberships to October, 1941, were read, and after certain changes agreed to by the Board the recommendations were adopted on motion duly made, seconded and carried. The committees thus established are as follows:

Executive Committee (President and four Directors)
A. S. Bedell (New York)
Wm. J. Orchard (Manufacturers)
Wm. M. Piatt (North Carolina)
C. G. Hyde (California)

General Policy Committee (Latest Living Past President as Chairman, three Directors, and three Members-at-Large. Three of the total number to be operators)

Directors:
H. E. Moses (Pennsylvania)
Harry R. Hall—operator (Maryland)
Linn H. Enslow (New York)

Members-at-Large:
Carl E. Green (Oregon)
George J. Schroepfer—operator (Minnesota)
L. L. Luther—operator (New York)

Publications Committee (Editor and at least four Members-at-Large)
Editor
F. W. Gilcreas—Chairman (New England)
LeRoy W. Van Kleeck (Connecticut)
F. C. Roberts (Arizona)
Chas. Velzy (New York)
Rolf Eliassen (New York)

James L. Ferebee (Wisconsin)
W. W. Towne (South Dakota)

Organization Committee (At least three Members-at-Large)
H. W. Streeter—Chairman (Federal)
Earnest Boyce (Kansas)
N. G. Damoose (Michigan)

Sewage Works Practice Committee (Editor and at least four Members-at-Large)
Editor
F. W. Mohlman—Chairman (Illinois)
J. J. Wirts (Ohio)
Geo. H. Craemer (Connecticut)
Morris Cohn (New York)
Gail P. Edwards (New York)
B. A. Poole (Indiana)
C. E. Keefer (Maryland)

Research Committee (At least five Members-at-Large)
Willem Rudolfs—Chairman (New Jersey)

Upon motion made, seconded and carried, it was unanimously

RESOLVED, That Wm. J. Orchard should at his early convenience turn over to the Treasurer of the Federation the funds remaining in the account of the 1940 Convention Finance Committee; and

FURTHER RESOLVED, That the Treasurer and Secretary be bonded at the Federation's expense as stated in the new Constitution and By-Laws; and

FURTHER RESOLVED, That the Treasurer be, and he hereby is, authorized to open a bank account for the Federation in a bank of his choosing in Chicago; that he is further authorized to complete and submit to the Secretary for transmittal to the bank the necessary resolutions required by the bank for the account; and that the signatures required for withdrawal shall be those of the President, Vice President, or Treasurer of the Federation when countersigned by either the Secretary or Treasurer of the Federation.

Upon motion duly made, seconded, and carried unanimously, it was

RESOLVED, That in recognition of the many years of faithful service of Mr. H. E. Moses to the Federation, Mr. Moses be made Honorary Secretary of the Federation with his present compensation continued to June 1, 1941.

FURTHER RESOLVED, That the Motivation Committee considers the Federation very fortunate that Dr. Mohlman is agreeable to continue as Editor on a basis to be determined by the Executive Committee. The Executive Committee is authorized to make such arrangements. Mr. Wisely is to be, and he hereby is, instructed to assist Dr. Mohlman as Managing Editor.

Upon motion duly made, seconded and carried, it was unanimously

RESOLVED, That a Convention Management Committee, consisting of the Chairman, two members of the Federation, and two members of the Manufacturers' Association, be created.

Upon motion made, seconded and carried unanimously, a vote of thanks was tendered to the Committee on Motivation for the fine work it had done in expediting the work of the day's meetings.

The Secretary was instructed to write a letter of thanks to the Hotel Pennsylvania in New York City for their cooperation in furnishing a room for the meeting.

There being no further business the meeting adjourned at 6:37 P.M.

H. E. MOSES,
Secretary-Treasurer.

Reviews and Abstracts

EXPERIENCES IN OPERATING A CHEMICAL–MECHANICAL SEWAGE TREATMENT PLANT

By George J. Schroepfer

Proceedings, A. S. C. E., 67, 61 (Jan., 1941)

The Minneapolis-St. Paul sewage treatment plant has been in operation since June 1, 1938. The author presents data on the performance of the plant and the cost of operation and maintenance, as well as on the improvement of the Mississippi River during the course of the first two years of operation. The plant has a design capacity of 134 M.G.D. and has the flow sheet of a chemical precipitation plant, plus magnetite filters for the effluent, and vacuum filters and incinerators for the sludge. The plant was designed so that treatment by a variety of processes could be provided to meet varying river requirements. Operation during the first two years indicated that with all of the units in operation, the following removals could be expected:

Treatment Process	5-day B.O.D.	Suspended Solids
Sedimentation only	40 to 45%	70 to 75%
Flocculation plus sedimentation	45 to 50%	75 to 80%
Flocculation and sedimentation, plus effluent filtration	50 to 55%	80 to 85%
Flocculation with chemicals, sedimentation, and effluent filtration (dependent upon quantities of chemicals)	55 to 70%	85 to 95%

With an average detention period of only 1.5 hours, the average removal of suspended solids was 69 per cent and of 5-day B.O.D. 38 per cent. During four months of 1939 and 1940, detention periods averaging 2.4 hours were used and the removal of suspended solids averaged 74.4 per cent and the B.O.D. 42.9 per cent. By using all of the settling tanks, a detention period of 3.2 hours could be obtained at present flows, which should result in still higher removals. These are not desired until further plants are constructed along the Mississippi River to care for wastes from neighboring communities. Difficulty was experienced in the handling of scum. The suction and discharge lines of the scum pumps frequently became clogged and required the addition of large quantities of water to transport it. After four months of operation, the scum discharge line had been reduced to one-tenth of its original area by grease incrustations. After consideration of a number of methods of handling, the ejection method was selected because of its possibilities of handling relatively dry scum, assisting in the final disposal. No difficulties were experienced with freezing of sewage in the settling tanks or effluent filters during the winter months when temperatures went as low as 25° F. below zero. Sewage temperatures dropped only about 4° F. through the plant. By careful control of sludge pumping, it has been possible to remove sludge from the tanks averaging between 7–8 per cent solids. In order to handle heavy sludge without frequent stoppages, it was found necessary to make provisions for blowing back suction lines with plant effluent or compressed air. Except under conditions of storm flow, the usual practice is to operate the sludge pumps three times daily, continuing pumping as long as the sludge remains heavy. As a means of maintaining as concentrated a sludge as possible, specific gravities are determined by weighing calibrated containers of sludge periodically during the pumping period. In connection with combined sewers, it was found that settling tank and sludge pumping difficulties were encountered when flows greater than 250 per cent of the average were taken into the plant. Samples taken at half-hour intervals before, during, and after rains in the early summer indicated suspended-solids strength up to 6000 p.p.m., compared with averages of approximately 275 p.p.m.

Operation of the vacuum filters over the two year period showed that an average filter rate of 4.87 lb./sq. ft./hr. could be maintained. In the early period of operation, filter cloths generally had to be removed after about 150 hours of use. Lime-blinding necessitated higher chemical dosages and more frequent washings, and ripping or rotting at seams required the use of a large number of tin patches, (as many as 30 to 40 on a filter) even with this short life. With reduced lime dosage, the economical cloth life has been increased to somewhat more than 300 hours and as much as 500 to 600 hours for several months. Beyond this time increased chemical feed is required, incommensurate with the cost of cloth replacement. Chemical dosages of approximately 2 per cent ferric chloride and 5 per cent lime are now being used.

Incineration of the sludge brought to light several interesting facts. The original estimate showed that approximately $2,500 worth of fuel oil a month would be required to support combustion. Instead, it was found that under practically all conditions of operation an excess of heat existed and no fuel was required for actual incineration. It was found necessary to dissipate more than 6,000,000 B.T.U. per hour per incinerator. The manufacturers first attempted to accomplish this by introducing water into the furnace through sprays. This was unsatisfactory to the Sanitary District, and a by-pass was finally installed to conduct pre-heated air direct to the stack. In this way, air at room temperature could be used for combustion, and the water would be reduced to reasonable quantities and its addition required on less frequent occasions. A total of 182,097 tons of filter cake were incinerated during the first two years. The average B.T.U. per pound of combustible solids in the sludge was 10,800 and the average volatile solids in the sludge cake was 58.5 per cent, with a moisture content of 65.1 per cent. The sludge cake was reduced by incineration to an ash containing less than 2 per cent volatile matter. The guaranteed capacity of each incinerator was 60 tons of dry solids per 24 hours. During the test run as much as 78.5 tons were incinerated in 24 hours. Experiments were made on the production of partly dried material by removal of a portion of the sludge from the top parts of the incinerator, using the heat of the remainder of the sludge incinerated for drying purposes. Studies are now being carried out at the Agricultural College of the University of Minnesota on uses of the sludge cake, dry sludge, or ash. The cost analysis shows that filtration and the conditioning cost $2.56 per dry ton and incineration costs $1.01 per dry ton, giving a total of $3.57 per ton of solids on a dry basis, or an average cost of $11,260 per month to handle 3,150 tons of dry sewage solids.

A marked improvement in the physical, bio-chemical, and bacteriological condition of the Mississippi River was noted. Through the Twin Cities, the floating scum, sleek and large masses of sludge, which in former summers covered as much as 50 per cent of the water surface in some areas, had practically disappeared. Foul odors of past years were no longer in evidence and game fish were returning. Recreational uses such as boating and fishing were in evidence. The river below the Twin Cities has shown an improvement, although it is still seriously affected by the untreated sewage and packing plant wastes from South St. Paul and Newport, having a population equivalent of from 200,000 to 400,000, depending upon the animals killed. The data taken at the Twin City Lock and Dam on the Mississippi River show that dissolved oxygen averaged 6.6 p.p.m. during 1939, whereas in 1935 it averaged as low as 1.7 p.p.m. The B.O.D. of the river at this point averaged 1.85 p.p.m. as against values above 4 previously. The total bacteria count per ml. showed an average of 11,000 as against 400,000 or over, previously. River bottom analyses were also made. A complete evaluation of the recovery of the Mississippi River will not be possible until the other communities install treatment plants. The author had previously made calculations on which the degree of treatment decided upon was based. It is hoped that these calculations can be checked by actual observation and a determination made of several factors affecting deoxygenation and reaeration. Preliminary calculations which have been made indicate that the type of treatment selected will meet maximum requirements of the Mississippi River and at the same time will permit variations of treatment to cope with different river dilution conditions and requirements.

ROLF ELIASSEN

WORLD'S LARGEST SEWAGE DISPOSAL PLANT WILL BE DOUBLED IN SIZE

Engineering News-Record, 125, 698 (Nov. 21, 1940)

The completion of the program for the complete treatment of all sewage from Chicago and neighboring communities will be brought about by the expansion of the Southwest sewage treatment plant of the Sanitary District of Chicago. The present capacity of 400 M.G.D. will be increased to provide activated sludge treatment for 900 M.G.D. of sewage.

To provide further purification of the Imhoff tank effluent at the West Side sewage treatment plant, studies were carried on over a period of four years on six different processes to determine the best method. After review by an independent board of engineers, a decision was reached to treat the effluent by the activated sludge process. Cost studies showed that it would be more economical to accomplish this treatment by an addition to the Southwest plant rather than building a separate activated sludge plant at the West Side. The elevation of the Imhoff tanks above the water surface of the aeration tanks at the Southwest plant will provide adequate head for gravity flow through 4,100 ft. of conduits, meters, and gates.

The contemplated enlargement to 900 M.G.D. capacity will be made in two stages. The first stage includes the installation of one turbo-blower of 100,000 c.f.s. capacity, the construction of 16 final settling tanks and 4 sludge concentration tanks, the enlargement of the sludge disposal plant, and the addition of facilities for handling screenings, scum, grit, coal, and fertilizer. Completion of this work will bring the rate of capacity to 500 M.G.D. and provide sludge disposal equipment for the ultimate 900 M.G.D. to be treated. The second stage will include the construction of a conduit from the West Side works with meter vaults and gate house. Eight aeration tanks, similar to those now in use, twenty-four final settling tanks, two additional blowers, operating galleries, service tunnels, effluent conduits, and appurtenances will be constructed.

Storm runoff equivalent to 50 per cent of normal dry-weather sewage flow will receive primary sedimentation, but only that part equivalent to 115 per cent of dry-weather flow will receive complete treatment. Excess solids will be stored for short periods in the aeration system by increasing the concentration of the mixed liquor as high as 4500 p.p.m. to smooth out the storm maxima and reduce the amount of sludge disposal equipment that would be required to remove solids as fast as they are received. The mixing of Imhoff tank effluent with the settled sewage of the Southwest plant will also smooth out the large variations in strength of the latter due to the periodic discharge of highly concentrated wastes from the stockyards and packing houses.

ROLF ELIASSEN

HEAT TREATMENT AS AN AID TO SLUDGE DEWATERING

BY C. LUMB

The Surveyor, 98, 287–291 (Dec. 6, 1940)

The author describes the installation, operating troubles, ten months' full scale operating results and operating costs of an installation at Halifax, England, for pretreating humus (from settling tanks following trickling filters) and waste activated sludge prior to dewatering by filter pressing methods. The process is known as the "Porteous" heat treatment process and is designed to deal with 25,000 gallons of raw sludge, containing approximately 5 to 1 by weight of dry humus to activated sludge solids, respectively, in an 8-hour day.

The process is as follows: raw sludge from a storage tank is pumped through a heat exchanger against steam pressure into cooking vessels in which the preheated sludge is cooked for 15 minutes at a temperature of 360 deg. F. at 150 lb. pressure. The sludge is then settled and decanted, the supernatant liquor drawn off and the settled residue piped to a thickened sludge storage tank. The thickened, heat treated sludge is filtered in filter presses. The decantate and press filtrate are settled in a separate tank

known as an effluent tank. The settled effluent is returned to the raw sewage; the sludge is pumped to the thickened sludge storage tank.

The heat exchanger comprises eighty-eight 25-ft. lengths of concentric double steel tubes. The inner tube is 2½ in. in diameter with the outer tube providing a ¾ in. annular space around the former. The tubes are set vertically in a steel shell and coupled together in series so that cold raw sludge enters the outer space at one end of the system and hot treated sludge enters the central core at the other end and the two sludges pass in countercurrent through these sections for about ½-mile to effect heat exchange. Velocity of the sludge in the inner tube is about 3 ft. per second and about 5 ft. per second in the outer tube.

The cooking vessels are of steel, each of gross capacity of 1500 gals., but intended to treat about 800 gal. per charge. Steam is passed into the vessels during the time they are filled and emptied. Sludge is not withdrawn until it has been cooked for 15 min. at 360 deg. F.

The heat treated sludge is decanted in two steel tanks having hopper bottoms. Each tank has a capacity of 14,000 gallons, equivalent to about four hours' production of treated sludge.

The thickened sludge storage tank is of reinforced concrete, circular in plan, and equipped with a stirring device.

The effluent tank used to settle decantate and press filtrate is of reinforced concrete having a capacity of 32,000 gallons.

There are three filter presses, by S. H. Johnson & Co., Ltd., of 2800 to 2900 lb. capacity each per discharge. The filter press cake is further dried in a shed heated by unit heaters.

The steam plant comprises two water-tube boilers each rated at 3,000 lb. of steam per hour at 180 lb. per square inch. The boilers are stoker-fired with recovered cinders, of calorific value 8,000 to 10,000 B.t.u. per pound, from the Corporation's refuse disposal works. One boiler only is used at a time, the other serving as stand-by.

The contract cost was £22,000.

Main operating troubles were due to difficulties in emptying the cooking vessels to synchronize with sludge pumping schedule, clogging of the sludge pumps and loss of output capacity due to inability to attain desired temperatures in the cooking vessels in the normal operating period. This latter difficulty was bound up with questions of boiler pressure and of gas liberated from the sludge on cooking. Low grade fuel makes it difficult to maintain boiler pressure and it has at times been necessary to shut down the process to wait for the boiler pressure to pick up. Gas vented from the cooking vessels caused some odor when exhausted through the chimney stack. This difficulty was eliminated by burning the gas under the boilers.

Operating results for the period, December, 1939 to September, 1940, inclusive are briefly as follows:

TABLE 2.—*Moisture Content*

Month	Raw Sludge	Thickened Sludge after Heat Treatment and Decantation
	Per Cent	Per Cent
December, 1939	94.7	87.6
January, 1940	94.8	90.2
February, 1940	94.7	88.0
March, 1940	94.9	88.7
April, 1940	95.0	87.9
May, 1940	94.9	89.8
June, 1940	95.5	91.4
July, 1940	94.7	89.4
August, 1940	93.9	88.7
September, 1940	94.0	90.5
Weighted average over full period	94.7	89.3

Results on dewatering the thickened sludge in the presses have been as follows:

TABLE 3.

	Average Pressing Time (Hours)	Average Cake Moisture	Average Age of Press Cloths	Nature of Press Cloths
		Per Cent	Weeks	
December	3.9	46.7	3.0	Cotton
January	5.2	43.4	6.5	Cotton
February	6.3	45.8	10.0	Cotton
March	4.2	42.5	2.0	Cotton and jute
April	4.3	40.1	4.1	Cotton and jute
May	3.9	37.4	2.5	Jute
June	4.0	37.6	2.7	Cotton and jute
July	4.1	42.3	2.5	Cotton
August	3.9	41.8	2.5	Cotton
September	4.0	40.6	2.5	Cotton
Weighted average	4.2	41.3	All states of cloths	

TABLE 4.—*Average Analyses of Sludges (Dry Basis)*

	Original Raw Sludge Received	Dried Cake Leaving Site (Final Product)
	Per Cent	Per Cent
Organic and volatile matter	63.6	51.2
Total nitrogen, as N	3.88	2.00
Phosphoric acid, as P_2O_5	3.33	4.26
Potash, as K_2O	0.31	0.23

TABLE 5.—*Steam Consumption and Heat Recovery*

	Overall Figure, Including Warming-up Each Morning		Net Operating Figure Not Including Warming-up	
	Steam Consumption, Lb. per Gallon Sludge Treated	Percentage Heat Recovery	Steam, Lb. per Gallon	Percentage Heat Recovery
		Per Cent		
December	1.26	66.8	—	—
January	1.24*	68.4	—	—
February	1.06	72.6	—	—
March	0.85	77.4	—	—
April	0.80	78.3	0.67	81.8
May	0.78	78.5	—	—
June	0.69	80.7	—	—
July	0.62	82.4	—	—
August	0.60	83.0	—	—
September	0.68	81.0	—	—

* First fortnight not included, readings not available.

TABLE 6.—*Average Analysis of Decantate and Press Liquor*

	Parts per 100,000
Total solids	1,135
Total solids, ash	165
4 Hours oxygen absorbed	301
5-day B.O.D.	422
Albuminoid nitrogen	46.5
Kjeldahl nitrogen	163

Over the full period, the volume of liquor has averaged 0.21 per cent of the sewage flow, although the ratio during actual hours of pumping (approximately 100 hours weekly) has exceeded this value.

Personnel employed to operate the plant comprise a plant superintendent, a boiler attendant and three laborers. Operating costs per ton are stated as follows:

	Cost per Ton, Pence
Wages, including running repairs	9.5
Power, including effluent pumping	1.6
Fuel, including cake drying	4.0
Press cloths	2.0
Water, including boiler conditioning	0.6
Sundry material and stores	1.0
	18.7
Less revenue from dried cake	3.5
Net cost per ton	15.2

K. V. HILL

CITY OF WORCESTER, MASSACHUSETTS, DEPARTMENT OF PUBLIC WORKS, BUREAU OF SEWERS

Annual Report of the Superintendent of Sewers for the Year Ending December 31, 1939

SEWAGE TREATMENT WORKS

No changes were made in the general method of operation of the sewage treatment works. Continued progress is made each year in maintenance work so that aside from poor paint condition of the iron walks and railings at the Imhoff tanks, in particular, the Works can be considered as being in excellent condition.

Sewage Flow. The total sewage flow during 1939 was 7472.52 million gallons; a daily average of 20.47 million gallons. It is interesting to note that the maximum sewage flow for any day, 7 A.M. to 7 A.M., during 1939 was only 44.55 million gallons. The normal figure generally falls between 50 and 58 million gallons.

Grit Chambers. Each grit chamber was flushed and cleaned seven times during the year. From 7472.5 million gallons of sewage there were deposited 876.6 cubic yards of material, which were removed from the chambers. This represents an average of 3.17 cubic feet of material per million gallons of sewage. The total cost of cleaning the chambers was $339.90, an average of 38.8 cents per cubic yard of material removed.

The sand filter on to which these flushings are discharged was cleaned in August. The Barber-Greene loader, our own two trucks and welfare labor were used. The cost of removing 1090.7 cubic yards of material to a low area, 700 to 1000 feet distant, was $715.37, an average of 65.6 cents per cubic yard.

Screening of Sewage. Both screen installations received needed overhauling of the raking mechanism. In addition to new chains and upper sprocket wheels, the lower wheels were replaced and the chain runs, both upper and lower, were refitted with lower plates or bottoms. The latter repair was the first of its kind made since the rakes were installed in November, 1930.

There were removed from 7472.5 million gallons of sewage, a total of 13,920 cubic feet of screenings, representing an average of 1.86 cubic feet per million gallons of sewage screened.

The cost of screen operation according to the Works payroll was $1148.11. This represents $3.14 per day; 8.2 cents per cubic foot of screenings removed to a low area 500 feet away; 15.2 cents per million gallons of sewage screened.

Imhoff Tanks. The Imhoff tanks have given no difficulties concerning their operation. The quantity of sewage treated by the tanks was 7376.82 million gallons, a daily average of 20.21 million gallons. The average detention period of the sewage was 2.9 hours.

The grease accumulation removed from the tanks amounted to 4,563 cubic feet; this is the largest yearly accumulation since 1934. The grease is run to diked areas and buried.

The sludge production during this past year totalled 12,841,810 gallons, or almost four million gallons more than in 1938. The tank influent totalled almost 900 million gallons less in 1939 than in 1938. The facts are (1) part of the sewerage system is on the combined plan, (2) the annual rainfall of 1939 was 3.2 inches less than normal, (3) industrial activities increased considerably during the latter half of the year and (4) normally, the sewage contains a daily average of from three to four million gallons of industrial waste liquors. Operation data pertaining to the sewerage system and to sewage treatment, if practiced, are valuable when considering the problem of sewage treatment.

The sludge drawn from the tanks had a specific gravity of 1.028; percentage dry solids, 6.52 and pH 6.7. The density of the sludge was about the same as in past years; the pH dropped from 6.8 to a new low of 6.7 with apparently no ill effect upon sludge digestion.

The sludge was well digested; the percentage of volatile matter in the dried solids averaged 44.10. The percentage of nitrogen increased nearly 0.5 per cent as compared with the past two years. The percentage of iron decreased to 3.69.

The data in Table I indicate that tank treatment of the stronger sewage of 1939 produced an effluent containing less settleable and suspended solids than that of 1938. The suspended solids content of the tank effluent averaged 88 parts per million. The biochemical oxygen demand

of the effluent averaged 115.8 parts per million, an increase of 14.2 parts, as compared with 1938.

Dosing Tanks. No difficulties have been encountered with dosing tank operation throughout the year. Replacements were made of the poorest sections of dosing tank covers as a part of an annual program for uniform maintenance expenditures.

Trickling Filters. The trickling filters treated 7136.12 million gallons of Imhoff tank effluent; an average of 19.55 million gallons daily. The average rate of filtration was 1.50 million gallons per acre per day.

The usual filter flooding for fly control was practiced from May to September and no complaints were received concerning filter flies. Nozzle clogging was more prevalent than usual during the last two months of the year owing to continued high winds, day after day.

In the 1938 report, it was stated that filter unloading had been almost entirely absent during the fall months. Filter unloading occurred from April through August, 1939, an unusually long period and during November and December, it has been greater than in 1938, despite this marked unloading earlier in the year.

Analysis of all of the data concerning trickling filter operation is shown in Table I and is summarized as follows:

Stronger sewage and Imhoff tank effluent placed a heavier load of organic matter upon the filters; consequently, the filter effluent contained more organic matter than in 1938. The same statement is true concerning the iron content of the effluent.

During January and February there was a period of fifteen days when all end nozzles were out owing to low atmospheric temperature. The influent discharged from the end nozzles was not purified. The cold temperature caused ice formation over the entire filter area and the influent discharged upon the filters was not well purified. Mention has been made that March and April, 1939, were colder than the corresponding months of 1938. All of these conditions resulted in filter effluent of increasing deterioration of quality during the first four months of 1939.

Although filter unloading early in the year continued for an unusually long time, the quality of the filter effluent improved quickly upon obtaining warmer atmospheric temperature and decreased rate of filter operation.

The filters successfully treated stronger influent demonstrating that filter ice conditions and low atmospheric temperature are the factors affecting winter results of operation.

The results of filter operation during December, 1939, when it was necessary to remove end nozzles for 48 hours during a period of eight days of low atmospheric temperature showed a drop in effluent stability and increased organic content of the effluent. The duration of this cold spell, December 23 on, was not long enough to affect the dissolved oxygen and nitrate nitrogen contents of the effluent during December.

Secondary Tanks. The secondary settling tanks handled 7136.12 million gallons of trickling filter effluent, an average of 19.55 million

gallons daily. The average detention period of the trickling filter effluent in the secondary or final settling tanks was 2.1 hours.

Efficient operation of the final settling tanks shows that the average suspended solids of the filter effluent, 126 parts per million, was reduced to 60 parts. The biochemical oxygen demand reduction was from 24.9 to 17.8 parts per million. The dissolved oxygen content of the filter effluent was but slightly reduced during its detention in the final settling tanks. The relative stability of the final effluent averaged 91 + per cent or the same as that of the filter effluent.

Sludge was pumped from the tanks once each week; during the summer, to the sludge concentration tanks and then to the small drying beds and during the remainder of the year to the winter bed area.

TABLE I.—*Suspended Solids, Biochemical Oxygen Demand*

	Susp. Solids P.P.M.				Per Cent Removal		B. O. D. P.P.M. 5 Days 20° C.				Per Cent Removal	
	Sew.	Imhoff Eff.	Tr. Fil. Eff.	Sec. Tk. Eff.	Imhoff Treat.	Sec. Tr.	Sew.	Imhoff Eff.	Tr. Fil. Eff.	Sec. Tk. Eff.	Imhoff Treat.	Entire Plant
January	183	85	85	55	53.5	69.9	170.6	115.3	25.8	23.9	32.4	86.0
February	213	85	93	61	60.1	71.4	161.4	110.1	28.2	24.0	31.8	85.2
March	163	82	90	59	49.7	63.9	140.9	99.1	26.2	20.1	29.7	85.8
April	146	69	122	70	52.7	52.1	114.7	80.8	20.1	13.7	29.5	88.0
May	224	95	213	78	57.5	65.2	186.8	124.8	30.4	20.1	33.2	89.3
June	258	99	213	66	61.6	74.4	193.4	137.0	36.7	23.7	29.2	87.8
July	236	79	172	59	66.5	75.0	211.6	134.4	24.3	14.9	36.5	93.0
August	253	100	136	60	60.5	76.3	200.0	117.2	18.2	11.8	41.4	94.1
September	264	100	98	47	62.1	82.2	208.1	123.6	12.0	8.1	40.6	96.1
October	279	96	82	44	65.6	84.2	210.9	122.6	20.2	11.5	41.9	94.6
November	251	82	114	53	67.3	78.9	209.7	127.1	27.4	19.4	39.4	90.8
December	278	97	120	58	65.1	79.2	198.8	127.5	27.3	19.6	35.9	90.2
1939	223	88	126	60	60.5	73.1*	178.5	115.8	24.9	17.8	35.1	90.0
1927	288	127			55.9		150.5	88.6	31.1	27.0	41.1	82.1
1928	275	114	120	77	58.6	35.9	152.9	98.6	20.4	18.8	35.4	87.8
1929	317	118	142	84	62.8	40.8	178.5	114.0	22.6	17.8	36.2	90.1
1930	291	117	165	86	59.8	47.9	211.6	142.5	31.0	24.4	32.6	88.5
1931	229	101	140	64	55.9	54.3	196.0	136.5	29.7	22.2	30.4	88.7
1932	219	94	143	62	57.1	56.6	211.5	140.0	34.0	22.7	33.8	88.3
1933	224	97	118	53	56.7	55.0	213.5	139.6	34.4	23.8	34.6	88.9
1934	240	95	97	55	60.4	43.3	241.0	147.6	43.9	35.8	38.7	85.2
1935	233	96	105	52	58.8	50.5	200.5	123.0	33.5	25.6	38.7	87.2
1936	256	97	92	55	62.2	40.2	207.2	129.5	36.9	29.1	37.5	86.0
1937	264	100	104	55	62.1	47.1	204.0	122.9	30.7	24.0	39.7	88.3
1938	207	89	100	54	57.0	73.9*	162.5	101.6	20.9	15.7	37.5	90.3
1939	223	88	126	60	60.5	73.1*	178.5	115.8	24.9	17.8	35.1	90.0

* Entire Plant.

Sludge Disposal. The sludge drying bed area is in three parts; summer Imhoff tank sludge is dried on 21 one-quarter acre beds; summer secondary tank sludge after concentration is dried on 32–18 × 110

ft. beds and during the winter, both sludges, the secondary without concentration, are pumped to 43 old one acre beds. The entire area is composed of former sand filters used for intermittent filtration of sewage.

Welfare help working with trucks have been employed throughout the season cleaning beds in the first two areas; in addition, sludge was removed from quite a few of the winter beds. From September 14 to December 14, three months, about 10 to 12 temporary laborers were employed cleaning winter beds. Funds for sludge removal were limited as well as the amount of available welfare help. At this time, there are fourteen one-acre beds from which the sludge was not removed.

The summary of costs of sludge removal is as follows:

Welfare	Cubic Yards	Cost		Total	Cubic Yard
		Trucks	Labor*		
Imhoff sludge	6694.2	$1212.86	$2658.63	$3871.49	$ .578
Secondary sludge	793.3	232.05	434.77	666.83	.841
Winter sludge	4753.5	959.47	2139.32	3098.79	.652
Temporary:					
Winter sludge	6822.0	1454.64	3168.60	4623.24	.677
Total	19,063.0	$3859.02	$8401.32	$12,160.34	.643

* No foreman charge. All labor at 50 cents per hour.

Why handle secondary tank sludge on small beds after concentration instead of on the winter beds at less cost per cubic yard of dried sludge for removal? The total of approximately 800 cubic yards of dried sludge represents the drying of almost the entire sludge production from April to December on 1.5 acres of bed area. Flexibility of bed operation; sludge drying and removal of the dried sludge and reservation of one-acre beds for winter sludge disposal represent $160.00 well expended.

Cost of Sewage Treatment

The cost of sewage treatment is summarized as follows:

	Total	Per Million Gallons
Grit Chamber	$ 716.14	$0.09
Screen	2,237.11	0.30
Imhoff Tanks	8,524.64	1.14
Trickling Filters	8,620.81	1.15
Secondary Tanks	5,687.86	0.76
Sludge Disposal	11,023.90	1.48
Laboratory	5,175.98	0.69
	$41,986.44	$5.61
Real Estate	980.25	
	$42,966.69	

The expenditure of $41,986.44 represents a cost of $5.61 per million gallons of sewage treated by the Works. The cost per capita served was approximately 22.1 cents for the year—1.84 cents per month.

Welfare labor is not included in these figures. The cost of removal of dried sludge from the beds by welfare labor was $5,232.72, using 50 cents per hour as the rate. All other costs are included in the figure above. The cost of welfare labor increases the treatment cost per million gallons of sewage to $6.31.

PROCEEDINGS OF THE FOURTEENTH ANNUAL CONFERENCE OF THE MARYLAND-DELAWARE WATER AND SEWERAGE ASSOCIATION

The Biofiltration System as a Means for Varying the Degree of Sewage Treatment. By A. J. FISCHER, pp. 11–27. This article gives a description of various applications of the biofiltration system, together with a discussion of factors influencing design and operation, B.O.D. loading, recirculation, clarifier design, dosing rates, filter bed design and distributors. Ten drawings and photographs and nine tables of operating data giving dosing rates, B.O.D. loading and per cent reductions are used to supplement and support the author's discussion.

The author concludes as follows:

1. The degree of treatment of sewage may be varied over a wide range by the use of the biofiltration system.

2. The single-stage process in which one filter and one clarifier is used, will effect B.O.D. reductions of 50–60 per cent.

3. The single stage complete system, using one filter and two clarifiers will give B.O.D. reductions of 75–80 per cent.

4. In the two-stage system where two filters and two clarifiers are used, B.O.D. reductions of 90–95 per cent may be effected.

5. The chief factors that influence the design and operation of all types of biofilter plants are B.O.D. loading on the filter, the volume of recirculated flow, and the clarifier overflow rate and detention.

6. The capacity of a filter for removing B.O.D. apparently varies with the strength and characteristics of the applied sewage. With normal strength domestic sewage, a maximum of 2.0 lb. of B.O.D. per cu. yd. of filter medium per day can be removed.

7. Recirculation of filter effluent back to the detention tank is of material aid in controlling the degree of purification obtained. In general the recirculation ratio should be increased in proportion to the increase in strength of the raw sewage. In the case of normal strength sewage this ratio should be about 2.0 for single stage intermediate treatment, 1.5 for single stage complete treatment and 1.0 for two-stage treatment.

8. The detention tank design becomes increasingly more important as B.O.D. load on the filters is increased. The average clarifier overflow rate should not exceed 800–1000 gallons per square foot per 24 hours in the case of the two-stage plants. Average clarifier detentions should not be less than 1.5–2.0 hours.

9. Within a range of about 8.0 to 100 m.g.a.d. dosing rates apparently do not affect the action in the filter bed as long as the B.O.D. load is not excessive.

10. Increasing the filter bed depth beyond 3 feet gives only a slight improvement in results.

11. The biofilter system may be applied for the pre-treatment of very strong industrial wastes. In the case of distillery wastes having a B.O.D. of about 20,000 p.p.m. over 90 per cent reduction in B.O.D. may be effected in a single-stage 3 ft. depth filter.

12. In the treatment of strong wastes such as distillery waste, very high B.O.D. loadings may be applied to the filters without seriously affecting their efficiency. In the case

of distillery waste, B.O.D. loadings of 18–20 lb. per cubic yard per day were applied. The removals in the filters were 15–18 lb. per cubic yard per day.

Discussion. By F. S. Friel, pp. 28–32. Further discussion of the design, operation and application of the biofiltration system is given. The influence of temperature on filter efficiency is emphasized.

Digestion tanks for the plant employing biofiltration should be larger than those employed for the standard trickling filter plant since no digestion occurs in the filter proper and the moisture content of the biofilter sludge is higher than that from the standard filter. Digestion space between 3 and 4 cu. ft. per capita is recommended.

Experiments with High-Rate Trickling Filters at Baltimore, Maryland. By C. E. Keefer and Herman Kratz, Jr., pp. 33–42. Discussion, Linn H. Enslow, pp. 42–44. A small portion of the existing trickling filters at the Baltimore plant was used for the experiments. These filters contain trap rock varying in size from 1 in. to 2.5 in. and are 8.5 ft. deep. At the start of the experimental work the filter stone was in good condition with no evidence of clogging. Two eight-arm rotary distributors each 47.5 ft. in diameter were erected on the filter. Throughout the experiments a portion of one of the existing filter beds adjacent to the experimental units was operated at a rate of 3 m.g.a.d. as a control.

The sewage applied to the filter had passed through bar screens with 0.75 in. clear openings and had been settled in primary tanks equipped for mechanical sludge removal. The primary tanks have an average theoretical detention period of two hours. Samples of the filter influent and effluent were collected hourly, composited for a 24 hour period and analyzed. The filter effluent samples were thoroughly stirred before analysis so that the analyses would be representative of the entire effluent.

Three groups of experiments were carried out. Experimental data are presented in tables and by means of graphs.

Based on the experimental evidence the following conclusions which apply particularly to Baltimore conditions were reached.

1. There is no reason to believe that ponding will occur at any rate of flow from 6.5 to 30 m.g.a.d.

2. As the rate of flow increases, a gradual increase in the B.O.D. of the effluent and a decrease in nitrification can be expected. This decrease in B.O.D. removal was not marked even when the flow was 10.0 m.g.a.d.

3. Even at high rates of application (26 m.g.a.d.) a reduction of approximately 30 per cent can be expected in the B.O.D. in winter and 70 per cent or more in summer.

4. A considerable portion of the B.O.D. can be removed in summer by shallow filters varying from 2 to 4 ft. deep when the rate is as high as 10 m.g.a.d. The removal would undoubtedly be less in winter.

5. If an effluent is to be better than that from sedimentation tanks and inferior to that from a low-rate trickling filter, a high rate filter may serve. Treatment comparable to chemical precipitation or sedimentation and magnetite filters can be obtained by sedimentation and high-rate trickling filters. The degree of treatment depends upon the rate of applying the sewage and the depth of the filters.

Inexpensive Contrivances Which Have Improved the Operation of a Small Sewage Treatment Works. By C. G. Weber, pp. 78–89. This is a summary of experiences at the Annapolis, Maryland, sewage treatment plant with chlorination, grit removal, sludge filtration and elutriation. Eight sketches and photographs illustrate methods and equipment. The improvements which were conceived and carried out by plant personnel have resulted in substantial savings in operating costs and improved plant performance.

This paper is discussed by H. R. Hancock and A. L. Genter, pp. 90–97.

The Effect of the Washington Sewage Disposal Plant on the Potomac River. By Paul D. McNamee, pp. 61–70. This paper presents a summary of a study made of the bacteriological and chemical quality of the Potomac River during 1938 and 1939. Sampling points corresponded to those used in surveys by the U. S. Public Health Service before the plant was installed. The data are compared with the results of the prior surveys and correlated with stream flow and temperature. The plant has been of value in raising the

dissolved oxygen concentration in the section of the river which needs it most. Approximately 20 tons of 5-day B.O.D. and 12 tons of heavy solids are removed daily by the treatment plant.

Discussion. By RALPH E. FUHRMAN, pp. 70–73. A discussion of certain characteristics of the Potomac River which affect its ability to absorb the imposed sewage load. Of particular importance are the tidal flats which, through the agency of the vegetative growths, furnish large amounts of oxygen to the water.

Discussion. By R. E. TARBETT. Past studies by the U. S. Public Health Service indicated that the Potomac River tidal flats produced oxygen during the summer period at a rate of 17.7 pounds per acre per day.

The author notes that physical changes taking place in and around the Washington area, particularly those affecting the flats, will eventually have a considerable effect upon the river pollution problems and will make it difficult to show by future studies just what effect the treatment of the Washington sewage has had upon river conditions.

The problem of water pollution control within the District is one that must be considered mainly from the standpoint of recreational use of the stream.

PAUL D. HANEY

FLASH DRYING OF SLUDGE

Chemical and Metallurgical Engineering, **48**, 108–111 (January, 1941)

A brief discussion of the flash-drying system employed by the Chicago Sanitary District is given. Twelve actual photographs of the Southwest sewage treatment plant are used to supplement the plant flow sheet which shows diagrammatically the various steps in the entire sewage treatment and sludge disposal processes.

PAUL D. HANEY

REFERENCES TO SEWAGE LITERATURE

September–December, 1940

American City. Volume 55

September, 1940 (No. 9).

"Seven Years' Operation Data, Grand Rapids Sewage Works," pp. 66–67.

"Sludge as Fertilizer." Le Roy W. VanKleeck, pp. 73–75.

October, 1940 (No. 10).

"New Sewage Treatment Plants for Springfield, Massachusetts." Alfred A. Burger, pp. 43–46.

"Small Activated Sludge Plant" (London, Ohio). Leonard McNeal, pp. 63–64.

November, 1940 (No. 11).

"Sewage Treatment" (Bedford, Ohio). Arthur H. Wedge, pp. 47–49.

"New Sewage Treatment Plants for Springfield, Massachusetts" (Indian Orchard Plant). Alfred A. Burger, pp. 66–67.

December, 1940 (No. 12).

"Large Trickling Filter Plant with Sludge Digestion" (Des Moines, Iowa), pp. 42–44.

"Using Sludge Gas," pp. 63–65.

Engineering News-Record. Volume 125

September, 26, 1940.

"New England's Newest Sewage Works." E. J. Cleary, pp. 396–401.

"Biofiltration Comes East," pp. 402–404.

"Dual Units Solve Resort Sewage Problem." A. Dale Swisher, pp. 405–406.

"Problems in Garbage-Sewage Treatment," pp. 407–408.

October, 10, 1940.

"Forming and Concreting Sewage Tanks," pp. 461–463.

"Revamping a 50 Year-Old Sewer System." W. D. P. Warren, pp. 475–476.

November 7, 1940.

"Practice and Problems in Sewage Disposal Service," pp. 611–613.

November 21, 1940.

"World's Largest Sewage Disposal Plant Will Be Doubled in Size," pp. 698–699.

December 5, 1940.

"Camp Water Supply and Sewage Disposal," pp. 769–770.

December 19, 1940.

"Biofiltration Effluent Used for Irrigation at Santa Paula," p. 834.

Public Works. Volume 71

September, 1940 (No. 9).

"Trickling Filters With Open Sidewalls to Improve Aeration." L. J. Voorhees, pp. 13–14.

October, 1940 (No. 10).

"Small Georgia Sewage Treatment Plant Treats 200,000 G.P.D.," p. 13.

"A Month's Operating Results at the Liberty Biofiltration Plant," pp. 16–18.

"Precautions in Handling Sludge Gas," p. 18.

"Experiences with Paints at a Sewage Treatment Plant," pp. 32–33.

November, 1940 (No. 11).

"Measures and Procedures to Prevent Sabotage of Water and Sewage Plants," p. 22.

"Water Supply and Sewage Disposal for Air Ports," p. 25.

December, 1940 (No. 12).

"Landscaping Fargo's Sewage Treatment Plant," F. W. Pinney, pp. 11–12.

"Water and Sewage Chemistry and Chemicals." W. A. Hardenbergh *et al.*, pp. 25–40.

Sewage Works Engineering. Volume 11

September, 1940.

"The Plant That 'Steel' Built (Gary, Ind.)." L. R. Howson, pp. 413–428.

"A Sanitary Sewerage System for Staunton, Va." Raymond C. Regnier, Jr., pp. 431–434.

"The Problem of Industrial Waste Disposal," pp. 435–437.

"When Municipal Businesses Are Valid Operations." Leo T. Parker, pp. 444–446.

October, 1940.

"Sewage Treatment Wins Its 'Y.'" Charles A. Emerson, Jr., pp. 483–491.

"A Symposium on Plant Operating Results." T. R. Lovell *et al.*, pp. 492–509.

"Review of 1940 Municipal Damage Suits." Leo T. Parker, p. 515.

November, 1940.

"'Battleship' Sewage Plant by the Sea." R. E. Koon, pp. 548–552.

"Illegal Contracts." Leo T. Parker, pp. 566–568.

December, 1940.

"Effect of Volatile Solvents on Bacterial Numbers in Sewage." H. Heukelekian and H. B. Schulhoff, pp, 593–594.

"A Quarantined Lakefront Reclaimed by Biofilter." Harry N. Jenks, pp. 595–597.

"Heat Regulation in Digesters at Oshkosh." R. W. Frazier, p. 598.

"High-Rate Recirculating Filter for Milk Wastes." E. F. Eldridge, pp. 599–600.

Water Works and Sewerage. Volume 87

September, 1940.

"Maintenance of Sewage Pumping Stations." A. L. Soden, pp. 417–421.

"Sewage Filtration with Silica Sand Filters. Part 2." Phillip B. Streander, pp. 422–429.

"Hydraulics in Connection with Water and Sewage Works." Marion L. Crist, pp. 433–436.

"Rotary Blowers in Activated Sludge Plants," pp. 440–447.

October, 1940.

"The Biofiltration System." Anthony J. Fischer, pp. 481–488.

"A New Sewer Maintenance Truck." E. P. Decher, pp. 489–491.

"Sewage Filtration. Part 3." Phillip B. Streander, pp. 493–495.

November, 1940.

"A Multiple Nomograph for Chlorine Demand Determinations." G. E. Symons and S. R. Kin, pp. 547–548.

December, 1940.

"Fertilizer and Fertility Value of Sewage Sludge." Willem Rudolfs, pp. 575–578.

"Liquids Do Not Flow 'En Masse.'" R. D. Nichols, pp. 579–582.

"Sludge Disposal with a Bit of Glamour." Wellington Donaldson, pp. 583–585.

"Cost Keeping." Waldo M. Porr, pp. 588–592.

Federation of Sewage Works Associations

OFFICERS OF MEMBER ASSOCIATIONS

Arizona Sewage and Water Works Association

President: A. W. Miller, Phoenix.
First Vice-President: G. A. Rhoads, Safford.
Second Vice-President: G. W. Seeley, Tucson.
Secretary-Treasurer: F. C. Roberts, Jr., Phoenix.
Directors: Phil J. Martin, Jr., Tucson; Robert M. Cushing, Phoenix; A. L. Frick, Jr., Los Angeles; Dave Ostrander, Holbrook; Bernard Schiller, Yuma; J. P. Sexton, Casa Grande.
Director, Board of Control: Phil J. Martin, Jr., Tucson.

California Sewage Works Association

President: Harold F. Gray, Berkeley.
First Vice-President: Fred D. Bowlus, Los Angeles.
Second Vice-President: Carl M. Hoskinson, Sacramento.
Secretary-Treasurer: William T. Ingram, Stockton.
Directors: H. W. Jewell, Los Angeles; B. D. Phelps, San Diego; C. F. Tennant, Long Beach; R. R. Ribal, Oakland; A. J. Castro, Jr., Santa Clara.
Director, Board of Control: C. G. Hyde, Berkeley.

Central States Sewage Works Association

President: C. C. Larson, Springfield, Ill.
First Vice-President: George Martin, Green Bay, Wis.
Second Vice-President: Kerwin L. Mick, St. Paul, Minn.
Third Vice-President: Don E. Bloodgood, Indianapolis, Ind.
Past President: B. A. Poole, Indianapolis, Ind.
Secretary-Treasurer: E. J. Beatty, Madison, Wis.
Director, Board of Control: George J. Schroepfer, St. Paul, Minn.

Dakota Water and Sewage Works Conference

North Dakota Section
President: R. M. Jenson, Grand Forks.
Vice-President: E. J. Pearson, Minot.
Secretary-Treasurer: Lloyd K. Clark, Bismarck.

South Dakota Section
President: J. E. Holst, Mitchell.
Vice-President: W. P. Wells, Aberdeen.
Secretary-Treasurer: W. W. Towne, Pierre.
Directors: S. W. Swanson, Rapid City; H. J. Steckler, Yankton; E. R. S. McGillicuddy, Elk Point; M. T. Wyatt, Pine Ridge; B. Percy, Winner; B. A. Nagle, Belle Fourche; G. T. Gunderson, Madison.
Director, Board of Control: W. W. Towne, Pierre.

Federal Sewage Research Association

President: C. C. Ruehhoft, Cincinnati, Ohio.
Vice-President: R. W. Kehr, Cincinnati, Ohio.
Secretary-Treasurer: C. T. Carnahan, Cincinnati, Ohio.
Members, Executive Committee: O. C. Hopkins, Watertown, Mass.; M. D. Hollis, Cincinnati, Ohio.
Director, Board of Control: A. P. Miller, New York City.

Georgia Water and Sewage Association

President: George H. Sparks, East Point.
First Vice-President: H. E. Whelchel, College Park.
Second Vice-President: W. H. Weaver, Decatur.
Secretary-Treasurer: Paul Weir, Atlanta.
Director, Board of Control: G. R. Frith, Atlanta.

Iowa Wastes Disposal Association

President: George C. Ahrens, Des Moines.
Vice-President: T. R. Lovell, Fort Dodge.
Secretary-Treasurer: Lindon J. Murphy, Ames.
Directors: Paul Winfrey, Des Moines; R. G. Miller, Vinton.
Director, Board of Control: Max Levine, Ames.

Kansas Water and Sewage Works Association

President: Robert Peart, Sterling.
Vice-Presidents: Warren Johnson, Wichita; Levi B. Smith, Paola; William O'Day, Coffeyville; F. W. Sieker, Yates Center.
Secretary-Treasurer: Earnest Boyce, Lawrence.
Director, Board of Control: Earnest Boyce, Lawrence.

Maryland-Delaware Water and Sewerage Association

President: George E. Harrington, Washington, D. C.
First Vice-President: Jack M. Jester, Hyattsville, Md.
Second Vice-President: Robert A. Norris, Sykesville, Md.
Secretary-Treasurer: Chesley F. Garland, Baltimore, Md.
Executive Committee: R. J. Stewart, Edgewood, Md.; E. C. Cromwell, Colgate, Md.; Clarke Gardner, Salisbury, Md.; J. W. Alden, Wilmington, Del.; A. M. Tawney, Fort Meade, Md., Ex-Officio.
Director, Board of Control: Harry R. Hall, Hyattsville, Md.

Michigan Sewage Works Association

President: A. B. Cameron, Jackson.
Vice-President: J. C. Marshall, Charlevoix.
Secretary-Treasurer: W. F. Shephard, Lansing.
Directors: J. F. Leemaster, Jackson; Allan Kronback, Monroe.
Director, Board of Control: N. G. Damoose, Battle Creek.

Missouri Water and Sewerage Conference

Chairman: John Allgeyer, St. Louis.
Vice-Chairman: Major C. Hagar, Boonville.

Secretary-Treasurer: W. A. Kramer, Jefferson City.
Executive Committee: Edward Myers, Maryville; George Russell, St. Louis; John Frie, Springfield; H. E. Newall, Webb City.
Director, Board of Control: George S. Russell, St. Louis.

New England Sewage Works Association

President: Walter J. Shea, Providence, R. I.
First Vice-President: Samuel M. Ellsworth, Boston, Mass.
Second Vice-President: R. H. Suttie, New Haven, Conn.
Secretary-Treasurer: LeRoy W. Van Kleeck, Hartford, Conn.
Directors: Herbert B. Allen, Fitchburg, Mass.; Walter M. Kunsch, Danbury, Conn.; Leonard W. Trager, Concord, N. H.
Director, Board of Control: F. W. Gilcreas, Albany, N. Y.
Ex-Officio Member: Arthur D. Weston, Boston, Mass.

New Jersey Sewage Conference

Chairman: Willem Rudolfs, New Brunswick.
Vice-Chairman: Asher Atkinson, New Brunswick.
Secretary: Richard C. Smith, Glen Ridge.
Treasurer: Willem Rudolfs, New Brunswick.
Director, Board of Control: Willem Rudolfs, New Brunswick.

New York State Sewage Works Association

President: Herbert H. Wagenhals, Syracuse.
Vice-President: Robert C. Wheeler, Albany.
Advisory Member: C. George Anderson, Rockville Centre.
Secretary-Treasurer: A. S. Bedell, Albany.
Assistant Treasurer: J. C. Brigham, Albany.
Assistant Secretary: A. W. Eustance, Albany.
Executive Committee: Rodney E. Cook, Riverhead; Channel Samson, Kenmore; H. W. Wagenhals, Syracuse; William Raisch, Forest Hills, L. I.; Joseph E. Rehler, Olean; Robert C. Wheeler, Albany; Lawrence L. Luther, Freeport; W. L. Malcolm, Ithaca; Charles R. Velzy, Buffalo.
Director, Board of Control: N. L. Nussbaumer, Buffalo.

North Carolina Sewage Works Association

Chairman: S. O. True, Greensboro.
Vice-Chairman: W. H. Hall, Durham.
Secretary-Treasurer: R. S. Phillips, Durham.
Director, Board of Control: W. M. Piatt, Durham.

Ohio Sewage Works Conference Group

President: C. D. McGuire, Columbus.
Vice-President: Floyd G. Browne, Marion.
Secretary-Treasurer: Frank Woodbury Jones, Cleveland.
Director, Board of Control: Frank Woodbury Jones, Cleveland.

Oklahoma Water and Sewage Conference

President: Elmer Edge, Oklahoma City.
Vice-President: L. H. Scott, Oklahoma City.

Secretary-Treasurer: H. J. Darcey, Oklahoma City.
Director, Board of Control: H. J. Darcey, Oklahoma City.

Pacific Northwest Sewage Works Association

President: A. D. Butler, Spokane, Wash.
First Vice-President: C. D. Forsbeck, Tacoma, Wash.
Second Vice-President: R. E. Koon, Portland, Ore.
Secretary: Fred Merryfield, Corvallis, Ore.
Director, Board of Control: John W. Cunningham, Portland, Ore.

Pennsylvania Sewage Works Association

President Emeritus: Elton D. Walker, State College.
President: George P. Searight, Carlisle.
First Vice-President: E. B. Swinehart, Pottstown.
Second Vice-President: Theodore S. Bogardus, Meadville.
Secretary-Treasurer: Bernard S. Bush, Wilkes-Barre.
Editor: J. R. Hoffert, Harrisburg.
Director, Board of Control: H. E. Moses, Harrisburg.

Rocky Mountain Sewage Works Association

President: Paul S. Fox, Santa Fe, New Mexico.
Secretary-Treasurer: Dana E. Kepner, Denver, Colo.
Directors: Frank C. Hill, Montrose, Colo.; J. E. Amend, Brighton, Colo.
Director, Board of Control: Chas. A. Davis, Denver, Colo.

Sanitary Engineering Division of the Argentine Society of Engineers (Argentina)

President: Julio Vela Huergo, Buenos Aires.
Secretary: Carlos Santos Rossell, Buenos Aires.
Director, Board of Control:

Sewage Division, Texas Section, S. W. W. A.

President: D. B. Dickson, Wichita Falls.
First Vice-President: S. C. Clark, San Benito.
Second Vice-President: M. J. Salmon, Commerce.
Third Vice-President: Roy Matthews, Albany.
Fourth Vice-President: W. F. Hicks, Paris.
Secretary: V. M. Ehlers, Austin.
Assistant Secretary-Treasurer: Mrs. Earl H. Goodwin, Austin.
Trustee: Tom Green, Austin.
Chairman, Sewage Research: R. M. Dixon, Dallas.
Director, Board of Control: V. M. Ehlers, Austin.

The Canadian Institute on Sewage and Sanitation

Past President: W. H. Riehl, Stratford, Ont.
President: Stanley Shupe, Kitchener, Ont.
Vice-President: W. L. McFaul, Hamilton, Ont.
Trustees: B. F. Lamson, St. Catherines, Ont.; H. S. Nicklin, Guelph, Ont.
Secretary-Treasurer: Albert E. Berry, Toronto, Ont.
Director, Board of Control:

The Institute of Sewage Purification (England)

President: Charles H. Ball, Davyhulme, Manchester.
Secretary-Treasurer: W. F. Freeborn, Hampton-on-Thames, Middlesex.
Director, Board of Control: J. H. Garner, Wakefield.

The Institution of Sanitary Engineers (England)

President: David M. Watson, Westminster.
Hon. Treasurer: J. W. Hammond, Romford, Essex.
Acting Secretary: Mrs. E. M. Kerry, Westminster.
Director, Board of Control: John E. Farmer, Worthing, Sussex.

Members of Federation and Subscribers to the Journal

MEMBERS OF FEDERATION AS OF DECEMBER 31, 1940

Arizona Sewage and Water Works Association

Mr. F. C. Roberts, Jr., *Secretary-Treasurer*, State Board of Health, Phoenix, Ariz.

Adams, E. H., Pittsburgh Equitable Meter Co., 2808 E. 12th St., Los Angeles, Calif. Calif.

Brown, Ike F., Supt. of Water & Sewerage, City Hall, Williams, Ariz.

Carollo, John A., Headman-Furgeson Co., Homebuilders Bldg., Phoenix, Ariz.

Cushing, Robert, 319 Homebuilders Bldg., Phoenix, Ariz.

Denison, W. R., Mgr., Ajo Improvement Co., Ajo, Ariz.

Dunnam, Herman, Asst. Water Supt., City Hall, Flagstaff, Ariz.

Follett, Eli, R. 2, Box 22, Glendale, Ariz.

Gilbert, A. J., Water Service Foreman, So. Pacific R. R., Tucson, Ariz.

Hall, Hilliard D., Grand Canyon, Ariz.

Harwell, A. A., Glendale, Ariz.

Hircock, Chas. W., 322 W. B. Ave., Glendale, Ariz.

Keye, Harmon Edward, 452 Carnegie Ave., Clairton, Pa.

Lewis, E. S., Non-Corrosive Products Co., 607 N. 19th Ave., Phoenix, Ariz.

Martin, Phil. J., City Water Dept., Tucson, Ariz.

Mathis, Alice, Engineering Dept., City Hall, Phoenix, Ariz.

Meade, F. Griffith, 2211 N. Ross St., Santa Ana, Calif.

Miller, Alden W., 1833 N. 13th Ave., Phoenix, Ariz.

Pearce, Geo. W., 106 S. 1st St., Glendale, Ariz.

Randall, Odie L., 29 S. 3rd St., Glendale, Ariz.

Roberts, F. C., Jr., State San. Engineer, State Board of Health, State Bldg. Annex, Phoenix, Ariz.

Saunders, James B., Home Realty Co., 2547 S. 6th Ave., Tucson, Ariz.

Schiller, Bernard, Co. Sanitary Engineer, County Court House, Yuma, Ariz.

Seeley, Geo. W., City Engineer, City Hall, Tucson, Ariz.

Sexton, J. P., Dist. Manager, Arizona Edison Co., Casa Grande, Ariz.

Smalley, R. T., Gen. Mgr., Arizona Edison Co., Douglas, Ariz.

Travaini, Dario, 3rd Fl., City Hall, Phoenix, Ariz.

Wickenburg, Town of, c/o Mildred L. Alrich, Wickenburg, Ariz.

Woods, F. X., Box 13, Wenden, Ariz.

California Sewage Works Association

Mr. Wm. T. Ingram, *Secretary-Treasurer*, P.O. Box 111, Stockton, California.

Adams, Allen A., Sterling Electric Motors, 5401 Telegraph Rd., Los Angeles, Calif.

Adams, W. K., City Engr., City Hall, Redding, Calif.

Albers, J. C., City Engineer, Public Service Bldg., 120 N. Howard St., Glendale, Calif.

Aldrich, Lloyd, City Engineer, Room 600, City Hall, Los Angeles, Calif.

Allen, Wm. A., Asst. Supt., City Hall, Pasadena, Calif.

American Cast Iron Pipe Co., Att.: W. R. Blair, 55 New Montgomery St., San Francisco, Calif.

Anaya, Marvin, San. Eng., Designer, 367 City Hall, San Francisco, Calif.

Appel, Alvin Arthur, Jr. Civ. Eng., 711 W. 123rd St., Los Angeles, Calif.

Arnold, G. E., San Francisco Water Dept. Millbrae, Calif.

Banks, Harvey O., 803 State Bldg., Los Angeles, Calif.

Banta, A. Perry, Engineer, 110 S. Broadway, 4th Floor, Los Angeles, Calif.

Bardoff, Julian L., Jr., Engr., 3022 Encinal Ave., Alameda, Calif.

Barnard, Archer E., 601 W. 5th St., Suite 905, Los Angeles, Calif.

Bates, John S., Cons. Eng., 3134 Eton Ave., Berkeley, Calif.

Batty, Frederic A., Supt. of Sewers, 942 S. Brouson Ave., Los Angeles, Calif.

Baugh, Charles, Chemist, 110 S. Broadway, Los Angeles, Calif.

Bell, Alexander, Pacific Coast Mgr., Wallace & Tiernan Co., Inc., 171 2nd St., San Francisco, Calif. (Deceased.)

Belt, Elmer B., Owner, Squires Belt Material Co., 37736 28th St., San Diego, Calif.

Benas, Benjamin, Richmond Sunset Sewage Treatment Plant, 4545 Lincoln Way, San Francisco, Calif.

Bennett, S. G., c/o City Hall, Santa Paula, Calif.

Best, G. R., Comm. Eng., General Electric Co., 212 N. Vignes St., Los Angeles, Calif.

Beyer, A. C., Wallace & Tiernan Co., Inc., 171 2nd St., San Francisco, Calif.

Bishop, H. N., City Eng., P. O. Box 333, Sunnyvale, Calif.

Borough, Reuben W., Member Bd. of Public Wks., L. A., City Hall, 402 Latona Ave., Los Angeles, Calif.

Bowen, M. R., 205 N. Greenleaf St., Whittier, Calif.

Bowlus, Fred D., 110 S. Broadway, 4th Floor, Los Angeles, Calif.

Boxall, F. G., City Hall, Brea, Calif.

Boyle, J. R. Lester, City Engineer, City Hall, Laguna Beach, Calif.

Brookman, H. R., Sales Mgr., S. L. Abbott Co., 135 King St., San Francisco, Calif.

Brown, Kenneth W., 374 W. Santa Clara St., San Jose, Calif.

Brown, R. F., 745 City Hall, Los Angeles, Calif.

Burnson, Blair I., Asst. San. Eng., East Bay Municipality Dist., 512 16th St., Oakland, Calif.

Byxbee, J. F., City Eng., P. O. Box 450, Palo Alto, Calif.

Calif. Assoc. Conc. Pipe Mfrs., P. O. Box 914, Fresno, Calif. Att.: H. W. Chutter, Pres.

California Corrugated Culvert Co., 7th & Parker Sts., Berkeley, Calif. Att.: Mr. A. W. Fraters, Secy.

California Institute of Technology, Att.: Franklin Thomas, Prof. of Civil Engineering, Pasadena, Calif.

California Packing Corp., 101 California St., San Francisco, Calif.

Carey, James L., Chief Electrician, Sewer Maintenance, 3155 Budau, Los Angeles, Calif.

Casey, John J., City Hall, City Engr., San Francisco, Calif.

Castello, W. O., Supt. of Sewer Dept., City Hall, Sacramento, Calif.

Castro, A. J., Jr., Plant Operator, 1303 Franklin St., Santa Clara, Calif.

Ceriat, Eugene, Construction Engineer, 1220 S. Lake St., Los Angeles, Calif.

Chapman, Clarke, Asst. Opr., 122 W. 4th St., Covina, Calif.

Chiarolla, Frank Vito, Douglas Aircraft Co., 854 N. Figueroa St., Los Angeles, Calif.

Clark, J. C., Chief Opr. Huntington Beach Plant, 518 11th St., Huntington Beach, Calif.

Clark, John A., 2644 Dwight Way, Berkeley, Calif.

Clark & Sons, N., c/o Bradley W. Wyatt, Supt. 4th & Pacific, Alameda, Calif.

Clements, Paul N., Gas Survey Foreman, 1412 W. 82nd St., Los Angeles, Calif.

Collins, A. Preston, 307 W. 1st St., 400 Klinker Bldg., Los Angeles, Calif.

Compton, C. R., 110 S. Broadway, 4th Floor, Los Angeles, Calif.

Conger, Charles C., City Eng., 145 W. Commercial St., Chino, Calif.

Cook, Lawrence H., Box 696, Menlo Park, Calif.

Cook, Max E., 100 Bush St., San Francisco, Calif.

Cooley, E. C., 625 Market St., Room 1414, San Francisco, Calif.

Corrao, Joseph, Supt. of Pumping Plants, 286 City Hall, San Francisco, Calif.

Cortelyou, H. P., Eng. Disposal of Waste, City Hall, Room 606, Los Angeles, Calif.

Crane, H. R., Salesman, 9059 Venice Blvd., Los Angeles, Calif.

Creears, T. H., 1824 S. Hope St., Los Angeles, Calif.

Cromer, Lionel, Opr., North Disposal Plant, R. 2, Box 183, Stockton, Calif.

Curfew, L. S., Mgr., Vapor Recovery Systems Co., 2820 N. Alameda St., Box 628, Compton, Calif.

Currie, David H., Eng., 1564 Arrowhead, San Bernardino, Calif.

Currie, Frank S., Con. Eng., 219 Andreson Bldg., San Bernardino, Calif.

Dakan, Earl W., Industrial Hygiene Serv., State Dept. of Public Health, 2002 Acton St., Berkeley, Calif.

Darnell, F. M., Asst. Civ. Eng., 708 City Hall, Los Angeles, Calif.

Davey, H. W., Plant Mechanic, Bakersfield Treatment Plant, 1021 Q. St., Bakersfield, Calif.

Davids, E. M., Vice Pres., Gladding, McBean Company, 2901 Los Feliz Blvd., Los Angeles, Calif.

Davidson & Fulmor, Civil Engrs., 3646 7th St., Riverside, Calif.

de Leon, Gregorio, Chief Eng., Metropolitan Water Dist., 176 Arroceros, Manila, P. I.

De Martini, Frank E., U. S. Public Health Service, 3rd & Kilgour Sts., Cincinnati, Ohio.

Derby, Ray L., San. Eng., Dept. of Water & Power, 3669 Terminal Annex, Los Angeles, Calif.

Dodson, Roy E., Jr., Eng., 816 Oregon Bldg., Portland, Ore.

Dommes, Sid F., Jr., Asst. San. Eng., 244 5th St., Richmond, Calif.

Duncan, Roland F., Operator, Sewage Disposal Plant, R. R. 1, Box 64-A, Santa Paula, Calif.

Dunstan, Gilbert H., Asst. Prof. San. Eng., University of Alabama, Box 1996, University, Ala.

Early, Fred J., Jr., Early Engineering Corp., Inc., 369 Pine St., San Francisco, Calif.

Eastman, T. F., 701 City Hall, Eng. Dept., Oakland, Calif.

Edwards, H. L., City Eng., 4852 Cypress St., La Mesa, Calif.

Egan, J. H., c/o Crane Company, 321 E. 3rd St., Los Angeles, Calif.

Ellinger, Morris, Eng., Lake Arrowhead, Calif.

Erickson, Una H., Sr. Eng., Plant Opr., City Hall, Bakersfield, Calif.

Everts, W. S., Canners League of Calif., 64 Pine St., San Francisco, Calif.

Faccinia, Frank, Operator, South Plant Stockton, 427 S. Harrison St., Stockton, Calif.

Fairbanks, E. G., Health & Safety Comm., Box 66, Manteca, Calif.

Farrar, J. H., Chief Opr., City Hall, Ontario, Calif.

Fiscus, A. E., Chief Opr., 1547 Ravenna Ave., Wilmington, Calif.

Fitch, T. A., 826 Yale St., Los Angeles, Calif.

Foreman, Merle S., Bacteriologist-Chemist, State Dept. of Public Health, 3093 Life Science Bldg., Berkeley, Calif.

Foster, Herbert B., Jr., Asst. San. Eng., State Dept. of Health, 479 Kentucky Ave., Berkeley, Calif.

Foster, William Floyd, Eng., Sewer & Storm Drain Design, 7th Floor, 333 W. 2nd St., Los Angeles, Calif.

Fraschina, Keeno, Asst. Supt. & Technician, Richmond Sunset Sewage Tr. Plant, 4545 Lincoln Way, San Francisco, Calif.

Frick, A. L., Jr., 2311 E. 8th St., Los Angeles, Calif.

Frickstad, Walter N., 803 City Hall, Oakland, Calif.

Froehde, F. C., City Eng. and Supt. of Streets, City Hall, Pomona, Calif.

Fulmer, F. B., Sect.-Treas., N. A. P. R. E., 589 Sycamore St., Oakland, Calif.

Gardner, R. T., Wallace & Tiernan, 2311 E. 8th St., Los Angeles, Calif.

Gascoigne, Geo. B., Cons. Eng., 1140 Leader Bldg., Cleveland, Ohio. (Deceased.)

General Electric Company, 212 N. Vignes, Los Angeles, Calif. Att: W. I. Kyte, Comm. Engr.

Gilkey, A. E., Opr. Sewage Treatment Plant, 332 Pleasant St., Roseville, Calif.

Gillespie, C. G., San. Eng., State Dept. Public Health, 3093 Life Science Bldg., Berkeley, Calif.

Gladding, Charles, Pres., Gladding Bros. Mfg. Co., 3rd & Keys Sts., San Jose, Calif.

Goodridge, Harry, City Engr., City Hall, Berkeley, Calif.

Goudey, R. F., Water & Power Dept., Box 240, Arcade Annex, Los Angeles, Calif.

Grant, A. J., Ass. Opr., 621 Thalia St., Laguna Beach, Calif.

Gray, Harold F., Sanitary & Hydraulic Engineer, 2540 Bonvenue Ave., Berkeley, Calif.

Gregory Sanitary & Municipal Reference Library, John H., City Hall, Columbus, Ohio.

Gregory, Ted. R., San. Eng., 199 Hilside, Kentfield, Calif.

Grunsky, Eugene L., Con. Eng., 833 Market St., Room 1101, San Francisco, Calif.

Gruss, A. W., Agent, The American Brass Co., 235 Montgomery St., San Francisco, Calif.

Hapgood, E. P., City Hall, Anaheim, Calif.

Harding, Robert G., Cons. Eng., 606 Utah Savings & Trust Bldg., Salt Lake City, Utah.

Harman, Judson A., 703 State Bldg., Los Angeles, Calif.

Harrington, J. H., City Hall, Signal Hill, Calif.

Hayler, Geo. R., Asst. City Engineer, City Hall, San Diego, Calif.

Henry, B. F., Chief Operator, Pomona Sewage Plant, P. O. Box 286, Pomona, Calif.

Hilton. Elton M., San. Inspector, National Park Service, Yosemite, Calif.

Hitchner, A. H., Eng., Oliver United Filters, Inc., 2900 Glascock St., Oakland, Calif.

Hommon, H. B., U. S. Public Health Service, Federal Office Bldg., Room 112, San Francisco, Calif.

Horton, F. C., Opr., Terminal Island, W. 118th Place, Los Angeles, Calif.

Hoskinson, Carl M., Chief Eng., Water Works, City Hall, Sacramento, Calif.

Huebner, Ludwig, Opr., Palo Alto Sewage Treatment Plant, Station A, Palo Alto, Calif.

Huth, Norman A., City Eng., City Hall, Visalia, Calif.

Hyde, Charles Gilman, Prof. in San. Engr., University of California, 11 Engineering Bldg., Berkeley, Calif.

Ingram, Fred R., 826 Shattuck, Berkeley, Calif.

Ingram, Wm. T., P. O. Box 111, Stockton, Calif.

Jacobson, John, Supt. of Repair & Power, U. C. Farm, Davis, Calif.

Jeffrey, H. H., City Hall, Rm. 111, Sacramento, Calif.

Jenks, Harry N., Cons. San. Eng., 345 Madrono Ave., Palo Alto, Calif.

Jennings, J. C., 112 City Hall, Sacramento, Calif.

Jewell, H. W., Chief Eng., Pacific Clay Products, 304 W. Ave. 26, Los Angeles, Calif.

Jewett, Herbert, 727 West Arden Ave., Glendale, Calif.

Johnson, Verner C., Supt. Disposal Plant, 227 S. Hollenbeck St., Covina, Calif.

Jones, Wayland, Supt. North Disposal Plant, R. 2, Box 182, Stockton, Calif.

Jorgenson, H. W., State Bur. of San. Eng., 3093 Life Science Bldg., Berkeley, Calif.

Kelly, Earl M., Eng., 811 W. 7th St., 301 Signal Oil Bldg., Los Angeles, Calif.

Kempkey, A., Cons. Eng., 1218 Hobart Bldg., San Francisco, Calif.

Kennedy, C. C., Atlas Bldg., 604 Mission St., San Francisco, Calif.

Kennedy, D. R., Cons. Supt., City Hall, Long Beach, Calif.

Kennedy, R. R., 604 Mission St., San Francisco, Calif.

Kinsman, Frederick, 725 Walnut St., Burlingame, Calif.

Kimball, Jack H., Asst. Supt. Water & Sewer Div., 740 Dartmouth St., Palo Alto, Calif.

Kivari, A. M., 811 W. 7th St., 301 Signal Oil Bldg., Los Angeles, Calif.

Kjellberg, G., Supt. of Sewers, 4411 Roubidoux, Riverside, Calif.

Knoedler, H. A., Inertol Co., 64 S. Park, San Francisco, Calif.

Knowlton, W. T., City Hall (705), Los Angeles, Calif.

Koebig & Koebig, Cons. Engrs., 458 S. Spring St., Los Angeles, Calif.

Kolb, Fred. W., Rep. for Proportioneers, Inc. and Bldrs. Iron Foundry, 598 Monadnock Bldg., San Francisco, Calif.

Kressly, Paul E., Cons. Eng., City Hall, Azusa, Calif.

Krohn, William, Supt. Water and Sewers, City Hall, Tracy, Calif.

Langelier, W. F., Dept. of Civil Eng., University of California, Berkeley, Calif.

Lawton, R. W., Cons. Eng., 1115 S. Hope St., Los Angeles, Calif.

Lee, Charles H., Cons. Hydraulic Eng., 58 Sutter St., San Francisco, Calif.

Lefever, R. W., Sewer Maintenance, Asst. Electrician, 3110 W. 59th St., Los Angeles, Calif.

Los Angeles Public Library, Serials Division, 530 S. Hope St., Los Angeles, Calif.

Los Angeles Public Library, Municipal Reference Library, 300 City Hall, Los Angeles, Calif.

Lowther, Burton, Cons. Engr., 710 Colorado Bldg., Denver, Colo.

Ludwig, Harvey F., c/o East Bay Cities Sewage Disposal Survey, City Hall, Berkeley, Calif.

Luippold, G. T., Luippold Engineering Sale Co., 1930 W. Olympic, Los Angeles, Calif.

Lund, Ralph F., Chief Chemist, Los Angeles Laboratory, 4277 10th Ave., Los Angeles, Calif.

Macabee, Lloyd C., Cons. Eng., 131 University Ave., Palo Alto, Calif.

MacDonald, Hugh H., Deputy City Attorney, 415 City Hall, Los Angeles, Calif.

Matsumaru, Isao, Chief Chemist, Div. of Municipal Sewage Research, 3168 Izumumachi Suita near Osaka, Japan.

Mattimoe, George E., Sewage Works Opr., Veterans Home, Yountville, Calif.

Mauldin, P. L., Opr. Hyperion Plant L. A., 1252 W. 97th St., Los Angeles, Calif.

May, Harold L., Chief Opr. Palo Alto Plant, 1192 Briton Ave., San Jose, Calif.

McBride, J. L., City Eng., City Hall, Santa Ana, Calif.

McDuell, John W., Sale Eng., 5330 Aldama St., Los Angeles, Calif.

McKinlay, Daniel, Sales Agt., International Filter Co., 611 Howard St., San Francisco, Calif.

McMillan, Donald C., City Mgr., 121 S. Coronado St., Ventura, Calif.

McMorrow, Bernard J., San. Engr. & Health Officer, Island of Hawaii, P. O. Box 916, Hilo, Hawaii.

Mechler, Louis W., Camarillo State Hospital, Camarillo, Ventura County, Calif.

Meyer, Louis P. H., Police S. F. Asst. Inspec., 583 Dolores St., San Francisco, Calif.

Miick, Fred E., Eng., Link Belt Company, 361 S, Anderson St., Los Angeles, Calif.

Mittelstaedt, R. E., Manager of Water Dept., City Hall, Sacramento, Calif.

Molitor, Paul, Supt. Madison Chatham Sewage Treatment Plant, 4 Willow St., Chatham, New Jersey.

Morris, Arval, Sales Engr., Sterling Electric Motors, Inc., Telegraph Rd. at Atlantic Blvd., Los Angeles, Calif.

Morrison, C. B., 708 City Hall, Los Angeles, Calif.

Munson, Laura A., Mrs., Box 200, Lafayette, Calif.

Neville, Jabez E., Neville Agric. Supply Co., 1300 Factory Place, Los Angeles, Calif.

Norris, Finlay J., Operator, 538 Franklin, Whittier, Calif.

O'Connell, Wm. J., Wallace & Tiernan, 137 Castilian Way, San Mateo, Calif.

Ogle, Harry B., Sales Mgr., Valley Conc. Pipe & Products Co., P. O. Box 402, Chico, Calif.

Ojai, City of, City Hall, Ojai, Calif.

Olney, H. Ross, Sewer Repair Foreman, 4215 W. Ave. 40, Los Angeles, Calif.

O'Neill, Ralph W., 2722 18th St., Bakersfield, Calif.

Ongerth, H. J., Jr. San. Eng., Calif. State Board of Health, 1911B-Berryman, Berkeley, Calif.

Pacific Foundry Company, 3100 19th St., San Francisco, Calif.

Painter, Carl E., Water Works Equipment Co., 149 W. 2nd South Salt Lake City, Utah.

Palmer, Harold K., Rm. 400, 110 S. Broadway, Los Angeles, Calif.

Parkes, G. A., Asst. Engr., Los Angeles City, 705 City Hall, Los Angeles, Calif.

Parr, James, Plant Opr., City Hall, Manteca, Calif.

Parsons, F. W., Asst. Engr., City Hall, Los Angeles, Calif.

Patterson, R. L., City Engineer, City Hall, Newport Beach, Calif.

Payton, Lyle, City Hall, Stockton, Calif.

Peterson, J. H., Staff Mgr. Transite Pipe Dept., Johns Manville Co., 116 New Montgomery St., San Francisco, Calif.

Phelps, B. D., Asst. City Engr., Rm. 266, Civic Center, San Diego, Calif.

Phelps, Tracy I., Asst. Eng., San. & Storm Drain Div. Office of Los Angeles Co. Engr., 716 Union League Bldg., 2nd & Hill Sts., Los Angeles, Calif.

Pickett, Arthur G., Deputy County Engr., 700 Union League Bldg., Los Angeles, Calif.

Pierce, C. L., 1628 Wayne St., South Pasadena, Calif.

Pleasanton, Town of, Town Hall, Pleasanton, Calif.

Pomeroy, Richard, Chemist, Box 353, Harbor City, Calif.

Popp, W. L., City Engineer, City Hall, San Jose, Calif.

Porter, H., Asst. City Engr., City Hall, San Mateo, Calif.

Post, Fred W., Sewage Plant Mgr., R. 3, Box 433, Lodi, Calif.

Primmer, B. J., Dist. Mgr., American Conc. & Steel Pipe Co., P. O. Box 13 Main Station, San Diego, Calif.

Ramseier, Roy E., 2813 Parker St., Berkeley, Calif.

Ranagan, Fred E., 823 W. 5th St., Pardee Engineering Co., Los Angeles, Calif.

Rantsma, W. F., City Hall, Fresno, Calif.

Rawn, A. M., Los Angeles County San. Dists., 110 S. Broadway, 4th Floor, Los Angeles, Calif.

Reinke, Edward A., State Dept. of Public Health, 3093 Life Sciences Bldg., Berkeley, Calif.

Reinoehl, Don, Associate Engineer, 131 University Ave., Palo Alto, Calif.

Reynolds, Leon B., Prof., Civil Engineering Dept., Stanford Univ., Palo Alto, Calif.

Ribal, Raymond Robt., 701 City Hall, Oakland, Calif.

Roberts, W. C., Dir. Pacific Engr. Lab., 604 Atlas Bldg., San Francisco, Calif.

Robinson, Willis S., 152 E. Louise St., Long Beach, Calif.

Robles, George G., Opr., 604 N. Church St., Lodi, Calif.

Rowntree, Bernard, Asst. Secy., Carmel Sanitary District, P. O. Box 83, Carmel, Calif.

Ruth, Leo W., Jr., Asst. Engr. Cook Research Labs., Menlo Park, Calif.

Sanchis, Jos. M., San. Eng., c/o American Consulate, Caracas, Venezuela, S. A.

Sauer, Victor W., 701 City Hall, Oakland, Calif.

Schapp, A., Attorney, 501 Hobart Bldg., San Francisco, Calif.

Segel, A., Civil Engineer, 817 Mattei Bldg., Fresno, Calif.

Senseman, Wm. B., Pacific Coast Mgr., Combustion Engineering Co., 406 S. Main St., Los Angeles, Calif.
Shaw, Paul R., c/o Fish & Game Commission, Ferry Bldg., San Francisco, Calif.
Shearer, A. B., San. Dist. No. 1 Marin, 11 Library Place, San Anselmo, Calif.
Shelton, M. J., City Eng., City of El Centro, El Centro, Calif.
Shook, H. E., Great Western Electro Chemical Co., 9 Main St., San Francisco, Calif.
Silberbauer, Walter R., Inspector, Campbell San. Dist., Box 614, Campbell, Calif.
Singer, Lewis P., Jr., P. O. Box 554, Asst. Eng., City Engr.'s Office, Lodi, Calif.
Skinner, John F., 1610 Idlewood Rd., Glendale, Calif.
Skinner, W., Supt. Water & Sewer Dept., City Hall, Box 22, Escondido, Calif.
Smith, Alva J., Cons. Eng., 810 Boylston St., Pasadena, Calif.
Smith, Chester A., Burns & McDonnell, Cons. Engrs., 107 W. Linwood Ave., Kansas City, Mo.
Smith, Frank E., Operator Santa Ana, 1100 E. Broadway, Anaheim, Calif.
Smith, H. O., Eng. of Sewer Design, City of Los Angeles, 745 City Hall, Los Angeles, Calif.
Smith, J. F., Great Western Electro-Chemical Co., 9 Main St., San Francisco, Calif.
Soroker, Sam, Dist. Sewer Foreman, 4900 Meridian St., Los Angeles, Calif.
Sotter, R. R., Chief Opr. Engineer, 4545 Lincoln Way, Richmond Sunset Sewage Tr. Plant, San Francisco, Calif.
Souther, Fred L., Box 2270, San Diego, Calif.
Stevenson, Ralph A., 641 Gibbons St., Los Angeles, Calif.
Stewart, Morgan E., Contra Costa Co., Health Dept., Room 125, Hall of Records, Martinez, Calif.
Stites, H. L., City Engr., 272 N. Olive Ave., Burbank, Calif.
Strangard, Edward L., Opr., Disposal Plant c/o Public Works, U. S. Naval Air Station, Alameda, Calif.
Strayer, Elmer C., Civ. Eng., 204 S. Olive Ave., Alhambra, Calif.
Stuart, Archer B., City Eng., P. O. Box 21, Healdsburg, Calif.
Studley, E. G., 705 City Hall, Los Angeles, Calif.
Swanson, S. C., Utility Man, P. O. Box 506, Manteca, Calif.
Taggart, J. M., Opr., 533 W. Wilshire, Fullerton, Calif.
Talbot, Frank D., Cons. Engineer, 804 Forum Bldg., Sacramento, Calif.
Tegtmeyer, L. G., Asst. Eng., 368 City Hall, San Francisco, Calif.
Tennant, Carl F., 142 W. Artesia Blvd., Long Beach, Calif.
Thatcher, Lynn M., State San. Eng., 126 State Capitol, Salt Lake City, Utah.
Thews, Vernon W., 2300 Pacific, San Pedro, Calif.
Tillotson, John, Operator Tracy, 4 E. 3rd St., Tracy, Calif.
Toman, R. S., Local Mgr. "Chemco," 911 Harrison St., San Francisco, Calif.
Towers, Charles, Warden, Pollution Detail State Div. of Fish & Game, State Bldg., Los Angeles, Calif.
Tsuji, Totaro, Chem. Division, Industrial Wastes Research, 933 Shojii, Kishibe Mura, Mishimagun, Osakafu, Japan.
Ullrich, C. J., Cons. Eng., 422 Ness Bldg., Salt Lake City, Utah.
Unger, Carl, Sewage Works Opr., 522 Oak St., Petaluma, Calif.
University of California Library, Division of Serials and Exchange, Berkeley, Calif.
University of Southern California Library, University Park, Los Angeles, Calif.
Updegraff, W. R., Western City Magazine, 458 S. Spring St., Los Angeles, Calif.
Van Norman, James H., 330 Loma Vista St., El Segundo, Calif.
Vapor Recovery Systems, Att. Promotional Dept., Drawer 231, Compton, Calif.
Vaughan, E. A., K. of P. Bldg., Lompoc, Calif.
Villaruz, Primo, Ass. San. Engr., 374 W. Santa Clara, San Jose, Calif.
Waggoner, E. R., 306 West Ave., 26, Los Angeles, Calif.
Walker, Walter J., Opr., Sewage Treatment Plant, 409 Railroad Ave., Decoto, Calif.
Walters, Grover L., 123 W. Wilshire Ave., Fullerton, Calif.
Warren, A. K., 110 S. Broadway (4th Fl.), Los Angeles, Calif. (Deceased.)
Watkins, H. H., Eng. and Secy., Cleaves Bldg., High St., Auckland Suburban Drainage Bd., Auckland, New Zealand.
Webb, L. C., City of Gridley, Gridley, Calif.
Weed, Sam A., Draftsman, Rm. 701 City Hall, Oakland, Calif.
West, Ezra, 308 N. 10th, Colton, Calif.
White, Geo C., Dist. Eng., Wallace & Tiernan, 171 2nd St., San Francisco, Calif.
White, R. E., Cons. Eng., 2617 20th St., Bakersfield, Calif.

White, W. W., State San. Eng., 25 Fordonia Bldg., Reno, Nev.
Wilder, A. D., Director, Dept. Public Wks., Rm. 360 City Hall, San Francisco, Calif.
Wintersgill, A. T., Box 145, Station A, Los Angeles, Calif.
Wirt, J. B., Operator, San Leandro, 735 Juana Ave., San Leandro, Calif.
Woodward, R. D., Chief Opr. & Mechanic, 463 Myrtle St., Laguna Beach, Calif.
Zuckweiler, G. C., 739 4th St., San Diego, Calif.

Central State Sewage Works Association

E. J. Beatty, *Secretary-Treasurer*, State Board of Health, Madison, Wisc.

Abplanalp, C. C., Wallace & Tiernan Co., 809 W. Washington Blvd., Chicago, Ill.
Adams, Chas. L., 202 Elks Bldg., Joliet, Ill.
Algonquin, Village of, McHenry County, Algonquin, Ill.
Allen, William G., 5315 N. Laramie Ave., Chicago, Ill.
Anderson, Geo. H., Annex Bldg., Herrin, Ill.
Anderson, Herbert A., Asst. State San. Eng., Wisconsin State Board of Health, City Hall, Rhinelander, Wisc.
Anderson, Newell, Moose Lake, Minn.
Anderson, Norval E., Civil Engineer, San. Dist. of Chicago, 618 Catherine Ave., La Grange, Ill.
Arbogast, Joseph, Naperville, Ill.
Arford, Wm., 2310 Roosevelt Ave., New Castle, Ind.
Arner, Charles, 247 E. 150th St., Harvey, Ill.
Ashby, Paul, R. R. 3, Muncie, Ind.
Ashdown, W. L., Supt. Sewage Treatment Plant, Bloom Township San. Dist. Chicago Heights, Ill.
Ashley, Clifford A., 506 N. West St., Wheaton, Ill.
Austin, R. J., 11316 Avenue L, Chicago, Ill.
Babbitt, H. E., San. Engineer, 204 Engineering Hall, University of Illinois, Urbana, Ill.
Backmeyer, David, Liberty Ave., Richmond, Ind.
Baetz, C. C., Box 51, Appleton, Wisc.
Baillie, E. P., 2700 Regent St., Madison, Wisc.
Baker, C. M., 2 S. Carroll St., Madison, Wisc.
Barnes, L. T., Supt., Wheaton San. Dist., 825 Irving Ave., Wheaton, Ill.
Barnett, G. R., 519 Comm. Bank Bldg., Peoria, Ill.
Barnhill, John T., c/o State Dept. of Public Health, Div. San. Engineering, Springfield, Ill.
Barth, John R., Room 108, Decatur Club Bldg., Decatur, Ill.
Bass, Frederic, Civ. Eng., University of Minnesota, Minneapolis, Minn.
Batchelor, W., 240 W. 43rd St., Indianapolis, Ind.
Baxter, Richard M., 51 Fox St., Aurora, Ill.
Baylis, John R., 1643 E. 86th St., Chicago, Ill.
Beatty, E. J., State Board of Health, Madison, Wisc.
Beaudoin, Robert E., 3424 Arden Ave., Hollywood, Ill.
Beck, A. J., 215 Southcote Rd., Riverside, Ill.
Bender, Dwight O., 932 N. Hawthorne Lane, Indianapolis, Ind.
Benson, R. W., 4604 2nd Ave., S., Minneapolis, Minn.
Berke, J. H., 740 N. Plankinton Ave., Milwaukee, Wisc.
Bernauer, George, Asst. San. Eng., District Health Office, Rm. 378, State Office Bldg., Madison, Wisc.
Berry, George A., R. 2, Box 440, Indianapolis, Ind.
Besozzi, Leo, 314 Hammond Bldg., Hammond, Ind.
Birdsall, L. I., General Chemical Co., 105 W. Madison St., Chicago, Ill.
Birkeness, O. T., Section 7, 809 W. Washington Blvd., Chicago, Ill.
Bjelajac, Vaso, 811 S. 1st St., Milwaukee, Wisc.
Black, Hayse H., Asst. San. Eng., State Dept. of Public Health, Springfield, Ill.
Black & Veatch, 4706 Broadway Bldg., Kansas City, Mo.
Bloodgood, Donald E., R. F. D. 3, Box 976 H., Indianapolis, Ind.
Boeke, Harley C., Sewage Treatment Plant, S. Main St., Racine, Wisc.
Bogema, Marvin, 132 Blair St., Ithaca, N. Y.
Boley, Arthur L., Asst. City Eng., City Hall, Sheboygan, Wisc.
Borchelt, T. C., Box 52, Tremont, Ill.
Bragg, Robert E., 5859 N. New Jersey St., Indianapolis, Ind.
Bragstad, R. E., City Hall, Sioux Falls, S. Dak.
Brensley, A. A., Supt. of Sewers, City Hall, Kankakee, Ill.
Brody, James, 417 Melrose Ave., Glen Ellyn, Ill.

Brook, Harry, Osgood, Ind.
Brower, James, 3021 N. 36th St., Milwaukee, Wisc.
Brown, George L., City Hall, Austin, Minn.
Browne, Floyd J., San. Eng., Marion Bldg., Marion, Ohio.
Bruden, C. O., 21 E. Gorham St., Madison, Wisc.
Brunner, Paul L., 1229 Swinney Ave., Fort Wayne, Ind.
Buchholz, Richard, Nekoosa, Wisc.
Bunger, Fred C., Dept. of Sanitation, Bloomington, Ind.
Burgeson, J. H., Opr., Sewage Treatment Plant, 301 Anderson Blvd., Geneva, Ill.
Burlingame, Hitchcock & Estabrook, Att.: Mr. Jos. B. Estabrook, 521 Sexton Bldg., Minneapolis, Minn.
Burrin, Thomas J., Sewage Treatment Plant, R. R. 1, Kokomo, Ind.
Bushee, Ralph J., 1502 Michigan Ave., La Porte, Ind.
Caccia, Pio, 528 S. Halsted St., Chicago, Ill.
Caldwell, David H., 113 Talbot Lab., University of Illinois, Urbana, Ill.
Caldwell, H. J., 803 W. College Ave., Jacksonville, Ill.
Callen, Loy A., 5245 W. Hirsch St., Chicago, Ill.
Calvert, C. K., 951 W. 20th St., Indianapolis, Ind.
Carey, Wm. N., 420 Guardian Bldg., St. Paul, Minn.
Carpenter, Carl B., 5618 Calumet Ave., Hammond, Ind.
City of Casey, Casey, Ill.
Caster, Arthur, c/o C. H. Hurd, Cons. Eng., 1039 Architect & Bldrs. Bldg., 333 N. Penn St., Indianapolis, Ind.
Chamberlain, L. H., 836 S. Michigan Ave., Chicago, Ill.
Cheadle, Wilford G., 4224 42nd Ave., S., Minneapolis, Minn.
Clark, E. S., Bacteriologist, Div. of San. Engineering, State Dept. of Public Health, Springfield, Ill.
Clodfelter, Howard T., Calumet Sewage Treatment Wks., 126th St. & Cottage Grove Ave., Chicago, Ill.
Cole, Chas. W., 220 W. La Salle Ave., South Bend, Ind.
Combs, H. F., 435 E. 88th Place, Chicago, Ill.
Consoer, Arthur W., Consoer, Townsend & Quinlan, 205 W. Wacker Drive, Chicago, Ill.
Cornilsen, C. K., Works Opr., Bloom Township, San. Dist., P. O. Box 1, Chicago Heights, Ill.
Corr, Ray H., Supt. of Sewers, Woodstock, Ill.
Corrington, C. E., Supt. Clinton San. Dist., Clinton, Ili.
Corrington, Kingsley, Chemist, 310 W. Mulberry St., Normal, Ill.
Cotton, Harry E., Armco Culvert Mfgs. Assn., Middletown, Ohio.
Cowing, Roy T., 821 Lake St., Oak Park, Ill.
Craig, Clifford, 310 Humiston St., Pontiac, Ill.
Crask, Rex, Greencastle Sewage Treatment Plant, Greencastle, Ind.
Cropsey, W. H., City Engineer, S. St. Paul, Minn.
Dallavia, Louis, Div. Public Works, City Hall, Duluth, Minn.
Darling, Orin M., Cons. Civil Eng., 2615 West Drive, Fort Wayne, Ind.
Davidson, Philip, c/o A. J. Jenny, 4136 W. Palmer, Chicago, Ill.
Dawson, F. M., Dean of College of Engineering, State Univ. of Iowa, Iowa City, Iowa.
DeBerard, W. W., Mgr., 520 N. Michigan Ave., Chicago, Ill.
DeBrun, John W., Jr., Resident Eng., Taylorville, Ill.
Decker, Walter G. Supt. of Public Works, Lawrenceburg, Ind.
Deckert, Christ, Sewage Treatment Works, Delavan, Wisc.
DeLeuw, C. E., 20 N. Wacker Drive, Chicago, Ill.
DePoy, A. G., 117 6th Ave., S., South St. Paul, Minn.
Deuchler, Walter E., 63 S. LaSalle St., Aurora, Ill.
Diamond Alkali Co., Att.: Clayton Hoyt, 2427 Oliver Bldg., Pittsburgh, 22, Pa.
Dick, Robert, 267 Columbia Ave., Elmhurst, Ill.
Dietrich, Paul, Eagle St., Crystal Lake, Ill.
Dietz, John, Plant Opr., Mundelein, Ill.
Division Sanitary Engineering, Dept. Public Health, State House, Springfield, Ill.
Domogalla, Bernhard, Dr., City Board of Health, 110 N. Hamilton St., Madison, Wisc.
Donohue, Jerry, P. O. Box 489, Sheboygan, Wisc.
Doubleday, Arnold R., 6815 Merrill Ave., Chicago, Ill.
Downer, Wm. J., Dept. of Public Health, Springfield, Ill.
Drake, James A., R.F.D. 4, Austin, Minn.
Dudley, Charles E., Opr. Sewage Works, Flora, Ill.

Dundas, Wm. A., Chicago San. Dist., 910 S. Michigan Ave., Chicago, Ill.
Duvall, Arndt J., 1509 Pioneer Bldg., St. Paul, Minn.
Duy, C., 625 Lebanon St., Aurora, Ill.
Ebaugh, G. M., 447 Standard Office Bldg., Decatur, Ill.
Eliasson, Rolf, Assoc. Prof. of San. Eng., N. Y. University, University Heights, N. Y.
Ellis, Albert, Indiana State Farm, Green Castle, Ind.
Epler, J. E., Danville San. Dist., Danville, Ill.
Erickson, Carl V., 320 Fourth St., LaSalle, Ill.
Erzen, C. A., 508 South Goodwin Apt, 5, Urbana, Ill.
Evans, R. W., Versailles, Ind.
Everson Mfg. Co., 214 W. Huron St., Chicago, Ill.
Farnsworth, George L., Jr., 230 Christie St., Ottawa, Ill.
Feltz, Fred C., Supt., Sewage Treatment Plant, Box 261, West McHenry, Ill.
Ferebee, James L., Box 1167, Milwaukee, Wisc.
Finch, Lewis S., 276 Century Bldg., Indianapolis, Ind.
Fisher, Homer G., 140 W. Webster, Benton, Ill.
Flickinger, Lloyd H., Diablo Heights, Canal Zone.
Ford, Robert, Engr., Centerville, Ind.
Forsberg, Ole, c/o Oliver Iron Mining Co., Hibbing, Minn.
Frazier, R. W., City Hall—Sewerage Commission, Oshkosh, Wisc.
Fredson, Anthony, Opr., Grays Lake, Ill.
Freeland, B. H., Supt. of Utilities, Bluffton, Ind.
Fulmer, Frank E., c/o Greeley & Hansen, Tullahoma, Tenn.
Fulton, E. A., 3 S. Meramec Ave., St. Louis, Mo.
Gail, A. L., North Shore San. Dist., 1015 St. Johns Ave., Highland Park, Ill.
Garrison, Peter L., 1246 N. Elm St., Muncie, Ind.
Gartner, W. H., R. 7, Fort Wayne, Ind.
Gerard, F. A., Asst. Civil Eng., Chicago San. Dist., 242 Columbia Ave., Park Ridge, Ill.
Geupel, Louis A., City Civil Eng. & Dir. of Public Works, 531 Rockerwood Ave., Evansville, Ind.
Giesey, J. K., Civil & San. Engr., 2121 Glenwood Ave., Toledo, Ohio.
Gifford, J. B., Chemist, Sewage Disposal Plant, 312 W. 8th St., Michigan City, Ind.
Ginsberg, S. D., 4731 Ingleside Ave., Chicago, Ill.
Gneagy, Harold, 1709 Cypress St., Highland, Ill.
Golly, M. R., Dist. Health Office, Xenia, Ill.
Goodman, Arnold H., 363 Downing Rd., Riverside, Ill.
Gottschalk, Harry, 617 S. Clinton, Fort Wayne, Ind.
Grabbe Construction Co., H. A., 500 Belle St., Alton, Ill.
Greek, Edward B., Opr., 26 E. Fourth St., Hinsdale, Ill.
Greeley, Samuel A., 6 N. Michigan Ave., Chicago, Ill.
Griffin, Ralph J., Box 391, Rantoul, Ill.
Gross, Carl D., Eng., State Dept. of Health, Springfield, Ill.
Grosshans, Edward W., 508 Lake St., Baraboo, Wisc.
Hageman, Roy C., 39th St. & 52nd Ave., Southwest Sewage Treatment Works, Cicero P. O., Chicago, Ill.
Hager, Fred, Opr., 426 June Terrace, Barrington, Ill.
Hagestad, Herman T., Cons. Eng., River Falls, Wisc.
Hahn, Howard, Sewage Plant, Dixon State Hospital, Dixon, Ill.
Hallden, John T., Vienna, Ill.
Hammond, F. D., Plant Supt., 433 N. Main St., Canton, Ill.
Haney, Joseph E., First Trust Bldg., Hammond, Ind.
Hanke, Carl C., 10061 S. Wood St., Chicago, Ill.
Hansen, Paul, 6 N. Michigan Ave., Chicago, Ill.
Hardman, Thomas T., 211 S. Center St., Terre Haute, Ind.
Harmeson, D. K., San. Engr. Div. of San. Engineeirng, Dept. of Public Health, Springfield, Ill.
Harmon, Jacob A., Cons. Engr., 945 Jefferson Bldg., Peoria, Ill.
Harper, Charles E., City Light & Water Plant, N. 5th St., Goshen, Ind.
Harris, George C., Sewage Treatment Works, Arlington Heights, Ill.
Hartman, B. J., Engr., P. O. Box 489, Sheboygan, Wisc.
Hartman, Byron K., 300 W. Pershing Rd., Chicago, Ill.
Hartung, N. E., 627 Seminary St., Richland Center, Wisc.
Hasfurther, Wm. A., 1813 Noble Ave., Springfield, Ill.

Haste, J. R., Asst. Plant Opr., 521 Green St., Rockford, Ill.
Hatfield, W. D., Decatur San. Dist., Decatur, Ill.
Hathaway, A. S., 1930 Sherman Ave., Evanston, Ill.
Heger, Harold, 646 N. Jefferson Ave., Indianapolis, Ind.
Heider, Robert N., 1098 W. Michigan Ave., Indianapolis, Ind.
Hein, Walter E., St. Charles, Ill.
Heiple, Loren R., San. Engr., 224 W. N. St., Hinsdale, Ill.
Heisig, Henry M., Sewerage Comm., Box 2079, Milwaukee, Wisc.
Hendrix, George K., Div. San. Engr., State Health Dept., Springfield, Ill.
Heneghan, George P., 1925 S. 54th Ave., Cicero, Ill.
Henn, Donald E., De Kalb Sanitary Dist., 922 Grove St., De Kalb, Ill.
Hermann, Frank, 3209 39th Ave., South, Minneapolis, Minn.
Herrick, T. L., 717 N. Washington St., Park Ridge, Ill.
Hersiz, S. B., Renville, Minn.
Hetherington, W. G., Opr., Sewage Works, 211 W. Second St., Sparta, Ill.
Heydon, F. G., 660 W. 8th Ave., Gary, Ind.
Hicks, Geo. W., Chicago Pump Co., 2336 Wolfram St., Chicago, Ill.
Hill, K. V., Greeley & Hansen, 6 N. Michigan Ave., Chicago, Ill.
Hodgin, S. W., City Civil Engineer, City Bldg., Richmond, Ind.
Hoganson, Lester O., 485 Frederick St., Burlington, Wisc.
Holderly, J. M., Neenah Menasha Sewerage Comm., Menasha, Wisc.
Holderman, John S., 434 S. 4th St., Kankakee, Ill.
Honens, R. W., 503 5th Ave., Sterling, Ill.
Hoth, Fred, Bartlett, Ill.
Howson, L. R., Alvord, Burdick & Howson, Suite 1401, 20 N. Wacker Dr., Chicago, Ill.
Hromada, Frank M., U. S. Southwestern Reformatory, El Reno, Okla.
Hudson, La Verne D., State Health Dept., Div. of San. Engr., Springfield, Ill.
Hull, S. P., c/o Culligan Zeolite Co., Northbrook, Ill.
Hunt, L. W., Supt. Galesburg Sanitary Dist., Galesburg, Ill.
Hunter, Harry, 202 Center St., West Chicago, Ill.
Hupp, John E., Jr., 720 Weller Ave., La Porte, Ind.
Hurd, Charles H., 333 N. Pennsylvania St., Indianapolis, Ind.
Hurd, Edwin C., San. Engr., 5821 Washington Blvd., Indianapolis, Ind.
Hursting, R. C., 115 S. 5th St., Richmond, Ind.
Hurwitz, Emanuel, 5017 Mozart St., Chicago, Ill.
Hutchins, Will A., Freeport, Ill.
Indiana State Board of Health, Bureau of San. Engineering, 1098 W. Michigan Ave., Indianapolis, Ind., Att.: B. A. Poole, Chief Eng.
International Filter Co., 325 W. 25th Place, Chicago, Ill.
Jackson, James A., 1098 W. Michigan St., Indianapolis, Ind.
Jeup, Bernard H., 2415 N. Talbott, Indianapolis, Ind.
Johnson, Arthur N., 513 24th St., Moline, Ill.
Johnson, Floyd E., 471 Barrett St., Elgin, Ill.
Johnson, L. J., 1327 Sheridan Rd., c/o Limestone Products Co., Menominee, Mich.
Johnson, Lloyd M., 910 S. Michigan Ave., Chicago, Ill.
Johnson, R. J., 731 Linn St., Peoria, Ill.
Johnson, W. T., Columbia Alkali Corp., 220 Tribune Tower, Chicago, Ill.
Jonas, Milton R., 5496 Cornell Ave., Chicago, Ill.
Jones, Howard H., Chief Opr., Sewage Treatment Works, 122 N. Calumet Ave., Michigan City, Ind.
Kafka, John, Sewage Treatment Plant, Clintonville, Wisc.
Kalste, Arthur, Opr., Sewage Treatment Plant, Cedar Grove, Wisc.
Kane, James I., Opr., Calumet Sewage Treatment Wks., 2122 W. 35th St., Chicago, Ill.
Kasser, Victor H., 202 E. Chicago St., Elgin, Ill.
Kewer, J. F., P. O. Box 152, Waukesha, Wisc.
King, Henry R., The Flamingo Hotel, 5520 S. Shore Drive, Chicago, Ill.
King, Richard, 133 Prospect St., Willimantic, Conn.
Kingsbury, Harold N., Dist. Health Office, Vaughn Library Bldg., Ashland, Wisc.
Kingston, Paul, Public Health Engineer, Minn. Dept. of Health, City Hall, Rochester, Minn.
Kinney, E. F., Route 13, Box 43-B, Indianapolis, Ind.
Kinsey, L. B., Civil Eng., Pekin, Ill.
Kirchoffer, W. G., Vroman Block, Madison, Wisc.
Kirkpatrick, John W., 1098 W. Michigan St., Indianapolis, Ind.
Klassen, C. W., Chief San. Eng., State Dept. of Public Health, Springfield, Ill.

Kleiser, Paul J., Asst. San. Engr., 925 E. Donald St., South Bend, Ind.
Knechtges, O., 1110 Vilas Ave., Madison, Wisc.
Koch, Phillip L., 947 E. Johnson St., Madison, Wisc.
Koetz, Lester, 2505 Elisha Ave., Zion, Ill.
Korfmacher, John A., Apt. 508, 100 Academy Ave., Pittsburgh, Pa.
Kramer, Harry P., 4017 W. End Ave., Chicago, Ill.
Kraus, L. S., Chemist, 510 Albany, Peoria, Ill.
Kuhl, F. A., Opr., Sewage Treatment Works, Breese, Ill.
Kuhner, Frank G., N. Elm & 13th St., Muncie, Ind.
Kulin, Harvey J., 118 Conradt Ave., P. O. Box 299, Kokomo, Ind.
Kulisch, Harry, 2918 N. Menard Ave., Chicago, Ill.
Lakeside Engineering Corp., 222 W. Adams St., Chicago, Ill.
Lamb, Miles, Supt., 227 W. Marshall St., Belvidere, Ill.
Lang, Lloyd, 420 Main St., Kimberly, Wisc.
Langwell, Louie, 305 W. Market St., Salem, Ind.
Larsen, Stanley J., c/o Minneapolis-St. Paul San. Dist., P. O. Box 3598, St. Paul, Minn.
Larson, C. C., Springfield San. Dist., Springfield, Ill.
Larson, Keith D., South St. Paul Sewage Treatment Plant, South St. Paul, Minn.
Larson, L. L., 1715 Crescent Ave., Fort Wayne, Ind.
Lea, Wm. L., State Laboratory of Hygiene, Madison, Wisc.
Lee, Oliver, 102 N. 4th St., Mt. Horeb, Wisc.
Lehmker, William, 2616 182nd St., Lansing, Ill.
Leland, Ben J., San. Engr., 737 S. Wolcott St., Chicago, Ill.
Leland, Raymond I., San. Engr., Manteno State Hospital, Manteno, Ill.
Lentfoehr, Charles E., Plant Opr., 322 N. Main St., Mayville, Wisc.
Leonard, O. M., c/o Oliver Leininger, Akron, Ind.
Lessig, D. H., Warsaw, Ind.
Lewis, R. K., 5009 Park Ave., Indianapolis, Ind.
Lind, A. Carlton, Chain Belt Co., 1600 W. Bruce St., Milwaukee, Wisc.
Lind, Gunner W., 4245 Snelling Ave., Minneapolis, Minn.
Link Belt Company, 300 W. Pershing Rd., Chicago, Ill.
Linsley, Scott E., 1557 Holton Ave., St. Paul, Minn.
Long, H. Maynard, Hillsboro, Ill.
Lord, Herbert O., 308 Tenney Bldg., Madison, Wisc.
Louis, Leo, 1098 W. Michigan Ave., Indianapolis, Ind.
Lueck, Bernard F., 621 Maple St., Neenah, Wisc.
Lustig, Joseph, City Engr., Janesville, Wisc.
McAnlis, Chauncey R., City Engr., Dept. of Public Works, Ft. Wayne, Ind.
McCarty, J. J., City Hall, Racine, Wisc.
McClenahan, W. J., 910 S. Michigan Ave., Chicago, Ill.
McClure, Ernest, Galva, Ill.
McCoy, M. H., 1541 Chicago Rd., Chicago Heights, Ill.
McIlvaine, Wm. D., Jr., Electrical Engr., Minn.-St. Paul San. Dist., Box 3598 Childs Rd., St. Paul, Minn.
McIntyre, John C., San. Engr., Sewage Treatment Plant, Cedar Rapids, Iowa.
McKee, Frank J., 1110 Harrison St., Madison, Wisc.
MacDonald, J. C., Opr., Sewage Plant, Brazil, Ind.
Mackin, John C., Nine Springs Sewage Treatment Wks., Madison, Wis.
Madison, James W., Plainfield, Ill.
Martens, L. P., 715 Central Ave., Wilmette, Ill.
Martin, George C., 314 N. Oneida St., Green Bay, Wisc.
Martin, Sylvan C., Div. of San. Engineering, State Dept. of Public Health, Springfield, Ill.
Mason, Clarence A., City Hall, Hammond, Ind.
Mathews, L. R., Three Rivers Filtration Plant, Ft. Wayne, Ind.
Mathews, W. W., 220 W. 44th Ave., Gary, Ind.
Mattheis, Clarence, 209 Spring St., Anna, Ill.
Mattson, Walfrid, I., 3220 2nd Ave. W., Hibbing, Minn.
Mauer, Peter J., 303 S. 3rd Ave., S. St. Paul, Minn.
Meadors, L. B., 228 S. 17th St., New Castle, Ind.
Merz, H. Spencer, 3227 W. Gate Parkway, Rockford, Ill.
Merwin, Willard, 714 E. Third Ave., Monmouth, Ill.
Metz, Roy L., Supt., Sewage Treatment Works, Carthage, Ill.

Mick, K. L., Chief Chemist, Minn.-St. Paul. San. Dist., P. O. Box 3598, St. Paul, Minn.
Mickle, Chas. T., 804 N. 7th Ave., La Grange, Ill.
Milinowski, Arthur S., 1411 Pioneer Blvd., St. Paul, Minn.
Miller, David R., 1318 W. Sycamore, Kokomo, Ind.
Miller, E. P., 1070 Elmore St., Green Bay, Wisc.
Miller, L. A., 712 E. Main St., Streator, Ill.
Milling, Martin A., 3931 Lomond Ave., Indianapolis, Ind.
Minneapolis-St. Paul San. Dist., Box 3598, St. Paul, Minn.
Mohlman, F. W., Dr., 910 S. Michigan Ave., Chicago, Ill.
Moore, Herbert, 904 S. Layton Blvd., Milwaukee, Wisc.
Moore, R. B., 930 K of P Bldg., Indianapolis, Ind.
Morgan, Philip F., 356 N. York St., Elmhurst, Ill.
Morkert, Kenneth, 54 S. Williams St., Frankfort, Ind.
Muegge, O. J., Asst. San Engr., State Board of Health, Madison, Wisc.
Mulvaney, M. B., 128½ Lincoln St., Marseilles, Ill.
Murphy, John A., 117 W. Blair St., West Chicago, Ill.
Myers, Harry L., 9541 S. Oakley Ave., Chicago, Ill.
Nadin, Joe W., 402 E. Court St., Paris, Ill.
Nash, D. A., 1028 N. Leamington Ave., Chicago, Ill.
National Aluminate Corp., 6216 W. 66th Place, Chicago, Ill.
Neiman, W. T., Cons. Engr., Freeport, Ill., 10 W. Douglas St.
Nelle, Richard S., State Dept. of Public Health, Springfield, Ill.
Nelson, C. L., Henney Bldg., Freeport, Ill.
Nelson, George I., 1626 Highland Ave., Chicago, Ill.
Newlund, Walter W., 913 Mary St., Pekin, Ill.
Nicholas, Forrest A., 7236 McCook Ave., Hammond, Ind.
Nichols, M. Starr, Chemist, Wisc. State Laboratory of Hygiene, Madison, Wisc.
Niemi, Arthur G., 220 W. Howard St., Hibbing, Minn.
Nordell, Carl H., Advance Engineering Corp., Board of Trade Bldg., Chicago, Ill.
Obma, Chester A., State Board of Health—Dist. No. 3, Fond du Lac, Wisc.
Ockershausen, R. W., General Chemical Co., 105 W. Madison St., Chicago, Ill.
Oeffler, W. A., Supt., Treatment Plant, Jasonville, Ind.
Okun, Daniel A., Public Health Service, 1309 Engineering Bldg., Cincinnati, Ohio.
Olson, Frank W., 16 S. Mallory St., Batavia, Ill.
O'Mara, Richard, Mech. Eng., c/o Western Precipitation Corp., 1016 W. 9th St., Los Angeles, Calif.
Orwicz, Bernard, 2939 W. Division St., Chicago, Ill.
Pacific Flush Tank Co., 4241 Ravenswood Ave., Chicago, Ill.
Page, R. W., 986 N. Court St., Rockford, Ill.
Palmer, John R., 1321 Monroe St., Evanston, Ill.
Palmer, Ralph M., 1818 Melrose Ave., Duluth, Minn.
Patterson, Orville W., 308 N. Clay St., Edinburg, Ind.
Pearse, Langdon, Chicago San. Dist., 910 S. Michigan Ave., Chicago, Ill.
Peck, E. M., Brinchman Bldg., Michigan City, Ind.
Pecker, Joseph S., 1011 Chestnut St., Philadelphia, Pa.
Peirce, W. A., Racine Water Dept., City Hall, Racine, Wisc.
Pekin, City of, Att.: Wm. Maurer, Sewage Wks. Operator, Pekin, Ill.
Peller, Leo R., 824 S. 17th Ave., Maywood, Ill.
Peterson, Ivan C., 130 N. Wells St., Chicago, Ill.
Peterson, Myhern C., Dist. Public Health Engineer, Box 308, Bemidji, Minn.
Peterson, R. W., 126th St. & Cottage Grove Ave., Chicago, Ill.
Pfeiler, L. F., 6210 Kimbark Ave., Jackson Park Sta., Chicago, Ill.
Pierce, George O., Asst. Prof. of Public Health Engr., University of Minnesota, Room 112, Millard Hall, Minneapolis, Minn.
Plummer, Raymond Benton, 1743 N. Adams St., South Bend, Ind.
Poindexter, G. G., 1179 S. Harvey Ave., Oak Park, Ill.
Poole, B. A., Eng., 333 W. Hampton Drive, Indianapolis, Ind.
Powell, J. C., Opr., Sewage Treatment Works, Princeton, Ill.
Price, R. C., 14 Rokeby Ave., Garrett Park, Md.
Prough, Fred K., 421 E. Ohio St., Bluffton, Ind.
Racek, L., Jr., Sauk City, Wisc.

Raiter, Clifford R., Minn.-St. Paul San. Dist., Box 3598, St. Paul, Minn.
Ralston, Geo. E., 1207 W. Pleasant St., Freeport, Ill.
Randolph, Verdun, San. Engr., 36½ S. Locust St., Pana, Ill.
Rankin, R. S., Engr., The Dorr Company, 221 N. LaSalle St., Chicago, Ill.
Ray, Frederick, 1124 Victory Court, Anderson, Ind.
Read, Homer V., General Delivery, Olney, Ill.
Ream, Edward F., Jr., 4241 N. Ravenswood Ave., Chicago, Ill.
Reardon, Wm. R., 1036 N. 17th St., Manitowoc, Wisc.
Red Wing Sewer Pipe Corp., Red Wing, Minn.
Reed, Paul W., 1098 W. Michigan, Indianapolis, Ind.
Rees, N. B., 415 Willard Ave., Bloomington, Ill.
Regan, T. H., 510 Sheridan St., Rockford, Ill.
Rein, L. E., Pacific Flush Tank Co., 4241 E. Ravenswood Ave., Chicago, Ill.
Reybold, D. C., Eng., The Dorr Company, 221 N. LaSalle St., Chicago, Ill.
Richards, P. W., 4720 Guilford, Indianapolis, Ind.
Richgruber, Martin, 521 Walroth St., Sparta, Wisc.
Richmen, W. F., 111 E. Sanborn St., Winona, Minn.
Richter, Paul O., 111 W. Washington St., Rm. 548, Chicago, Ill.
Riedesel, Henry A., Spring Creek Rd., Rockford, Ill.
Roab, F. H., Mgr., Water & Light Dept., Columbus, Wisc.
Robins, Maurice L., Minn.-St. Paul San. Dist., P. O. Box 3598, St. Paul, Minn.
Roe, Frank C., The Carborundum Company, Niagara Falls, N. Y.
Rogers, Harvey G., State Board of Health, University Campus, Minneapolis, Minn.
Rogers, W. H., Supt., Downers Grove San. Dist., Downers Grove, Ill.
Rohlich, Gerald A., Dept. of Civil Eng., Carnegie Inst. of Tech., Pittsburgh, Pa.
Roland, Robert J., 2 N. Weinbach, Evansville, Ind.
Romaine, Burr, 237 Vincent St., Fond du Lac, Wisc.
Rosemeyer, Alfred, Box 155, Red Bud, Ill.
Ross, W. E., Supt., Richmond Sewage Treatment Wks., 435 S. 9th, Richmond, Ind.
Rowen, R. W., Vice Pres., Nichols Eng. & Research Corp., 60 Wall Tower, New York, N. Y.
Rowinski, N. M., Oneida Bank Bldg., Rhinelander, Wisc.
Ruble, E. H., Duluth Health Dept., 409 City Hall, Duluth, Minn.
Ruchhoft, C. C., U. S. P. H. S., E. 3rd & Kilgour Sts., Cincinnati, Ohio.
Rugdal, H. T., Supt., Sewage Treatment Plant, Kenosha, Wisc.
Rule, Harry A., St. Elmo, Ill.
Russell, J. H., Works Opr., Rochelle, Ill.
Ryan, Joseph P., 7746 Coles Ave., Chicago, Ill.
Sager, John C., San. Eng., Minn.-St. Paul San. Dist., Box 3598, St. Paul, Minn.
Sakellariou, Evans N., 4033 W. End Ave., Chicago, Ill.
Sanders, M. D., Res. Chemist, Swift & Co., Chem. Lab., Union Stock Yards, Chicago, Ill.
Sargent, H. H., Supt., Sewage Treatment Wks., 320 N. Locust St., Sycamore, Ill.
Sawyer, Clair N., 2280 Loring Place, Bronx, N. Y.
Schaller, Norbert C., 4408 Towle Ave., Hammond, Ind.
Scheidt, Burton A., 1700 W. 91st Place, Chicago, Ill.
Schier, Lester C., 206 W. Saveland Ave., Milwaukee, Wisc.
Schildman, W. H., 922 Doolin Ave., Jacksonville, Ill.
Schlenz, H. E., Pacific Flush Tank Co., 4241 Ravenswood Ave., Chicago, Ill.
Schmidt, Otto J., 3711 Greenview Ave., Chicago, Ill.
Schneider, J. J., 6155 S. Albany Ave., Chicago, Ill.
Schriner, P. J., Chemist, 195 S. Fraser, Kankakee, Ill.
Schroepfer, Geo. J., Box 3598, St. Paul, Minn.
Schwark, Wm. A., Railroad Ave., Glenview, Ill.
Schwartz, Oswald, Street Commissioner, Cederburg, Wisc.
Schwob, Carl E., 1800 W. Filmore St., Chicago, Ill.
Scott, Cliffton A., The American Well Works, Aurora, Ill.
Scott, Roger J., 3522 Jackson Blvd., Chicago, Ill.
Shubart, C. A., Princeton, Ind.
Sidwell, Clarence G., Chemist, 601 E. California, Urbana, Ill.
Sieg, J. G., 121½ S. Side Square, Macomb, Ill.
Simplex Ejector & Aerator Corp., 2400 W. Madison St., Chicago, Ill.

Slagle, Elmer C., Room 115, Court House, Duluth, Minn.
Sleeger, Warren H., P. O. Box 3598, St. Paul, Minn.
Smith, Dell, 420 W. 4th St., Rochester, Ind.
Smith, E. E., Elgin Sanitary Dist., Elgin, Ill. (Deceased.)
Smith, Fred J., 908 W. 2nd St., Rock Falls, Ill.
Smith, J. Irwin, 1503 Vine St., Harvey, Ill.
Smith, R. Trumbull, Sales Engr., Wallace & Tiernan Co., 416 Flour Exchange Bldg., Minneapolis, Minn.
Sorrell, W. H., 223 S. Washington, Knightstown, Ind.
Spaeder, Harold J., 218 W. Chester, Monticello, Ill.
Spencer, C. C., The Dorr Company, 221 N. La Salle St., Chicago, Ill.
Sperry, Walter A., P. O. Box 241, Aurora, Ill.
Spiegel, Milton, 6334 N. Oakley Ave., Chicago, Ill.
Spiess, Reinhold, Litchfield, Ill.
Stapleton, K. K., City Eng., City Hall, Jacksonville, Ill.
Stauff, Paul V., Park Hotel, Eveleth, Minn.
Steffen, A. J., San. Engr. Dist. No. 2, Elkhorn, Wisc.
Steffes, Arnold M., Rollingstone, Minn.
Steindorf, R. T., Chain Belt Co., 20 N. Wacker Drive, Chicago, Ill.
Stemper, J. Alex., Opr., Sewage Treatment Works, Oconomowoc, Wisc.
Storey, Ben M., 2240 Edgecombe Rd., St. Paul, Minn.
Sund, Gustrom, Plant Opr., Altoona, Wisc.
Suter, Max, 405 W. Elm St., Urbana, Ill.
Swope, Gladys, Sewage Treatment Wks., Dahringer Rd., Waukegan, Ill.
Tanari, Myron, P. O. Box 66, Ladd, Ill.
Tapleshay, John A., 4102 Harwood Rd., South Euclid, Ohio.
Tapping, C. H., 7718 Cornell, Chicago, Ill.
Tempest, N. F., Portland Cement Assoc., 33 W. Grand Blvd., Chicago, Ill.
Thalheimer, Marce, E. Pearl St., Batesville, Ind.
Thayer, Paul M., 3933 N. Prospect Ave., Milwaukee, Wisc.
Tholin, A. L., 6701 Oconto Ave., Chicago, Ill.
Thomas, Ariel A., State & Trust Bank Bldg., Highland, Ill.
Thornton, Arthur F., Russell B. Moore Co., 930 K. of P. Bldg., Indianapolis, Ind.
Todd, J. A., 103 W. Oak St., Kewanee, Ill.
Tomek, A. O., Sewage Disposal Plant, Two Rivers, Wisc.
Townsend, Darwin W., 839 N. Marshall St., Milwaukee, Wisc.
Travis, Frank D., Inertol Co., Inc., 437 Orleans St., Chicago, Ill.
Trenthart, L. S., 1319 E. 3rd St., Duluth, Minn.
Troemper, A. Paul, San. Eng., Dept. of Public Health, Division of San. Engineering, Springfield, Ill.
Trulander, Wm. M., 1316 7th St., S., Minneapolis, Minn.
Tubich, George, 113 Talbot Laboratory, Urbana, Ill.
Turpin, U. F., 2518 Ridgeway Ave., Evanston, Ill.
Unger, Gilbert C., Jr., Imperial Hotel, 7th & Jefferson, Louisville, Ky.
Urban, W. J., c/o Consoer, Townsend & Quinlan, 211 W. Wacker Drive, Chicago, Ill.
Urbana & Champaign San. Dist., P. O. Box 18, Urbana, Ill.
Van Breda, A. J., Gilman, Ill.
Van Praag, Alex, Jr., 447 Standard Office Bldg., Decatur, Ill.
Vigna, John B., Supt. Public Works, Collinsville, Ill.
Wahlstrom, Carl A., 419 N. 23rd St., La Crosse, Wisc.
Walbridge, Thornton, Supt., Sewage Treatment Works, Dahringer Rd., Waukegan, Ill.
Walker, Donald, 555 Walnut St., Aurora, Ill.
Walker, Vernon L., State Dept. of Public Health, Div. San. Engineering, Springfield, Ill.
Walraven, W. B., Springfield San. Dist., Springfield, Ill.
Walton, Graham, Instructor Hydr. and San. Engineering, University of Wisconsin, Madison, Wisc.
Ward, C. N., Meade, Ward & Hunt, State Journal Bldg., Madison, Wisc.
Ward, Oscar, 4100 S. Cedar St., Marshfield, Wisc.
Wardwell, T. M., City Mgr., Rhinelander, Wisc.
Warrick, L. F., State Board of Health, Madison, Wisc.
Watters, T. G., 824 E. Washington St., Hoopeston, Ill.
Weart, James G., 811 S. State St., Springfield, Ill.
Weber, E. J., Plant Opr., Oconomowoc, Wisc.
Weeber, W. Keith, Dis. Health Unit, c/o 7 City Hall, Springfield, Ill.
Weil, M. L., Pres., Chicago Pump Co., 2336 Wolfram St., Chicago, Ill.

Wells, E. Roy, Civil Eng., Court House, Geneva, Ill.
West, A. W., Asst. San. Eng., Wisc. State Board of Health Dist. Office No. 7, Rutledge Charity Bldg., Chippewa Falls, Wisc.
Wheeler, C. E., Jr., Calumet Sewage Treatment Works, 125th St. & Cottage Grove Ave., Chicago, Ill.
Wheeler, Duane, 4037 Gilliot St., Duluth, Minn.
Whittaker, H. A., Chief San. Engr., State Dept. of Health, University Campus, Minneapolis, Minn.
Whittemore, L. C., Engr., Chicago Sanitary Dist., 910 S. Michigan Ave., Chicago, Ill. (Deceased.)
Wilbur, C. C., 2760 Thomas Ave., S., Minneapolis, Minn.
Wileman, C. S., 548 Rockefeller Bldg., Cleveland, Ohio.
Wiley, John S., Room 304, 210 State St., New Orleans, La.
Wiley, Ralph B., School of Civ. Eng., Purdue University, West Lafayette, Ind.
Willett, C. K., Engr., City National Bank Bldg., Dixon, Ill.
Williams, Clyde E., 2180 Hollywood Place, South Bend, Ind.
Williams, Leon, 2231 Glenwood, Toledo, Ohio.
Williams, William D., 522 S. 6th St., Stillwater, Minn.
Williamson, F. Martin, 1174 Wesley Ave., Oak Park, Ill.
Wills, Walter, Linton, Ind.
Wilson, Harry L., 3634 47th Ave., S., Minneapolis, Minn.
Wilson, J. B., 5300 Boulevard Place, Indianapolis, Ind.
Wilson, John, 610 Torrey Bldg., Duluth, Minn.
Wirth, Harvey E., Bur. of San. Eng., 1 W. Wilson St., Madison, Wisc.
Wisely, F. E., 4101 Lafayette Ave., St. Louis, Mo.
Wisely, W. H., Mgr., Urbana & Champaign San. Dist., Urbana, Ill.
Wisniewski, Theo., City Hall Annex, State Board of Health, Green Bay, Wisc.
Wittenborn, E. L., Div. of San. Eng., State Health Dept., Springfield, Ill.
Woltmann, J. J., Cons. Eng., 225 Unity Bldg., Bloomington, Ill.
Woodman, Lorrin E., 111 Dean St., Woodstock, Ill.
Woodward, F. L., Public Health Eng., Bureau of Health, Public Safety Bldg., St. Paul, Minn.
Yeomans Brothers Company, 1433 Dayton St., Chicago, Ill.
Zack, S. I., Filtration Equipment Corp., 10 E. 40th St., New York, N. Y.
Zurbuch, N. F., Dime Bank Bldg., Fort Wayne, Ind.

Dakota Water and Sewage Works Conference

(North Dakota Section)

Lloyd K. Clark, *Secretary-Treasurer*, State Dept. of Health, Bismarck, N. Dak.

Bavone, A. L., Asst. San. Engr., State Dept. of Health, Bismarck, N. Dak.
Clark, L. K., State Health Dept., Bismarck, N. Dak.
Lauster, K. C., State Dept. of Health, Bismarck, N. Dak.
Lindsten, H. C., 301 Hamilton Bldg., Winnipeg, Manitoba, Canada.
Pinney, F. W., 1401 8th St., N., Fargo, N. Dak.
Toman, George J., Assoc. San. Engr., State Dept. of Health, Bismarck, N. Dak.

(South Dakota Section)

W. W. Towne, *Secretary-Treasurer*, Division of Sanitary Engineering, S. D. State Board of Health, Pierre, S. Dak.

Berry, S. C., City Engineer, Lead, S. Dak.
Bragstead, R. E., City Engineer, City Hall, Sioux Falls, S. Dak.
Buck, W. H., Asst. San. Eng., State Board of Health, Pierre, S. Dak.
Carl, Charles E., Inst. of Civil Engr., S. Dak. State College, Brookings, S. Dak.
Cochrane, W. F., 4925 Military Ave., Omaha, Nebr.
Doerr, Earl, Waterworks Supt., Centerville, S. Dak.
Holst, J. S., Supt., Sewage Works, Mitchell, S. Dak.

Manne, Arthur S., Civil Eng., Aberdeen, S. Dak.
Mather, Edward K., Dakota Engineering Co., 309 Western Bldg., Mitchell, S. Dak.
Mathews, E. R., San. Eng., State Board of Health, Pierre, S. Dak.
Mitchell, Robert D., c/o Malcolm Pirnie, 25 W. 43rd St., New York, N. Y.
Morris, Lee, Water & Sewer Supt., Custer, S. Dak.
Murschel, Jacob, Supt. Water & Sewage, Webster, S. Dak.
Poston, R. F., San. Eng., Wilson Dam, Ala.
Price, Charles R., Supt. Sewage Treatment Plant, Box 590, Rapid City, S. Dak.
Reed, Ralph, Asst. City Engr., Watertown, S. Dak.
Robinson, J. C., Milk Sanitation Engr., State Board of Health, Pierre, S. Dak.
Schroeder, W. L., Water & Sewer Comm., Miller, S. Dak.
Schulz, E. H., Supt., Sewer and Water Department, Box 235, Watertown, S. Dak.
Sorbel, J. L., Asst. San. Engr., Pierre, S. Dak.
Spieker, Roy G., San. Eng., Pennington County Unit, Rapid City, S. Dak.
Spies, Kenneth H., Asst. San. Eng., State Board of Health, Pierre, S. Dak.
Towne, W. Waldo, Dir., Div. of San. Eng., Capitol Annex, Pierre, S. Dak.

Federal Sewage Research Association

Charles T. Carnahan, *Secretary-Treasurer*, U. S. P. H. S., East Third and Kilgour Sts., Cincinnati, Ohio.

Berry, C. Radford, 1215 N. 2nd St., Harrisburg, Pa.
Bibelhausen, L. A., U. S. Indian Service, P. O. Box 93, Neopit, Wisc.
Butterfield, C. T., U. S. Public Health Service, 3rd & Kilgour Sts., Cincinnati, Ohio.
Carlson, H. R., San. Eng. Asst., U. S. Public Health Service, Room 112, Federal Office Bldg., San Francisco, Calif.
Carnahan, Charles T., U. S. Public Health Service, E. 3rd & Kilgour Sts., Cincinnati, Ohio.
Chambers, Cecil W., Ohio Dept. of Health Lab., Ohio State University, Columbus, Ohio.
Cohen, Stuart, U. S. Public Health Service, E. 3rd & Kilgour Sts., Cincinnati, Ohio.
Collins, W. D., U. S. Geological Survey, Interior Bldg., Washington, D. C.
Crohurst, Harry R., U. S. Public Health Service, Room 1309, Enquirer Bldg., Cincinnati, Ohio.
Dopmeyer, A. L., U. S. Public Health Service, Room 112, Federal Office Bldg., San Francisco, Calif.
Ettinger, M. B., U. S. Public Health Service, E. Third & Kilgour Sts., Cincinnati, Ohio.
Fisher, Lawrence, U. S. P. H. S., Riggs Bank Bldg., 14th St. & Park Rd., Washington, D. C.
Frank, Leslie C., U. S. P. H. S., 19th & Constitution Ave., Washington, D. C.
Freeman, A. B., U. S. P. H. S., Riggs Bank Bldg., Washington, D. C.
Fuchs, Abraham W., U. S. P. H. S., 19th & Constitution Ave., Washington, D. C.
Fuhrman, Ralph E., Sewage Treatment Plant, Blue Plains, D. C.
Gordon, J. B., Rm. 309, District Bldg., Washington, D. C.
Herringer, E. J., U. S. P. H. S., 857 U. S. Court House, Chicago, Ill.
Hollis, L. M., U. S. P. H. S., Rm. 1309, Enquirer Bldg., Cincinnati, Ohio.
Hommon, H. B., The District Engineer, U. S. P. H. S., Rm. 210, Federal Office Bldg., San Francisco, Calif.
Hopkins, Omar C., 38 Standish Rd., Watertown, Mass.
Hoskins, J. K., 25th & E. Sts., N. W., Washington, D. C.
Jones, S. Leary, Health & Sanitation Section, Tennessee Valley Auth., Wilson Dam., Ala.
Kachmar, John F., U. S. P. H. S., E. 3rd & Kilgour Sts., Cincinnati, Ohio.
Kehr, Robert W., U. S. P. H. S., 3rd & Kilgour Sts., Cincinnati, Ohio.
King, Kenneth K., Sr. San. Engr., 448 W. 68th Terrace, Kansas City, Mo.
Kochtitsky, O. W., Jr. San. Engr., 3 Shadowlawn Drive, Chattanooga, Tenn.
Lackey, James B., U. S. P. H. S., 3rd & Kilgour Sts., Cincinnati, Ohio.
Lamoureux, V. B., U. S. P. H. S., Rm. 112, Federal Office Bldg., San Francisco, Calif.
LeBosquet, M., Rm. 1309 Enquirer Bldg., Cincinnati, Ohio.
Le Van, J. H., National Inst. of Health, Div. of Ind. Hygiene, Bethesda, Md.
Linders, Edward, Gordon Hotel, 916 16th St., N. W., Washington, D. C.

MacKenzie, Vernon G., U. S. P. H. S., E. 3rd & Kilgour Sts., Cincinnati, Ohio.
Maier, F. J., U. S. P. H. S., Subtreasury Bldg., Wall, Pine & Nassau Sts., New York, N. Y.
McCallum, G. E., Sanitation Section, U. S. P. H. S., 25th & E. Sts., Washington, D. C.
McNamee, Paul D., Sewage Treatment Plant, Blue Plains, D. C.
Megregian, Stephen, Jr. Chemist, U. S. P. H. S., E. 3rd & Kilgour Sts., Cincinnati, Ohio.
Middleton, Francis M., Jr., U. S. P. H. S., E. 3rd & Kilgour Sts., Cincinnati, Ohio.
Miller, A. P., Sub-Treas., Wall & Pine Sts., New York, N. Y.
Moore, W. A., Chemist, U. S. P. H. S., 3rd & Kilgour Sts., Cincinnati, Ohio.
Moss, F. J., U. S. P. H. S., 19th & Constitution Ave., N. W., Washington, D. C.
Nesheim, Arnold, 924 Elm St., Salt Lake City, Utah.
Norris, Francis I., Jr. Chemist, U. S. P. H. S., E. 3rd & Kilgour Sts., Cincinnati, Ohio.
Old, H. N., U. S. P. H. S., Washington, D. C.
Placek, O. R., Jr. Chemist, E. 3rd & Kilgour Sts., Cincinnati, Ohio.
Purdy, William C., E. 3rd & Kilgour Sts., Cincinnati, Ohio.
Reed, Geo. D., 3931 Plainville Rd., Cincinnati, Ohio.
Ricketts, Allen T., Brookmont, Georgetown Station, Washington, D. C.
Robertson, J. L., Jr., Rm. 327, Federal Bldg., Memphis, Tenn.
Ruchhoft, C. C., Prin. Chemist, U. S. P. H. S., E. 3rd & Kilgour St., Cincinnati, Ohio.
Scott, Guy R., Tennessee Valley Authority, Sanitation Section, Wilson Dam, Ala.
Shaw, Frank R., U. S. P. H. S., Rm. 857, U. S. Court House, Chicago, Ill.
Smith, Russell S., U. S. P. H. S., E. 3rd & Kilgour Sts., Cincinnati, Ohio.
Snapp, Russell G., U. S. P. H. S., 3rd & Kilgour Sts., Cincinnati, Ohio.
Streeter, H. W., E. 3rd & Kilgour Sts., Cincinnati, Ohio.
Sullivan, E. C., San. Engr., Interstate Sanitary Dist. No. 4, Rm. 304, New Orleans, La.
Tarbett, R. E., U. S. P. H. S., 19th & Constitution Ave., N W., Washington, D. C.
Tate, Guy M., Jr., c/o Jefferson County Board of Health, Birmingham, Ala.
Theriault, E. J., National Inst. of Health, Bethesda, Md.
Walker, William W., Dr., U. S. P. H. S., E. 3rd & Kilgour Sts., Cincinnati, Ohio.
Weibel, S. R., U. S. P. H. S., Rm. 1309, Enquirer Bldg., Cincinnati, Ohio.
Woodward, R. L., U. S. P. H. S., Rm. 1309, Enquirer Bldg., Cincinnati, Ohio.
Wright, Charles T., U. S. P. H. S., Interstate San. Dist. No. 6, San Juan, P. R.
Yaffe, C. D., Supt., State Dept. of Health, Columbus, Ohio.

Georgia Water and Sewage Association

Paul Weir, *Secretary-Treasurer*, Superintendent Filtration, Atlanta Water Works, 1194 Hemphill Ave., Atlanta, Ga.

Brockman, J. C., Dr., University of Georgia, P. O. Box 45, Athens, Ga.
de Jarnette, N. M., Director Water Laboratory, State Board of Health, State Capitol, Atlanta, Ga.
English, W. B., Supt. of Sewage Treatment, Cedartown, Ga.
Enloe, V. P., Supt., R.F.D. 5, Atlanta, Ga.
Frith, G. R., 136 Vidal Blvd., Decatur, Ga.
Gran, John E., Dr., Library of Chemistry, University of Alabama, University, Ala.
Gray, Odell W., Chemist Water Softening Plant, Thomasville, Ga.
Handley, L. W., Water Plant Opr., La Grange, Ga.
Hansell, Wm. A., Asst. Chief Const. & Engr. of Sewers, City Hall, Atlanta, Ga.
Hoy, J. R., San Engr., 408 Hildebrandt Bldg., Jacksonville, Fla.
Huckeba, W. L., Supt. Filtration, Carrollton, Ga.
Jacobs, L. L., Supt. Filtration, Newnan Water Works, Newnan, Ga.
Jones, T. A., Supt. Light & Water Dept., Fort Valley, Ga.
Kahn, J. M., 42 W. 25th St., Atlanta, Ga.
Keown, Roy L., Master Mechanic & Chief Engr., Clark Thread Co., Clarkdale, Ga.
Knapp, H. A., Supt., Intrenchment Creek Disposal Plant, Boulder Crest Drive, S. E. Atlanta, Ga.
Leitch, John C., Engr. National Tube Co., 1532 Chandler Bldg., Atlanta, Ga.
Lenert, Louva G., Div. San. Engr., State Dept. of Health, P. O. Box 88, Swainsboro, Ga.
Lowe, Thomas M., Prof., Head Prof. Dept. of Civil Eng., Alabama Polytechnic Institute, Auburn, Ala.

Mathews, Henry M., Supt. Water & Light Dept., Thomasville, Ga.
Newton, R. O., Rep., W. S. Dickey Clay Mfg. Co., 686 Greenwood Ave., Atlanta, Ga.
Shelton, Edw. N., Tennessee Corp., 621 Grant Bldg., Atlanta, Ga.
Simonton, Lewis, Supt. Filtration, Griffin Water Works, Griffin, Ga.
Wallis, L. E., Supt. Water Works, Elberton, Ga.
Weaver, W. H., Supt. Water Works, Decatur, Ga.
Weir, Paul, Supt., Filtration Atlanta Water Works, 1194 Hemphill Ave., Atlanta, Ga.
Whelchel, H. E., Supt., Filter Plant, College Park, Ga.

Iowa Wastes Disposal Association

Lindon J. Murphy, *Secretary-Treasurer*, Iowa State College, Ames, Iowa.

Ahrens, G. C., Asst. San. Engr., State Dept. of Health, 1207 Des Moines St., Des Moines, Iowa.
Alden, Town of, c/o G. F. Bigelow, Town Clerk, Alden, Iowa.
Baker, Stanley L., City Engr., Newton, Iowa.
Bartow, Edward, Prof., Research Laboratory, Johns Manville Corp., Manville, N. J.
Caine, Richard, Supt., Duluth Sewage Disposal Plant, 706 W. 7th St., Duluth, Minn.
Currie, C. H., Pres., Currie Engineering Co., Webster City, Iowa.
Dawson, F. M., Dean of College of Engineering, State University of Iowa, Iowa City, Iowa.
Des Moines, City of, c/o Paul Winfrey, City Engineer's Office, Des Moines, Iowa.
Dixon, C. S., 4501 Washburn Ave., South, Minneapolis, Minn.
Doonan, R. E., City Supt., City of Waverly, Waverly, Iowa.
Dye, Elmer E., Chief Chemist, J. E. Decker & Sons, Mason City, Iowa.
Edwards, B. E., Supt. of Sewage Works, Webster City, Iowa.
Garwood, Kirk, Operator Sewage Plant, Grinnell, Iowa.
Green, Howard R., 208–210, Bever Bldg., Cedar Rapids, Iowa.
Hall, M. G., Hall Engineering Company, Centerville, Iowa.
Hinman, Jack J., Chief, Water Laboratory Division, State Hygienic Labs., Iowa City, Iowa.
Klippel, Floyd, City Manager, 321 Stevens St., Iowa Falls, Iowa.
Kramer, David, Supt. of Sewers, Allison, Iowa.
Levine, Max, Bacteriology Department, Iowa State College, Ames, Iowa.
Lovell, Theodore R., Engr., Sewage Plant, City Hall, Fort Dodge, Iowa.
Marzek, E. J., 3231 Fourth Ave., Sioux City, Iowa.
Miller, Robert G., Supt. Sewage Plant, 807 Fourth Ave., Vinton, Iowa.
Morrell & Company, John, Att.: Mr. Frank C. Raney, Pur. Agt., Ottumwa, Iowa.
Murphy, Lindon J., Engineering Extension Service, Iowa State College, Ames, Iowa.
Nemmers, W. P., Nemmers and Clark, Hubbell Bldg., Des Moines, Iowa.
Richey, C. E., Dist. Public Health Office, Centerville, Iowa.
Rostenbach, Royal Edwin, U. S. P. H. S., Rm. 1309 Enquirer Bldg., Cincinnati, Ohio.
Russell, Don B., City Engr., Oskaloosa, Iowa.
Sampson, J. A., Public Health District No. 4, Court House, Fort Dodge, Iowa.
Schenk, E. E., Cons. Engr., Waterloo, Iowa.
Schliekelman, R. J., Dist. Public Health Office, Journal Bldg., Washington, Iowa.
Schrack, Bert, 621 1st St., S. W. Oelwein, Iowa.
Sedlacek, A. J., Supt. of Sewage Works, Pocahontas, Iowa.
Smith, Charles E., Supt. of Utilities, Winterset, Iowa.
Spragg, H. J., Supt., Iowa Great Lakes Sewage Works, Box 187, Arnolds Park, Iowa.
Stanley, C. M., Young and Stanley, Inc., 211 Iowa Ave., Muscatine, Iowa.
Strelow, J. L., Supt. of Sewage Works, 2324 East St., Davenport, Iowa.
Waterman, Earle L., Prof. of San. Engr., State University of Iowa, Iowa City, Iowa.
Whisler, Ben A., Civil Engineering Dept., Iowa State College, Ames, Iowa.
Wieters, A. H., Chief Engr., State Dept. of Health, Des Moines, Iowa.
Wilson, C. T., 620 W. Third St., Waterloo, Iowa.
Woolley, B. C., City Engineer, Le Mars, Iowa.
Young, Frank E., City Engr., City Hall, Cedar Rapids, Iowa.

Kansas Water and Sewage Works Association

Earnest Boyce, *Secretary*, State Board of Health, Lawrence, Kansas.

Boyce, Earnest, Engr., State Board of Health, Lawrence, Kans.
Boyer, J. A., Chemist, Water Dept., Fort Scott, Kans.
Burns & McDonnell, Cons. Engrs., 107 N. Linwood Blvd., Kansas City, Mo.
Frerking, A. G., c/o W. S. Dickey Co., Kansas City, Mo.
Haney, Paul, Asst. Engr., 1745 Louisiana St., Lawrence, Kans.
Johnson, Warren W., 443 N. Exposition Ave., Wichita, Kans.
Kaler, P. E., 1522 W. 16th St., Topeka, Kans.
Lewis, Clay W., Western Sales Mgr., Marblehead Lime Co., 1220 R. A. Long Bldg., Kansas City, Mo.
Lingo, H. L., Water & Light Supt., Horton, Kans.
Meeker, Robert H., Wichita Water Co., Wichita, Kans.
Mitchell, Ansel N., 310 Ward Parkway, Kansas City, Mo.
Paulette, R. J., Cons. Engr., National Service Reserve Life Bldg., Topeka, Kans.
Peart, Robert, City Manager, Sterling, Kans.
Pensinger, L. C., 1332 Oak St., Kansas City, Mo.
Smith, Levi B., Water Supt., Paola, Kans.
Spaeth, Julius, Box 746, Salina, Kans.
Staley, H. H., Cons. Engr., 372 New England Bldg., Topeka, Kans.
Sulentic, S. A., 327 New England Bldg., Topeka, Kans.
Wilson, Murray A., Paulette & Wilson, Salina, Kans.
Wood, Lawrence E., County San. Engr., Marion, Kans.
Young, Lewis A., 1704 Mississippi St., Lawrence, Kans.

Maryland-Delaware Water and Sewerage Association

Chesley F. Garland, *Secretary-Treasurer*, State Dept. of Health, 2411 N. Charles Street, Baltimore, Md.

Armeling, Geo. K., 4031 Bonner Rd., Baltimore, Md.
Bingley, W. McLean, 4011 Monticello St., Richmond, Va.
Blohm, A. W., 2411 N. Charles St., Baltimore, Md.
Clement, R. C., 6629 32nd St., N. W., Washington, D. C.
Cromwell, Edward C., Baltimore Sewage Treatment Plant, Colgate, Md.
Enoch Pratt Free Library, Periodicals Dept., Cathedral, Franklin & Mulberry Sts., Baltimore, Md.
Finck, G. E., Bureau of Sewers, Municipal Bldg., Baltimore, Md.
Funk, John B., City Engineer, Brunswick, Md.
Garland, Chesley F., Jr., Asst. San. Engr., Md. State Dept. of Health, 2411 N. Charles St., Baltimore, Md.
Genter, Albert L., Wyman Park Apartments, Baltimore, Md.
Hall, Harry R., Deputy Chief Engineer, Washington Surb. San. Dist., Hyattsville, Md.
Hopkins, Ed. S., Montebello Filters, Hillen Rd., Baltimore, Md.
Keefer, C. E., 1918 Mt. Royal Terrace, Baltimore, Md.
Kenney, Norman D., Assoc. Engr., Whitman, Requardt & Smith, W. Biddle St. at Charles, Baltimore, Md.
Kratz, Herman,, 4200 Connecticut Ave., Baltimore, Md.
MacMurray, L. C., Res. Engr., Md. State Dept. of Health, 2411 N. Charles St., Baltimore, Md.
Maryland State Dept. of Health, 2411 N. Charles St., Baltimore, Md.
Munroe, W. C., Chief Eng., Anne Arundel County San. District, Glen Burnie, Md.
Owings, Noble L., Asst. Eng., Washington Suburban San. Dist., Hyattsville, Md.
Powell, S. T., Professional Bldg., 303 N. Charles St., Baltimore, Md.
Smith, Paul L., 5404 Tramore Rd., Baltimore, Md.
Whitman, Requardt & Smith, Charles & Biddle Sts., Baltimore, Md.
Williamson, A. E., San. Eng., State Board of Health, Jacksonville, Fla.
Wolman, Abel, Prof. of San. Eng., Johns Hopkins University, Latrobe Hall, Homewood, Baltimore, Md.

Michigan Sewage Works Association

W. F. Shephard, *Secretary-Treasurer*, State Dept. of Health, Lansing, Mich.

Adams, Milton P., Secy. Stream Control Commission, Lansing, Mich.
Anderson, Herb, City of Bad Axe, Mich.
Anderson, R. A., Supt. Sewage Treatment Plant, Muskegon Heights, Mich.
Bean, Geo. E., City Mgr., Escanaba, Mich.
Bowers, T. C., 202 E. Ganson St., Jackson, Mich.
Boyd, J. W., 442 Grant St., Grand Haven, Mich.
Brown, C. U., Cass City, Mich.
Brumm, Allen S., Nashville, Mich.
Butler, Emmet, Box 81, Milford, Mich.
Carney, George, Brighton, Mich.
Clark, M. S., 1853 E. Beardsley, Elkhart, Ind.
Corson, H. C., City Eng., Birmingham, Mich.
Crawn, R. D., 1208 W. Ganson St., Jackson, Mich.
Croom, Thomas G., 340 W. 55th St., New York, N. Y.
Damoose, N. G., R. R. 6, Box 535, Battle Creek, Mich.
DeHooghe, Bernard A., 818 Minnesota, Gladstone, Mich.
DeLano, Huntley, 138 Withey St., Grand Rapids, Mich.
Dickman, Dorian H., Box 1808, R. R. 1, Royal Oak, Mich.
Dickson, Harvey, 2983 Alter Rd., Detroit, Mich.
Burley, Fred H., 9300 W. Jefferson, Detroit, Mich.
Chamier, Albert, 9300 W. Jefferson, Detroit, Mich.
Doane, Ercell J., 106 E. Ash, Mason, Mich.
Dodge, H. P., 809 Rose Ave., Ann, Arbor, Mich.
Dornbush, Don, 25 W. Maple, Fremont, Mich.
Dorr, Fred., 113 N. Gainsborough, Royal Oak, Mich.
Dowd, Ira, 1813 Belle Ave., Flint, Mich.
Doyle, Thomas J., 274 E. Boulevard N., Pontiac, Mich.
Durand, Edwin M., 259 Paris Ave., S. E., Grand Rapids, Mich.
Edgecomb, G. O., 311 S. Clay St., Greenville, Mich.
Ehlers, Ralph B., Dow Chemical Company, Midland, Mich.
Eldridge, E. F., Eng. Exp. Sta., Michigan State College, E. Lansing, Mich.
Ellis, Norman T., 213 Clinton St., Grand Haven, Mich.
Fargo Engineering Company, Jackson, Mich.
Fishbeck, Kenneth, 2117 W. St. Joseph, Lansing, Mich.
Forton, R. G., 319 Barlow, Traverse City, Mich.
Francis, Geo. W., Francis Engineering Company, Eddy Bldg., Saginaw, Mich.
Gahagan, H. B., Armour Leather Co., Holland, Mich.
Gates, Lloyd R., Dr., University of Michigan, 140 W. Medical Bldg., Ann Arbor, Mich.
Graham, James E., Berrien Springs, Mich.
Green, R. A., 600 N. Pleasant, Jackson, Mich.
Groen, Michael A., 7446 Ternes, Dearborn, Mich.
Gustafson, Ivar, 311 N. Harrison St., Ludington, Mich.
Habermehl, C. A., 14521 Strathmoor, Detroit, Mich.
Hauer, Gerald, 921 Joslin St., S., Grand Rapids, Mich.
Hawken, Dalton, Rochester, Mich.
Hayward, Homer, Michigan Dept. of Health, Bureau of Engineering, Lansing, Mich.
Heeg, H. H., 403 Jewett St., Howell, Mich.
Hoad, W. C., Col., 2108 Melrose St., Ann Arbor, Mich.
Jacka, S. C., City Engineer, Lansing, Mich.
Jackson, R. B., 527 W. Ganson St., Jackson, Mich.
Jackson, T. L., St. Ignace, Mich.
Jellema, John F., 526 Central Ave., Holland, Mich.
Jennings, L. R., 508 E. Main St., Owosso, Mich.
Jones, Frank, 802 W. Genesee, Lansing, Mich
Kammerling, Lane, 194 E. 7th St., Holland, Mich.
Kelley, R. E., 119 S. Maple St., Sturgis, Mich.
Killmar, C. M., Health Dist. 4, Rogers City, Mich.
Klang, Marvin F., 8070 Elgin Ave., Detroit, Mich.
Kronbach, Allen, 218 Maple Ave., Monroe, Mich.
Kunze, Albert T., 797 Central Ave., Wyandotte, Mich.
Ladue, Charles, Clio, Mich.
Lanigan, J. A., 797 Central Ave., Wyandotte, Mich.
Lawton, George, Lawton, Mich.
Leemaster, J. F., 1036 Lansing Ave., Jackson, Mich.

Lehner, Walter J., 76 S. Wilson Blvd., Mt. Clemens, Mich.
Lenderink, Andrew, 222 Commerce Bldg., Kalamazoo, Mich.
Leonhard, Harold M., 3107 Van Alstyne, Wyandotte, Mich.
Lesher, C. E., 550 Grove St., East Lansing, Mich.
Liddle, E. G., 16880 Fielding, Detroit, Mich.
Lucas, W. R., 16190 Archdale Ave., Detroit, Mich.
McGrath, C. P., 116 Clinton St., Mt. Clemens, Mich.
McKenna, Harold R., 520 E. 3rd St., Flint, Mich.
MacFarlane, W. D., 14365 Marlowe Ave., Detroit, Mich.
McRae, John, 612 S. 17th St., Escanaba, Mich.
Mallman, W. L., Michigan State College, East Lansing, Mich.
Mallory, Howard, 811 Barton Drive, Ann Arbor, Mich.
Marshall, J. C., Charlevoix, Mich.
Matthews, Richard, Analyst, City Testing Lab., Muskegon, Mich.
Max, John, 1105 W. Cross St., Ypsilanti, Mich.
May, D. C., Ayres, Lewis, Norris & May, Wolverine Bldg., Ann Arbor, Mich.
Meserva, Charles, Chelsea, Mich.
Mogelnicki, Stanley J., Municipal Bldg., Birmingham, Mich.
Montgomery, J. Robert, Disposal Plant Opr., c/o Caro State Hospital, Caro, Mich.
Morrill, Arthur, Engr. of Sewage Treatment, 9300 W. Jefferson Ave., Detroit, Mich.
Mudgett, C. T., Sewage Treatment Works, Muskegon, Mich.
Musgrove, Robert, Sewage Treatment Works, Grand Rapids, Mich.
Muskegon, City of, c/o Carl Peterson, City Mgr., Muskegon, Mich.
Norgaard, John, 1501 27th St., S. E., Washington, D. C.
Oehlke, Henry E., 505 8th Ave., Manistee, Mich.
Oeming, L. F., 1534 E. Grand River, Lansing, Mich.
Ohr, Milo F., 742 College Ave., S. E., Grand Rapids, Mich.
Older, Fred, City of Ypsilanti, Ypsilanti, Mich.
Olson, Herbert A., 205 S. State St., Ann Arbor, Mich.
Orton, J. W., 9206 Sorrento Ave., Detroit, Mich.
Packard, O. E., Charlotte, Mich.
Patriarche, John M., City Hall, East Lansing, Mich.
Pierce, W. E., Whitehall, Mich.
Pierson, Otto J., Northern Mich. Tuberculosis San., Gaylord, Mich.
Pomeroy, C., Hartford, Mich.
Ponto, W., 513 Fountain, Ann Arbor, Mich.
Potts, Harry G., Pennsylvania Salt Co., Wyandotte, Mich.
Powers, Thos. J., R. F. D. 4, Midland, Mich.
Raymond, N. I., 610 Pine St., Owosso, Mich.
Reedy, Timothy D., Supt., Sewage Treatment Plant, Flint, Mich.
Reynolds, M. W., 313 Shiawassee St., Durand, Mich.
Ritter, Bruce, Lake Odessa, Mich.
Rooks, C. P., Zeeland, Mich.
Rudd, Wm. C., Bureau of Water, Rm. 241, S. Pier 4, Delaware & Chestnut Sts., Dept. of Wharves, Docks, & Ferries, Philadelphia, Pa.
Rumsey, James R., 1265 Allen Rd., S. E., R. R. 6, Grand Rapids, Mich.
Sageman, Norman, 216 Moores River Drive, Lansing, Mich.
Shephard, W. F., Mich. Dept. of Health, Lansing, Mich.
Slausson, J. B., 223 S. Rogers St., Mason, Mich.
Smith, Harold L., 525 Center, Alma, Mich.
Smith, Robert J., Michigan Department of Health, State Office Bldg., Lansing, Mich.
Smith, S. H., Supt. Board of Public Works, South Haven, Mich.
Smith, Walter E., Wallace & Tiernan Company, Inc., 415 Brainard St., Detroit, Mich.
Snedeker, L. La Verne, Sewage Treatment Plant, Adrian, Mich.
Stegeman, Paul, Water Dept., Midland, Mich.
Stewart, H., 5264 Argyle, Dearborn, Mich.
Stielstra, Clarence, 3811 Concord St., Midland, Mich.
Sullivan, J. Donald, Alma Savings Bank Bldg., Alma, Mich.
Tarbell, J., 1404 4th St., Jackson, Mich.
Theroux, Frank R., Civil Engineering School, Mich. State College, East Lansing, Mich.
Venn, Frank, Pentwater, Mich.
Vermette, F. L., Sewage Treatment Plant, Pontiac, Mich.
Weeber, Earle R., 420 Federal Sq. Bldg., Grand Rapids, Mich.
Wegner, Herman R., 3527 David Scott Bldg., Detroit, Mich.
Welch, Pierre R., The Michigan Alkali Company, Wyandotte, Mich.

Whitmore, Earl R., City Engr., Port Huron, Mich.
Wigg, C. V., Box 697, Bessemer, Mich.
Williams, W. B., Williams & Works, County Bldg., Grand Rapids, Mich.
Witcher, C. Preston, 707 W. Washington, Ann Arbor, Mich.
Wolohan, L. J., 7719 Indiana Ave., Dearborn, Mich.
Wyllie, George F., R. 1, Box 424, Lansing, Mich.
Young, Robert A., c/o Consoer, Townsend & Quinlan, 211 W. Wacker Drive, Chicago, Ill.
Zimmer, Walter E., Eng., Wolverine Engr. Co., Mason, Mich.

Missouri Water and Sewerage Conference

Warren Kramer, *Secretary-Treasurer*, State Board of Health, 200 Monroe Street, Jefferson City, Mo.

Bridges, F. B., Supt. Water & Light Dept., Kahoka, Mo.
Haskins, Chas. A., Cons. Eng., Finance Bldg., Kansas City, Mo.
Kehr, Wm. Q., State Board of Health, Jefferson City, Mo.
Lindell, O. V., The Dorr Company, 6315 Brookside Plaza, Kansas City, Mo.
Luebbers, Ralph H., College of Engineering, University of Missouri, Columbia, Mo.
Menefee, James H., P. O. Box 71, Webb City, Mo.
Russell, George, Mun. and San. Engr., 7025 Etzel Ave., University City, Mo.
St. Louis Public Library, Olive & 14th Sts., St. Louis, Mo.
Wheatly, Wm. D., Chemist, Pittsburgh Plate Glass Co., Crystal City, Mo.
Wilke, Harvey R., Supt., Columbia Sewage Disposal Plant, Lowry Bldg., Columbia, Mo.

New England Sewage Works Association

LeRoy W. Van Kleeck, *Secretary-Treasurer*, State Dept. of Health, State Office Bldg., Hartford, Conn.

Abrams, Milton F., 17 Battery Place, New York, N. Y.
Adams, George O., Lawrence Experiment Station, State Department of Health, Lawrence, Mass.
Agar, Charles G., Div. of Sanitation, State Dept. of Health, Albany, N. Y.
Albertson, John G., 886 Midland Rd., Oradell, N. J.
Allen, Herbert B., Sewage Treatment Plant, Fitchburg, Mass.
Almquist, Frederick O. A., Conn. State Dept. of Health, State Office Bldg., Hartford, Conn.
Baird, Charles O., Jr., Teacher, Northeastern University, 316 Huntington Ave., Boston, Mass.
Baldwin, C. W., Syntron Company, 230 Congress St., Boston, Mass.
Balmer, Robert R., Jr., State Engr., 4 Federal Court, Springfield, Mass.
Barbour, Frank A., Cons. Engr., 1120 Tremont Bldg., Boston, Mass.
Bauer, Henry W., Supt., 181 Ridge Rd., Middletown, Conn.
Benford, William R., Brown University, Providence, R. I.
Berg, Stanley Edward, 65 South St., Stanford, Conn.
Bogren, George G., Weston and Sampson, 14 Beacon St., Boston, Mass.
Bolde, Abraham C., Rm. 511-A State House, Boston, Mass.
Bolieau, Clifton W., c/o Malcolm Pirnie, 25 W. 43rd St., New York, N. Y.
Bond, Philip E., 189 High St., Holyoke, Mass.
Bowers, Samuel W., c/o MacKenzie & Bowers, Southington, Conn.
Bowler, Edmond Wesley, Prof., University of New Hampshire, Durham, N. H.
Bradlee, Warren R., Winchendon, Mass.
Brigham, Harold L., Water & Sewer Commission, Marlboro, Mass.
Brooks, John H., Jr., E. Worcester St., Worcester, Mass.
Brule, Abundius A., 157 Chestnut St., Central Falls, R. I.
Bryant, H. M., P. O. Box 102, Milton, N. H.
Buck, Robinson D., 650 Main St., Hartford, Conn.
Bugbee, Julius W., Supt. Sewage Disposal Works, 25 New York Ave., Providence, R. I.
Bugbee, Raymond C., 17 Monument St., Groton, Conn.

Burden, Harry P., Assoc. Prof., Tufts College, Medford, Mass.
Burdoin, Allen J., Cons. Engr., 85 Washington St., Wellesley Hills, Mass.
Burr, R. S., American Brass Company, Waterbury, Conn.
Burrell, Robert, Opr., 39 Howard St., West Haven, Conn.
Camp, Thomas R., Assoc. Prof., Massachusetts Inst. of Tech., Cambridge, Mass.
Campbell, Arthur T., State Engr., 165 Capitol Ave., Hartford, Conn.
Carpenter, Howard F., 25 New York Ave., Providence, R. I.
Carson, Caryl C., Box 1139, Hartford, Conn.
Cary, Willis E., 5 Chesterfield Rd., Worcester, Mass.
Chase, E. Sherman, Metcalf & Eddy, 1300 Statler Bldg., Boston, Mass.
Clark, H. W., Cons. Engr., 89 Broad St., Boston, Mass.
Clarke, V. B., Box 582, Ansonia, Conn.
Cobb, Edwin B., 142 Vernon St., Norwood, Mass.
Coburn, S. E., 1300 Statler Bldg., Boston, Mass.
Cohn, Morris M., 1101 Lexington Ave., Schenectady, N. Y.
Cook, Horace J., Sewer Supt., 268 Court St., Auburn, Me.
Copeland, William R., Rm. 317, State Office Bldg., Hartford, Conn.
Copley, Charles H.,, 513 Winthrop Ave., New Haven, Conn.
Coy, Arthur H., Water & Sewer Dept., Westerly, R. I.
Craemer, George H., Opr., Municipal Bldg., Hartford, Conn.
Craig, W. Allen, Mfgr., 21 Berkeley Rd., Avondale Estates, Ga.
Cutting, Merritt E., Auburn St., Cherry Valley, Mass.
Damon, Nelson A., 34 Spring St., Amherst, Mass.
Damon, Wayne F., 161 West St., Leominster, Mass.
Darby, George M., c/o The Dorr Company, Westport, Conn.
Darling, Fred A., Sewer Supt., Franklin, Mass.
DeHaas, Nicholas, Box 176, Linwood, Mass.
Dept. of Civil Engineering, University of Maine, Wingate Hall, Orono, Me.
Dion, Clarence K., 28 Chester Ave., Westerly, R. I.
Disario, G. M., Fed. Engr., Chief of San. Div., Ministry of Public Works, Caracas, Venezuela, S. A.
Donnini, Frank L., 19 Mitchell St., New Britain, Conn.
Dudley, Richard E., Rm. 410, City Hall, Springfield, Mass.
Dyer, Samuel, Memorial Bldg., Framingham, Mass.
Eddy, Harrison P., Jr., 3100 Statler Bldg., Boston, Mass.
Ellsworth, Samuel M., Cons. Engr., 12 Pearl St., Boston, Mass.
Fair, Gordon M., Prof., 7 Scott St., Cambridge, Mass.
Fairfield State Hospital, Newtown, Conn.
Fales, Almon L., c/o Metcalf & Eddy, Statler Bldg., Boston, Mass.
Farnham, Arthur B., City Engineer, Pittsfield, Mass.
Ferris, James E., Electro Bleaching Gas Co., 60 E. 42nd St., New York, N. Y.
Fitzgerald, J. E., Jr., Field Point Mfg. Corp., Edgewood Station, Providence, R. I.
Fleming, Paul V., 1272 Massachusetts Ave., North Adams, Mass.
Flood, Frank L., c/o Metcalf & Eddy, Statler Bldg., Boston, Mass.
Foote, Kenneth E., Rm. 501, Hall of Records, New Haven, Conn.
Gilcreas, F. Wellington, Secy., Division of Laboratories & Research, New Scotland Ave., Albany, N. Y.
Giles, J. Henry L., State Dept. of Health, State Office Bldg., Hartford, Conn.
Gisborne, Frank R., Opr., Arcadia Rd., Old Greenwich, Conn.
Gladue, Donat J., 210 High St., Bristol, R. I.
Goff, James S., Sewer Supt., P. O. Box 298, Hyannis, Mass.
Graemiger, Joseph A., 7 Earl St., West Warwick, R. I.
Greenleaf, John W., Jr., 232 Pond St., Westwood,, Mass.
Green, Herbert, Mun. Engr., City Hall, Worcester, Mass.
Greenwich, Sewer Commission, Rm. 7, Town Bldg., Greenwich, Conn.
Griffin, Guy E., 6 Grove St., Cos Cob, Conn.
Hanrath, William J., Sewage Pumping Sta., Pittsfield, Mass.
Hanson, George I., Boston Post Rd., Marlboro, Mass.
Harper, M. J., Merco Nordstrom Valve Co., 50 Church St., New York, N. Y.
Healy, William A., 83 Main St., Exeter, N. H.
Hill, G. Everett, 15 Bell St., Orange, N. J.
Hiller, Paul W., Innis Speiden & Co., 117 Liberty St., New York, N. Y.

Holmes, Harry E., Mass. State Dept. of Health, 511–A State House, Boston, Mass.
Holmgren, Richard F., Chief Engr., Water Resources Board, Concord, N. H.
Hoover, Charles R., Prof., 8 Pike Place, Middletown, Conn.
Horne, Ralph W., 11 Beacon St., Boston, Mass.
Houser, George C., 220 Clyde St., Brookline, Mass.
Howard, P. F., 138 Bartlett Rd., Winthrop, Mass.
Jackson, J. Frederick, Cons. Engr., 36 Cannon St., Hamden, Conn.
Jenckes, J. Franklin, Jr., Fields Point Mfg. Corp., Providence, R. I.
Johnson, Eskil C., Div. of San. Engr., 335 State Office Bldg., Providence, R. I.
Jordan, Edward C., 147 High St., Reading, Mass.
Joy, C. Fred, Jr., 50 Meredith Circle, Milton, Mass.
Kappe, Stanley E., 2019 Rittenhouse Sq., Philadelphia, Pa.
Karalekas, Peter C., State Engr., Westfield State Hospital, Westfield, Mass.
Kelsey, Walter, Lord & Burnaham Co., Irvington, N. Y.
Knowlton, Kenneth F., 11 Roxbury Ave., Natick, Mass.
Kunsch, Walter, 25 E. Pearl St., Danbury, Conn.
Lamb, Clarence F., Waterman Engineering Co., 86 Weybosset St., Providence, R. I.
Langford, Leonard L., 441 Lexington Ave., New York, N. Y.
Lannon, William, 21 Bridge St., Putnam, Conn.
Lanphaer, Roy S., Worcester Sewage Treatment Plant, Post Office Sta. C., Worcester, Mass.
Lebetkin, George, Bureau of Public Works, Engineering Dept., Hartford, Conn.
Lehr, Eugene L., 15 Summit St., Manchester, Conn.
Locke, Edw. A., 21 Forster St., Hartford, Conn.
Lounsbury, Elmer Irving, Darien, Conn.
MacLeod, Myron, 470 Fourth Ave., New York City.
Maguire, Chas., 613 Turks Head Bldg., Providence, R. I.
Mannheim, Robert, The Mathieson Alkali Wks., Inc., 911 Hospital Trust Bldg., Providence, R. I.
Mariner, W. S., 82 High St., Canton, Mass.
Martzell, Paul C., 60 Mead Ave., Port Chester, N. Y.
McCall, Joseph F., U. S. Veterans' Bureau Hospital, Bedford, Mass.
McDonald, John, 67 Hartford Terrace, Springfield, Mass.
McKee, Jack E., 112 Pierce Hall, Harvard University, Cambridge, Mass.
McMahon, Walter A., 76 Brookside Ave., Torrington, Conn.
Merrill, Walter E., 511–A State House, Boston, Mass.
Meyer, Carl F., Prof. of Civil Eng., Worcester Poly. Institute, Worcester, Mass.
Moat, C. P., Chemist, 2 Colchester Ave., Burlington, Vt.
Moore, Edward W., 7A Pierce Hall, Harvard University, Cambridge, Mass.
Morgan, Edward F., Jr., Supt. of Public Works, Hudson, Mass.
Muldoon, Joseph A., 849 Hancock Ave., Bridgeport, Conn.
Naylor, William, Supt., Water and Sewers, Maynard, Mass.
Newland, James A., Pres., Henry Souther Engineering Co., 11 Laurel St., Hartford, Conn.
Nicoli, Frank A., 56 Howard St., Springfield, Mass.
Olmsted, C. Henry, 740 Main St., East Hartford, Conn.
Palmer, Benjamin M., 114 Thayer Bldg., Norwich, Conn.
Perry, Earl R., City Hall, Worcester, Mass.
Petrie, William P., Supt., Sewage Disposal Plant, Norwalk, Conn.
Pool, Charles L., R. I. Public Health Commission, 335 State Office Bldg., Providence, R. I.
Pratt, Gilbert H., 350 Newbury St., Boston, Mass.
Proudman, Chester F., New Canaan Sewage Disposal Plant, New Canaan, Conn.
Puffer, Stephen P., Town Hall, Amherst, Mass.
Quinn, Francis T., 116 South St., Westboro, Mass.
Quinn, Thomas A., 116 South St., Westboro, Mass.
Raymond, Herbert E., Water, Sewer & Drain Dept., City Hall, Keene, N. H.
Richardson, Charles G., Builders Iron Foundry, Providence, R. I.
Robb, Charles G., Engineering Dept., Municipal Bldg., Hartford, Conn.
Roche, Edward C., 5020 Stickney Ave., Cleveland, Ohio.
Roche, J. P., Camp Lonergan, C. C. C., Voluntown, Conn.

Rogers, John A., Opr., 6 Central Ave., Milford, Conn.
Sanderson, W. W., 11 S. Lake Ave., Albany, N. Y.
Sawyer, Robert W., Jr., 25 W. 43rd St., New York, N. Y.
Scott, Warren J., 34 Garfield Rd., West Hartford, Conn.
Shea, Walter J., 327 State Office Bldg., Providence, R. I.
Sheppard, Frederick, "Municipal Sanitation," 24 W. 40th St., New York City.
Sherman, Leslie K., 1131 Cottage Grove Rd., Bloomfield, Conn.
Sieverding, O. C., 25 Somerset St., Elmwood, Conn.
Smithwick, John J., 699 Stanley St., New Britain, Conn.
Snell, J. R., Dr., 17 Everett St., Cambridge, Mass.
Snow, Willis J., State Engr., State Water Commission, State Office Bldg., Hartford, Conn.
Solander, Arvo A., 1407 21st Ave., S., Nashville, Tenn.
Soule, Ralph M., 511–A State House, Boston, Mass.
Stearns, Donald E., Rhode Island State College, Kingston, R. I.
Sterling, Clarence I., Westfield State Hospital, Westfield, Mass.
Stock, Mitchell B., P. O. Box 804, Bridgeport, Conn.
Sullivan, Ernest J., 511–A State House, Boston, Mass.
Suttie, R. H., Prof., Dept. of Civil Engineering, Yale University, New Haven, Conn.
Tarlton, Ellis Alvord, Salem & Beverly Water Supply Board, Filtration Plant, Beverly, Mass.
Tentschert, Francis P., c/o The Dorr Co., Inc., 570 Lexington Ave., New York, N. Y.
Thayer School of Civ. Eng., Edward S. Brown, Jr., Dartmouth College, Hanover, N. H.
Thompson, E. H., 1308 Elm St., Stratford, Conn.
Thompson, Robert B., The Dorr Company, Inc., Westport, Conn.
Tierney, Lawrence J. J., 518 Rice Bldg., 10 High St., Boston, Mass.
Trager, Leonard W., N. H. State Board of Health, Concord, N. H.
Tuttle, Leon E., Mun. Engr., Town Hall, Stamford, Conn.
Van Atta, John W., Ralph B. Carter Pump Co., 53 Park Place, New York, N. Y.
Van Kleeck, LeRoy W., State Dept. of Health, State Office Bldg., Hartford, Conn.
Wadhams, S. H., Gen., State Water Commission, State Office Bldg., Hartford, Conn.
Walker, Philip B., 18 Summit St., Whitinsville, Mass.
Watertown Fire District, Watertown, Conn.
Watters, George E., 536 Montauk Ave., New London, Conn.
Wentworth, John P., 1300 Statler Bldg., Boston, Mass.
Weston, Arthur D., Rm. 511, State House, Boston, Mass.
Weston, R. S., Cons. Engr., 14 Beacon St., Boston, Mass.
Whipple, Melville C., 112 Pierce Hall, Cambridge, Mass.
Whitlock, Henry C., City Hall, Waterbury, Conn.
Wiggin, David C., Jr., 773 Farmington Ave., West Hartford, Conn.
Winch, Norman M., 46 Birds Hill Ave., Needham, Mass.
Woodward, William H., 159 Sumner Ave., Springfield, Mass.
Worthington, Erastus, Insurance Bldg., Dedham, Mass.
Wright, Edward, State Engr., Mass. State Dept. of Health, 511–A, State House, Boston, Mass.
Wuraftic, Joseph, 335 State Office Bldg., Providence, R. I.

New Jersey Sewage Conference

Richard C. Smith, *Secretary*, 29 High Street, Glen Ridge, N. J.

Adams, J. K., Sewage Disposal Plant, Tenafly, N. J.
Atkinson, Asher, City Engr., City Hall, New Brunswick, N. J.
Bear, E. J., 107 Hillside Ave., Livingston, N. J.
Bonacci, L. N., Research Corporation, Bound Brook, N. J.
Boreiszo, J., 39 Clay St., Milltown, N. J.
Burack, W. D., 90 Sycamore Ave., Livingston, N. J.
Cameron, Geo., 1905 Kuehnle Ave., Venice Park, Atlantic City, N. J.
Campbell, Wm., Jr., 136 Russell Rd., Fanwood, N. J.
Capalbo, James, Lower Notch Rd., Little Falls, N. J.

Chamberlain, Noel S., 492 Rutherford Ave., Trenton, N. J.
Cleary, Edward J., Old Quarry Rd., Upper Montclair, N. J.
Corson, B. I., Camden County Vocational School, Merchantville, N. J.
Cowles, M. W., Hackensack Water Company, Dept., Filtration & Sanitation, New Milford, N. J.
Decker, E. P., City Hall, Newark, N. J.
Devoe, Kermit, South River Sew. Division, South River, N. J.
Evans, F. M., Boro Engineer, Glen Rock, N. J.
Farrent, James, 443 E. 29th St., Paterson, N. J.
Ferguson, Gerald, 225 N. Bridge St., Somerville, N. J.
Fontenelli, Louis, 109 Winslow Place, Garwood, N. J.
Franzozo, Anthony, Manville Sewage Works, Manville, N. J.
Frenchman, J. L., 68 Manning Place, Keansburg, N. J.
Gadomski, Albert J., 709 Parker St., Perth Amboy, N. J.
Gehm, Harry Willard, Agric. Experiment Station, New Brunswick, N. J.
Gibbons, M. M., 961 Frelinghuysen Ave., Newark, N. J.
Harley, Frank E., Fair Lawn Radburn Trust Co. Bldg., Fair Lawn, N. J.
Heinemann, B., 945 E. 163rd St., New York, N. Y.
Henderson, C. N., N. J. Agricultural Experiment Station, New Brunswick, N. J.
Heukelekian, H., Short Course Bldg., Agric. Experiment Station, New Brunswick, N. J.
Ingols, Robert, Agric. Experiment Station, New Brunswick, N. J.
Kachorsky, M. S., Manville Sewerage Works, Manville, N. J.
Kee, William J., Supt., Middlesex Borough Sewage Treatment Works, River Rd., East Bound Brook, N. J.
Killam, E. T., 142 Maiden Lane, New York, N. Y.
Kupper, C. J., Bound Brook, N. J.
Lehmann, Arthur F., 31 Martin Terrace, Hackensack, N. J.
Lendall, Harry N., Prof., Dept. of Municipal and San. Eng., Rutgers University, New Brunswick, N. J.
Littman, M. L., 22 Yates Ave., Newark, N. J.
Long, James C., Box 82, N. J. State Hospital, Greystone Park, N. J.
McMenamin, C. B., 302 Melrose Ave., Bound Brook, N. J.
Mallalieu, W. C., P. O. Box 384, Boonton, N. J.
Miles, Henry J., Dept. of Civ. Eng., University of Florida, Gainesville, Fla.
Moggio, Wm. A., Div. of Public Health, University of North Carolina, Chapel Hill, N. C.
Nichol, Gordon B., Dept. of Water & Sewage, N. J. Agricultural Experiment Station, New Brunswick, N. J.
Nisnevitz, Oscar, Jersey Homestead, N. J.
Norcom, George D., 90 Broad St., New York, N. Y.
Ocean City Sewer Service Co., Ocean City, N. J.
Orchard, Wm. J., Sales Mgr., Wallace & Tiernan Co., Newark, N. J.
Pope, Lester, 656 Schiller Ave., Trenton, N. J.
Porges, Ralph, 411 Atlanta Ave., Sheffield, Ala.
Ridenour, G. M., Assoc. Prof., Dept. of Civil Eng., The Pennsylvania State College, State College, Pa.
Roberts, L. M., 219 Willow St., Bound Brook, N. J.
Roznoy, Louis W., 2481 Vaux Hall Rd., Union, N. J.
Rudolfs, Willem, Dr., Short Course Bldg., Agricultural Exp. Station, New Brunswick, N. J.
Rush, De Witt E., 190 Main St., Sayreville, N. J.
Sandford, Chester, 223 Lenox Ave., South Orange, N. J.
Seid, Sol., 58 Suydam St., New Brunswick, N. J.
Setter, Lloyd R., 50-18 217th St., Bayside, N. Y.
Seydel, Herman, 135 Halladay St., Jersey City, N. J.
Sibila, Rocco, 19 Canal St., Raritan, N. J.
Simmerman, John S., 215 Wildwood Ave., Pitman, N. J.
Slagle, B. A., Dr., 100 Hudson Ave., North Plainfield, N. J.
Smith, P. A., 66 Stanley Rd., South Orange, N. J.
Smith, R. C., 24 High St., Glen Ridge, N. J.
Superintendent, Englewood Sewerage Company, Englewood, N. J.
Tozzi, John, 87 E. Main St., Somerville, N. J.
Trubnick, Eugene, Anheuser-Busch, Inc., Old Bridge, N. J.
Weiss, H., Sewer Supt., East Paterson, N. J.
West, Leslie E., 105 Mill Rd., Irvington, N. J.
Witter, Carl W., Anheuser-Busch, Inc., Old Bridge, N. J.
Wittwer, Norman C., 36 Elmhurst Ave., Trenton, N. J.

New York State Sewage Works Association

A. S. Bedell, *Secretary-Treasurer*, State Department of Health, Albany, N. Y.

Abrams, M. F., 17 Battery Place, New York, N. Y.
Aeryns, Albert N., 716 Greenwood Ave., Brooklyn, N. Y.
Agar, Charles C., Div. of Sanitation, State Dept. of Health, Albany, N. Y.
Agostinelli, Anthony J., Plant Opr., 38 Holden St., Charlotte Station, Rochester, N. Y.
Albertson, J. G., 663 Orchard St., Oradell, N. J.
Aldrich, E. H., c/o Reeves Newsom, 500 Fifth Ave., New York, N. Y.
Allen, A. F., State Dept. of Health, State Office Bldg., Albany, N. Y.
Alsdorf, William R., 91 Mt. Ave., Highland Falls, N. Y.
Althouse, Raymond R., 95 Elmwood Ave., Union, N. J.
American Well Works, Inc., 165 Broadway, New York, N. Y. Att.: Mr. F. J. Smith, Mgr.
Anderson, C. George, 66 Sherman Ave., Rockville Centre, N. Y.
Anderson, Arthur W., 760 Lincoln Blvd., Long Beach, L. I., N. Y.
Anderson, S. P., Pilgrim State Hospital, Brentwood, N. Y.
Andres, William H., Gowanda State Hospital, Collins, N. Y.
Andrews, Harry S., 601 Oneida St., Fulton, N. Y.
Angell, J. M., Jr., Gillette Publishing Co., 155 E. 44th St., New York, N. Y.
Armstrong, Frank W., 13 Hubble St., Bath, N. Y.
Artese, Philip, 751 E. 224th St., Bronx, N. Y.
Asch, Abram B., 10 E. 40th St., New York, N. Y.
Ashe, John R., 22 Homan Blvd., Hempstead, Long Island, N. Y.
Bachmann, Frank, 110–56 71st Ave., Forest Hills, Long Island, N. Y.
Badger, Irvin S., 723 Ackerman Ave., Syracuse, N. Y.
Baker, Roy, 70 S. Bayles Ave., Port Washington, N. Y.
Barasch, William, 2300 Ocean Ave., Brooklyn, N. Y.
Bardet, Paul E., Jamaica Disposal Plant, 150th Ave. & 132nd St., South Ozone Park, N. Y.
Barker, Stanley T., Lt. Comdr., C. E. C. U. S. N. R., Room 2436, Navy Bldg., Washington, D. C.
Barnes, Robert J., 20 5th Ave., Oneonta, N. Y.
Barnhill, Kenneth G., 25 E. 99th St., New York, N. Y.
Barron, James L., 121 Fulton Ave., Hempstead, Long Island, N. Y.
Bates, R. D., State Dept. of Health, 65 Court St., Buffalo, N. Y.
Baumgartner, William H., E. I. Du Pont de Nemours & Co., Grasselli Chemicals Dept., Wilmington, Del.
Becker, John, 505 Vine St., Liverpool, N. Y.
Bedell, A. S., Div. of Sanitation, State Dept. of Health, Albany, N. Y.
Bell, E. Arthur, Box 41, Essex Falls, N. J.
Berg, Stanley E., 9413 74th St., Woodhaven, N. Y.
Bernhardt, Carl J., P. O. Box 707, Jamestown, N. Y.
Bersten, Murray, 230 Ross St., Brooklyn, N. Y.
Besselievre, Edmund B., Paseo Colon 285, Buenos Aires, Argentine, S. America.
Best, Robert B., 71 Maple St. Great Neck, N. Y.
Besthoff, Silas, 22 E. 40th St., New York, N. Y.
Bevan, John G., Guggenheim Bros., 3771 10th Ave., New York, N. Y.
Bidwell, Milton H., 70 Stevens St., Oceanside, N. Y.
Biele, F. J., 184 Nassau Ave., Huntington, N. Y.
Binger, Walter D., Commr. of Borough Works, Municipal Bldg., New York, N. Y.
Bishop, Marshall H., 143 S. Midler Ave., Syracuse, N. Y.
Board of Water, Light & Sewer Commissioners, Hamilton, N. Y.
Bogert, C. L., 30 Church St., New York, N. Y.
Bowe, Thomas F., 110 William St., New York, N. Y.
Boyce, Ralph E., 555 Rugby Rd., Brooklyn, N. Y.
Bradley, John L., 140 W. Main St., Goshen, N. Y.
Bradner, B. E., 240 Halstead Ave., Harrison, N. Y.
Brallier, Paul S., P. O. Box 616, Niagara Falls, N. Y.
Brender, Max M., Ferndale, N. Y.
Breuchaud, Jules R., 155 E. 44th St., New York, N. Y.
Brigham, John C., State Dept. of Health, State Office Bldg., Albany, N. Y.

Brigham, John C., Jr., 56 Church St., Montclair, N. J.
Broderick, Joseph A., 26 N. Eckar St., Irvington, N. Y.
Brower, J. Singleton, 39 Center St., Woodmere, Long Island, N. Y.
Brown, Edward J., 188 St. Johns Place, Brooklyn, N. Y.
Brumbaugh, W. V., National Lime Association, 927 15th St., N. W., Washington, D. C.
Buck, Geo. H., 3100 Connecticut Ave., Washington, D. C.
Bumstead, John C., 368 Broadway, Saratoga Springs, N. Y.
Burczak, William J., 8 Byrd St., Glen Cove, N. Y.
Burgess, Harold, 212 5th Ave., N., Troy, N. Y.
Burr, George H., 314 Pleasant Ave., Hamburg, N. Y.
Byble, Duane, 287 Spring St., Ossining, N. Y.
Caird, James M., Cannon Bldg., Troy, N. Y.
Capen, Charles H., Jr., 8 Florence Place, West Orange, N. J.
Carbone, Edward A., 3150 Bailey Ave., Bronx, N. Y.
Carmichael, David W., 225 Bamford Ave., Hawthorne, N. J.
Carpenter, George D., City Hall, Ithaca, N. Y.
Carpenter, Harry C., 218 Wisner Ave., Middletown, N. Y.
Carpenter, L. V., New York University, University Heights, New York, N. Y.
Carpenter, William T., 125 Worth St., New York, N. Y.
Carter Co., Ralph B., Att.: Mr. J. W. Van Atta, 53 Park Place, New York, N. Y.
Cerny, Paul J., 441 Lexington Ave., Room 1102, New York, N. Y.
Chamberlain, Wm. T., 75 Pierrepont St., Brooklyn, N. Y.
Chase, E. Sherman, Metcalf & Eddy, 1300 Statler Bldg., Boston, Mass.
Chicago Pump Company, 2336 Wolfram St., Chicago, Ill.
Chisholm, Colin B., Bird Island Sewage Treatment Wks., Buffalo, N. Y.
Christian, James B., 197 Maple Ave., Rockville Centre, N. Y.
Cipriano, Anthony G., 691 7th St., Buffalo, N. Y.
Clark, Robert N., State Dept. of Health, Old Court House, Ithaca, N. Y.
Clementi, Paul T., 168 W. 77th St., New York, N. Y.
Clift, M. A., Nichols Eng. & Research Corp., 60 Wall Tower, New York, N. Y.
Coates, John J., c/o Sheppard T. Powell, Chem. Eng., 330 N. Charles St., Baltimore, Md.
Cohn, Morris M., 1101 Lexington Ave., Schenectady, N. Y.
Cole, E. Shaw, 125 Wildwood Ave., Upper Montclair, N. J.
Collyer, Joseph C., Room 2100, Municipal Bldg., New York, N. Y.
Comstock, Walter C., 135 N. 11th St., New Hyde Park, Long Island, N. Y.
Conklin, Chester A., 180 Forest Hill Drive, Syracuse, N. Y.
Cook, Rodney E., Main St., Riverhead, Long Island, N. Y.
Copeland, William R., State Office Bldg., Hartford, Conn.
Cordell, Mona, Miss, Wards Island Sew. Treatment Plant, New York, N. Y.
Costello, John J., 631 Perine St., Elmira, N. Y.
Cottrell, H. S., 117 Liberty St., New York, N. Y.
Cowell, John E., 160 School St., Oyster Bay, N. Y.
Cowles, M. Warren, Hackensack Water Company, New Milford, N. J.
Cox, C. R., State Dept. of Health, Albany, N. Y.
Craig, W. Allen, 7816 Cedarbrook St., Philadelphia, Pa.
Crawford, H. V., General Electric Co., Schenectady, N. Y.
Cullison, Eugene F., 1 Cooks Lane, Highland Falls, N. Y.
Dappert, Anselmo F., 64 Winnie Rd., Delmar, N. Y.
Davidson, F. G., Valley Cottage, Lake Rd., Nyack, N. Y.
Davis, Walter S., 686 Myrtle Ave., Albany, N. Y.
Dayton, Alfred E., 273 Murray St., Newark, N. J.
DeBrito, F. Saturnino, Jr., Ciaxo Postal 1631, Rio de Janeiro, Brazil, S. America.
DeGroat, Frank N., Birchwood Ave., Nyack, N. Y.
Deming, Harold A., 412 Wilson Ave., East Rochester, N. Y.
DeMunn, E. M., Main St., Genesee, N. Y.
Denise, Wm. D., 486 Denise Rd., Rochester, N. Y.
Dennis, C. E., 102 Seneca St., Watkins Glen, N. Y.
Devendorf, Earl, State Dept. of Health, Albany, N. Y.
Diehl, H. B., Reeves Pulley Co., 76 Dey St., New York, N. Y.

Dobson, William T., 4851 Grand Central Terminal, New York, N. Y.
Dobstaff, Robert, Jr., 4867 Seneca St., Ebenezer, N. Y.
Dobstaff, Robert W., Sr., 135 Aurora Ave., Gardenville, N. Y.
Dolomite Products Co., 750 L. A. Bank Bldg., Rochester, N. Y.
Doman, Joseph, 291 White St., Hartford, Conn.
Donaldson, Wellington, 125 Worth St., Dept. of Public Works, New York, N. Y.
Dougherty, James E., Jr., 2600 Davidson Ave., New York, N. Y.
Dougherty, Richard J., 2857 Sedgwick Ave., Bronx, N. Y.
Downes, John R., Supt. Joint Sewage Treatment Works, Bound Brook, N. J.
Dresselt, Edward L., 7 North St., Cobleskill, N. Y.
Drexel, Frederick, 6266 60th Drive, Maspeth, Long Island, N. Y.
Driscoll, Timothy J., 217 Benziger Ave., New Brighton, N. Y.
Duane, John M., Street & Sewer Comm'r., Minoa, N. Y.
Duffiey, Frank J., 3370 Decatur Ave., Bronx, N. Y.
Dunne, E. R., Professional Bldg, Lynbrook, N. Y.
Dyckman, Warren W., Room 2100, Municipal Bldg., New York, N. Y.
Eager, Vernon, 60 Dewey Ave., Buffalo, N. Y.
Edinger, Harry F., 110 Prince St., Kingston, N. Y.
Edwards, Gail P., Wards Island Treatment Plant, Wards Island, N. Y.
Edwards, William L., Gowanda State Hospital, Gowanda, N. Y.
Ehle, Virgil, 21 Grand St., Gloversville, N. Y.
Ehler, John A., 306 Milton Rd., Rye, N. Y.
Eich, Henry F., 1333 Decatur St., Brooklyn, N. Y.
Electro Refractories & Alloys Corp., Att.: Mr. L. U. Milward, 622 Andrews Bldg., Buffalo, N. Y.
Enslow, L. H., 155 E. 44th St., New York, N. Y.
Epstein, Harold, Room 1038, City Hall, Buffalo, N. Y.
Erdwurm, Emil, 1137 Roanoke Ave., Far Rockaway, Long Island, N. Y.
Eustance, Arthur W., State Dept. of Health, State Office Bldg., Albany, N. Y.
Eustance, Harry W., 159 Rock Beach Rd., Rochester, N. Y.
Evansky, Frank J., 1332 Feller Ave., New York, N. Y.
Faber, Harry A., 50 E. 41st St., New York, N. Y.
Fair, Gordon M., 7 Scott St., Cambridge, Mass.
Farrell, Eugene J., 774 Mt. Prospect Ave., Newark, N. J.
Farrell, Michael, 222 Mason St., Canandaigua, N. Y.
Fassnacht, George G., 5805 Lowell Ave., Indianapolis, Ind.
Fenaughty, Thomas, 315 E. 4th St., Watkins Glen, N. Y.
Fenger, J. W., 24 Idlewood Place, Hamburg, N. Y.
Fenton, John V., Professional Bldg., Lynbrook, N. Y.
Fernandez, John U., 1950 E. 29th St., Brooklyn, N. Y.
Ferris, J. E., Electro Bleaching Gas Co., 60 E. 42nd St., New York, N. Y.
Field, W. T., Watertown, N. Y.
Firth, Elmer W., Borough Hall, Kew Gardens, N. Y.
Fischer, Anthony J., c/o The Dorr Company, 570 Lexington Ave., New York, N. Y.
Fischer, Philip C., 110 Bennett Ave., Yonkers, N. Y.
Fitzgerald, J. A., 271 Main St., Hudson Falls, N. Y.
FitzSimons, Richard H., 225 Raymond St., Rockville Centre, N. Y.
Five, Helge, 680 Northern Blvd., Great Neck, N. Y.
Fleet, Gerald A., State Dept. of Health, 65 Court St., Buffalo, N. Y.
Foley, William M., Schenectady County Home, Hetcheltown Rd., Schenectady, N. Y.
Forbes, Albert F., Box 285, Watkins Glen, N. Y.
Forster, M. H., 154 Woodward Ave., Buffalo, N. Y.
Fort, Edwin J., Huntington, Long Island, N. Y.
Fortenbaugh, J. Warren, 155 Hamlin Rd., Buffalo, N. Y.
Frawley, Daniel, 308 Bronson St., Painted Post, N. Y.
Fuller, Andrew J., 57 Maxwell Ave., Geneva, N. Y.
Fuller, N. M., 302 Laurens St., Olean, N. Y.
Galata, Richard L., 8829 Ft. Hamliton Parkway, Brooklyn, N. Y.
Ganshaw, Elmer, Supt. of Public Works, Springville, N. Y.

Gardner, Geo. W., Miller Bldg., Lowville, N. Y.
Gascoigne, Geo. B., San. Eng., Euclid Ave. at E. 9th St., Cleveland, Ohio. (Deceased.)
Gates, Justin F., James St., Middletown, N. Y.
Gavett, Weston, 973 Kenyon Ave., Plainfield, N. J.
Gelbke, Arthur W., Apartado 655, Guayaquil, Ecuador, S. America.
Gerardi, Angelo P., 1782 Westchester Ave., Bronx, N. Y.
Gere, William S., 117 James St., Syracuse, N. Y.
Germond, Earl, 315 Grove St., Montclair, N. J.
Gilcreas, F. Wellington, Div. of Labs., State Dept. of Health, Albany, N. Y.
Gill, J. Francis, Comm. of Works, W. Oneida St., Oswego, N. Y.
Gillespie, Robert L., Jr., 1119 E. 10th St., Brooklyn, N. Y.
Gilman, Floyd, 19 South Ave., Manchester, N. Y.
Glace, I. M., 22 S. 22nd St., Harrisburg, Pa.
Glynn, William J., Frazier St., Brockport, N. Y.
Goldsmith, Philip, 589 Flatbush Ave., Brooklyn, N. Y.
Goodenough, Frank H., 90 Concord Ave., White Plains, N. Y.
Gorman, Richard C., Jr., 44 Genesee St., Hornell, N. Y.
Gould, Richard H., 125 Worth St., New York, N. Y.
Grace, Francis J., 174 W. 65th St., New York, N. Y.
Graham, Edward J., 1810 3rd Ave., Watervliet, N. Y.
Greig, John M. M., 30 Church St., New York, N. Y.
Grelick, David, 110 Van Cortland Park, S., New York, N. Y.
Grieff, Victor C., 173 Beach 139th St., Belle Harbor, Long Island, N. Y.
Griffin, F. T., 2220 16th St., Troy, N. Y.
Grover, Robert H., 18 Princeton St., Williston Park, Long Island, N. Y.
Gyatt, W. P., 169 Milnor Ave., Syracuse, N. Y.
Haberer, John C., 254 Delaware Ave., Delmar, N. Y.
Haemmerlein, Victor E., Village Hall, East Aurora, N. Y.
Hale, Arnold H., 365 Linden Rd., R. 1, Brighton, N. Y.
Hall, Frank H., 341 Willis Ave., Mineola, N. Y.
Hall, Frederic H., 36 State St., Albany, N. Y.
Hallock, Emerson C., 6 Northview Place, White Plains, N. Y.
Halm, Ernest W., 112–18 205th St., Hollis, Queens, N. Y.
Halpin, John, 18 Park Ave., Port Washington, N. Y.
Halstead, Douglas M., 110 7th St., Garden City, N. Y.
Hamm, William C., 9 Locust Ave., Port Washington, N. Y.
Hammond, F. G., 1 Park Place, Canton, N. Y.
Hansen, August E., 415 Lexington Ave., New York, N. Y.
Hanson, John R., 9 Douglas Ave., Babylon, N. Y.
Hardenbergh, W. A., 310 E. 45th St., New York, N. Y.
Harding, J. C., 19 E. Main St., Mt. Kisco, N. Y.
Hardinge Company, F. E. Finch, Rep., York, Pa.
Harrison, Edward F., 2450 N. Broad St., Philadelphia, Pa.
Hart, Charles G., 424 Durston Ave., Syracuse, N. Y.
Harvey, Carl, 4819 S. Paul Blvd., Rochester, N. Y.
Hawley, Arthur A., 25 7th St., Woodlawn, Lackawanna, N. Y.
Hayes, John A., South Street Extension, Warwick, N. Y.
Hazen, Richard, c/o Malcolm Pirnie, 25 W. 43rd St., New York, N. Y.
Hedgepeth, L. L., Penn. Salt Co., 1000 Widener Bldg., Philadelphia, Pa.
Hedges, Horace P., 72 S. Bayles Ave., Port Washington, N. Y.
Henderson, Chas. F., 10 School St., Port Washington, Long Island, N. Y.
Hendon, H. H., 216 Court House, Birmingham, Ala.
Henel, Wm. F., 47 Spooner St., Hugenot, Staten Island, N. Y.
Henkel, George E., 348 S. Union St., Cranford, N. J.
Henry, Augustine, 105–27 87th St., Ozone Park, N. Y.
Herberger, Arthur Henry, 205 S. Long Beach Ave., Freeport, Long Island, N. Y.
Hess, Seth G., 242 W. 76th St., New York, N. Y.
Heubi, Thomas, 45 Washington Ave., Fredonia, N. Y.
Higgins, William J., 118 W. 84th St., New York, N. Y.
Highberger, W. W., 158 Summit Ave., Mt. Vernon, N. Y.

Hill, G. Everett, 15 Bell St., Orange, N. J.
Hirschel, Leslie, 226–15 139th Ave., Laurelton, Long Island, N. Y.
Hoefling, Wm. L., General Chemical Co., 1 W. Genesee St., Buffalo, N. Y.
Hoey, John B., 477 Middle Neck Rd., Great Neck, N. Y.
Hogan, James W. T., 551 Wales Ave., New York, N. Y.
Hogan, William J., 574 Willow Ave., Cedarhurst, Long Island, N. Y.
Holbrook, A. R., 2104 White Ave., Knoxville, Tenn.
Holland, Frank H., 312 Archer St., Freeport, N. Y.
Holloway, Frank M., Vapor Recovery Systems Co., 30 Church St., Suite 2214, New York, N. Y.
Holmes, Glenn D., 615 Starrett-Syracuse Bldg., Syracuse, N. Y.
Holmquist, Chas. A., State Dept. of Health, Albany, N. Y.
Honigman, Elkono G., 125 Worth St., Room 823, New York, N. Y.
Hopkins, L. S. R., 76 William St., New York, N. Y.
Hopper, Allen O., 217 East Ave., Rochester, N. Y.
Horton, Theodore, Sandwich, Cape Cod, Mass.
Hotchkiss, H. T., Jr., Supv. Chemist, Municipal Bldg., Larchmont, N. Y.
Howson, J. T., 28 Market St., Westfield, N. Y.
Hubbard, Winfred D., 145 Pearl St., Kingston, N. Y.
Huber, Harold J., 139 Broadway, Lancaster, N. Y.
Hulak, S. M., 717 Main St., Niagara Falls, N. Y.
Hults, William S., Jr., 54 Irma Ave., Port Washington, N. Y.
Hurst, William O., Millbrook, N. Y.
Hutcheson, H. D., 604 Colton Ave., Newark, N. Y.
Illig, Louis, Harlem Valley State Hospital, Wingdale, N. Y.
Industrial Chemical Sales Co., Inc., 230 Park Ave., New York, N. Y., Att.: Noel Statham.
Inertol Company, 401 Broadway, New York, N. Y.
Iscol, George, 125 Worth St., Room 816, New York, N. Y.
Johns-Manville Corp., Att.: C. A. McGinnis, 22 E. 40th St., New York, N. Y.
Johnson, Clement, 171 N. Forest Ave., Rockville Centre, N. Y.
Johnson, Herbert O., 10 Broadway, Great Neck, N. Y.
Johnson, John W., 65 Tillinghast Place, Buffalo, N. Y.
Jones, Daniel, 54 Centre Ave., New Rochelle, N. Y.
Jones, E. M., 68th & Upland Sts., Philadelphia, Pa.
Jordan, Harry B., 22 E. 40th St., Room 2601, New York, N. Y.
Kaiser, William B., Harlem State Hospital, Wingdale, N. Y.
Kappe, S. E., 627 W. Kingsley St., Philadelphia, Pa.
Kass, Nathan I., 167 Beaumont St., Brooklyn, N. Y.
Keeler, J. Harold, 795 Lake St., White Plains, N. Y.
Kehoe, Daniel J., 78 W. 7th St., Oswego, N. Y.
Kairn, K. A., 293 Larkin St., Buffalo, N. Y.
Kelleher, Joseph A., 157–24 27th Ave., Flushing, Long Island, N. Y.
Keller, Jacob, East Ave., Shortsville, N. Y.
Keller, Lyndon M., 217 Lark St., Albany, N. Y.
Kellogg, Clarence E., 3 Barone Ave., Mt. Morris, N. Y.
Kelly, Clarence, 403 Westminster Rd., Cedarhurst, N. Y.
Kemp, Harold A., Office of Chief of Engrs., U. S. A., Washington, D. C.
Kennedy, William, Huntington Sewer Plant, Huntington, Long Island, N. Y.
Kennedy, W. Russell, 4 "B" St., Niagara Falls, N. Y.
Ketcham, Charles G., 479 Auburn Ave., Buffalo, N. Y.
Ketcham, Joseph M., Gilbert St., Northport, N. Y.
Kiker, John E., Jr., N. Y. State Dept. of Health, 35 Market St., Poughkeepsie, N. Y.
Kilcawley, Edward J., Rensselaer Polytechnic Inst., Troy, N. Y.
Kimler, Alexander, 608 Osborn St., Brooklyn, N. Y.
Kin, Stephen R., 33 Bogardus St., Buffalo, N. Y.
Kirsner, Charles, 125 Spruce St., Cedarhurst, Long Island, N. Y.
Kivell, Wayne A., c/o The Dorr Company, 570 Lexington Ave., New York, N. Y.
Klegerman, M. H., 50 Church St., New York, N. Y.
Klinck, Frank, 408 Westminster Rd., Cedarhurst, Long Island, N. Y.
Knez, Cosmo M., 2433 Yates Ave., Bronx, N. Y.
Knox, Stuart K., 25 Warfield Rd., Montclair, N. J.

Koplowitz, Sol., 112 Matoaka Ct., Williamsburg, Va.
Kozma, Albert B., 43 Barrows Ave., Rutherford, N. J.
Krell, A. J., c/o W. Raisch Associates, 227 Fulton St., New York, N. Y.
Kreuter, Clarence, 116 E. William St., Waterloo, N. Y.
Kriegel, Paul, Box 214, Attica, N. Y.
Kulberg, Abraham J., 125 Worth St., Room 823, New York, N. Y.
Kunowski, Peter, 389 Jewett Ave., Port Richmond, Staten Island, N. Y.
Lambert, Francis J., Sewage Disposal Plant, Batavia, N. Y.
Lange, John F., 72 School St., Glen Cove, N. Y.
Langford, Leonard L., 441 Lexington Ave., New York, N. Y.
Larkin, W. H., State Dept. of Health, 34 South St., Middletown, N. Y.
Larsen, Ernest A., 34 Grove St., Geneva, N. Y.
Laughlin, William G., 270 Madison Ave., New York, N. Y.
LaValley, Edward C., 130 Melbourne Ave., Syracuse, N. Y.
Laverty, Francis J., 3900 Spuyten Duyvil Parkway, New York, N. Y.
Lawlor, Jerome N., 120 Farrington Ave., North Tarrytown, N. Y.
Lawlor, Thomas F., 140 S. Cherry St., Poughkeepsie, N. Y.
Lawrence, John, 43 Columbia St., Liberty, N. Y.
Lawrence, William H., 510 McDonough St., Brooklyn, N. Y.
Ledford, Geo. L., 8943 Jollet Ave., Niagara Falls, N. Y.
Ledwith, James J., Dept. of Public Works, 125 Worth St., New York, N. Y.
LeFebure, Fabian J., 148–32 60th Ave., Flushing, N. Y.
Lehman Sewer Pipe Co., Inc., 32 Court St., Brooklyn, N. Y., Att.: Mr. A. R. D'Aleo.
Leiby, F. E., 78 Elmwood Ave., Rye, N. Y.
Levy, Harry W., 2129 Municipal Bldg., New York, N. Y.
Lewis, John V., 54 Court St., Rochester, N. Y.
Lieber, Maxim, Lt., P. O. Box 17, Ft. Belvoir, Va.
Limestone Products Corp. of Amer., Spring St., Newton, N. J., Att.: Mr. R. L. Quait.
Link Belt Company, M. B. Tark, Rep., Philadelphia, Pa.
Lippelt, Hans B., 9428 78th St., Ozone Park, N. Y.
Loomis, Harry E., 1112 Teall Ave., Syracuse, N. Y.
Lord & Burnham Co., 2 Main St., Irvington, N. Y.
Lose, Charles, Jr., 221 N. Ave. E, Cranford, N. J.
Lose, Charles, III, 40 Payn Ave., Chatham, N. J.
Losee, James R., 25 Rosehill Ave., Tarrytown, N. Y.
Lozier, William S., 10 Gibbs St., Rochester, N. Y.
Luther, L. L., 46 N. Ocean Ave., Freeport, N. Y.
Lynch, Daniel E., Jr., 810 Ocean Ave., Brooklyn, N. Y.
Lynch, James T., 86 Genesee St., Auburn, N. Y.
MacCallum, C., 12 Reid Ave., Port Washington, Long Island, N. Y.
MacCrea, J. M., 153 Oakland St., Syracuse, N. Y.
McLaughlin, Carroll W., 266 Fulton Ave., Hempstead, N. Y.
Magee, George W., Hudson River State Hospital, Poughkeepsie, N. Y.
Malick, Anthony J., 312 E. Oak St., Olean, N. Y.
Malcolm, W. L., Cornell University, Ithaca, N. Y.
Mallory, Edward B., 169 E. Clinton Ave., Tenafly, N. J.
Manahan, Patrick, Supt. of Sewage Disposal Works, Briarcliff Manor, N. Y.
Mann, Alfred H., 111 N. 18th St., Olean, N. Y.
Mann, Uhl T., 6 Samson St., Cortland, N. Y.
Marrs, Paul, Box 87, Comack, N. Y.
Marshall, E. A., 167 Lafayette Ave., Geneva, N. Y.
Marshall, W. B., 2314 E. Wyoming Place, Apt. E, Milwaukee, Wisc.
Martin, A. E., 35 Mang Ave., Kenmore, N. Y.
Martin, Alexander G., 36 Kinsy Ave., Kenmore, N. Y.
Martin, Edward J., Jr., 24 S. Washington St., Tarrytown, N. Y.
Martin, Geo. H., Jr., 107 Lake Ave., Tuckahoe, N. Y.
Martin, Warren S., Grenada Place, Massapequa, N. Y.
Marx, Frank, Highland, N. Y.
Mathers, George, 112 Roosevelt Ave., Garden City, N. Y.
Maxwell, W. E., P. O. Box 92, Schenectady, N. Y.
McBreen, Charles, Orangeburg, N. Y.

McCarthy, Justin J., 69 School St., Arlington, Mass.
McCarty, William F., 112 McAllister Ave., Syracuse, N. Y.
McDonald, Michael D., N. Y. State Dept. of Public Health, 65 Court St., Buffalo, N. Y.
McDonald, Roland G., 409 Madison St., East Rochester, N. Y.
McDonnell, George H., 24 Canal St., South Hadley Falls, Mass.
McInerney, Gerald J., 544 S. Main St., Elmira, N. Y.
McKeeman, Edwin C., 154 Colonial Ave., Freeport, Long Island, N. Y.
McLaughlin, R. M., 11 Gene Place, White Plains, N. Y.
McLean, Clement, Iola Sanitarium, Rochester, N. Y.
McPhail, James L., 141 Mt. View Ave., Staten Island, N. Y.
McShea, James, Box 121, Wassaic, N. Y.
Meiers, Walter W., 195–10 42nd Ave., Flushing, N. Y.
Mendelsohn, I. W., 3412 Oliver St., N. W., Washington, D. C.
Meneke, K. E., Filtration Engineering, Inc., 205 W. Wacker Drive, Chicago, Ill.
Meron, L. A., City Hall, Glens Falls, N. Y.
Michaels, John, Bureau of Sewers, Borough Hall, Kew Gardens, N. Y.
Miljevic, Nicholas, 31 Gates Ave., Lackawanna, N. Y.
Miller, Fred M., 30 Chestnut St., Glen Cove, N. Y.
Miller, Wallace T., Municipal Bldg., Ossining, N. Y.
Milliken, Harold E., Plant Opr., 101 Swift St., Auburn, N. Y.
Mitchell, Louis, College of Applied Science, Syracuse University, Syracuse, N. Y.
Monsell, Harry M., 525 1st St., Greenport, N. Y.
Mooney, Earl E., 845 Busti Ave., Buffalo, N. Y.
Moore, George W., 26 Culver Parkway, Rochester, N. Y.
Morey, Burrows, Apt. D–12, 703 W. Ferry St., Buffalo, N. Y.
Morgenroth, Fritz, c/o Mrs. S. Saphir, 1544 E. 17th St., Brooklyn, N. Y.
Mowbray, George A., 31 Hobart Ave., Port Chester, N. Y.
Mower, Stanley E., 923 University Blk., Syracuse, N. Y.
Mulcahy, James P., 49 Forest Row, Great Neck, N. Y.
Munding, Germaine G. (Miss), 51 Morton St., New York, N. Y.
Mundt, Charles H., 316 Grey St., Buffalo, N. Y.
Murphy, Reginald A., Willard, N. Y.
Nesbit, George H., 67 Adams St., East Rockaway, N. Y.
Nesin, Benj. C., 230 Hart St., Brooklyn, N. Y.
Netto, J. P. DeLemos, Caixa Postal 3244, Rio de Janeiro, Brazil, S. America.
Neves, Lourenco Baeta, Dr., Prof. da Universidade de Minas Ceraesm, Rua Claudio Manoel, 1185, Bello Horizonto, Minas Geraes, Brazil, S. America.
Nevitt, I. H., 1091 Eastern Ave., Toronto, Ont., Canada.
Newsom, Reeves, 500 5th Ave., New York, N. Y.
Nichols, Arthur E., 495 Van Cortland Park Ave., Yonkers, N. Y.
Nicholson, C. P., 93 Pierce Ave., Hamburg, N. Y.
Nielsen, A. F., 120 Broadway, New York, N. Y.
Nussbaumer, Newell L., 327 Franklin St., Buffalo, N. Y.
Nussberger, Fred., 44 14th Rd., Broad Channel, N. Y.
O'Brien, Earl F., 3613 Midland Ave., Syracuse, N. Y.
O'Brien, James E., 335–B New Scotland Ave., Albany, N. Y.
O'Connor, William F., Jr., 14 Bayley Ave., Yonkers, N. Y.
O'Dell, W. H., 30 W. Main St., Webster, N. Y.
Ogden, Henry N., 416 Hanshaw Rd., Ithaca, N. Y.
O'Hara, Franklin, 75 Stowe St., Lowville, N. Y.
Okun, Abraham H., 4 Lakewood Ave., Monticello, N. Y.
Okun, W. H., 125 Worth St., New York, N. Y.
O'Leary, William A., 2728 Hendrick Hudson Parkway, Apt. B–66, Bronx, N. Y.
Owen, Mark B., Hudson House, Ardsley-on-Hudson, N. Y.
Pardee Engineering Co., Inc., c/o Wallace & Tiernan, Newark, N. J.
Parker, Charles F., Box 93, North Windham, Me.
Patterson, Roy K., 61 Sprague Rd., Scarsdale, N. Y.
Paul, Lewis G., R. F. D. 3, Hamburg, N. Y.
Peck, Lawrence J., Box 387, Delmar, N. Y.
Pecker, Joseph S., 524–7 Victory Bldg., 1011 Chestnut St., Philadelphia, Pa.

Pennsylvania Salt Mfg. Co., Att.: Mr. F. G. Rodenburgh, 9 E. 41st St., New York, N. Y.
Perlstein, Edward, South Fallsburgh, N. Y.
Perrine, J. Franklin, Hunterspoint Ave., Borough Hall, Long Island, N. Y.
Perroni, Joseph, 183 Marine Ave., Brooklyn, N. Y.
Peterson, Earl L., P. O. Box 261, Nyack, N. Y.
Phelps, E. B., Prof., 630 W. 168th St., New York, N. Y.
Phelps, E. K., 322 Fairmount Rd., Ridgewood, N. J.
Phillips, H. N., 140 St. Andrews Lane, Glen Cove, N. Y.
Philion, W. I., 49 Elm St., Hudson Falls, N. Y.
Pineus, Sol, 225 W. 86th St., New York, N. Y.
Pinkey, Glenn E., 40 South Ave., Webster, N. Y.
Pitkin, Ward H., 70 Bay Drive Harbour, Green, Massapequa, N. Y.
Pittsburgh Equitable Meter, 607 Iroquois Bldg., Pittsburgh, Pa., Att.: C. F. Thomas.
Polakov, Nicholas N., N. Y. C. Dept. of Sanitation, 45 Lafayette St., Room 808, New York, N. Y.
Pollock, John M., 28 Amherst Rd., Port Washington, N. Y.
Porter, William, 55 Union St., Balston Spa, N. Y.
Potter, Alexander, 50 Church St., New York, N. Y.
Potts, Clyde, 30 Church St., New York, N. Y.
Powell, A. R., Dr., Koppers Research Corp., Koppers Bldg., Pittsburgh, Pa.
Powell, W. B., City Hall, Long Beach, N. Y.
Provost, Andrew J., Jr., Darien, Conn.
Purdie, David J., Room 904, 20 Vesey St., New York, N. Y.
Quaely, Martin F., Guggenheim Bros., 202nd St. & 10th Ave., New York, N. Y.
Quigley, T. T., 2422 E. 74th St., Chicago, Ill.
Raisch, William, 6945 Manse St., Forest Hills, N. Y.
Rath, Henry M., 27 Center Drive, Malba, Long Island, N. Y.
Reardon, Joseph F., Westside Ave., Garnersville, N. Y.
Reed, Paul H., 447 Clinton Ave., S., Rochester, N. Y.
Regelsen, Alfred E., 65 W. Sunrise Highway, Freeport, Long Island, N. Y.
Rehler, Joseph E., 111 Monroe Terrace, Olean, N. Y.
Reisch, Eugene A., 33 Kermit Ave., Buffalo, N. Y.
Reisert, Michael J., 488 Oakland Ave., Cedarhurst, Long Island, N. Y.
Requardt, G. J., Biddle & Charles Sts., Baltimore, Md.
Ribner, Morris, Mt. Prospect Lab., 355 Park Place, Brooklyn, N. Y.
Rice, Lawrence G., 908 College Ave., Niagara Falls, N. Y.
Rice, Lawrence H., 2161 Tiebout Ave., New York, N. Y.
Richter, Ernest W., 13 LeGrande Ave., Tarrytown, N. Y.
Rickard, Grover E., No. 11 City Hall, City Water Works, Burlington, Vt.
Riddick, Thomas M., 369 E. 149th St., New York, N. Y.
Riedel, John C., 505 Macon St., Brooklyn, N. Y.
Riley, Harley M., N. Y. State Health Dept., Rm. 709, Press Bldg., Binghamton, N. Y.
Riordan, J. T., 1091 210th St., Queens, Long Island, N. Y.
Robert, C. R., Dr., 524 W. 57th St., New York, N. Y.
Roberts, Jack, 515 Dorlands Ave., Toronto, Ont., Canada.
Robinson Clay Products Co., The, c/o A. T. Case, Empire State Bldg., New York, N. Y.
Robinson, George L., 4851 Grand Central Terminal, New York, N. Y.
Rocco, John, 20 Queen St., Freeport, N. Y.
Rock, Harold F., State Dept. of Health, 16 Dietz St., Oneonta, N. Y.
Rocker, Christian G., 202 Maple Ave., Rockville Centre, N. Y.
Roe, Frank C., Carborundum Company, c/o Porous Products & Lab. Ware Dept., Niagara Falls, N. Y.
Rogers, Allan H., 1110 Seventh St., Garden City, N. Y.
Rowan, Thomas C., Garnersville, N. Y.
Ryan, J. Samuel, 99 Olean St., Boliver, N. Y.
Ryan, Wm. A., 107 Ridge Rd., East Rochester, N. Y.
Ryon, Henry, State Dept. of Public Works, Albany, N. Y.
Saetre, Leif, Box 484, Great Neck, N. Y.
Sage, Howard D., 192 S. Main St., Mechanicville, N. Y.
Salle, Anthony, 81 Buffalo Ave., Long Beach, N. Y.
Salvato, Joseph, c/o N. Y. State Dept. of Health, 35 Market St., Poughkeepsie, N. Y.
Sammis, L. A., P. O. Box 96, East Northport, Long Island, N. Y.

Samson, Channel, 100 Midland Ave., Kenmore, N. Y.
Sanborn, J. F., 30 Church St., New York, N. Y.
Sanderson, Wallace W., 58 Glendale St., Albany, N. Y.
Santilli, Frank, 125 Worth St., Rm. 823, New York, N. Y.
Savage, Edward, 120 Broadway, New York, N. Y.
Saville, Thorndike, Dean, Box 65, New York University, University Heights, N. Y.
Schaefer, Edward J., 111–21 125th St., Ozone Park, N. Y.
Scheller, Geo. M., 26 Proctor Ave., Buffalo, N. Y.
Scherer, Paul, 718 E. 53rd St., Brooklyn, N. Y.
Schmidt, William F., 53 Pierce St., Concord, S. I., N. Y.
Schmuller, Frederick M., Rm. 823, 125 Worth St., New York, N. Y.
Schreiner, W. R., c/o Dr. Burke Diefendorf, 412 Rogers Bldg., Glens Falls, N. Y.
Schwartz, Louis, 396 E. 3rd St., Brooklyn, N. Y.
Scott, Rossiter S., 112 Park Ave., New York, N. Y.
Scott, Roy D., State Hospital, Central Islip, N. Y.
Scott, Walter M., 145 S. Third Ave., Mount Vernon, N. Y.
Scovill, John R., 138 Forest Ave., Pearl River, N. Y.
Scudder, Aubrey P., 80 Hamilton St., Rockville Centre, N. Y.
Searls, Glenn, Pine Grove Ave., Rochester, N. Y.
Seifert, William P., 77 Highview Ave., Tuckahoe, N. Y.
Semon, H. G., Sewage Disposal Plant, Tonawanda, N. Y.
Shapiro, Charles M., 4552 Bedford Ave., Brooklyn, N. Y.
Shapiro, Robert, 30–07 88th St., Jackson Heights, L. I., N. Y.
Sheppard, Frederick, 24 W. 40th St., New York, N. Y.
Sheridan, Thomas J., 200 C. Northern Blvd., Albany, N. Y.
Shockley, Homer, G., 7004 Colonial Rd., Brooklyn, N. Y.
Shurtleff, L. B., Supt. of Public Works, Liverpool, N. Y. (Deceased.)
Sibbald, Charles T. A., 111 Delaware Ave., Albany, N. Y.
Sickler, Archie, H., 52 Dellwood Rd., Eggertsville, N. Y.
Sigworth, E. A., 48 Minell Place, Teaneck, N. J.
Simon, Samuel S., 125 Worth St., Rm. 816, New York, N. Y.
Simplex Valve & Meter Co., 342 Madison Ave., New York, N. Y.
Simpson, R. W., 112 Culver Rd., Buffalo, N. Y.
Simson, Paul W., State Dept. of Health, 34 South St., Middletown, N. Y.
Skinner, J. F., 3333 W. 4th St., Los Angeles, Calif.
Slocum, Adelbert I., 515 Beach 68th St., Arverne, N. Y.
Slough, John, 117 Scott Ave., Wellsville, N. Y.
Smith, Benjamin L., Rm. 808, 11 N. Pearl St., Albany, N. Y.
Smith, E. A. Cappelen, 120 Broadway, New York, N. Y.
Smith, Edward J., 1112 Ferry Ave., Niagara Falls, N. Y.
Smith, Harold, 143 North Long Beach Rd., Rockville Centre, N. Y.
Smith, L. R., 4 Pine St., Canton, N. Y.
Smith, Walter R., 28 Harrison Ave., Kenmore, N. Y.
Snow, William J., State Engr., State Water Comm., State Office Bldg., Hartford, Conn.
Snyder, N. S., 995 Ellicott Square, Buffalo, N. Y.
Solomon, G. R., 257 Broadway, Troy, N. Y.
Solvay, Sales Corp., 40 Rector St., New York, N. Y. Att.: Mr. C. Grossman.
Soper, Romayne, 82 Cayuga St., Seneca Falls, N. Y.
Soreff, Joseph, 777 E. 175th St., Bronx, N. Y.
Sparr, A. E., 4825 40th St., Sunnyside, L. I., N. Y.
Speirs, George W., 115–91 223rd St., St. Albans, N. Y.
Spencer, Albert M., 38 Elm St., Hudson Falls, N. Y.
Spier, Daniel R., 1800 W. Colvin St., Syracuse, N. Y.
Splitt, Howard A., 325 Hawley St., Rochester, N. Y.
Spry, Fred J., Lincoln Hall, Cornell University, Ithaca, N. Y.
Stache, Paul, Box 339, Kings Park, L. I., N. Y.
Stalbird, James A., State Engr., Paul Smith Bldg., Saranac Lake, N. Y.
Stanley, Wm. E., Engr., School of Civ. Engr., Cornell University, Ithaca, N. Y.
Steffensen, S. W., 125 Worth St., Rm. 821, New York, N. Y.

Stepanek, Charles H. B., 506 E. 19th St., New York, N. Y.
Stepsis, John S., Central Islip State Hospital, Central Islip, L. I., N. Y.
Sterns, Edward A., 207 Long Ave., Hamburg, N. Y.
Stevenson, Albert H., c/o Malcolm Pirnie, 25 W. 43rd St., New York, N. Y.
Stilson, Alden E., 216 E. 45th St., New York, N. Y.
Stolz, Stanley B., State Dept. of Health, 34 South St., Middletown, N. Y.
Strait, Ernest C., 5 Brandreth St., Ossining, N. Y.
Straub, Conrad P., 806 E. Seneca St., Ithaca, N. Y.
Strong, Bruce F., 1111 Washington St., Olean, N. Y.
Strowbridge, John C., Supt. of Water & Sewers, Dundee, N. Y.
Stuart, Fred E., Activated Alum. Corp., Curtis Bay, Baltimore, Md.
Sullivan, Leroy E., Jr., 62 Gould Place, Caldwell, N. J.
Svenson, Sven H., 957 E. Ferry St., Buffalo, N. Y.
Swanz, Howard G., 29 Woodlawn Ave., Buffalo, N. Y.
Sweeney, R. C., 217 Lark St., Albany, N. Y.
Sweeney, Willard G., 2 Clare Rd., East Hempstead, N. Y.
Sylvester, William L., 336 Kenmore Rd., Douglaston, N. Y.
Symons, G. E., Bird Island Laboratory, Buffalo, N. Y.
Taggart, Robert S., 268 Guy Park Ave., Amsterdam, N. Y.
Tallamy, Bertram Dalley, 5488 Main St., Williamsville, N. Y.
Tapax Mfg Co., 201–03 Hoyt Ave., Mamaroneck, N. Y.
Tapman, Walter P., 76–12 35th Ave., Jackson Heights, L. I., N. Y.
Taylor, Henry W., 11 Park Place, New York, N. Y.
Taylor, Warren G., Prof., 38 Union Ave., Schenectady, N. Y.
Tentschert, Francis F., 570 Lexington Ave., c/o Dorr Company, New York, N. Y.
Terhoeven, G. E., 76 Navel Ave., Buffalo, N. Y.
Terwilliger, Frank, 15 Bedford Ave., Middletown, N. Y.
Tetzlaff, Frank, 181 Park Ave., Freeport, L. I., N. Y.
Thamasett, Otto E., J. N. Adams Memorial Hospital, Perrysburg, N. Y.
Thayer, Reginald H., 21 Morsemere Place, Yonkers, N. Y.
Thomas, Howard S., 25 Exchange St., Rochester, N. Y.
Thompson, M. H., State Health Dept., State Office Bldg., Albany, N. Y.
Thompson, Thomas C., 348 Baynes St., Buffalo, N. Y.
Thomson, F. N., Rm. 403, 18 Pearl St., Utica, N. Y.
Thomson, J. B. F., 322 Main St., Huntington, N. Y.
Timmers, Walter W., State Dept. of Public Works, State Office Bldg., Albany, N. Y.
Tolman, S. L., c/o Jeffrey Mfg. Co., Columbus, Ohio.
Tompkins, James, Albany Post Rd., Ossining, N. Y.
Torpey, Wilbur H., 2162 University Ave., Bronx, N. Y.
Torrey, William L., 28 Laurel St., Buffalo, N. Y.
Tove, William B., 990 President St., Buffalo, N. Y.
Trimble, Earle J., Municipal Bldg., Morgan St., Ilion, N. Y.
Trotti, Patrick J., 155 Depeyster St., North Tarrytown, N. Y.
Turbine Sewer Machine Sales Co., 109 Crosby St., New York, N. Y. Att.: Wm. Appleby.
Underpinning & Foundation Co., Inc., 155 E. 44th St., New York, N. Y.
Valerio, Paul F., 161 Shelter St., Rochester, N. Y.
Van Denburg, J. W., c/o Dept. of Public Works, 125 Worth St., New York, N. Y.
Vanderlip, Arthur N., Prof., Connecticut State College, Storrs, Conn.
Van Deusen, E. J., 21 Pearl St., Malone, N. Y.
Van Wyck, George W., 134 Main St., Nyack, N. Y.
Velz, C. J., 39 Tompkins Ave., Hastings-on-Hudson, N. Y.
Velzy, Charles R., 113 Covington Rd., Buffalo, N. Y.
VerDow, William H., 269 Murray St., Newark, N. Y.
Voigt, Richard C., 1060 Military Rd., Kenmore, N. Y.
Voorhis, Chester E., 253 Sunrise Highway, Rockville Centre, N. Y.
Vredenburg, Edward L., 20 Van Orden Ave., Spring Valley, N. Y.
Vrooman, Morrell, 21–23 N. Main St., Gloversville, N. Y.
Wagenhals, H. H., 411 Herald Bldg., Syracuse, N. Y.

Wagner, Edward P., 55 W. 42nd St., New York, N. Y.
Wailes Dove Hermiston Corp., 17 Battery Place, New York, N. Y. Att.: Mr. M. F. Abrams.
Wald, David, 41 Washington Ave., Brooklyn, N. Y.
Walker, Chas. L., 201 Fairmont Ave., Ithaca, N. Y.
Wannenwetsch, T. A., 414 Pleasant Ave., Hamburg, N. Y.
Ward, George C., 118 Depot Place, South Nyack, N. Y.
Warde, John S., 7 Whitewood Ave., West New Brighton, S. I., N. Y.
Wardle, J. McClure, Dept. of Public Works, Hudson, N. Y.
Ware, Howard, Union, N. Y.
Warren, George D., Cor. Broad & Church St., Lyons, N. Y.
Watkins, William W., 130 East St., Oneonta, N. Y.
Watson, Carl H., 19 Barstow Rd., Great Neck, N. Y.
Wechter, William H., 1436 Clay St., Bronx, N. Y.
Welsch, W. Frederick, 5 Fairway, Hempstead, N. Y.
Westcott, Arthur, Inst. for Male Defective Delinquents, Napanoch, N. Y.
Westergaard, Viggio, Dept. of Public Works, 125 Worth St., New York, N. Y.
Weston Company, L. A., Dean St., Adams, Mass.
Wetherell, Joseph H., Electro Bleaching Gas Co., 60 E. 42nd St., New York, N. Y.
Wheeler, Robert C., 36 State St., Albany, N. Y.
Whitley, F. H., New York University, University Heights, N. Y.
Wigley, Chester G., Shelton Hotel, 49th & Lexington Ave., New York, N. Y.
Willcomb, George E., 12 S. Lyons Ave., Menands, N. Y.
Williams, R. L., c/o Guggenheim Bros. Lab., 202nd St., & 10th Ave., New York, N. Y.
Wilson, C. R., 150 Ludington St., Syracuse, N. Y.
Wilson, John A., Jr., Highwood Ave., Tenafly, N. J.
Wing, F. K., City Engr., Rm. 501 City Hall, Buffalo, N. Y.
Winne, Geo., 144 Maple Ave., Altamont, N. Y.
Winslow, George W., 61 Keene Ave., Floral Park, N. Y.
Woelfle, Arthur H., 758 Main St., Dunkirk, N. Y.
Woese, Carl F., 1001 Burnet Ave., Syracuse, N. Y.
Wood, Herbert M., 117 W. Sunrise Highway, Freeport, N. Y.
Woodhull, Charles R., 37 North St., Newburg, N. Y.
Worthington Pump & Mach. Corp., Sewer Dept., Harrison, N. J. Att.: Mr. H. J. Meeker, Mgr.
Wright, Chilton A., 99 Livingston St., Brooklyn, N. Y.
Wyckoff, Charles R., 285 Riverside Drive, New York, N. Y.
Yatteau, George A., 1000 Winton Rd. N., Rochester, N. Y.
Young, W. W., P. O. Box 8 White Plains, N. Y. (Deceased.)
Youngs, Benjamin K., 112 Wardman Rd., Kenmore, N. Y.
Zack, Samuel I., c/o Filtration Equipment Corp., 10 E. 40th St., New York City.
Zeigler, Frederick C., 95 Stratford Ave., White Plains, N. Y.
Zeitler, Braman E., 32 Church St., Pittsford, N. Y.
Zieres, Floyd B., Roscoe, N. Y.
Zollner, Frederick D., 35 State St., Batavia, N. Y.
Zuppinger, William, Blasdell, N. Y.

North Carolina Sewage Works Association

Mr. R. S. Phillips, *Secretary-Treasurer*, P.O. Box 1170, Durham, North Carolina.

Abell, D. S., Asst. Engr., N. C. State Board of Health, Raleigh, N. C.
Andrews, John, Asst. Engr., Div. of Sanitary Engineering, State Board of Health, Raleigh, N. C.
Bain, Ernest B., 120 New Bern Ave., Raleigh, N. C.
Baity, H. G., Prof. of Eng., University of North Carolina, Chapel Hill, N. C.
Booker, Warren, H., Director, Div. of Sanitary Engr., State Board of Health, Raleigh, N. C.
Brannock, Mr. D. York, Chem. Engr., Water Wks. & Sewage Disposal Plant, 315 Vance St., Laurinburg, N. C.
Briggs, O. L., Sr., Supt. of Water, Waynesville, N. C.

Brown, John L., Jr., Supt., Cannon Mills Company, Box 242, Concord, N. C.
Bunker, Mr. F. L., P. O. Box 1122, Charlotte, N. C.
Burchard, E. D., Dist. Engr., U. S. Geological Survey, 220 P. O. Bldg., Asheville, N. C.
City Water Dept., Mr. F. G. Doggett, Supt., Mt. Airy, N. C.
Clapp, Milton, Jr., Chemist, 3737 Selwyn Ave., Charlotte, N. C.
Davis, H. F., District Mgr., 1902 Pinewood Circle, Charlotte, N. C.
Davis, P. D., Assoc. Engr., W. M. Piatt, Constr. Engr., Durham, N. C.
Dickson, W. K., Civil Engr., 119 Circle Ave., Charlotte, N. C.
Doane, Norman D., 831 E. Morehead St., Charlotte, N. C.
Durham Water Dept., D. McGregor Williams, Durham, N. C.
Ebert, R. E., Chemist, Water Dept., 1368 E. Sprague St., Winston-Salem, N. C.
Ecusta Paper Corp., Mr. Herbert F. Finck, Hydraulic Engr., Pisgah Forest, N. C.
English, Jas. A., City Engr. & Supt., Water Works, Salisbury, N. C.
Evans, Wm. J., Filter Plant Oprtr., Box 819, Oxford, N. C.
Franklin, W. M., Box 3162, Dilworth Sta., Charlotte, N. C.
Frisk, Paul W., Chemical Engr., 920 Haywood Rd., Asheville, N. C.
Gotaas, Harold B., Assoc. Prof., Sanitary Engineering, Univ. of North Carolina, Chapel Hill, N. C.
Grady, Robert H., Research Fellow, North Carolina State College, Colonial Rd., Raleigh, N. C.
Greenlee, J. L., Asst. Supt., Municipal Water Dept., Charlotte, N. C.
Gregory, Robert W., Foreman of Filter Plant, Proximity Print Wks., 19 Upland Drive, Greensboro, N. C.
Grinnell Company, Inc., S. O. Thorne, Branch Mgr., P. O. Box 2229, Charlotte, N. C.
Hall, W. H., Engineering Dept., Duke University, College Station, Durham, N. C.
Haywood, R. W., Jr., 748 Public Ledger Bldg., Philadelphia, Pa.
Henderlite, J. H., City Chemist, Gastonia, N. C.
Heyward, T. C., Mech. & Elec. Engr., 1408 Independent Bldg., Charlotte, N. C.
Jarrett, J. M., State Board of Health, Raleigh, N. C.
Johnson, F. M., c/o District Health Dept., Box 154, Murphy, N. C.
Kearney, E. W., State Board of Health, Morganton, N. C.
Kellogg, James W., Bact. & Chemist, State Lab. of Hygiene, Raleigh, N. C.
King, William B., Water Plant Opr., Water & Sewage Dept., City Hall, Oxford, N. C.
Lassiter, L. I., San. Engr., Consolidated Bd. of Health, Wilmington, N. C.
LeClere, Arthur B., Sales Engr., T. C. Heywood, 1408 Independent Bldg., Charlotte, N. C.
Lesslie, Mr. John N., Jr., Chemist, Water Department, Salisbury, N. C.
Lubow, Louis A., Chemist, Water Dept., 1021 N. Gregson St., Durham, N. C.
Luther, Robert W., Plant Supt., Public Utility Commission, Box 56, Elizabeth City, N. C.
Lyon, A. S., Supt., Public Works, Rocky Mount, N. C.
Malone, J. R., Chemist, Durham Water Dept., 1312 N. Gregson St., Durham, N. C.
Marshall Field Co., Leaksville, N. C.
Mengel, C. W., Director, Public Works & Service, City Hall, Greensboro, N. C.
Merritt, Will D., Supt., Water Dept. & City Engr., Mount Airy, N. C.
Moggio, Wm. A., Div. of Public Health, Univ. of North Carolina, Chapel Hill, N. C.
Moore, Geo. S., Supt., Water & Light Dept., Albemarle, N. C.
Nance, E. L., Erwin Creek Plant, Charlotte, N. C.
Olsen, W. C., Cons. Engr., Raleigh, N. C.
Parker, J. C., Supt., Public Utility Comm., Main & Martin Sts., Elizabeth City, N. C.
Parks, W. J., Jr., Supt., Water Sheds, Asheville, Swannanoa, N. C.
Peirson, Nat. D., Cons. Engr., Peirson & Whitman, Security Bank Bldg., Raleigh, N. C.
Perkins, J. L., High Point, N. C.
Phillips, R. S., Water Dept., P. O. Box 1170, Durham, N. C.
Piatt, Wm. M., Consulting Engr., Durham, N. C.
Pollock, John M., Supt., Sewage Treatment, Spindale, N. C.
Purser, John R., Jr., Treas., J. R. Purser Sales Eng. Inc., Suite 816, Independence Bldg., Charlotte, N. C.
Randall, C. C., Supt., Lincolnton Water Dept., Lincolnton, N. C.
Redding, Harry P., Engr., Durham Water Dept., Durham, N. C.
Rhyne, C. E., Supt., Water Works, Gastonia, N. C.

Rice, Palmer J., Filter Plant Opr., Water Dept., 2401 Chapel Hill Rd., Durham, N. C.
Robinson, T. C., Supt., Light & Water Dept., Granite Falls, N. C.
Seaman, Henry, Champion Fibre Co., Canton, N. C.
Smedberg, C. W., 315 Woodbine St., Greensboro, N. C.
Smith, Waymon, Water Works Supt., Marshall Field Co., Leaksville, N. C.
Spence, W. O., Supt. of Filtration, Sanford, N. C.
Starling, Charles H., Sales Engr., International Filter Co., 417 Fenton Place, Charlotte, N. C.
Swartz, Martin, Supt., Water & Light Comm., Greenville, N. C.
Thomas, R. Allen, Commissioner, Public Works, City Hall, Winston-Salem, N. C.
Thomas, E. R., Supt., Municipal Water Dept., Burlington, N. C.
Thompson, H. E., Supt. of Filtration, Univ. of North Carolina, Chapel Hill, N. C.
Tull, E. R., Supt., Municipal Water Plant, Rockingham, N. C.
Van Camp, P. M., Civil Engr., Southern Pines, N. C.
Vest, W. E., Supt., Water Works, Charlotte, N. C.
Warrenton Water Co., Harold R. Skillman, Supt., Warrenton, N. C.
Williams, C. B., Supt., Water & Light Dept., Lexington, N. C.
Williams, Macon W., Lenoir, N. C.
Wooten, M. Frank, Jr., Cons. Engr., 1004 Latta Arcade, Charlotte, N. C.
Yow, W. E., Supt., Water Department, Asheboro, N. C.

Ohio Sewage Works Conference Group

Frank W. Jones, *Secretary-Treasurer*, 1140 Leader Bldg., Cleveland, Ohio.

Allton, Robert A., City Hall, Columbus, Ohio.
Avery, J. W., 5812 Nicholas St., Omaha, Nebr.
Backherms, A. B., 3438 Sherel Circle, Cincinnati, Ohio.
Backherms, Louis E., 4301 Schwallie Ave., Bridgetown, Cincinnati, Ohio.
Barnes, George E., Prof., Case School of Applied Science, Cleveland, Ohio.
Barnes, L. B., 127 Meeker St., Bowling Green, Ohio.
Barstow, E. D., Barstow & LeFeber, Inc., 31 N. Summit St., Akron, Ohio.
Barton, Ben H., 207 Locust St., Findlay, Ohio.
Bartow, Leslie W., 2420 Homestead Place, Cincinnati, Ohio.
Bahnke, Geo. C., 400 E. College St., Oberlin, Ohio.
Blanchard, H. E., c/o A. H. Fretter, 603 S. Broadway, Medina, Ohio.
Blosser, D. S., Columbus Grove, Ohio.
Bradshaw, W. L., San. Engineering Div., The Jeffrey Mfg. Co., Columbus, Ohio.
Britt, C. E., 505 S. Maple St., Bowling Green, Ohio.
Broestl, Andrew J., 1140 Leader Bldg., Cleveland, Ohio.
Browne, Floyd G., Box 134, Marion, Ohio.
Bryant, C. T., Supt., Sewage Treatment Works, Pleasant & Dayton Aves., Springfield, Ohio.
Budd, Chester B., Southerly Sewage Treatment Wks., R. F. D. 3, Brooklyn Station, Cleveland, Ohio.
Burger, A. A., Engr., 3306 Elsmere Rd., Shaker Heights, Cleveland, Ohio.
Calkins, Lyle W., Chemist, Sewage Treatment Works, Bay View Park, Toledo, Ohio.
Cameron, A. B., 811 Oakridge Drive, Jackson, Mich.
Case School of Applied Science, Att.: Prof. George E. Barnes, Dept. of Civil Engineering, Euclid Ave., Opp. Wade Park, Cleveland, Ohio.
Clover, I. N., 28 Byers Ave., Akron, Ohio.
Collier, James R., 217 Harwood St., Elyria, Ohio.
Craum, J. M., 355 Hippodrome Annex, Cleveland, Ohio.
Critser, W. H., 6609 8th St., N. W., Washington, D. C.
Cummins, Walter, 2021 Mason St., Toledo, Ohio.
Dixon, G. Gale, Rm. 242, Chestnut St. Pier, Philadelphia, Pa.
Duerr, A., 110 Willow St., Liverpool, N. Y.
Ellms, J. W., 1310 W. 112th St., Cleveland, Ohio.
English, C. C., Banes, Cuba.
Fisher, F. P., Wallace & Tiernan Co., 811 Perry-Payne Bldg., Cleveland, Ohio.
Flower, G. E., 4720 W. 15th St., Cleveland, Ohio.
Ford, Curry E., c/o National Carbon Co., Madison Ave. & W. 117th St., Cleveland, Ohio.

Frick, Edward J., 10409 Fortune Ave., Cleveland, Ohio.
Gerdel, W. C., Westerly Sewage Treatment Works, Bulkley Blvd. at W. 58th St., Cleveland, Ohio.
Gray, D. M., Louisville Cement Co., Louisville, Ky.
Growdon, Howard C., 915 30th St., Portmouth, Ohio.
Hagerty, L. T., Sewage Disposal Plant, Bedford, Ohio.
Hall, G. Albro, 130 Northridge Rd., Columbus, Ohio.
Harris, C. H., Sewage Treatment Works, Massillon, Ohio.
Harroun, F. E., 711 Chitty Ave., Akron, Ohio.
Hatch, B. F., Burgess & Niple, 568 E. Broad St., Columbus, Ohio.
Hauck, Charles F., 10816 Clifton Blvd., Cleveland, Ohio.
Havens, William L., 1140 Leader Bldg., Cleveland, Ohio.
Heffelfinger, D. D., 498 W. High St., Alliance, Ohio.
Hoover, C. B., 252 E. 17th Ave., Columbus, Ohio.
Houser, C. S., 165 S. Paint St., Chillicothe, Ohio.
Jones, Frank Woodbury, 1140 Leader Bldg., Cleveland, Ohio.
Kimberly, A. E., 20 S. Third St., Columbus, Ohio.
Kline, H. S., 35 Valley View Drive, Dayton, Ohio.
Klingbeil, Ray J., 1494 Union Ave., Columbus, Ohio.
Knox, W. H., Asst. Engr., State Dept. of Health, Pure Oil Bldg., Columbus, Ohio.
Krunich, M. D., Sewage Treatment Works, R.F.D. 7, Akron, Ohio.
Leach, Walter L., 1140 Leader Bldg., Cleveland, Ohio.
Leist, Ervin F., Seyfert Ave., Circleville, Ohio.
Lesher, Carl E., Jr., 18 Wilson Drive, Ben Avon Heights, Pittsburgh, Pa.
Lower, J. R., Chemist in charge, Bucyrus Water Works, Bucyrus, Ohio.
MacDowell, R. F., 401 Chester-Twelfth Bldg., Cleveland, Ohio.
MacLachlen, Angus, 1740 E. 12th St., Cleveland, Ohio.
McDill, Bruce M., State Dept. of Health, Pure Oil Bldg., Columbus, Ohio.
McGuire, C. D., 448 Clinton St., Columbus, Ohio.
McIntyre, Frank J., 144 E. Lakeview Ave., Columbus, Ohio.
McNeal, Leonard, Sewage Treatment Plant, London, Ohio.
Mock, Alvin M., 1140 Leader Bldg., Cleveland, Ohio.
Monroe, S. G., Stream Pollution Investigation, 3rd & Kilgour Sts., Cincinnati, Ohio.
Morehouse, W. W., Director, Water Dept., 308 U. B. Annex, Dayton, Ohio.
Moseley, Harry H., 1140 Leader Bldg., Cleveland, Ohio.
Nagel, W. B., 847 Catalpa Drive, Dayton, Ohio.
Nelson, Frederick G., 221 N. LaSalle St., Chicago, Ill.
Niles, A. H., Supt., Sewage Treatment Works, Bay View Park, Toledo, Ohio.
O'Flaherty, Dr. Fred., Director, Dept. of Leather Research, University of Cincinnati, Cincinnati, Ohio.
Palocsay, Frank S., 8108 Clark Ave., Cleveland, Ohio.
Pease, Maxfield, 4614 Prospect Ave., Cleveland, Ohio.
Pettit, Charles, 665 Wooster Rd., W., Barberton, Ohio.
Regester, Robert T., 401 Gittings Ave., Cedarcroft, Baltimore, Md.
Roth, R. F., Municipal Bldg., Oxford, Ohio.
Ruck, Franklin, Engr., Water Softener & Sewage Disposal Plants, R. R. 3, Troy, Ohio.
Rupp, Daniel H., Water Dept., City Hall, Topeka, Kans.
Schade, Willard F., Havens & Emerson, Leader Bldg., Cleveland, Ohio.
Schaetzle, T. C., 502 Municipal Bldg., Akron, Ohio.
Scott, R. D., Chief Chemist, Division of Labs., State Dept. of Health, Columbus, Ohio.
Sheets, W. D., 240 Binns Blvd., Columbus, Ohio.
Shick, V. R., Chief Opr., Van Wert Sewage Treatment Plant, 1053 W. Main St., Van Wert, Ohio.
Smigel, Walter A., 16612 Invermere, Cleveland, Ohio.
Smiley, Paul E., 324 Pointview Ave., Dayton, Ohio.
Smith Company, A. H., The, 2140 Ashland Ave., Rm. 206, Toledo, Ohio.
Smith, E. E., Supt., Water & Sewage, Lima, Ohio.
Snyder, R. F., City Hall, Massillon, Ohio.
Stewart, F. D., Prin. Asst. Engr., State Dept. of Health, Pure Oil Bldg., Columbus, Ohio.
Swanker, R. L., 12065 Edgewater Drive 21, Cleveland, Ohio.

Sweeney, R. C., Dist. San. Engr., Division of Sanitation, State Dept. of Albany, Albany, N. Y.

Tatlock, M. W., 2600 Salem Ave., Dayton, Ohio.

Taylor, Frank S., City Hall, Defiance, Ohio.

Tenenbaum, Meyer, Westerly Sewage Treatment Wks., Bulkley Blvd. at W. 58th St., Cleveland, Ohio.

Tolles, Frank C., 1140 Leader Bldg., Cleveland, Ohio.

Turner, J. R., Sewage Disposal Plant, Mansfield, Ohio.

Wahmhoff, John J., Supt., Sewage Treatment Works, 427 E. Harmon St., Delphos, Ohio.

Walker, C. C., 1826 W. 1st Ave., Columbus, Ohio.

Waring, F. H., Chief Engr., State Health Dept., c/o Pure Oil Bldg., Columbus, Ohio.

Wenger, J. H., 83 N. Broadway, Westerville, Ohio.

Whirl, William H., 1406 Eastview Ave., Columbus, Ohio.

Williams, P. A., 1101 Brown St., Akron, Ohio.

Willis, Robert E., 411 N. North St., Washington, C. H., Ohio.

Wirts, J. J., Easterly Sewage Treatment Works, 14101 Lake Shore Drive, Cleveland, Ohio.

Young, F. D., 1140 Leader Bldg., Cleveland, Ohio.

Oklahoma Water and Sewage Conference

H. J. Darcey, *Secretary-Treasurer*, Oklahoma City, Okla. State Health Dept.

Stapley, Edward R., 27 College Circle, Stillwater, Okla.

Pacific Northwest Sewage Works Association

Fred Merryfield, *Secretary-Treasurer*, Civil Engineering Dept., Oregon State College, Corvallis, Oregon.

Bamford, J. H., Water Supt., Dayton, Wash.

Barney, J. W., City Mgr., Hillsboro, Ore.

Barthlow, C. L., Supt., Water & Sewer, Zillah, Wash.

Blezard, J., Water Supt., Kimberley, British Columbia, Can.

Bow, Wilson F., San. Engr., Court House, Bellingham, Wash.

Briggs, Raymond J., Cons. Engr., 210 Noble Bldg., Boise, Idaho.

Butler, A. D., City Engr., Spokane, Wash.

Campbell, Maxwellton S., 1412 Smith Tower, Seattle, Wash.

Carter, Isaac Newton, Prof. School of Engineering, Univ. of Idaho, Moscow, Idaho. (Deceased.)

Charlton, David, Dr., 2340 S.W. Jefferson St., Portland, Ore.

Chase, H. W., Water Supt., Colfax, Wash.

Clare, H. C., c/o State Div. Public Health, State Chemist's Office, Boise, Idaho.

Cloyes, W. J., Lane County Health Dept., Court House, Eugene, Ore.

Clubb, William C., City Engr., Eugene, Ore.

Corey, R. H., Cons. Engr., 909 Bedell Bldg., Portland, Ore.

Culp, King, San. Engr., Wenatchee, Wash.

Cunningham, John W., Spalding Bldg., Portland, Ore.

Davis, J. H., City Engr., Salem, Ore.

Early, Mart, Water Supt., Moscow, Idaho.

Eriksen, Arne, Chemist, State Pollution Commission, Gig Harbor, Wash.

Everts, C. M., Jr., 816 Oregon Bldg., Portland, Ore.

Forsbeck, C. D., City Engr., Dept. of Public Works, Tacoma, Wash.

Gearhart, John C., c/o Stevens & Koon, 1203 Spalding Bldg., Portland, Ore.

Gilman, N. A., Water Supt., Yakima, Wash.

Gooch, E. W., City Engr., Bellingham, Wash.

Green, Carl E., 816 Oregon Bldg., Portland, Ore.

Hall, Claude, Asst. Supt. of Utilities, 703 E. 3rd St., Ellensburg, Wash.

Hall, G. D., 416 A. E. Larson Bldg., Yakima, Wash.

Hamilton, R. F., 116 Engineers Camp Murray, Fort Lewis, Wash.

Harris, Roy M., 1412 Smith Tower, Seattle, Wash.

Harrison, Bert, Harrison Pipe Co., 3615 E. B St., Tacoma, Wash.

Heiss, Edward, District Engr., Wallace & Tiernan Sales Corp., 917 Terminal Sales Bldg., Seattle, Wash.

Hill, W. R., Parker & Hill, 2021 Smith Tower, Seattle, Wash.
Hockley, C. P., Cons. Engr., Guardian Bldg., Portland, Ore.
Holter, A. L., Assoc. Engr., County City Bldg., Seattle, Wash.
Howard, C. M., Concrete Pipe Mfrs. Assoc., 92 Nickerson St., Seattle, Wash.
Hoydar, A. L., Water & Sewer Dept., Selah, Wash.
Hughes, W. P., City Water Supt., Lewiston, Idaho.
Irwin, G. M., City Engr. & Water Commissioner, City Engineers Office, Victoria, British Columbia, Can.
Jackson, T. B., Pres. & Gen. Mgr., Boise Water Corp., 623 Idaho St., Boise, Idaho.
Jensen, Emil C., San. Engr., City County Health Dept., Yakima, Wash.
Knittel, E. A., Water & Sewage Supt., Lynden, Wash.
Koon, Ray E., Spalding Bldg., Portland, Ore.
Kretschmar, Dr. G. G., Walla Walla College, College Place, Wash.
Leonard, W. V., State San. Engr., Div. of Public Health, Boise, Idaho.
Lovejoy, W. L., City Engr. and Water Supt., Hoquiam, Wash.
McCleary, E. L., Supt., Silverton Water Commission, Silverton, Ore.
McGuire, M. H., General Mgr., Water & Light Dept., McMinnville, Ore.
McLean, R. F., Supt., Water Dept., Walla Walla, Wash.
McNamara, W. P., Engr. City Eng'g. Dept., 402 County City Bldg., Seattle, Wash.
MacIntire, Kenneth, Yakina Farm Labor Camp, P. O. Box 1312, Yakima, Wash.
Malony, W. L., 414 Symons Bldg., Spokane, Wash.
Mathews, Frank E., P. O. Box 487, Ellenburg, Wash.
Merryfield, Fred, Civil Eng'g. Dept., Oregon State College, Corvallis, Ore.
Morrow, Ben., Engr. & General Mgr., Bureau of Water Works, Portland, Ore.
Nasi, Kaarlo, San. Engr., Territorial Dept. of Health, Juneau, Alaska.
Nelson, Ben C., City Mgr., Pullman, Wash.
Nichols, V. R., Water Supt., Wapato, Wash.
Nolte, Fred W., San. Inspector, Water Dept., City Hall, Bellingham, Wash.
Pierron, Wm., Sr., San Inspector, City Hall, Bellingham, Wash.
Seufer, Paul E., Asst. Public Health Engr., State Dept. of Health, Smith Tower, Seattle, Wash.
Shera, Bryan, Engr., Penna. Salt Mfg. Co., Tacoma, Wash.
Shirley, Donald L., Mgr., Link Belt Company, 1637 N. W. 14th Ave., Portland, Ore.
Signor, C. V., City Engr., Grants Pass, Ore.
Small, R. L., Sanitarian, 420 East A. St., Moscow, Idaho.
Smith, B. G., City Engr., Camas, Wash.
Smith, C. H., Sewer Engr., City Hall, Portland, Ore.
Smith, Harvey J., City Engr., Moscow, Idaho.
Smith, Wendell H., City Engr., St. Anthony, Idaho.
Snyder, Prof. M. K., Civil Engineering Dept., Washington State College, Pullman, Wash.
Stockman, L. R., Cons. Engr., Box 635, Baker, Ore.
Sylliassen, M. O., 986 Dexter-Horton Bldg., Seattle, Wash.
Sylvester, Robert O., San. Engr., Cowlitz County Health Dept., Courthouse, Kelso, Wash.
Turner, E. S., W. S. Turner & Co., Pacific Bldg., Portland, Ore.
Tyler, R. G., Prof., Dept. of Civil Engineering, University of Washington, Seattle, Wash.
Van Horn, R. B., Prof., Exec. Head, Dept. of Civil Engineering, Univ. of Washington, Seattle, Wash.
Vognild, R. O., Hooker Electro-Chemical Co., Tacoma, Wash.
Ward, Paul, Asst. State San. Engr., Division of Public Health, Boise, Idaho.
Williams, Chas. H., City Engr., Olympia, Wash.
Wilson, Thomas M., Sanitarian, Public Health Dept., Klickitat Co., Goldendale, Wash.

Pennsylvania Sewage Works Association

Bernard S. Bush, *Secretary-Treasurer*, Pa. Dept. of Health, Kirby Health Center, Wilkes-Barre, Pa.

Alexander, J. D., City Councilman, City Bldg., New Castle, Pa.
Allison, T. H., Plumber, Tresslers Orphans Home, Loysville, Pa.
Anderson, W. R., Borough Supt., 228 Market St., New Wilmington, Pa.
Armstrong, Paul A., Chemist, Pa. Sanitary Water Bd., 824 Porter St., Easton, Pa.

Bailey, S. C., Danville State Hospital, Danville, Pa.

Bainbridge, David W., 208 Yeakel Ave., Chestnut Hill, Philadelphia, Pa.

Barrick, M. J., Dist. Engr., Dept. of Health, 28 E. 3rd St., Williamsport, Pa.

Baum, H. J., City Engr., 3205 Broad Ave., Altoona, Pa.

Beckett, R. C., State San. Engr., State Board of Health, Dover, Del.

Boardman, John, San. & Hydr. Engr., 426 Walnut St., Philadelphia, Pa.

Boardman, Wm. Hunter, Jr., Civil, Hyd. & San. Engr., 426 Walnut St., Philadelphia, Pa.

Bogardus, Theodore S., Asst. City Engr., Meadville, Pa.

Bolenius, Robert M., Chemist, 115 N. Franklin St., Lancaster, Pa.

Boone, George H., Chief Opr., Sewage Treatment Plant, 713 Church St., Norristown, Pa.

Brown, Dr. Glenn V., 312 E. Main St., Mechanicsburg, Pa.

Brumbaugh, W. Vernon, National Lime Assn., 927 15th St., N. W., Washington, D. C.

Buck Hill Falls Co., Att.: Elliot Wells, Rep., Buck Hill Falls, Pa.

Burnside, Lewis E., City Engr., Sharon, Pa.

Bush, Bernard S., Asst. Engr., Pa. Dept. of Health, Kirby Health Center, Wilkes-Barre, Pa.

Campbell, John, Cons. Engr., The Chester Engineers, 210 E. Parkway, Pittsburgh, Pa.

Carpenter, J. D., Civil Engr., 600 N. 2nd St., Harrisburg, Pa.

Carpenter, Lewis V., New York University, University Heights, Box 106, New York, N. Y. (Deceased.)

Chambersburg, Boro of, J. Hase Mowrey, Rep. Public Utilities, Chambersburg, Pa.

Chase, Sherman E., Metcalf & Eddy, Statler Bldg., Boston, Mass.

Cleland, R. R., 222 Hartswick Ave., State College, Pa.

Clouser, L. H., Tenn. Valley Authority, Rm. 615, Union Bldg., Knoxville, Tenn.

Colitz, Michael J., Ass. San. Engr., Kirby Health Center, Wilkes-Barre, Pa.

Copple, Isaac, Opr., Providence Rd., Media, Pa.

Craig, Robert H., Cons. Engr., Chamber of Commerce Bldg., Harrisburg, Pa.

Cunningham, H. L., Allentown State Hospital, Allentown, Pa.

Daniels, F. E., 2115 N. 2nd St., Harrisburg, Pa.

Darby, W. A., The Dorr Co., 570 Lexington Ave., New York, N. Y.

Davis, E. Watson, Asst. Civil Engr., Rm. 506, S. Office Bldg., Harrisburg, Pa.

Dawson, Lafayette Wm., Borough of Jersey Shore, 1102 Locust St., Jersey Shore, P. O. Box 303, Pa.

Dawson, Thomas T., Harwood Beebe Co., Montgomery Bldg., Spartansburg, S. C.

Dechant & Sons, W. H., F. H. Dechant, Rep., 632 Washington St., Reading, Pa.

Dept. of Streets & Public Imp., South Sewage Treatment Wks., Lancaster, Pa.

Diefendorf, Fred G., Supt., 346 W. 8th St., Erie, Pa.

Douglas, R. M., Civil Engr., 912 Columbia Bank Bldg., Pittsburgh, Pa.

Eastburn, W. H., Rep., The Mathieson Alkali Wks., Inc., Widener Bldg., Philadelphia, Pa.

Edgerley, Edward, 343 N. West End Ave., Lancaster, Pa.

Emerson, C. A., Havens & Emerson, Woolworth Bldg., New York, N. Y.

Emigh, William C., Coatesville, Pa.

Eppley, Robert G., 722 Lehigh Ave., Lancaster, Pa.

Evans, David A., San. Disposal Engr., c/o P. O. Box 862, Reading, Pa.

Faber, Harry A., San. Engr., Chlorine Institute, 50 E. 41st St., New York, N. Y.

Fales, Almon L., Metcalf & Eddy, Statler Bldg., Boston, Mass.

Flanagan, Joseph E., Jr., Ass. San. Engineer, U. S. Public Health Service, 418 Oakland Ave., Greensburg, Pa.

Fleming, M. C., Engr., Hardinge Company, Inc., York, Pa.

Freeburn, H. M., Chief Engr., Phila. Suburban Water Co., 1251 Montgomery Ave., Wynnewood, Pa.

Freund, J. P., Vice-Pres. & Plant Engr., Wyomissing Valley Disposal Co., P. O. Box 940, Reading, Pa.

Friel, F. S., Albright & Friel, 1520 Locust St., Philadelphia, Pa.

Foster, Norman, Cons. Engr., Damon & Foster, Chester Pike & High St., Sharon Hill, Pa.

Gascoigne, Geo. B., 1140 Leader Bldg., Cleveland, Ohio. (Deceased.)

Gidley, H. K., c/o State Health Dept., Charleston, W. Va.

Gilbert, J. J., San. Engr., 201 Wheatsheaf Lane, Abington, Pa.

Gill, Paul, 725 Chestnut St., Indiana, Pa.

Glace, I. M., 22 S. 22nd St., Harrisburg, Pa.

Glace, I. M., Jr., Asst. Engr., I. M. Glace & Assoc., 22 S. 22nd St., Harrisburg, Pa.
Goff, William A., Cunard Bldg., Philadelphia, Pa.
Gorman, William A., Pa. Dept. of Health, Harrisburg, Pa.
Grabowski, John J., 18 N. 4th St., Sharpsburg, Pa.
Grace, C. F., Polk State School, Polk, Pa.
Grossart, I. J. H., 816 Chew St., Allentown, Pa.
Gulden, H. B., Borough Engr., State College, Pa.
Gwin, Lewis L., Reg. Prof. Eng., 106 Aldrich Ave., Llyswen, Altoona, Pa.
Haddock, Fred R., Chief Engr., Roberts Filter Mfg. Co., Darby, Pa.
Hart, W. B., Supt., Gas, Acid & Drainage Dept., 602 Manor Rd., Penfield, Upper Darby, Pa.
Hartzell, E. F., Supt., Palmerton Disposal Co., Palmerton, Pa.
Harvey, J. R., Pa. Dept. of Health, 609 Trust Bldg., Meadville, Pa.
Haseltine, T. R., 2310 "B" Street, Bakersfield, Calif.
Haworth, J. Victor, Boro Sec., Moylan, Rose Valley, Pa.
Haydock, Chas., Cons. Engr., 311 Commercial Trust Bldg., Philadelphia, Pa.
Hedgepeth, L. L., Research Chemist, Pa. Salt Mfg. Co., 1000 Widener Bldg., Philadelphia, Pa.
Herr, H. N., 114 Java Ave., Hershey, Pa.
Hess, Joseph C., Jr., Chairman, Sewer Com., Ambler Boro Council, 412 Tennis Ave., Ambler, Pa.
Hewitt, A. C., Chief Engr., American Lime & Stone Co., Bellefonte, Pa.
Hibschman, Charles A., Supt., Ambler Borough, Ambler, Pa.
Hilborn, Gerald, Supt., Sewage Disposal Plant, 233 Bridge St., Spring City, Pa.
Hill, Theo. C., Hill & Hill, Engrs., North East, Pa.
Hoak, Richard D., Mellon Institute of Industrial Research, Pittsburgh, Pa.
Hodge, W. W., Head, Dept. of Chemical Engineering, West Virginia University, Morgantown, W. Va.
Hoeflich, G. C., 619 Saude Ave., Essington, Pa.
Hoff, Clarence W., Asst. Supt. of San. Drainage, Lower Merion Township, 75 E. Lancaster Ave., Ardmore, Pa.
Hoffert, J. R., Pa. Dept. of Health, Harrisburg, Pa.
Hynes, H. A., Supt., Disposal Plant, 414 E. 19th St., Chester, Pa.
Imbt, M. Russell, Sales Engr., Stroudsburg Septic Tank Co., 312 Main St., Stroudsburg, Pa.
Jenne, Lyle L., Cons. Engr., 819 City Hall Annex, Philadelphia, Pa.
Johnson, Earle P., Flannery Bldg., Pittsburgh, 13, Pa.
Johnson, H. B., Sewer Supt., Media, Pa.
Jones, Everett M., Sales Mgr., Simplex Valve & Meter Co., 68th & Upland Sts., Philadelphia, Pa.
Jones, Frank Woodbury, Havens & Emerson, Leader Bldg., Cleveland, Ohio.
Kappe, S. E., 627 W. Kingsley St., Philadelphia, Pa.
Kasperski, Frank E., Asst. San Engr., 2225 Taggart St., Philadelphia, Pa.
Keatley, C. R., Army Engineers, c/o The Engineer Board, Fort Belvoir, Va.
Keefer, R. K., Supt., Sewage Treatment Plant, 339 South St., Clarion, Pa.
Kelsey, Walter, Lord & Burnham Co., Irvington on Hudson, N. Y.
Kinsel, H. L., Asst. Engr., Bureau of Water, 317 E. Gorgas Lane, Philadelphia, Pa.
Kochin, Milton, Chemist, Pa. Dept. of Health, 1602 Center Ave., Pittsburgh, Pa.
Kremer, Robert W., Pa. Dept. of Health, 1st National Bank Bldg., Greensburg, Pa.
Krumm, Harry J., City Chemist, Jefferson & Lawrence, Allentown, Pa.
Krumm, Harry J., Jr., Chemist, Pa. Dept. of Health, 608 Crawford County Trust Bldg., Meadville, Pa.
Langford, L. L., Eastern Sales Mgr., Pacific Flush Tank Co., 441 Lexington Ave., New York, N. Y.
Lauer, Charles N., Supt., Sewage Disposal Plant, City Hall, York, Pa.
Leahy, S. James, Engr., Research Laboratories, Lancaster Iron Works, Inc., 85 Zabriskie St., Hackensack, N. J.
Leh, Willard, Asst. San. Engr., 1376 Perkiomen Ave., Reading, Pa.
Link Belt Company, M. B. Tark, Rep., Philadelphia, Pa.
Long, George S., Designing Engr., R. D. 4, Elizabethtown, Ky.
Lubrecht, Frank S., Consulting Engr., 310 Hazleton National Bank Bldg., Hazleton, Pa.
Lutz, Howland C., Field Asst., 1413 West St., Annapolis, Md.

Mallory, E. B., Director, Research Labs., Lancaster Iron Works, Inc., 85 Zabriskie St., Hackensack, N. J.

Mansfield, M. G., Rep., Morris Knowles, Inc., 507 Westinghouse Bldg., Pittsburgh, Pa.

Manz, Erwin C., 584 E. Martin St., Roxborough, Philadelphia, Pa.

Matter, L. D., 2536 Lexington St., Harrisburg, Pa.

McAdoo & Allen Welting Co., S. Hellertown Ave., Quakerstown, Pa.

McAllister, Paul J., Engr., Link Belt Company, 2045 Hunting Park Ave., Philadelphia, Pa.

Menantico Sand & Gravel Co., P. O. Box 65, Millville, N. J.

Merkel, Paul P., Cons. Chemist, 1528 N. 11th St., Reading, Pa.

Miller, J. John, Asst. San. Engr., 308 Warren St., New Cumberland, Pa.

Miller, Roy, Treatment Plant Opr., 1640 Lincoln Ave., Northampton, Pa.

Milligan, Francis B., 2314 Walnut St., Camp Hill, Pa.

Molitor, Paul, Sr., Cons. Operating Engr., Chatham, N. J.

Monn, Edgar P., Opr., Sewage Treatment Plant, Mt. Alto Sanatorium, Fayetville, Pa.

Monroe, Lowell W., Borough Mgr., City Bldg., Elwood City, Pa.

Montagna, S. D., Box 308, Cecil, Washington Co., Pa.

Moore, Charles A., Opr., Sewage Disposal Plant, 450 Green St., Royersford, Pa.

Morgan, L. S., District Engr., Pa. Dept. of Health, Rms. 410–417, First National Bank Bldg., Greensburg, Pa.

Morris, Paul J., Sewage Treatment Plant, 319 S. 6th St., Reading, Pa.

Moses, H. E., 1522 N. 2nd St., Harrisburg, Pa.

Mount Penn, Borough of, Att.: Alvin G. Binkley, Rep., 2054 Fairview St., Mount Penn, Reading, Pa.

Mowry, Robert B., District Engr., Wallace & Tiernan Co., Inc., 1505 Race St., Philadelphia, Pa.

Murdock, William, San. Engr., 1123 Cornell St., Pittsburgh, Pa.

Nazareth Sewerage Co., Andrew G. Kern, Treas., The Trumbower Co., Inc., Easton Rd., Nazareth, Pa.

New Eastern State Penitentiary, Richard B. Paul, Sewage Opr., Grateford, Pa.

Nugent, Franklin J., 10 N. Greenwood St., New Castle, Pa.

O'Donnell, R., 119 S. Atherton St., State College, Pa.

Olewiler, Grant M., Asst. Supt., Health & Drainage, 75 E. Lancaster Ave., Ardmore, Pa.

Palmer, I. Charles, City-County Bldg., Rm. 423, Bureau of Sewers, Pittsburgh, Pa.

Palmer, Gilbert, Supt., Disposal Plant, 19 Second St., Stroudsburg, Pa.

Payrow, Harry G., Rep., Asst. Prof. Sanitary Engineering, Dept. of Civil Engineering, Lehigh University, Bethlehem, Pa.

Pearson, S. R., Chief Opr., Conshohocken Sewage Treatment Plant, Conshohocken, Pa.

Pecker, Joseph S., Cons. Engr., 900 Victory Bldg., 1011 Chestnut St., Philadelphia, Pa.

Pfreimer, Harold A., San. Engr., The Alturns, 1509 16th St., N. W., Washington, D. C.

Phila. Bureau of Engineering Surveys & Zoning, City of Philadelphia, 1103 City Hall Annex, Philadelphia, Pa.

Phillips, Roy L., City Engr., Meadville, Pa.

Ralston, Wilmer R., Sewerage Opr., 214 William St., Downingtown, Pa.

Reed, J. H., Diamond Alkali Co., 2400 Oliver Bldg., Pittsburgh, Pa.

Reilly, John J., Cons. Engr., 500 Newrose Bldg., Main & Spring Sts., Pittston, Pa.

Reuning, Howard T., Engineering Dept. Elk Tanning Co., 330 Allenhurst Ave., Ridgway, Pa.

Rhoads, Edward J., Supt., Sewage Treatment Plant, City of Lancaster, 531 Chester St., Lancaster, Pa.

Rice, John M., Cons. Engr., 2502 Grant Bldg., Pittsburgh, Pa.

Ricker, W. H., Jr., Dept. of Civil Engineering, 523 W. Beaver Ave., State College, Pa.

Rogers, D. Paul, Sr. Chemist, State Health Dept., Harrisburg, Pa.

Rogers, H. L., Sew. Treat. Plant Opr., City of Easton, City Hall, Easton, Pa.

Rosengarten, W. E., Twp. Engr., 75 E. Lancaster Ave., Ardmore, Pa.

Ross, John T., Director, Streets & Public Impr. Sewage Disposal Plant, City of Chester, Ft. of Clayton St., Chester, Pa.

Rutter, Lee D., Supt. of Sewers, City Hall, Lebanon, Pa.

St. Michaels Industrial School, John McGough, Rep., Hoban Heights, Pa.

Schaut, George G., 1308 W. Ontario St., Philadelphia, Pa.

Scheffer, Louis K., 1013 Green St., Harrisburg, Pa.

Schnupp, Leonard J., 702 Westmoreland Ave., Jeannette, Pa.
Schwartz, H. L., Eastern District Rep., The American Well Works, Inc., 515 Commercial Trust Bldg., Philadelphia, Pa.
Searight, Geo. P., Borough Mgr., Carlisle, Pa.
Seltzer, J. M., Chief Chemist, Rep., Elkins Tannery, Elkins, W. Va.
Setter, Lloyd R., 50-18 217th St., Bayside, N. Y.
Shaw, George H., Parkman Rd., Hillandale, Silver Spring, Md.
Sheen, Robert T., Ch.E., 7711 Orchard Way, Chestnut Hill, Pa.
Shelley, Harry, Pa. Dept. of Health, Harrisburg, Pa.
Shertzer, J. H., City Engr., Lancaster, Pa.
Shiffer, J. Paul, Sewer Commissioner, Elizabethtown, Pa.
Siebert, Christian L., Exec. Engr., Sanitary Water Board, Pa. Dept. of Health, Harrisburg, Pa.
Smith, Marvin L., Asst. San. Engr., Pa. Dept. of Health, Kirby Health Center, Wilkes-Barre, Pa.
Smith, Merlin D., Sewage Plant Opr., Laurelton State Village, Laurelton, Pa.
Snelsire, William, Rep., Pa. Salt Mfg. Co., 641 Union Trust Bldg., Pittsburgh, Pa.
Spear, William B., Sewage Disposal Plant, R. D. 7, Chambersburg, Pa.
Speiden, H. W., Dept. of Civil Engineering, West Virginia University, Morgantown, W. Va.
Stevenson, W. L., 2214 N. 2nd St., Harrisburg, Pa. (Deceased.)
Stewart, H. M., 35th & Allegheny Ave., Philadelphia, Pa.
Stiles, Morrison N., Supt., Radnor-Haverford Sewage Treatment Plant, Glendale Rd., R. F. D. 1, Newton Square, Pa.
Swab, Bernal H., San. Engr., 713 1st Ave., Altoona, Pa.
Swinehart, Eugene B., Chief Opr., Pottstown Boro Sewage Disp. Plant, 1133 South St., Pottstown, Pa.
Tarman, John E., W. H. & L. D. Betz, Chem. Engrs., 235 W. Wyoming Ave., Philadelphia, Pa.
Taylor, Henry W., Cons. Engr., 11 Park Place, New York, N. Y.
Thorn, Wm. J., Branch Mgr., 401 N. Broad St., Innis, Speiden & Co., Philadelphia, Pa.
Trebler, H. A., Chemical Engr., 1403 Eutaw Place, Baltimore, Md.
Trescott, Boyd, 230 E. Front St., Berwick, Pa.
Tygert, C. B., Rep., Wallace & Tiernan Co., Inc., 208 Jackson Ave., Rutherford, N. J.
Umbenhauer, E. J., 1815 Rosaria St., Laredo, Texas.
Wagner, Edwin B., Downingtown, Pa.
Walker, Edward A., Asst. San. Engr., 17 College Ave., Mount Pleasant, Pa.
Walker, Elton D., Dept. of Eng., Pa. State College, State College, Pa.
Warren State Hospital, H. A. Otterson, Rep. Warren, Pa.
Wayne Laboratories, The, Att.: J. J. Shank, 17 E. Main St., Waynesboro, Pa.
Weachter, Horace, Rep., Boro of Lansdale, 110 Courtland St., Lansdale, Pa.
Weisel, W. O., City Engr., Supt. of Public Works, 68 Hillside Ave., Doylestown, Pa.
Welsford, H. R., Pa. State Dept. of Health, 1st National Bank Bldg., Greensburg, Pa.
Wertz, C. F., Cons. Engr., 1522 Woolworth Bldg., New York, N. Y.
Weston, Roy F., 3144 Passyunk Ave., Philadelphia, Pa.
Whitby, Steve, Culbert-Whitby Co., 2019 Rittenhouse St., Middle City Station, Philadelphia, Pa.
Whitcomb, Leon R., 408 West Ave., Jenkintown, Pa.
White Haven Sanatorium, Att.: R. A. Dodson, Rep., White Haven, Pa.
Wiest, Gordon J., Chemist, 1214 Pine Lane, Chester, Pa.
Williams, A. C., Township Engr., Haverford Township, Upper Darby Post Office, Oakmont, Pa.
Williams, James C., Opr., Sewage Treatment Plant, Danville State Hospital, Danville, Pa.
Wilt, Marlin E., Pa. Dept. of Health, Harrisburg, Pa.
Wirt, R. M., San. Engr., Court House, Arlington, Va.
Woodring, R. W., City Chem. & Bac., Bethlehem City Lab., 3rd & Adams Sts., Bethlehem, Pa.
Woodward, John D., Chief Opr. & Chem., Conshohocken Sewage Treatment Plant, Conshohocken, Pa.
Yenchko, John, Asst. San. Engr., Pa. Dept. of Health, Kirby Health Center, Wilkes-Barre, Pa.
Yerkes, Milton R., Engr., Radnor Twp., Wayne, Pa.
Young, C. H., Dist. Engr., Pa. Dept. of Health, 608-09 Crawford County Trust Bldg., Meadville, Pa.

Young, F. D., Cons. Engr., 1140 Leader Bldg., Cleveland, Ohio.

Young, Norman C., Borough Manager, Borough Hall, Phoenixville, Pa.

Rocky Mount Sewage Works Association

Dana E. Kepner, *Secretary*, 1921 Blake Street, Denver, Colo.

Amend, J. E., Water & Sewer Supt., City Hall, Brighton, Colo.

Burnite, T. B., 1863 Wazee St., Denver, Colo.

Cederberg, C. R., 1420 Dahlia, Denver, Colo.

Coberly, Carroll H., Cons. Engr., 1441 Welton St., Denver, Colo.

Coy, Burgis, City Engr., City Hall, Ft. Collins, Colo.

Davis, Charles A., City San. Engr., City and County Bldg., Denver, Colo.

Denver Public Library, Att.: Mr. F. M. Veatch, Technical Dept., Civic Center, Denver, Colo.

Donnell, Geo. M., Cons. Engr., Worland, Wyo.

Dorr Company, Inc., The, Att.: E. C. Reybold, Sec. Rep., 1009 17th St., Denver, Colo.

Elliot, S. F., City Engr., City Hall, Pueblo, Colo.

Gelder, R. W., Cons. Engr., 1629 13th Ave., Greeley, Colo.

Goldenberg, Charles N., Cons. Engr., P. O. Box 822, Santa Fe, N. M.

Grand Junction, City of, c/o Bruce Bronson, City Mgr., Grand Junction, Colo.

Gross, Dwight D., Chief Engr., Bd. of Water Comm., City & County Bldg., Denver, Colo.

Heaslit, Walter, Water & Sewer Supt., Arvada, Colo.

Hendrie & Bolthoff Mfg. & Supply Co., Capt., J. S. Smith, Vice-Pres. Rep., 1635 17th St., Denver, Colo.

Hill, Frank C., Water & Sewer Supt., City Hall, Montrose, Colo.

Holden, E. G., Supt., R. R. 2, Box 30, Pueblo, Colo.

Howe, Ben V., State San. Engr., Argonaut Hotel, Denver, Colo.

Howell, Eugene, San. Engr., 130 Frederick St., San Francisco, Calif.

Jenks, Glen, Sewage Plant Supt., 150 W. Heald St., Sheridan, Wyo.

Kepner, Dana E., 1921 Blake St., Denver, Colo.

Lewiston, City of, c/o Jos. M. Schmit, City Engr., City Hall, Lewiston, Mont.

Lock Joint Pipe Co., Att.: Mr. Wm. B. Freeman, Branch Mgr., 1716 California St., Denver, Colo.

Luton, Max, Water & Sewer Supt., City Hall, Gillette, Wyo.

Lyndes, H. E., Mgr., General Chemical Co., Denver, Colo.

McClintock, H. C., City Mgr., Boulder, Colo.

New Mexico Bureau of Public Health, Att.: Paul S. Fox, San. Engr., P. O. Box 711, Santa Fe, New Mexico

Nisbet, Geo. A., Water & Sewer Supt., Palisade, Colo.

Osborn, L. C., City Engr., Loveland, Colo.

Pacific Flush Tank Co., 4241 Ravenswood Ave., Chicago, Ill.

Schirk, J. M., P. O. Box 1611, Casper, Wyo.

Sheridan, City of, c/o Frank Scullin, Water Comr., Sheridan, Wyo.

Simson, George, Jr., Vice Pres., Denver Sewer Pipe & Clay Co., P. O. Box 2329, Denver, Colo.

Slee, Angus E., City Engr., City Hall, Longmont, Colo.

Streeter, Robert L., Civil Engr., Gillette, Wyo.

Watson, Henry G., City Engr., 102 City & County Bldg., Cheyenne, Wyo.

Williams, L. O., State San. Engr., State House, Cheyenne, Wyo.

Sewage Division—Texas Section, S. W. W. A.

V. M. Ehlers, *Secretary-Treasurer*, State Department of Health, Austin, Texas.

Baugh, W. L., Jr., Regional Engr., Box 1495, Lubbock, Texas.

Becker, Philip G., Jr., 1009 Orange St., Fort Worth, Texas.

Berg, E. J. M., Route 7, Box 186, San Antonio, Texas.

Billings, C. H., Jr., State Dept. of Health, P. O. Box 385, Weslaco, Texas.

Bureau of Sanitary Engineering, State Dept. of Health, Austin, Texas.

Connell, Dr. C. H., Box 43, Faculty Exchange, College Station, Texas.

Crockett, V. P., Engr., Collin County Health Unit, McKinney, Texas.

Dickson, D. B., Supt. & Chemist, Box 1739, Wichita Falls, Texas.

Gauntt, W. C., Box 113, McKinney, Texas.
Green, Tom C., Supt., City Sewage Treatment Plant, Austin, Texas.
Haneman, A., Jr., P. O. Box 2138, Corpus Christi, Texas.
Hardy, W. R., San. Engr., City Health Dept., Fort Worth, Texas.
Hatch, G. M., Jr., San. Engr., City Health Dept., Dallas, Texas.
Helland, H. R. F., Cons. Engr., Frost National Bank Bldg., San Antonio, Texas.
Hinyard, J. N., c/o City Water Dept., El Paso, Texas.
Joiner, W. N., Water Works Supt., San Marcos, Texas.
Livingston, L. E., 3921 Purdue St., Dallas, Texas.
Mahlie, W. S., City Chemist, Water Filtration Plant, Fort Worth, Texas.
Moor, W. C., Chemist, Armour & Co., Stock Yards Station, Fort Worth, Texas.
Powell, W. L., 2022 Republic Bank Bldg., Dallas, Texas.
Ryan, T. J., City San. Engr., City Health Dept., Houston, Texas.
Smallhorst, David, P. O. Box 358, Austin, Texas.
Steel, E. W., Prof., Texas A. & M. College, College Station, Texas.
Thomas, F. W., 1135 S. Trenton St., Tulsa, Okla.
Tinning, J. D., Water & Sewer Supt., Eldorado, Texas.
Weiss, R. H., P. O. Box 533, Kerrville, Texas.
Wells, William N., Chemist, c/o O. C. Watson, 2517 Bridle Path, Austin, Texas.
Whedbee, Edgar, Sr. Engr., City Water Dept., Dallas, Texas.
Wilkins, Homer J., Cons. Engr., Bay City, Texas.

The Canadian Institute on Sewage and Sanitation

Albert E. Berry, *Secretary-Treasurer*, Sanitary Enigneering Div., Ontario Dept. of Health, Toronto, Ontario, Canada.

Adams, F. P., City Engr., City Hall, Brantford, Ontario, Canada.
Anderson, C. S., Engr., Tisdale Twp., South Porcupine, Ontario, Canada.
Archibald, S. W., Cons. Engr., 489 Richmond St., London, Ontario, Canada.
Armstrong, C. G. R., Cons. Engr., Bartlett Bldg., Windsor, Ontario, Canada.
Babe, W. K., Sales Mgr., Road Materials Div., The Pedlar People, Ltd., Oshawa, Ontario, Canada.
Baird, E. M., Township Engr., 11 Avalon Blvd., Scarborough, Ontario, Canada.
Ball, Frank C., Sewer Engr., City Hall, London, Ontario, Canada.
Baty, J. Bernard, Dept. of Civil Eng., Queen's University, Kingston, Ontario, Canada.
Berry, A. E., Director, Sanitary Eng. Div., Ontario Dept. of Health, 235 Gainsboro Rd., Toronto, Ontario, Canada.
Bieth, Robert, Mayor, Preston, Ontario, Canada.
Bird, T. A., Ass. Sewage Disp. Opr., 12 Horne St., London, Ontario, Canada.
Bowness, G. W., Gen. Mgr., Nichols Eng. & Research Corp. of Canada, Ltd., University Tower Blvd., Montreal, Quebec, Canada.
Bradley, Harold D., Deputy St., Commr., 90 Albert St., Toronto, Ontario, Canada.
Brakenridge, Charles, City Engr., City Hall, Vancouver, B. C., Canada.
Brereton, W. P., City Engr., c/o Greater Winnipeg San. Dis., 223 James Ave., Winnipeg, Manitoba, Canada.
Brereton, W. P., Greater Winnipeg Sanitary District, Sewage Treatment Plant, Old Kilfonan, Manitoba, Canada.
Bryce, W. F. M., Sewer Engr., Transportation Bldg., Ottawa, Ontario, Canada.
Burnett, A. H., Supt., Union Sewerage Comm., Town Hall, Mimico, Ontario, Canada.
Burnett, J. A., Engr. in Charge Street Cleaning Dept., 90 Albert St., Toronto, Canada.
Byram, Arthur T., Asst. San. Engr., Ontario Dept. of Health, 312–A Quebec Ave., Toronto, Ontario, Canada.
Casey, Wm., Pres., Canadian Locomotive Co., Ltd., 610 Federal Bldg., Toronto, Ontario, Canada.
Cleveland, E. A., Chairman, Vancouver & Dists. Joint Sewerage & Drainage Board, 1303 Sun Bldg., Vancouver, B. C., Canada.
Cliff, D. P., Chairman, Sewers Committee, Dundas, Ontario, Canada.
Collins, W. H., Sewer Engr., City of Hamilton, 16 Senator Ave., Hamilton, Canada.
Cooke, P. N., Sales Mgr., Norton Co. of Canada, Ltd., Hamilton, Ontario, Canada.

Cousineau, A., Supt., Engr., Div. of Sanitation, Dept. of Health, City Hall Annex, Montreal, P. Q., Canada.

Cyr, Rene, Asst. Chief Engr., Ministry of Health, 89 E. Notre Dame St., Montreal, Quebec, Canada.

Darling, E. H., Cons. Engr., 513 Pigott Bldg., Hamilton, Ontario, Canada.

Desmaris, R. J., City Engr., 451 Park St., W., Windsor, Canada.

Durrant, W. K. F., Chief Opr., Sewage Disposal Works, P. O. Box 43, Moose Jaw, Saskatchewan, Canada.

Edmonds, W. R., Asst. San. Engr., Ont. Dept. of Health, 25 St. Leonards Ave., Toronto, Ontario, Canada.

Falls, O M., Comm. of Works, Township of York, 40 Jarvis St., Toronto, Ontario, Canada.

Ferguson, G. H., Chief Engr., Dept. of Pensions & National Health, Daly Bldg., Ottawa, Ontario, Canada.

Francis Hankin & Co., Ltd., 2028 Union Ave., Montreal, Canada.

Fraser, Charles E., Fraser, Brace, Ltd., 107 Craig St., W. Montreal, Canada.

French, R. Del., Prof., Highway & Mun. Eng'g., McGill University, Montreal, Canada.

Gibeau, H. A., Asst. Chief City Engr., 5618 Phillips Ave., Montreal, Quebec, Canada.

Gill, A. F., National Research Council, Ottawa, Ontario, Canada.

Goforth, W. W., Mgr., Canadian Institute of Plumbing & Heating, Canada Cement Bldg., Montreal, Quebec, Canada.

Grassie, C. A., Town Engr., Port Colborne, Ontario, Canada.

Hamel, Edouard, Chief Engr., City Hall, Quebec, P. Q., Canada.

Hanenberg, A. L., Supv., Spring Valley Sewage Treatment Plant, 94 Fairview Ave., Kitchener, Ontario, Canada.

Hansford, Albert E., Chief Opr., Stratford Sew. Disposal Plant, 70 Argyle St., Stratford, Ontario, Canada.

Harris, R. C., Commissioner of Works, City Hall, Toronto, 2, Canada.

Hawtrey, R. O., Asst. Engr., York Twp., 40 Jarvis St., Toronto, Canada.

Hitchcock, Simon E., Opr., Sewage Disposal Plant, 39 Oxford St., Woodstock, Ontario, Canada.

Hobson, N. C., Asst. Wks. Mgr., Canadian Industries, Ltd., Salt & Alkali Div., Toronto Ontario, Canada.

Hogg, Alex. M., Town Engr., P. O. Box 85, Noranda, Quebec, Canada.

Howard, N. J., Director, Filtration Plant Laboratory, 410 Lake Shore Rd., Centre Island, Toronto, Ontario, Canada.

Hubel, J. H., Chem. Engr., Development Dept., Canadian Industries, Ltd., Montreal, P. Q., Canada.

Jack, D., Asst., Engr., Dept. of National Health, 22 Bank of Nova Scotia Bldg., St. Catherines, Ontario, Canada.

Jack, Grant R., Comm. of Works, Township of East York, 787 Coxwell Ave., Toronto, Ontario, Canada.

Kay, L. A., Asst. San. Engr., Ontario Dept. of Health, 807 Richmond St., W., Toronto, Ontario, Canada.

Kinney, J. B., Mgr., Wallace & Tiernan Co., Ltd., 345 Sorauren Ave., Toronto, Ontario, Canada.

Knight, Ray R., Toronto Mgr., Francis Hankin & Co., 165 Spadina Ave., Toronto, Ontario, Canada.

Lafreniere, Theo J., Provincial San. Engr., Bureau of Health of Quebec, 89 E. Notre Dame, Montreal, Quebec, Canada.

Lamson, B. F., City Engr., St. Catharine, Ontario, Canada.

Lawson, W. S., Chief Eng., Dept. of Justice, Confederation Bldgs., Ottawa, Ontario, Canada.

Lea, W. S., Cons. Eng., 1226 University St., Montreal, P. Q., Canada.

McCannel, D. A. R., City Eng., City Hall, Regina, Saskatchewan, Canada.

McFaul, W. L., City Engr., Hamilton, Ontario, Canada.

McNiece, L. G., Town Engr., Orillia, Ontario, Canada.

McWilliams, D. B., Mgr., Dresser Mfg. Co., Ltd., 60 Front St., W., Toronto, Ontario, Canada.

MacDonald, G. A., Cons. Eng., Bank of Hamilton Bldg., 67 Yonge St., Toronto, Ontario, Canada.

McDonald, N. G., Cons. Eng., 1130 Bay St., Toronto, Ontario, Canada.

MacKenzie, C. J., Dean of Engineering, University of Saskatchewan, Saskatoon, Saskatchewan, Canada.

MacLaren, J. F., Cons. Engr., 1130 Bay St., Toronto, Ontario, Canada.

MacLaren, L. A., 31 Granville Rd., Hampstead, Montreal, P. Q., Canada.

MacLean, J. D., Town Engineer, Box 433, Timmins, Ontario, Canada.

MacNicol, N., Works Comm., 333 Lonsdale Rd., Forest Hill, Ontario, Canada.
Malcolm, Wm. L., Dir. Civil Engineering, Cornell University, Ithaca, N. Y.
Manning, P., Comm. of Works, Port Dalhousie, Ontario, Canada.
Marsh, H. M., Vice Pres., W. J. Westaway Co., Ltd., Hamilton, Ontario, Canada.
Maxwell, G. E., Supt., Public Utilities Comm., Simcoe, Ontario, Canada.
Menzies, D. B., Prov. San. Engineer, 218 Administration Bldg., Edmonton, Alberta, Canada.
Menzies, J. Ross, 170 Place d'Youville, Montreal, Quebec, Canada.
Miller, W. C., City Engineer, 67 Gladstone St., St. Thomas, Ontario, Canada.
Mills, S. W., 105 Glengrove Ave., Toronto, Ontario, Canada.
Moloney, Grant, Editor, Canadian Engineer, 341 Church St., Toronto, Ontario, Canada.
Montreal Sewers Comm., City Hall, Montreal, Quebec, Canada.
Mott, C. A., City Engineer, Belleville, Ontario, Canada.
Munroe, E. H., Supt., Disposal Plant York Twp., 18 Normanna Ave., Toronto, Ontario, Canada.
Murdock, Charles R., Town Engineer, Kapuskasing, Ontario, Canada.
Necker, C. E., Town Engineer, Town Hall, Waterloo, Ontario, Canada.
Nicklin, H. S., City Engineer, City Hall, Guelph, Ontario, Canada.
Oke, Ernest E. W., Manager and Engineer, Public Utilities Comm., Cochrane, Ontario, Canada.
Owen, Mark B., Hudson House, Ardsley-on-Hudson, N. Y.
Palmer, Fred C., 147 O'Connor Drive, Toronto, Canada.
Parsons, R. H., City Engr., 133 Simcoe St., Peterborough, Ontario, Canada.
Patterson, W. E., Chief Chemist, Sternson Labs., Brantford, Ontario, Canada.
Perry, A. H., Asst. Engr., P. O. Box 1012, Vancouver, B. C., Canada.
Phelps, Geo., Engr. of Sewers, Dept. of Works, City Hall, Toronto, Ontario, Canada.
Plamondon, Sarto, San. Engr., Amos, Quebec, Canada.
Pontbriand, P. N., K. C., Administrator & Solicitor, Sorel, Quebec, Canada.
Potter, R. E., City Engr., Nelson, British Columbia, Canada.
Pringle, H. L., Mgr., Public Utilities Comm., Whitby, Ontario, Canada.
Rawson, E. Otto, Town Eng., Barrie, Ontario, Canada.
Redfern, W. B., Cons. Eng., Excelsior Life Bldg., 36 Toronto St., Toronto, Ontario, Canada.
Riehl, W. H., City Eng., City Hall, Stratford, Ontario, Canada.
Roberton, L. T., Sewage Disposal Eng., 565 William St., London, Ontario, Canada.
Robinson, B., Dist. Mgr., Hardinge Co., Inc., 159 Bay St., Toronto, Ontario, Canada.
Robinson, I. F., Contractor for Removal of Sludge, 28 Langarth St., London, Ontario, Canada.
Roe, Frank C., San. Eng., Canadian Carborundum Co., Ltd., Niagara Falls, N. Y.
Rogers, M. W., Mgr. Public Utilities Comm., Carleton Place, Ontario, Canada.
Russell, J. P., Editor, Engineering & Contract Record, 347 Adelaide St., W., Toronto, Ontario, Canada.
Scheak, H. M., 75 Rosedale Heights, Toronto, Ontario, Canada.
Scott, W. M., Chairman of Comm., Greater Winnipeg San. Dist., 185 King St., Winnipeg, Canada.
Shook, H. R., Asst. Sales Mgr., National Sewer Pipe Co., 44 Victoria St., Toronto, Ontario, Canada.
Shupe, S., City Eng., City Hall, Kitchener, Ontario, Canada.
Smith, W. T. E., Sales Eng., Link Belt Ltd., 791 Eastern Ave., Toronto, Ontario, Canada.
Spellman, W. A., Eng.-Tech. Twp., Kirkland Lake, Ontario, Canada.
Stalker, W. D., Mgr. Pub. Util. Comm., Simcoe, Ontario, Canada.
Storrie, Wm., Cons. Eng., 1130 Bay St., Toronto, Ontario, Canada.
Symes, C. B., City Engineer, Fort William, Ontario, Canada.
Ternent, A., Comm. of Works, 83 De Forest Rd., Swansea, Ontario, Canada.
Theaker, K., Chief Opr. Sewage Disposal Plant, Guelph, Ontario, Canada.
Thomas, A. H. R., Supt. Public Utilities Commission, 874 Lake Shore Rd., New Toronto, Ontario, Canada.
Thomson, William R., 99a Bloor St., W., Toronto, Ontario, Canada.
Ure, Wilfred Gordon, City Eng., Woodstock, Ontario, Canada.
Van Benschoten, J., Mgr. Paterson Engineering Co., of Canada, Ltd., 58 Pelham Ave., Toronto, Ontario, Canada.
Veitch, Wm. M., City Engineer, City Hall, London, Ontario, Canada.

Watmough, W. W., Supt. Chemist, Depew Disposal Plant, 57 Erie Ave., Hamilton, Ontario, Canada.

Williamson, R. C., Technical Service, Canadian Industries, Ltd. House, Montreal, Quebec, Canada.

Wood, J. R., Asst. City Eng., City Hall, Calgary, Alberta, Canada.

Young, C. R., Prof., Dept. of Civil Engineering, University of Toronto, Toronto, Ontario, Canada.

Sanitary Engineering Division of Argentine Society of Engineers

Carlos Santos Rossell, *Secretary*, Centro Argentino de Ingenieros, Cerrito, 1250, Buenos Aires, S. A.

Barbeito, Arturo Auderut, Anchorena 1451, 3rd Floor, Buenos Aires, Argentina, S. America.

Carrique, Carlos S., Gral. Paz. 1856, Buenos Aires, S. America.

The Institute of Sewage Purification—England

J. H. Garner, *Secretary*, 28 Aberford Road, Wakefield, Yorks., England.

Alford, J. S., 11 Victoria St., Westminster, London, S.W. 1, England.

Allen, A. J., Half Moon St., Sherborne, Dorset, England.

Allen, F. W., Hacken Sewer Works, Great Lever, Bolton Lancs., England.

Artist, L. J., Sewage Works, Calder Vale, Wakefield, Yorks., England.

Balfour & Sons, D., 45 South St., Durham, England.

Barker, A., Bankside, Greenfield, N. Oldham, England.

Barraclough, D. H., Sewage Works, Denton, N. Manchester, England.

Bell, H. D., Sewage Works, Burton Grange, Barnsley, England.

Beswick, G., Sewage Works, Slacks Valley, Middleton Junction, N. Manchester, England.

Bolton, J. F., Ames Crosta Mills & Co. Ltd., Moss Iron Works, Heywood, Lancs., England.

Calvert, A., 43 Station Rd., Darnall, Sheffield, England.

Campbell, J. L., Manor Farm Sewage Works, Reading, Berkshire, England.

Clifford, W., "Mayecroft" Stourbridge Rd., Wombourn, Wolverhampton, England.

Cockroft, T. N., Sewage Works, Leigh, Lancs., England.

Covill, R. W., Sewage Works, Denton, Gravesend, Kent, England.

Drummond, A. H., Sewage Works, Hook Rd., Epsom, Surrey, England.

Duxbury, S., Bungalow, Summerhouse Hill, Cardington, Beds., England.

Edmondson, J. H., Sewage Works, Wincobank, Sheffield, England.

Etheridge, W., 37 Baginton Rd., Coventry, England.

Evans, S. C., Coseley Sewage Works, Foxyards, Tipton, Staffordshire, England.

Fidler, G. C., 122 Standen Rd., Wincobank, Sheffield, England.

Finch, J., Sewage Works, Aldwarke, Parkgate, Rotherham, England.

Flowers, E., Balby Sewage Works, Woodfield Rd., Doncaster, England.

Fowler, G., Brighouse Sewage Works, Cooper Bridge, Mirfield, Yorks., England.

Fowler, G. J., Mackay's Garden Annexe, Graemes Rd., Cathedral, P. O., Madras, India.

Freeborn, W. F., 34 Cardinal's Walk, Hampton-on-Thames, Middlesex, England.

Furphy, H. G., 465 Collins St., Melbourne, Victoria, Australia.

Garner, J. H., Brynfield, 28 Aberford Rd., Wakefield, Yorks., England.

Gillard, J. E., Sewage Works, Leamington, Warwickshire, England.

Goldthorpe, H. H., Shelley, Huddersfield, England.

Gough, T., Sewage Works, The Bottoms, Heckmondike, Yorkshire, England.

Graham, J. A., Sewage Works, Naburn, York, England.

Hambleton, F. T., Outfall Works, Prestbury, N. Macclesfield, England.

Hamlin, C. H., Sewage Works, Windmill Rd., Luton, Beds., England.

Hicks, R., Sewage Works, Hamilton, Scotland.

Hodgson, E., Irrigation Farm, Harrington Rd., S. Norwood, London, S.E., England.
Hodgson, H. J. N., 22 Brae Rd., Glenelg Gardens, S. Australia.
Holroyd, A., Chemist, Dagenham Urban District Council, Riverside Sewage Works, Rainham, Essex, England.
Houlihan, J. E., 4 Strongbow Rd., Eltham, London, S.E. 9, England.
Howarth, J. P., Sewage Disposal Works, Longford Rd., Cannock, Staffs., England.
Hoyle, W. H., "Dilkusha," 47 Victoria Rd., Topsham, Nr. Exeter, Devon, England.
Humphrey & Sons, Howard, 17 Victoria St., Westminster, London, S.W. 1, England.
Hunter, A., Sewage Dept., City Chambers, 50 John St., Glasgow, Scotland.
Hurley, J., Sewage Works, Tettenhall, Wolverhampton, England.
Jarvis, Alec. C., Capt., Jens Kofoedsgade 4, Copenhagen, Denmark.
Jennings, A., 327 Walmersley Rd., Bury, Lancs., England.
Jepson, C., Sewage Works, Davyhulme, Manchester, England.
Joglekar, N. D., Waterworks & Mech. Engr. Baroda Municipality, Baroda, India.
Johnson, W. H., 32 St. John's Rd., Corstorphine, Edinburgh 12, Scotland.
Jones, C. B. O., City of Coventry Chemical Lab., Whitley, Cov., England.
Kershaw, Arnold, Chippenham Lane, Slough, Buckinghamshire, England.
Kessener, Ir. H., J. P. Coenstraat 1, 'S-Gravenhage, The Hague, Holland.
Kumra, Mohan Lal, Sanitary Supt., Conservancy Lines, White Rd., Quetta, India.
Lamb, P., Esq., Sewage Disposal Works, Bromwich Rd., Worcester, England.
Lea, J. E., The Lea Recorder Cornbrook Park Rd., Manchester 15, England.
Leigh, H. G., 28, W. Leigh Rd., Blackburn, Lancs., England.
Lockett, W. T., West Middlesex Main Drainage Works, Oak Lane, Isleworth, Middlesex, England.
Lovett, M., Sewage Works, Tettenhall, Wolverhampton, England.
Lumb, C., Salterhebble, Halifax, England.
Makepeace, W. H., Sewer Engineer's Office, Leek Rd., Stoke-on-Trent, England.
Meats, G. R. E., Fairleigh, Coventry Rd., Burbage, Hickley, England.
Miller, A. S., Sewage Works, Manor Farm, Reading, Berks., England.
Modak, B. L., Rao Bahadur, Yeshoda Dham, Post Deccan, Gymkhana, Poona, 4, India.
Modak, N. V., City Eng., Bombay Municipality, Bombay, India.
Mountfort, L. F., "Claverings," Montagu Rd., Edmonton, London, N. 9, England.
Mumford, G., Mrs., c/o Activated Sludge, Ltd., 100 Victoria St., London, S.W. 1, England.
Myatt, H., Sewage Works, Toll End, Tipton, Staffs, England.
Parker, R. J., c/o Geo. Kent, Ltd., Luton, Bedfordshire, England.
Pledger, A., "Granta" Camels Head, Wolseley Rd., Plymouth, England.
Poole, S. B., 11 Clive Ave., Dales Lane, Whitefield, Manchester, England.
Price, D. H. A., Sewage Works, Roch Mills, Rochdale, Lancs., England.
Proctor, J. W., Sewage Disposal Works, Knostrop, Leeds, England.
Reynolds, A. V., Sewage Farm, Blurton Waste, Longton, Staffs., England.
Ribbius, F. J., Van Boetzelaerlaan 71, The Hague, Holland.
Scott, W., Sewage Works, Bury, Lancs., England.
Scouller, W. D., Sewage Disposal Works, Deighton, Huddersfield, England.
Sidle, R. S., H. M. Office of Works, Storey's Gate, Westminster, London, S.W. 1, England.
Smith, G. C., Sewage Works, Campbell Rd., Swinton, Manchester, England.
Spacey, T., Sewage Works, Harpenden, Herts, England.
Stanbridge, H. H., Sewage Works, Hook Rd., Epsom, Surrey, England.
Staynes, E. H., Sewage Works, Mitchell Laithes, Dewsbury, England.
Stone, A. R., Stoke Farm, Stoke Bardolph, Nottingham, England.
Taylor, H., Stalybridge and Dukinfield Joint Sewage Works, Bradley Hirst, Dukinfield, England.
Taylor, H. W., 1 Saville Place, Newcastle-on-Tyne, England.
Taylor, Harold, Regal Chambers, Cavendish St., Chesterfield, England.
Taylor, J., "Langwood" Foxdenton Lane, Chadderton, Oldham, England.
Thompson, J. T., Sewage Works, Knostrop, Leeds, England.
Thornhill, S., Sewage Works, Newbridge Lane, Old Whittington, Chesterfield, England.
Townend, C. B., West Middlesex Main Drainage Works, Isleworth, Middlesex, England.
Ward, A. R., Sewage Works, Heathside Farm, Cheadle Heath, Stockport, England.

Wardman, F. L., Broad Street Chambers, 44, Easy Row, Birmingham, England.
Watson, W., Sewage Works, Dockfield, Shipley, Yorks., England.
Waterhouse, A. G., c/o Peter Spence & Co., Ltd., National Bldg., St. Mary's Parsonage, Manchester, England.
Weir, E. McG., 61 Colne Rd., Burnley, Lancs., England.
Wilkinson, F., Red Lion Farm, Norton Canes, Cannock, Staffs, England.
Wishart, J. M., "Silver Lea," Little Sutton Rd., Four Oaks, Warwickshire, England.
Wontner-Smith, H., Sewage Works, Esholt Hall, N. Shipley, Yorks., England.
Wrigley, Frank, County Medical Officer's Dept., Shire Hall, Nottingham, England.

The Institution of Sanitary Engineers—England

Mrs. E. M. Kerry, *Acting Secretary*, 118 Victoria Street, Westminster, S. W. 1, England.

Alford, John S., M. Inst., C. E., F. I. S. E., 11, Victoria St., London, S.W. 1, England.
Armstrong, J. D., A. I. S. E., Messrs. Trinidad Leaseholders, Ltd., Pointe-A Pierre, Trinidad, B. W. I.
Ashby, E. Hamilton, E. S. I., M. R. R. P. H. H. M. I. S. E., 1 Mitre Court Bldg., Inner Temple, London, E.C. 4, England.
Aslamidis, A., F. F. Sco. A. M. I. S. E., 6 Vernon Rd., Bushey, Herts., England.
Balsom, E. V., A. M. I. Mech. E., F. I. S. E., 100, Victoria St., London, S.W. 1, England.
Barclay, W. G., M. R. San. I., M. I. S. E., 71 Wensleydale Rd., Hampton, "Carlisle" Middlesex, England.
Behah, Zadik, A. I. S. E., 77 Russell St., London, W.C. 1, England.
Binding, C., M. S. I. A., A. M. I. S. E., 11 Burntwood Close, London, S.W. 18, England.
Blizard, W. D., B. Sc., M. Inst., C. E., F. I. S. E., Lansdowne House, Castle Lane, Southampton, England.
Brassey-Edwards, S., c/o Messrs. Ames Crosta Mills & Co., Ltd., Abbey House, Victoria St., London, S.W. 1, England.
Brown, W. Fillingham, B. Sc., A. M. I. C. E., M. I. S. E., Claxton, Copthorne Rd., Rickmansworth, Herts., England.
Burnet, J. G., A. M. I. S. E., Knox Manor, Knox St., Double Bay, Sydney, N. S. W., Australia.
Clark, H. W., Stud. Inst., C. E., A. M. I. M. & Cy., A. M. I. S. E., 16 Edison Rd., Welling, Kent, England.
Collard, A. E., 24 St. Mary's Rd., Ealing, London, W. 5, England.
Collier, H., Esq., A. M. I. S. E., A. R. San. I., Mena, Garstang Rd., Broughton, Near Preston, England.
Coombs, E. P., A. M. I. S. E., 2 Victoria Ave., Finchley, London, N. 3, England.
Cotterell, G. T., A. P. I. Cotterell & Son, 54 Victoria St., Westminster, London, S.W. 1, England.
Davies, A. T., 16 Jan Smuts Ave., Parktown, Johannesburg, S. Africa.
Easdale, W. C., F. I. S. E., M. S. E., 1 Victoria St., London, S.W. 1, England.
Ely, E. H., B. Sc., Assoc. M. Inst., C. E., A. M. I. S. E., 14 Spencer Rd., London, S.E. 24, England.
Fah, C. Thum, Stud. I. S. E., 778 Club Rd., Ipoh, F. M. S., Malaya.
Farmer, J. E., A. M. I. S. E., 14 Homefield Rd., Worthing, Sussex, England.
Faulkner, T. G., 41 Wantage Rd., Didcot, Berkshire, England.
Fraser, Francis Ernest, c/o Messrs. Dawson & Fraser, San. Engineers, Pretoria, S. Africa.
Gillet, R. T., Chief Architect's Division, H. M. Office of Works, Storey's Gate, London, S.W. 1, England.
Gregory, L. L., Corporation Sewage Works, Salisbury, Wilshire, England.
Haworth, W. D., Assoc. M. I. C. E., M. S. E., A. M. I. S. E., St. Martins, Pwllgles, Mold Flintshire, Wales.
Hesford, L., M. R. San. I., F. I. S. E., "Dorlan," Scalford Rd., Melton Mowbray, Leicestershire, England.
Hodges, H. E. W., M. R. San. I., A. M. I. S. E., 13 Braundton Ave., Sidcup, Kent, England.
Hoskins, Nandy, M. S. E., F. I. S. E., 18 Bolingbroke Grove, London, S.W. 11, England.
Lawson, A. M., A. M. I. S. E., c/o Richardson & Cruddas, First Line, Beach, Madras, India.
McCrae, K. C., Stud. Inst., C. E., A. M. I. S. E., The Limes, West Bergholt, Essex, England.
Martin, Arthur J., 108 St. Georges Square, London, S.W. 1, England. (Deceased.)

Montes, Jose-Garcia, Jr., Avenida de Belgica 4, Habana, Cuba.

Moore, F. Owen, c/o Messrs. John Taylor & Sons, Caxton House, Westminster, S.W. 1, England.

Munro, A. D., Public Works Dept., P. O. Box 3142, Johannesburg, S. Africa.

Murray, A. E. Scott, Barnfield, Blythe Rd., Bromley, Kent, England.

Noguera, Gustavo S., Civil Engineer, Apartado 1509, Bogota, Columbia, S. America.

Porteous & Company, W. K., Abbey House, Victoria House, Westminster, London, S.W. 1, England.

Renfrew, J. Harvey, c/o Mrs. W. J. Pullenegagem, The Temple, Bambalapitiga, Colombo, Ceylon, India.

Sciver, A., 28 Victoria St., London, S.W. 1, England.

Shete, V. G., P. O. Box 39, Poona, India.

Stanley, Stephen, Astral Court, Kingsford, N. S. W. (Rainbow & Willis Sts.), Australia.

Streeter, S. H., Capt., "Santasu," Warren Rd., Guilford, Surrey, England.

Summers, M. W., Assoc. M. Inst. C. E., A. M. Inst. W. E., F. I. S. E., "Arran" Broom Way, Oatlands Park, Weybridge, England.

Taylor, Godfrey M. C., M. C., M. Inst. C. E., F. I. S. E., Caxton House, Westminster, London, S.W. 1, England.

Tigar, Leonard Aldridge, 105 Richmond Park Rd., Bournemouth, Hampshire, England.

Walker, P. S., The Winnats, Castleton Drive, Banstead, Surrey, England.

Warren, L. B., A. M. I. S. E., St. George's Bldg., Chater Rd., Hong Kong, China.

Watson, David M., 3 Central Bldgs., Westminster, London, S.W. 1, England.

Wennholm, S. V., "Glendon," Rutland St., Kogarah, New South Wales, Australia.

Westwood, H. W., D. Sc. (Eng.) F. R. S. A., Assoc. M. Inst. C. E., A. I. A. S., M. I. S. E., 87 Egerton Park, Rock Ferry, Cheshire, England.

Williams, G. Bransby, M. Inst. C. E., F. I. S. E., 28 Victoria St., London, S.W. 1, England.

Young, C. H., A. M. I. S. E., 7 Hale St., Ipoh, Fed. Malay States.

NON-ASSOCIATION SUBSCRIBERS TO SEWAGE WORKS JOURNAL IN THE UNITED STATES AS OF DECEMBER 31, 1940

Alabama

State Board of Health, Bureau of Sanitation, 519 Dexter Ave., Montgomery, Ala.
Tenn. Coal, Iron & R. R. Co., c/o Mr. A. Clinton Decker, Sanitary Engr., Birmham, Ala.

Arkansas

Arkansas State Board of Health, Att.: Mr. F. L. McDonald, State San. Engr., Little Rock, Ark.
University of Arkansas, General Library, Fayetteville, Ark.

California

Stanford University, Library, Stanford University, Calif.
Twining Laboratories, The, P. O. Box 1320, Fresno, Calif.

Colorado

Great Western Sugar Co., The, Technical Library, P. O. Box 5308, Terminal Annex, Denver, Colo.
University of Colorado, Library, Boulder, Colo.

Connecticut

Fuller & McClintock, Fairfield Woods Rd., Fairfield, Conn.
General Medical Library, Sterling Hall of Medicine, 333 Cedar St., New Haven, Conn.
State Dept. of Health, 165 Capitol Ave., Hartford, Conn.
Wesleyan University, Library, Middletown, Conn.

District of Columbia

George Washington University, Library, 2023 G. St., N.W., Washington, D. C.
Sanborn, N. H., National Canners Association, 1739 H St., N.W., Washington, D. C.
Scientific Library, Patent Office, Commerce Bldg., Washington, D. C.
U. S. Dept. of Agriculture, Library, Washington, D. C.

Florida

Bureau of Agricultural Chemistry and Engineering, U. S. Dept. of Agriculture, H. W. von Loesecke, U. S. Citrus Prod. Station, Box 83, Winter Haven, Fla.
State Board of Health, Library, Jacksonville, Fla.
University of Florida, University Library, Gainesville, Fla.

Georgia

Ga. Dept. of Public Health, Rm. 149, State Capitol, Att.: W. H. Weir, Atlanta, Ga.
Wiedeman & Singleton, Inc., Box 1878, Atlanta, Ga.

Illinois

Armour College of Engineering, Library, 3300 Federal St., Chicago, Ill., Att.: Miss Nell Steele.
Clay Products Association, 111 W. Washington St., Chicago, Ill.
Conover, George, The American City, Daily News Bldg., Chicago, Ill.
Conquest, Victor, Chemical Research Dept., Armour & Co., Union Stock Yards, Chicago, Ill.
Cutler, Charles E., 224 W. Washington St., Freeport, Ill.
Greater Peoria Sanitary & Sewage Disposal District, Ft. of Darst St., Peoria, Ill.
John Crerar Library, Chicago, Ill.
Northwestern University, Library, Evanston, Ill.
Raymond Pulverizer Division, Combustion Engineering Co., Inc., Att.: Mr. C. W. Gordon, 1319 N. Branch St., Chicago, Ill.
Shell Oil Company, Inc., Wood River, Ill., Libr. Refinery Main Office.
State Water Survey, Dept. of Registration and Education, 57 Chemistry Bldg., Urbana, Ill.
University of Illinois, Library, Periodical Dept., Urbana, Ill.

Indiana

City Engineer, City Hall, Crawfordsville, Ind.

Hay, Julian A., 4249 Monroe St., Gary, Ind.
Mathews, W. W., 220 W. 44th Ave., Gary, Ind.
Page, F. O., 6341 Moraine Ave., Hammond, Ind.
Public Library, 5th Ave., at Adams St., Gary, Ind.
Purdue University, Library, Lafayette, Ind.
Rose Polytechnic Institute, Terre Haute, Ind., Att.: John L. Bloxsome, Libr.
Ross, Edward J., 3753 Washington St., Gary, Ind.
Sanitary District of Gary, Gary, Ind.
Standard Oil Co., Research Dept., Library, Whiting, Ind.

Iowa

Buell & Winter Engineering Co., 510 Insurance Bldg., Sioux City, Iowa.
Garwood, Kirk, Operator, Sewage Plant, Grinnell, Iowa.
Graham, Ralph C., Supt. of Construction, City Hall, Davenport, Iowa.
Iowa State College, Library, Ames, Iowa.
State University of Iowa, Library, Library Annex, Iowa City, Iowa.

Kansas

University of Kansas, Library, Periodical Dept., Lawrence, Kans.
Wichita, City of, Engineering Department, Wichita, Kans.

Kentucky

Dugan, F. C., 620 S. 3rd St., Louisville, Ky.
Lexington, City of, M. J. McGruder, City Engineer's Office, Lexington, Ky.

Louisiana

Division of Research & Statistics, Dept. of Conservation, P. O. Box 4055, University, La.
Louisiana State University, Library, University, La.
Newland, Stewart H., 225 Albany St., Shreveport, La.
O'Neill, John H., San. Engr., La. State Board of Health, Civil District Court Bldg., New Orleans, La.
Tulane University Library, New Orleans, La.
Voorhies, L. J., City Hall, Baton Rouge, La.

Maryland

Johns Hopkins University, Library, Baltimore, Md.
University of Maryland, Library, College Park, Md.
Wm. Welch Medical Library, The, 1900 E. Monument St., Baltimore, Md.

Massachusetts

Berrigen, Thomas A., 108 High Rock Lane, Westwood, Mass.
Harvard Engineering School, 209 Pierce Hall, Cambridge, Mass.
Mass. Dept. of Public Health, Rm. 541, State House, Boston, Mass.
Mass. Institute of Technology, Library, Cambridge A, Mass.
Tufts College, Library, Tufts College, 57, Mass.
Worcester Polytechnic Institute, Att.: Miss Emily M. Haynes, Libr., Worcester, Mass.

Michigan

Detroit Public Library, Woodward & Kirby Aves., Detroit, Mich.
Dow Chemical Company, Library, Midland, Mich.
Michigan College of Mining & Technology, Library, Houghton, Mich.
Michigan Dept. of Health, Library, Bureau of Education, Lansing, Mich.
Sewage Treatment Plant, Escanaba, Mich.
University of Michigan, General Library, Ann Arbor, Mich.

Minnesota

Ellerbe & Co., 1021 First National Bank Bldg., St. Paul, Minn.
Halvorson, H. Orin, Dr., Dept. of Bacteriology & Immunology, University of Minn., The Medical School, Minneapolis, Minn.
Kraft, George M., Rural Route 1, Fairmont, Minn.
Minnesota Dept. of Health, Division of Sanitation, University of Minn. Campus, Minneapolis, Minn.
Schmucker, R. A., City Chemist & Bacteriologist, New Ulm, Minn.
University of Minnesota, Library, Minneapolis, Minn.

Missouri

Main Library, 9th & Locust Sts., Kansas City, Mo.

Russell, George, Mun. & San. Engr., 7025 Etzel Ave., University City, Mo.
University of Missouri, Engineering Library, Columbia, Mo.
University of Missouri, Library, School of Mines & Metallurgy, Rolla, Mo.

Montana

Montana State College, Library, Bozeman, Mont.

Nebraska

Barklage, O. F., Sales Engr., 223 Keen Hotel, Omaha, Nebr.
Cudahy Packing Co., The, Laboratory, S. Side Station, Omaha, Nebr.
Dunmire, E. H., 2774 South St., Lincoln, Nebr.
Fitzsimmons, M. S., 2604 Y, Lincoln, Nebr.
Henningson Engineering Co., Inc., 326–30 Union State Bank Bldg., Omaha, Nebr.
Interstate Machinery & Supply Co., Omaha, Nebr.
Scott, Wardner G., 618 First National Bank Bldg., Lincoln, Nebr.
University of Nebraska, Library, Station A, Lincoln, Nebr.

New Hampshire

None.

New Jersey

Blaettler, Paul X., 509 Cooper St., Camden, N. J.
Braun, Miss Anna E., 30 Bridge St., Hackensack, N. J.
Cole, E. J., Libr., Calco Chemical Co., Inc., Bound Brook, N. J.
DuPont de Nemours & Co., E. I., Librarian, Parlin, N. J.
Lafferty, Wm. L., Supt., Camden Co. Sewage Disposal Plant, Grenloch P. O., Lakeland, N. J.
Library, The, Agricultural Experiment Station, New Brunswick, N. J.
Newark College of Engineering & Newark Technical School, 367 High St., Newark, N. J.
Oleri, Frank J., 721 Bergenline Ave., West New York, N. J.
Rutgers University Library, New Brunswick, N. J.
State Dept. of Health, Att.: The Director of Health, Trenton, N. J.

New York

Buffalo Sewer Authority, Laboratory, Bird Island Pier, Ft. W. Ferry St., G. E. Symons, Chief Chemist, Buffalo, N. Y.
Chlorine Institute, Inc., The, 50 E. 41st St., New York, N. Y.
College of Physicians & Surgeons, Library, 630 W. 168th St., Columbia University, New York, N. Y.
Columbia University Library, Accessions Dept., New York, N. Y.
Cornell University Library, Att.: Otto Kinkeldey, Libr., Ithaca, N. Y.
Crimmins, Thomas, 734 Lexington Ave., New York, N. Y.
Eglof, Dr. Warren K., Niagara University, Niagara University, N. Y.
Elder, Dr. A. L., Bowne Hall, Syracuse University, Syracuse, N. Y.
General Chemical Co., P. O. Box 149, Long Island City, N. Y., L. H. Lab.
Glens Falls, City of, Glens Falls, N. Y.
Gordon, Fred F., 1200 Park Ave., Rochester, N. Y.
Greenawalt, John E., Greenawalt Engineering Co., Inc., 135 E. 42nd St., New York, N. Y.
Hooker Electrochemical Co., Library, Niagara Falls, N. Y.
Mathieson Alkali Works, Inc., 60 E. 42nd St., New York, N. Y.
Mathieson Alkali Works, Inc., Niagara Falls, N. Y.
National Aniline & Chemical Co., Library, Buffalo, N. Y.
New York Public Library, Municipal Reference Branch, 2230 Municipal Bldg., New York, N. Y.
New York State Library, Albany, N. Y.
New York University, Library, University Heights, N. Y.
Paully, F. G., Cambridge Instrument Co., Inc., Grand Central Terminal, New York, N. Y.
Pratt, J. B., Jr., c/o H. J. Baker & Bros., 271 Madison Ave., New York City.
Queens Borough Public Library, Periodical Dept., 89–14 Parsons Blvd., Jamaica, N. Y.
Riordan, James T., 109–01 210th St., Queens, L. I., N. Y.
Rome, City of, Att.: City Engr., Dept. of Public Works, City Hall Bldg., Rome, N. Y.
Simmons, Wm. H., Mt. Kisco Laboratory, 28 South St., Mt. Kisco, N. Y.

Solvay Process Co., The, Librarian, Syracuse, N. Y.

North Carolina

Duke University Library, Duke Station, Durham, N. C.
North Carolina State College, D. H. Hill Library, Raleigh, N. C.

North Dakota

Armour & Co., Att.: Subscription Dept., West Fargo, N. D.
Grand Forks, City of, Sewage Treatment Plant, John B. Kleven, Supt., Grand Forks, N. D.
University of North Dakota, Library, University Station, Grand Forks, N. D.

Ohio

Burgess & Niple, 568 E. Broad St., Columbus, Ohio.
Cleveland Public Library, Order Dept., 325 Superior Ave., N.E. Cleveland, Ohio.
Henry, Thomas B., c/o H. P. Jones & Co., 2nd National Bank Bldg., Toledo, Ohio.
Jones & Company, H. B., 606 Second National Bank Bldg., Toledo, Ohio.
Kroone, T. H., 201 Plymouth Bldg., Cleveland, Ohio.
Krumm, Tahlman, 65 Meadow Park Rd., Bexley, Columbus, Ohio.
McVay, Darrell, 704 Cherry St., Findlay, Ohio.
Municipal Reference Bureau, Rm. 244, City Hall, Cincinnati, Ohio.
Ohio State University, Library, Columbus, Ohio.
Ohio University, Library, Athens, Ohio.
Public Library, Cincinnati, Ohio.
Medical Officer in Charge, U. S. Public Health Service, Stream Pollution Investigations, 3rd & Kilgour Sts., Cincinnati, Ohio.
Sowers, George B., 1836 Euclid Ave., Cleveland, Ohio.
Uhlmann, P. A., 330 Linsppe Drive, Columbus, Ohio.

Oklahoma

Alexander & Pollard, Terminal Bldg., Oklahoma City, Okla.
Cecil, Lawrence K., 747 Kennedy Bldg., Tulsa, Okla.
Oklahoma A. & M. College, Library, Stillwater, Okla.

Oregon

Forrester, A. C., 2826 N.E. 63rd Ave., Portland, Ore.
Library Assn. of Portland, 801 S.W. 10th Ave., Portland, Ore.
Oregon State Agricultural College, Library, Corvallis, Ore.
Smithson & Gilbert, Pilot Butte Inn, Bend, Ore.

Pennsylvania

Atlantic Refining Co., The, Att.: W. B. Hart, 3144 Passyunk Ave., Philadelphia, Pa.
Carnegie Library, Bucknell University, Lewisburg, Pa.
Carnegie Library of Pittsburgh, Periodical Room, 4400 Forbes St., Pittsburgh, Pa.
Commandant, The Medical Field Service School, Carlisle Barracks, Pa.
Elkland Leather Company, Elkland, Pa.
Heinz Company, H. J., 1062 Progress St., N. S., Pittsburgh, Pa., Att.: Engineering Dept.
Hunn, Wm. R., 39 Forest Ave., Morton, Pa.
Olson, H. M., 171 Longue Vue Drive, Mt. Lebanon, Pittsburgh, Pa.
Ozone Processes, Inc., 1500 Walnut St., Philadelphia, Pa.
Pennsylvania State College, The, School of Engineering Reading Room, 110 Main Engineering Bldg., State College, Pa.
Sharples Specialty Co., The, Att.: Mr. C. M. Ambler, 23rd & Westmoreland Sts., Philadelphia, Pa.

Rhode Island

Brown University, Library, Providence, Rhode Island

South Carolina

Blackwelder, C. D., Box 1615, Greenville, S. C.
Clemson College Library, Miss Cornelia Graham, Libr., Clemson, S. C.
Fry, E. D., Supt., P. O. Box 1416, Greenville, S. C.

South Dakota

Huron, City of, Huron, S. Dak.
South Dakota State College, Library, Att.: H. Dean Stallings, Agric. & Mech. Arts, Brookings, S. Dak.

Tennessee

Dept. of Public Health, Division of San. Engineering, 420 6th Ave. N., Nashville, Tenn.
Lewis, Fred J., Dean, Vanderbilt University, School of Engineering, Nashville, Tenn.
Murfreesboro, City of, Att.: Mr. S. S. Cox, Murfreesboro, Tenn.
Tennessee Valley Authority, Technical Library, H. C. Bauer, Knoxville, Tenn.
Vanderbilt University, Library, Nashville, Tenn.

Texas

Division of Industrial Hygiene & Chemical Labs., State Board of Health, Austin, Texas, Att.: Dr. Carl A. Nau, Director.
Freeport Sulphur Co., Att.: J. B. Chatelain, Freeport, Texas.
Freese and Nichols, 407–410 Capps Bldg., Fort Worth, Texas.
Myers & Noyes, Cons. Civil Engrs., 2204 Tower Petroleum Bldg., Dallas, Texas.
Operator, Sewer Disposal Plant, City Hall, Corpus Christi, Texas.
Parkhill, G. W., Assoc. Prof., Texas Technological College, Dept. of Civil Engineering, Lubbock, Texas.
San Antonio, City of, 102 Dwyer, Health Dept., San Antonio, Texas.
Southwestern Laboratories, Box 737, San Antonio, Texas.
University of Texas, Library, Serials Acquisition, Austin, Texas.
Zeller, P. J. A., Research Assoc., Engineering Experiment Station, A. & M. College, College Station, Texas.

Utah

Davis County Health Dept., Att.: Dr. D. Keith Barnes, Farmington, Utah.

Virginia

Patton, H. M., 1735 N. Troy St., Arlington, Va.
Phipps & Bird, Inc., Richmond, Va.
State Health Dept., Bureau of San. Eng., 601 State Office Bldg., Richmond, Va.
Wiley & Wilson, 906–910 Peoples Bank Bldg., Lynchburg, Va.

Washington

Municipal Reference Branch Library, 508 A County City Bldg., Seattle, Wash.
State College of Washington Library, c/o W. W. Foote, Libr., Pullman, Wash.

West Virginia

Bruce, Kyle L., Supt., Sanitary Board of Bluefield, Bluefield, W. Va.

Wisconsin

City Clerk, City of Shawano, Shawano, Wisc.
Marathon Chemical Company, Rothschild, Wisc.
Municipal Reference Lib., City Hall, Milwaukee Public Lib., Milwaukee, Wisc.
Todd, Leon J., Supt., Milton Sewage Treatment Plant, Milton, Wisc.
University of Wisconsin, Library, Madison, Wisc.

Cuba

Bequer, Ing. Gustavo A., Calle 19 No. 711, entre Paseo y A. Vedado, Habana, Cuba.
Goicoechea, Prof. Leandro de, Escuela de Ingenieros y Arquitectos, Universidad de la Habana, Habana, Cuba.
Martinez, Sergio S., Calle H. No. 354, Vedado, Habana, Cuba.
Santana, Rogelio A., Bruno Zayas 114, Vibora, Habana, Cuba.
Sociedad Cubana, De Ingenieros, Avenida de Belgica No. 258, Habana, Cuba.

Philippine Islands

City Engineer, City of Baguio, P. I.
Manosa, M., Asst. Manager, Metropolitan Water District, P. O. Box 2174, Manila, P. I.
Metropolitan Water District, P. O. Box 383, Manila, P. I.

Foreign Non-Association Subscribers to Sewage Works Journal

Africa

Bateman, Edward L., P. O. Box 1671, Johannesburg, S. Africa.
City Engineer, The, P. O. Box 1049, Johannesburg, S. Africa.
City Engineer, City Hall, Durban, Natal, S. Africa.
Controller of Stores & Buyer, Municipal Council, P. O. Box 7776, Johannesburg, S. Africa.

Disposal Works Laboratory, c/o Town Council of Springs, Springs, Transvaal, S. Africa.
Griffin, J. D., P. O. Box 2155, Johannesburg, S. Africa.
Maskew-Miller, Ltd., 29 Adderley St., Cape Town, S. Africa.
Medical Officer of Health, P. O. Box 1049, Johannesburg, S. Africa.
Secretary for Public Works, Departmental Ref. P. W. D. New Government Offices, Vermulen St., Pretoria, S. Africa.
Town Engineer, The, Office of the Town Clerk, P. O. Box 17, Stellenbosch Municipality, S. Africa.
Van Schaik, Vir. J. L., BPK, Church St., Central, Pretoria, Transvaal, S. Africa.

Australia

Anderson, V. G., Collins House, 360 Collins St., Melbourne C. 1, Victoria, Australia.
Controller, The, Government Stores Dept., Murray St., Perth, W. Australia.
Garlick & Stewart, Messrs., 34 Queen St., Melbourne C. 1, Australia.
Gutteridge, A. G., Capel Court, 375 Collins St., Melbourne C. 1, Victoria, Australia.
Hepburn, Mr., Public Health Dept., 295 Queen St., Melbourne, Victoria, Australia.
Johnston, J., Engineering & Water Supply Dept., Sewage Treatment Works, Glenelg, S. Australia.
Ley, J. B., "Krargee," 293 Church St., Richmond, E1; Australia.
Librarian, The, M. W. S. & D. Board, 45 Reservoir St., Sydney, N. S. W., Australia.
Melbourne & Metrop. Board of Works, 110 Spencer St., Melbourne C. 1, Australia.
Public Library of Victoria, Melbourne, Australia.
Rigby, Ltd., 16 Grenfell St. & Imperial Place, Adelaide, S. Australia.
Saunders, Dr. G., Medical Officer, Metropolitan Water Sewerage & Drainage Board, 341 Pitt St., Sydney, Australia.
School of Public Health & Tropical Medicine, Commonwealth of Health Dept., University of Sydney, Att.: Mr. Harvey Sutton, Sydney, Australia.
Secretary, The, Irrigation Water Supply & Sewerage, Executive Bldgs., George St., Brisbane, Queensland, Australia.
Secretary, Works & Services Branch, Dept. of the Interior, Canberra, F. C. T., Australia.
Showers, V. A., c/o Scott & Murphy, 465 Collins St., Melbourne C. 1, Victoria, Australia.
State Rivers & Water Supply Comm., c/o Mr. G. Pedlow, Treasury Gardens, Melbourne C. 2, Australia.
Sydney Technical College, Library, Ultimo, Sydney, N. S. W., Australia.
Water Sewerage & Drainage Board, Librarian, 45 Reservoir St., Sydney, N. S. W., Australia.

Belgium

Bibliotheque de la Revue Universelle des Mines, 12, Quai Paul Van Hoegaerden, Liege, Belgium.
Solvay & Co., 33 Rue Prince Albert, Bruxelles, Belgium, Section E.
Verlinden, Albert, Bureau Postal, Tirlemont, Belgium.

British West Indies

Chief Engineer, The Water Commission, Kingston, Jamaica, B. W. I.

Canada

Bowering, Reginald, Public Health Engr., Provincial Board of Health, Victoria, B. C., Canada.
Dept. of Public Health, J. C. Schaeffer, San. Engr., Regina, Saskatchewan, Canada.
Dorr Company, 602 Victory Bldg., Toronto, Ontario, Canada.
Ecole Polytechnique, 1430 St. Denis St., Montreal, Canada.
Haddon, A. M., City Engr., 608 Civic Block, Edmonton, Alberta, Canada.
Howard, N. J., Director, Filtration Plant Lab., 410 Lake Shore Rd., Centre Island, Toronto, Ontario, Canada.
Provincial Bureau of Health, c/o Dr. Lapierre, Dir., 89 Notre-Dame St., E. Montreal, Quebec, Canada.
Queen's University Library, The Douglas Library, Kingston, Ontario, Canada.
University of Saskatchewan, The Library, Saskatoon, Saskatchewan, Canada.
University of Toronto, Library, Toronto 5, Canada.

China

Augustine Library, Cheeloo University, Shantung Christian University, Tsinan, Shantung, China.

Chief Sanitation Chemist, Shanghai Municipal Council, Shanghai, China.
Chu, Dr. C. K., Director, Public Health Personnel Training Institute, Wei Sheng, Shu, Kweiyang, China.
Dairen Shiyakusho, The, "Bunshoka," Dairen, South Manchuria.
National Wuhan University, The Library, WK 15, Kiating, Szechuen, China.
University Library, National Southwest Associated Univ., Kunming, China.

Denmark

Andr. Fred. Host & Son, Bredgade 35, Copenhagen, Denmark.
Gad's Boghandel, G. E. C., Vimmelkaftet 32, Copenhagen, Denmark.
Joergensen, Arthur, Norregade 20, Copenhagen K, Denmark.

Dutch East Indies

Eykman Instituut, Batavia Centrum, Centraal Lab. v. d. D. V. G., Oranje Blvd., 69, Dutch East Indies.

Egypt

Director General, The, Main Drainage Dept., Cairo, Egypt.
Semry, E. El., Inspector, Drainage Section, Municipalities Dept., Cairo, Egypt.

England

Adams Hydraulics, Ltd., Peaseholme Green, York, England.
Chief Engineer, Rm. S. B., 486, County Hall, London, S.E. 1, England.
Edwards, R. W., United Dairies, Ltd., 34 Palace Court, London, W. 2, England.
Farrer, Messrs. Wm. E., Ltd., Crown Works, Hall Green, Birmingham 28, England.
General Chemicals, Ltd., I. C. I., Records Dept., Cunard Bldg., Liverpool, England.
General Chemicals, Ltd., I. C. I., Central Laboratory, Widnes, England.
Harwood, F., 24 Box Ridge Ave., Purley, Surrey, England.
Henderson, Mr., Messrs. Hatchards, Ltd., 187 Piccadilly, London, W. 1, England.
Library, Accessions Dept., Science Museum, London, S.W. 7, England.
Manchester Corp., Rivers Dept., Wm. Porthouse, Secy., Town Hall, Manchester 2, England.
Medical Officer of Health, 328, County Hall, London, S.E. 1, England.
Patent Office Library, Librarian, 25 Southampton Bldgs., Chancery Lane, London, W.C. 2, England.
Standard Ironworks, Att.: G. H. Watts, Pub. Mgr., Colchester, England.
Whitehead, H. C., Birmingham Tame & Rea Drainage Bd., Rookery Park, Erdington, Birmingham, England.

Finland

Helsingin kaupungin Rakennustoimisto, Katurakennusosasto, Kasarminkatu 21, Helsinki, Finland.

France

Bibliotheque de l'Institute Pasteur, 20, Boulevard Louis XIV, Lille (Nord), France.
Omnium d'Assainissement, 20 Rue d'Athens, Paris, 9e, France.

Germany

Bach, Dr. Herman, 9 Hewaldstr. Berlin-Schoenberg, Germany.
Bibliothek der Technischen Hochschule, Berlinerstr. 171–172, Berlin-Charlottenburg 2, Germany.
Deutsche Chemische Gesellschaft, Sigismundstrasse 4, Berlin W. 35, Germany.
Emschergenossenschaft, Postfach 219, Kronprinzenstrasse No. 24, Essen, Germany.
Hirschwaldsche Buchhandlung, Unter den Linden 60, Berlin N.W. 7, Germany.
Imhoff, Dr. Karl, Hansa-Haus, Essen, Germany.
Rohde, Herbert, Dr. Ing., Ruhrverband, Kronprinzenstrasse 37, Essen, Germany.
Ruhrverband, Kronprinzenstrasse 37, Essen, Germany.
Scheuring, Dr. L., Bayer Biologische Versuchsanstalt, Veterinarstr. 6, Munchen 2, Germany.
Sierp, Dr. F., Staatwald, Eichbenstr. 70, Essen, Germany.
Tierarztliches Institut der Universitat, Veterinarstrasse 6, Munchen, Germany.

Holland

Dorr-Oliver, N. V., Att.: C. A. Hoogterp, 40 Wassenaarscheweg, The Hague, Holland.
Oostwoud Wijdenes, Ir. J. M. J. W., Alberdingk Thijmlaan 4, Bussum, Holland.

Hungary

Kozponti Csatorna es Szivattyutelep, Goroksari ut 31, Budapest IX, Hungary.

India

Apte, V. G., B.E. (Civil), District Engr., Water Supply & Dr. District, Holkar State, Indore, India.

Dani, P. P., B.E., Duncan, Stratton & Co., 5 Bank St., Fort Bombay, India.

Delhi Joint Water & Sewage Board, Engr. & Secretary, New Delhi, India.

Director, The, All Indian Institute of Hygiene, San. Engineering Dept., Calcutta, India.

Divisional Engineer, The, Maintenance Division, Drainage Dept., Hyderabad, Deccan, India.

Dyer, Brian R., 24 Raja Santosh Rd., Alipore, Calcutta, India.

King Institute, Director, Guindy, Saidapet, P. O. Madras, So. India.

Kotwal, Y. N., B.A., B.Sc.A.I.I.Sc., Manager, Chemist, Sewage Purification Works, Tulsi, Pipe Rd., Dadar, Bombay, India.

Mehta, R. S., State Engr., Drainage Section, Bhavnagar, P.W.D., India.

Sanitary Engineer, Bureau of San. Engineering Dept. of Public Health, Mysore State, Bangalore, India.

Ireland

University College, The Library, Periodical Dept., Cork, Ireland.

Italy

Biblioteca Instituto di Sanita Pubblica, Viale Regina Margherita 299, Roma, Italy.

Cambi, Ing. Franco, Piazza L. Da Vinci 7, Milano, Italy.

Dorr, Oliver, S.A.I., Corso del Littorio 3, Milano, Italy.

Ente Autonomo, Acquedotto Pugliese, Foggia, Italy.

Neri, Filippo, Prof., Direttore dell Instituto d'igene e Batterialogie dell R. Universita, Via S. Giacomo 12, Bologna, Italy.

Ufficio Technico Del Comune, di Livorno, Italy.

Japan

"Doboku" Engineering College, Kyushu Imperial University, Fukuoka, Japan.

Ford, J. B., c/o Sanki K.K.K., Sanshin Bldg., Hibiyam, Tokyo, Japan.

"Gesui Ka," c/o Maruzen Co., Ltd., (Branch Office) Sanjo Dori, Kyoto, Japan.

Gifushi Suido Jimusho, The, Miedera Machi, Gifu Shi, Japan.

Hirose, K., Prof., Dr., c/o Institute of Civil Engineering (Doboku Kyoshitse), Faculty of Engineering, Tokyo Imperial University, Hongo, Tokyo, Japan.

Ito, Sumio, 9 Kommatsu-cho 1 chome, Chikusaku, Nagoya, Japan.

Kosei Kagaku Kenkyusho/MZ, Inst. of Public Health, Shirokane Dai Machi, Shiba, Tokyo, Japan.

Nagoya Shiyakusho, Shomubo Keirika, Minami Sotobori Cho, Nishiku, Nagoya, Japan.

Nankodo Kyoto Branch, Termachi Oike, Kyoto City, Japan.

Niigata University of Medicine, The Library, Niigata, Japan.

Nishihara, S., 12, 1 chome, Tamachi, Shibaku, Tokyo, Japan.

Nonaka, Hachiro, c/o Mr. Ueda, No. 30, Miyazono-Dor, 5 chome Nakano-Ku, Tokyo, Japan.

Osaka Shiritsu Eisei Shikensho, The Kita Ohgimachi Kitaku, Osaka, Japan.

Shibata, Saburo, c/o Mikawashima-Osui-Shobunjo, Mikawashima-Machi, Arakawa-Ku, Tokyo, Japan.

Suidobu, O. S., c/o Maruzen Co., Osaka Branch, Bakuromachi, Osaka, Japan.

Suidobu Shomuka, The, c/o Maruzen Co., Kobe Branch, Akashimachi, Kobe, Japan.

Tairiku, Kagakuin, The, Toshoshitsu, Hsinking, Manchoukuo.

Tanaka, Akira, No. 301, Asagaya 3 chome, Suginami-ku, Tokyo, Japan.

Yamanashi Koto Kogyo Gakko, Yamanashi Technological College, Kofu, Yamanashi, Japan.

Yokohama Water Works Office, Yokohama City Office, Yokohama, Japan.

Yonemoto, S., Cons. Engr., Public Works Bureau of Home Dept., 96 1 chome, Sugamomachi, Tokyo, Japan.

New Zealand

Under-Secretary, The, Dept. of Internal Affairs, Wellington, New Zealand.

Palestine

None.

Portugal

Garcia, Paul Ressano, R. Marquez da Fronteira 133–3–E, Portugal, Lisboa.

Prazeres, Agnelo C., 14–R, Joaquim Bonifacio, Lisbon, Portugal.

Romania

Institutul di Igiene si Igiena Sociala, Universitatea din Cluj, Cluj, Romania.

Russia

Arkhitekt, Stroit Ekspertn. Sowet, Pl. Ostrowskogo 7, Leningrad, U. S. S. R.

Below, P. S., Prof., Nowaja Basmannaja, 1-y, Basmanniy per 12, kw. 15, Moskva, U. S. S. R.

Centr. Naughnej, Sel. Khoz, Bib-ke, Orlikov. per 1/11. Moskva, U. S. S. R.

Cent. Stroiteljn. Bib Ka, Bagazh. Moskva 2, U. S. S. R.

Giprobum Tekhnich. Bib-ke, Institutsk. per 5, Leningrad Lesnoje, U. S. S. R.

Gl. Pochtamt, Jaschik 939, Moskva, U. S. S. R.

Glav. Pochtamt, Pocht. Jaschik 500/1111, Moskva, U. S. S. R.

Glav. Pochtamt, Pocht. Jaschik 100, N. 21, Moskva, U. S. S. R.

Gorjkovsk. Obl. N. T. Bib-ke, Universitetsk ul 28, Gorjkij, U. S. S. R.

Gos. Nauchnoj Medicinskoj Bib-ke, NKX, SSSR, Sadovaja Kudrinskaja N. 1, Moskva 69, U. S. S. R.

Kharjk Inzh. Stroit Inst. T. Bib-ke, Shatilowka pr. SP Lenina 2, Kharjow, U. S. S. R.

Leningr. Nauch Issled Ins. Tut, Kommun. Khoz WA, Pr. Volodarskogo N. 22, 2–J, Et Leningrad 104, U. S. S. R.

Mosk. In-t Inzhen, Kommunaljn, Stroiteljstwa, Tverskoj-Jamakoj per 17, Moskva, U. S. S. R.

Naughnoj, Biblioteke Industrial Instituta, ul. Prosveschenija N. 120, Novocherkassj, U. S. S. R.

Nautschnoi Bib-Ke Narkomtiash., Delovoi Dvor-IV, Podiesd. Moskva, U. S. S. R.

Tekhnich Bib-ke Centrospecstroja, Pokrovka 37, Moskva, U. S. S. R.

Uprawl Stroiteljstwa, Dworca Sowetow, Tekhn. Bib-Ka, Kropotkinskaja Nab. 45/1, Moskva, 19, U. S. S. R.

Vsesojuz Nauch. Issled Ins. Tut, Vodgeo Nauch Tekh. Bib-Ka., B. Kochki D.N. 17 A, Moskva, 48, U. S. S. R.

Wses Institutu Kommunaljn Sanitari, Pogodinskaja, U1 10, Moskva, 48, U. S. S. R.

Scotland

Babtie, Shaw & Morton, 17 Blythswood Square, Glasgow C. 2, Scotland.

Glasgow Corporation, City Analyst's Dept., 20 Trongate, Glasgow, Scotland.

Stephen, F. M., Esq., County Drainage Engineer, 23, Clydesdale St., Hamilton, Lanarkshire, Scotland.

Thomson, A. L., Sewage Wks. Mgr., High Rd., Motherwell, Lanarkshire, Scotland.

South America

Altoberro, J. C., 2029 Charrua St., Montevideo-Uruguay, S. America.

deFreitas, Valle Filho, J. Dr., Rua Domingos de Moraes 300, Sao Paulo, Brazil, S. America.

Dempsey, W. T., c/o Colombian Petroleum Co., Apartado 100, Cucuta, Colombia, S. America.

Direccion de Saneamiento Seccion Estudios, Soriano 882, Montevideo, Uruguay, S. America.

Direccion General de Aprovisionamiento del Estado, Casilla 24–D, Santiago, Chile, S. America.

Director del Departamento de Hidraulica, Direccion General de Obras Publicas, Santiago, Chile, S. America.

Dorgival Olivera, Rue da Imperatriz 58, Recife, Brazil, S. America.

Ferreira, Mario Leal, Dr., Caixa Postal 1280, Rio de Janeiro, Brazil, S. America.

Harmanos, Broquetas, Colonia 1133, Montevideo, Uruguay, S. America.

Ortiz, Pedro C., Calle 18–A, No. 1–75, Bogota, Colombia, S. America.

Rio de Janeiro City Improvements Co., 69 Santa Luzia, Caixa 403, Rio de Janeiro, Brazil, S. America.

Rubio, Sr. L. Pedro, Diagonal Norte 567, Buenos Aires, Argentina, S. America.

Sanazar, Mirza, Calle Cordoba 1336, Buenos Aires, S. America.

Senores Caja Habilacion Popular, Departamento Tecnico, Seccion Ingenieria, Avda B. O'Higgins 1489, Santiago, Chile, S. America.

Straits Settlements

Municipal Engineer, The, Sewerage Dept., Municipal Offices, Singapore, Straits Settlements.

Sweden

Aktiebolager Noridska Bokhandeln, Drottinggatan 7, Stockholm, Sweden.
Boras Stads Byggnadskontor, Boras, Sweden.
Byggnadskontoret, Norrkoping, Sweden.
Kgl. Tekniska, Hoegskolans Bibliotek Valhallavaegen, Stockholm, Sweden.
Spak, Dr. Hakan, Holmgatan, Karlskrona, Sweden.
Tillsynsmyndigliet, roronde Vattenfarorcningar, Drottningholm, Sweden.
Vattenbyggndasbyran, A. B., Humlegarsgatan 29, Stockholm, Sweden.

Switzerland

Versuchsanstalt f. Wasserbau, E. T. H., Beratungsstelle f. Abwasserreingigung & Trinkwasserversorgung, Gloriastrasse 37, Zurich 7, Switzerland.
Waser, E., Prof. Dr., Kantonschemiker, 15 Fehrenstrasse, Zurich 7, Switzerland.

Turkey

Robert College, Library, Bebek, Istanbul, Turkey.

Wales

Unifloc Reagents Limited, 2/3 St. Mary St., Swansea, Wales.

Yugoslavia

Borcic, B. Dr., Institute of Hygiene, Mirogojska cesta 4–48, Zagreb, Jugoslavia.

ALPHABETICAL LIST OF MEMBERS OF THE FEDERATION

Abell, D. S. North Carolina.
Abplanalp, C. C. Central States.
Abrams, M. F. New York.
Adams, Chas. L. Central States.
Adams, E. H. Arizona.
Adams, F. P. Canada.
Adams, George O. New England.
Adams, J. K. New Jersey.
Adams, Milton P. Michigan.
Adams, W. K. California.
Aeryns, A. N. New York.
Agar, Charles G. New York.
Agostinelli, Anthony J. New York.
Ahrens, G. C. Iowa.
Albers, J. C. California.
Albertson, J. G. New York.
Alden, Town of. Iowa.
Aldrich, E. H. New York.
Aldrich, Lloyd. California.
Alexander, J. D. Pennsylvania.
Alford, John S. England (I. S. E.).
Algonquin, Village of. Central States.
Allen, A. F. New York.
Allen, A. J. England (I. S. P.).
Allen, F. W. England (I. S. P.).
Allen, Herbert B. New England.
Allen, Wm. A. California.
Allen, William G. Central States.
Allison, T. H. Pennsylvania.
Allton, Robert A. Ohio.
Almquist, Frederick O. A. New England.
Alsdorf, William R. New York.
Althouse, Raymond R. New York.
Amend, J. E. Rocky Mountain.
American Cast Iron Pipe Co. California.
American Well Works Inc. New York.
Anaya, Marvin. California.
Andersen, C. George. New York.
Anderson, Arthur W. New York.
Anderson, C. S. Canada.
Anderson, Geo. H. Central States.
Anderson, Herbert A. Central States.
Anderson, Herb. Michigan.
Anderson, Newell. Central States.
Anderson, Norval E. Central States.
Anderson, R. A. Michigan.
Anderson, S. P. New York.
Anderson, W. R. Pennsylvania.
Andres, William H. New York.
Andrews, Harry S. New York.
Andrews, John. North Carolina.
Angell, J. M., Jr. New York.
Appel, Alvin Arthur. California.
Arbogast, Joseph. Central States.
Arford, Wm. Central States.
Armeling, Geo. K. Maryland-Delaware.
Armstrong, C. G. R. Canada.
Armstrong, Frank W. New York.
Armstrong, J. D. England (I. S. E.).
Armstrong, Paul A. Pennsylvania.
Arner, Charles R. Central States.
Arnold, G. E. California.
Artese, Philip. New York.
Artist, L. J. England (I. S. P.).
Asch, Abram B. New York.
Ashby, E. Hamilton. England (I. S. E.).
Ashby, Paul. Central States.
Ashdown, W. L. Central States.
Ashe, John F. New York.
Ashley, Clifford A. Central States.
Aslamidis, A. F. England (I. S. E.).
Atkinson, Asher. New Jersey.
Austin, R. J. Central States.
Avery, J. W. Ohio.

Babbitt, H. E. Central States.
Babe, W. E. Canada.
Bachmann, Frank. New York.
Backherms, A. B. Ohio.
Backherms, Louis E. Ohio.
Backmeyer, David. Central States.
Badger, Irvin S. New York.
Baetz, C. C. Central States.
Bailey, S. C. Pennsylvania.
Baillie, E. P. Central States.
Bain, Ernest B. North Carolina.
Bainbridge, David W. Pennsylvania.
Baird, Charles O., Jr. New England.
Baird, E. M. Canada.
Baity, H. G. North Carolina.
Baker, C. M. Central States.
Baker, Roy. New York.
Baker, Stanley L. Iowa.
Baldwin, C. W. New England.
Balfour & Sons. England (I. S. P.).
Ball, Frank C. Canada.
Balmer, Robert R., Jr. New England.
Balsom, E. V. England (I. S. E.).
Bamford, J. H. Pacific Northwest.
Banks, H. O. California.
Banta, A. Perry. California.
Barasch, William. New York.
Barbeito, Arturo Auderut. Argentina.
Barbour, Frank A. New England.
Barclay, W. G. England (I. S. E.).
Bardet, Paul E. New York.
Bardoff, Julian L., Jr. California.
Barker, A. England (I. S. P.).
Barker, Stanley T. New York.
Barnard, Archer F. California.
Barnes, George E. Ohio.
Barnes, L. B. Ohio.
Barnes, L. T. Central States.
Barnes, Robert J. New York.
Barnett, G. R. Central States.
Barney, J. W. Pacific.

Barnhill, John T. Central States.
Barnhill, Kenneth G. New York.
Barraclough, D. H. England (I. S. P.).
Barrick, M. J. Pennsylvania.
Barron, James L. New York.
Barstow, E. D. Ohio.
Barth, John R. Central States.
Barthlow, C. L. Pacific.
Barton, Ben H. Ohio.
Bartow, Edward. Iowa.
Bartow, Leslie W. Ohio.
Bass, Frederic. Central States.
Batchelor, W. Central States.
Bates, John S. California.
Bates, R. D. New York.
Batty, F. A. California.
Baty, J. Bernard. Canada.
Bauer, Henry W. New England.
Baugh, Charles. California.
Baugh, W. L., Jr. Texas.
Baumgartner, Wm. H. New York.
Baum, H. J. Pennsylvania.
Bavone, A. L. Dakota.
Baxter, Richard M. Central States.
Baylis, John R. Central States.
Bean, Geo. E. Michigan.
Bear, E. J. New Jersey.
Beatty, E. J. Central States.
Beaudoin, Robert E. Central States.
Beck, A. J. Central States.
Becker, John. New York.
Becker, Philip G., Jr. Texas.
Beckett, R. C. Pennsylvania.
Bedell, A. S. New York.
Behah, Zadik. England (I. S. E.).
Behnke, George C. Ohio.
Bell, E. Arthur. New York.
Bell, H. D. England (I. S. P.).
Belt, Elmer B. California.
Benas, Benjamin. California.
Bender, Dwight O. Central States.
Benford, William R. New England.
Bennett, S. G. California.
Benson, R. W. Central States.
Berg, E. J. M. Texas.
Berg, Stanley E. New York.
Berke, J. H. Central States.
Bernauer, George F. Central States.
Bernhardt, Carl J. New York.
Berry, A. E. Canada.
Berry, C. Radford. Federal.
Berry, George A. Central States.
Berry, S. C. Dakota.
Berstea, Murray. New York.
Besozzi, Leo. Central States.
Besselievre, Edmund B. New York.
Best, Robert B. New York.
Besthoff, Silas. New York.
Beswick, G. England (I. S. P.).
Bevan, John G. New York.
Beyer, A. C. California.
Bibelhausen, L. A. Federal.
Bidwell, Milton H. New York.
Biele, F. J. New York.
Bieth, Robert. Canada.
Billings, C. H. Texas.
Binding, C. England (I. S. E.).
Binger, Walter D. New York.
Bingley, W. McLean. Maryland-Delaware.
Bird, T. A. Canada.
Birdsall, L. I. Central States.
Birkeness, O. L. Central States.
Bishop, H. N. California.
Bishop, Marshall H. New York.
Bjelajac, Vaso. Central States.
Black, Hayse H. Central States.
Black & Veatch. Central States.
Blanchard, H. E. Ohio.
Blezard, J. Pacific.
Blizard, W. E. England (I. S. E.).
Bloodgood, Donald E. Central States.
Blosser, D. S. Ohio.
Board of Water, Light & Sewer Commissioners. New York.
Boardman, John. Pennsylvania.
Boardman, Wm. Hunter, Jr. Pennsylvania.
Boeke, Harley C. Central States.
Bogardus, Theodore S. Pennsylvania.
Bogema, Marvin. Central States.
Bogert, C. L. New York.
Bogren, George G. New England.
Bolde, Abraham C. New England.
Bolenius, Robert M. Pennsylvania.
Boley, Arthur L. Central States.
Bolieau, Clifton W. New England.
Bolton, J. F. England (I. S. P.).
Bonacci, L. N. New Jersey.
Bond, Philip E. New England.
Booker, Warren H. North Carolina.
Boone, George H. Pennsylvania.
Borchelt, T. C. Central States.
Boreiszo, J. New Jersey.
Borough, Reuben W. California.
Bowe, Thomas F. New York.
Bowen, M. R. California.
Bowers, Samuel W. New England.
Bowers, T. C. Michigan.
Bowler, Edmond Wesley. New England.
Bowlus, Fred D. California.
Bowness, G. W. Canada.
Bow, Wilson F. Pacific.
Boxall, F. G. California.
Boyce, Earnest. Kansas.
Boyce, Ralph E. New York.
Boyd, J. W. Michigan.
Boyer, J. A. Kansas.
Boyle, J. R. Lester. California.
Bradlee, Warren R. New England.
Bradley, Harold D. Canada.
Bradley, John L. New York.
Bradner, Basil E. New York.
Bradney, Leland. Central States.
Bradshaw, W. L. Ohio.
Bragg, Robert E. Central States.
Bragstad, R. E. Dakota, Central States.
Brakenridge, Charles. Canada.

Brallier, Paul S. New York.
Brannock, D. York. North Carolina.
Brassey-Edwards, S. England (I. S. E.).
Brender, Max M. New York.
Brensley, A. A. Central States.
Brereton, W. P. Canada.
Breuchaud, Jules R. New York.
Bridges, F. B. Missouri.
Briggs, O. L., Sr. North Carolina.
Brigham, Harold L. New England.
Brigham, John C., Jr. New York.
Brigham, J. C. New York.
Briggs, Raymond J. Pacific Northwest.
Britt, C. E. Ohio.
Brockman, C. J. Georgia.
Broderick, Joseph A. New York.
Brody, James. Central States.
Broestl, Andrew J. Ohio.
Brook, Harry. Central States.
Brookman, H. R. California.
Brooks, John H., Jr. New England.
Brower, James. Central States.
Brower, J. Singleton. New York.
Brown, C. U. Michigan.
Brown, Edward J. New York.
Brown, George L. Central States.
Brown, Glen V. Pennsylvania.
Brown, Ike F. Arizona.
Brown, John L., Jr. North Carolina.
Brown, Kenneth W. California.
Brown, R. F. California.
Brown, W. Fillingham. England (I. S. E.).
Browne, Floyd G. Ohio, Central States.
Bruden, C. O. Central States.
Brule, Abundius A. New England.
Brumbaugh, W. V. New York, Pennsylvania.
Brumm, Allen S. Michigan.
Brunner, Paul L. Central States.
Bryant, C. T. Ohio.
Bryant, H. M. New England.
Bryce, W. F. M. Canada.
Buchholz, Richard. Central States.
Buck, George H. New York.
Buck Hill Falls Co. Pennsylvania.
Buck, Robinson D. New England.
Buck, W. H. Dakota.
Budd, Chester B. Ohio.
Bugbee, Julius W. New England.
Bugbee, Raymond C. New England.
Bumstead, John C. New York.
Bunger, Fred C. Central States.
Bunker, F. L. North Carolina.
Burack, W. D. New Jersey.
Burchard, Edwin Day. North Carolina.
Burezak, William J. New York.
Burden, Harry P. New England.
Burdoin, Allen J. New England.
Burger, A. A. Ohio.
Burgeson, J. H. Central States.
Burgess, Harold. New York.
Burlingame, Hitchcock & Estabrook. Central States.
Burnet, J. G. England (I. S. E.).
Burnett, A. H. Canada.
Burnett, J. A. Canada.
Burnite, T. B. Rocky Mountain.
Burnside, Lewis E. Pennsylvania.
Burnson, Blair I. California.
Burns & McDonnell. Kansas.
Burr, George H. New York.
Burr, R. S. New England.
Burrell, Robert. New England.
Burrin, Thomas J. Central States.
Bushee, Ralph J. Central States.
Bush, Bernard S. Pennsylvania.
Butler, A. D. Pacific Northwest.
Butler, Emmet. Michigan.
Butterfield, C. T. Federal.
Byble, Duane. New York.
Byram, Arthur T. Canada.
Byxbee, J. F. California.

Caccia, Pio. Central States.
Caine, Richard. Iowa.
Caird, James M. New York.
Caldwell, David H. Central States.
Caldwell, H. L. Central States.
Calderara Orall J. New England.
California Corrugated Culvert Co. California.
California Packing Corporation. California.
Calkins, Lyle W. Ohio
Callen, Loy A. Central States.
Calvert, A. England (I. S. P.).
Calvert, C. K. Central States.
Cameron, A. B. Ohio.
Cameron, Geo. New Jersey.
Camp, Thomas R. New England.
Campbell, Arthur T. New England.
Campbell, Harry M. Central States.
Campbell, John. Pennsylvania.
Campbell, J. L. England (I. S. P.).
Campbell, M. S. Pacific Northwest.
Campbell, Wm., Jr. New Jersey.
Capalbo, James. New Jersey.
Capen, Charles H., Jr. New York.
Carbone, Edward A. New York.
Cardwell, Edward C. Central States.
Carey, James L. New York.
Carey, Wm. N. Central States.
Carl, Charles E. Dakota.
Carlson, H. R. Federal
Carmichael, David W. New York.
Carnahan, Charles T. Federal.
Carney, George. Michigan.
Carollo, John. Arizona.
Carpenter, Carl B. Central States.
Carpenter, George D. New York.
Carpenter, Harry C. New York.
Carpenter, Howard F. New England.
Carpenter, J. D. Pennsylvania.
Carpenter, William T. New York.
Carrique, Carlos S. Argentine.
Carson, Caryl. New England.
Carter Co., Ralph B. New York.
Cary, Willis E. New England.
Case School of Applied Science. Ohio.

Casey, City of. Central States.
Casey, John J. California.
Casey, William. Canada.
Castello, W. O. California.
Caster, Arthur. Central States.
Castro A. J., Jr. California.
Cederberg, C. R. Rocky Mountain.
Ceriat, Eugene. California.
Cerny, Paul J. New York.
Chambers, Cecil W. Federal.
Chamberlain, L. H. Central States.
Chamberlin, Noel S. New Jersey.
Chamberlain, Wm. T. New York.
Chambersburg, Boro of. Pennsylvania.
Chapman, Clarke. California.
Charlton, David. Pacific Northwest.
Chase, E. Sherman, New York, New Jersey.
Chase, H. W. Pacific Northwest.
Cheadle, Wilford G. Central States.
Chiarolla, Frank V. California.
Chicago Pump Company. New York.
Chisholm, Colin B. New York.
Christian, James B. New York.
Cipriano, Anthony G. New York.
Clapp, Milton Jr. North Carolina.
Clare, H. C. Pacific Northwest.
Clark, E. S. Central States.
Clark, H. W. England (I. S. E.).
Clark, H. W. New England.
Clark, John A. California.
Clark, J. C. California.
Clark, L. K. Dakota.
Clark, M. S. Central States.
Clark, Robert N. New York.
Clarke, V. B. New England.
Cleary, Edward J. New Jersey.
Cleland, Ralph R. Pennsylvania.
Clement, R. C. Maryland-Delaware.
Clementi, Paul T. New York.
Clements, Paul N. California.
Cleveland, E. A. Canada.
Cliff, D. P. Canada.
Clifford, W. England (I. S. P.).
Clift, M. A. New York.
Clodfelter, Howard T. Central States.
Clouser, L. H. Pennsylvania.
Clover, I. N. Ohio.
Cloyes, W. J. Pacific Northwest.
Clubb, William C. Pacific Northwest.
Coates, John J. New York.
Cobb, Edwin B. New England.
Coberly, Carroll H. Rocky Mountain.
Coblentz, J. M. Iowa.
Coburn, S. E. New England.
Cochrane, W. F. South Dakota.
Cockroft, T. N. England. (I. S. P.).
Cohen, Stuart. Federal.
Cohn, Morris M. New York, Central States.
Cole, Charles W. Central States.
Cole, E. Shaw. New York.
Colitz, Michael J. Pennsylvania.
Collard, A. E. England (I. S. E.).
Collier, H. England (I. S. E.).
Collier, James. Ohio.
Collins, A. Preston. California.
Collins, W. D. Federal.
Collins, W. H. Canada.
Collyer, Joseph C. New York.
Combs, Harold F. Central States.
Compton, C. R. California.
Comstock, Walter C. New York.
Conger, Charles C. California.
Conklin, Chester A. New York.
Connell, C. H. Texas.
Consoer, Arthur W. Central States.
Cook, Horace J. New England.
Cook, Lawrence H. California.
Cook, Max E. California.
Cook, Rodney E. New York.
Cooke, P. N. Canada.
Cooley, E. C. California.
Coombs, E. P. England (I. S. E.)
Copeland, William R. New England.
Copley, Charles H. New England.
Copple, Isaac, Pennsylvania.
Corbett, Walter E. New England.
Cordell, Miss Mona. New York.
Corey, R. H. Pacific Northwest.
Cornilsen, C. K. Central States.
Corr, Ray H. Central States.
Corrao, Joseph. California.
Corrington, C. E. Central States.
Corrington, Kingsley. Central States.
Corson, B. I. New Jersey.
Corson, H. C. Michigan.
Cortelyou, H. P. California.
Costello, John J. New York.
Cotterell, G. T. England (I. S. E.).
Cotton, Harry E. Central States.
Cottrell, H. S. New York.
Cousineau, A. Canada.
Covill, R. W. England (I. S. P.).
Cowell, John E., New York.
Cowing, Roy T. Central States.
Cowles, M. W. New Jersey.
Cox, C. R. New York.
Coy, Arthur H. New England.
Coy, Burgis. Rocky Mountain.
Craemer, George H. New England.
Craig, Clifford. Central States.
Craig, Robt. H. Pennsylvania.
Craig, W. Allan. New England.
Crane, H. R. California.
Crask, Rex. Central States.
Craun, J. M. Ohio.
Crawford, H. V. New York.
Crawn, R. D. Michigan.
Creears, T. H. California.
Critser, W. H. Ohio.
Crockett, V. P. Texas.
Crohurst, Harry R. Federal.
Croll, J. B. England (I. S. P.).
Cromer, Lyle. California.
Cromwell, Edward C. Maryland-Delaware.
Croom, Thomas G. Michigan.
Cropsey, W. H. Central States.

Cullison, Eugene F. New York.
Culp, King. Pacific Northwest.
Cummings, G. J. California.
Cummins, Walter. Ohio.
Cunningham, A. C. New England.
Cunningham, H. L. Pennsylvania.
Cunningham, John W. Pacific Northwest.
Curfew, L. S. California.
Currie, C. H. Iowa.
Currie, David H. California.
Currie, Frank S. California.
Cushing, Robert. Arizona.
Cushman, S. P. Central States.
Cutler, Charles E. Central States.
Cutting, Merritt E. New England.
Cyr, Rene. Canada.

Dallavia, Louis. Central States.
Damon, Nelson A. New England.
Damon, Wayne F. New England.
Damoose, N. G. Michigan.
Daniels, F. E. Pennsylvania.
Dappert, Anselmo F. New York.
Darby, George M. New England.
Darby, W. A. New England.
Darling, E. H. Canada.
Darling, Fred A. New England.
Darling, Orrin M. Central States.
Darnell, F. M. California.
Davey, H. W. California.
Davids, E. M. California.
Davidson, F. G. New York.
Davidson & Fulmor. California.
Davidson, Philip. Central States.
Davis, Charles A. Rocky Mountain.
Davis, E. Watson. Pennsylvania.
Davis, H. F. North Carolina.
Davis, J. H. Pacific Northwest.
Davis, P. D. North Carolina.
Davis, Walter S. New York.
Dawson, F. M. Central States.
Dawson, Lafayette Wm. Pennsylvania.
Dawson, Thomas T. Pennsylvania.
Dayton, Alfred E. New York.
Deberard, W. W. Central States.
Debrito, Jr., F. Saturnino. New York.
Debrun, John W., Jr. Central States.
Dechant, F. D. Pennsylvania.
Decker, E. P. New Jersey.
Decker, Walter. Central States.
Deckert, Christ. Central States.
Degroat, Frank N. New York.
Dehaas, Nicholas. New England.
Dehooge, Bernard A. Michigan.
Dejarnette, N. M. Georgia.
Delano, Huntley. Michigan.
De Leon, Gregorio. California.
Deleuw, C. E. Central States.
Demartini, Frank E. Federal.
Deming, Harold A. New York.
Demunn, E. M. New York.
Denise, Wm. D. New York.
Denison, W. R. Arizona.
Dennis, C. E. New York.
Depoy, A. G. Central States.
Derby, Ray L. California.
Desmarais, R. J. Canada.
Des Moines, City of. Iowa.
Deuchler, Walter E. Central States.
Devendorff, Earl. New York.
Devoe, Kermit. New Jersey.
Diamond Alkali Co. Central States.
Dick, Robert. Central States.
Dickman, Dorian H. Michigan.
Dickson, D. B. Texas.
Dickson, Harvey. Michigan.
Dickson, W. K. North Carolina.
Dieffendorf, Fred G. Pennsylvania.
Diehl, H. B. New York.
Dietrich, Paul. Central States.
Dietz, Jess C. Central States.
Dietz, John. Central States.
Dilles, Paul F. New York.
Dion, Clarence K. New England.
Disario, G. M. New England.
Dixon, C. S. Central States.
Dixon, G. Gale. Ohio.
Doane, Ercell J. Michigan.
Doan, Norman D. North Carolina.
Dobson, William T. New York .
Dobstaff, Robert, Jr. New York.
Dobstaff, Robert W., Sr. New York.
Dodge, H. P. Michigan.
Dodson, Roy E., Jr. California.
Doerr, Earl. Dakota.
Doggett, F. G. North Carolina.
Dolomite Products Co. New York.
Doman, Joseph. New York.
Domke, L. C. Central States.
Dommes, Sid F. California.
Domogalla, Bernhard. Central States.
Donaldson, Wellington. New York.
Donnell, Geo. M. Rocky Mountain.
Donohue, Jerry. Central States.
Doonan, R. E. Iowa.
Dopmeyer, A. L. Federal.
Dornbush, Don. Michigan.
Dorr, Company, Inc., The. Rocky Mountain.
Dorr, Fred M. Michigan.
Doubleday, Arnold R. Central States.
Dougherty, James E., Jr. New York.
Dougherty, Richard J. New York.
Douglass, R. M. Pennsylvania.
Dowd, Ira. Michigan.
Downer, Wm. J. Central States.
Downes, John R. New York.
Doyle, Thomas J. Michigan.
Drake, James A. Central States.
Dresselt, Edward L. New York.
Drexel, Frederick. New York.
Driscoll, Timothy J. New York.
Drummond, A. H. England (I. S. P.)
Duane, John M. New York.
Dudley, Charles E. Central States.
Duerr, Arlie. Ohio.
Duffiey, Frank J. New York.

Duffy, John J. New York.
Dumonte, Robert. Ohio.
Duncan, Roland F. California.
Dundas, Wm. A. Central States.
Dunnam, Herman. Arizona.
Dunne, E. R. New York.
Dunstan, Gilbert H. California.
Durand, Edwin M. Michigan.
Durham Water Dept. North Carolina.
Durrant, W. K. F. Canada.
Duvall, Arndt J. Central States.
Duxbury, S. England (I. S. P.).
Duy, C. Central States.
Dyckman, Warren W. New York.
Dye, Elmer E. Iowa.
Dyer, Samuel. New England.

Eager, Vernon. New York.
Early, Fred J., Jr. California.
Early, Mart. Pacific Northwest.
Easdale, W. C. England (I. S. E.).
Eastburn, W. H. Pennsylvania.
Eastman, T. F. California.
Ebaugh, G. M. Central States.
Ebert, R. E. North Carolina.
Ecusta Paper Corp. North Carolina.
Eddy, Harrison P., Jr. New England.
Edge, L. C. Georgia.
Edgecomb, George. Michigan.
Edgehoffer, Albert. New York.
Edgerley, Edward. Pennsylvania.
Edinger, Harry F. New York.
Edmonds, W. R. Canada.
Edmondson, J. H. England (I. S. P.).
Edward, William L. New York.
Edwards, B. E. Iowa.
Edwards, Gail P. New York.
Edwards, H. L. California.
Egan, J. H. California.
Eggert, E. G. Georgia.
Ehle, Virgil. New York.
Ehler, John A. New York.
Ehlers, Ralph B. Michigan.
Eich, Henry F. New York.
Eldridge, E. F. Michigan.
Electro Refractories & Alloys Corp. New York.
Eliassen, Rolf. New York.
Ellinger, Morris. California.
Elliot, S. F. Rocky Mountain.
Ellis, Albert. Central States.
Ellis, Norman T. Michigan.
Ellms, J. W. Ohio.
Ellsworth, Samuel M. New England.
Ely, E. H. England (I. S. E.).
Emerson, C. A. Pennsylvania.
Emigh, William C. Pennsylvania.
Englewood Sewerage Company. New Jersey.
English, C. C. Ohio.
English, James A. North Carolina.
English, W. B. Georgia.
Enloe, V. P. Georgia.
Enoch Pratt Free Library. Maryland-Delaware.
Enslow, L. H. New York.
Epler, J. E. Central States.
Eppley, Robert G. Pennsylvania.
Epstein, Harold. New York.
Erdle, Gardner F. New York.
Erdwurm, Emil. New York.
Erickson, Carl V. Central States.
Erickson, Una H. California.
Eriksen, Arne. Pacific Northwest.
Erzen, C. A. Central States.
Etheridge, W. England (I. S. P.).
Ettinger, M. B. Federal.
Eustance, Arthur W. New York.
Eustance, Harry W. New York.
Evans, David A. Pennsylvania.
Evans, F. M. New Jersey.
Evans, R. W. Central States.
Evans, S. C. England (I. S. P.).
Evans, Wm. J. North Carolina.
Evansky, Frank J. New York.
Everson, Mfg. Co. Central States.
Everts, C. M., Jr. Pacific Northwest.
Everts, W. S. California.

Faber, Harry A. New York.
Faccinia, Frank. California.
Fah, C. Thum. England (I. S. E.).
Fair, Gordon M. New England, New York.
Fairbanks, E. G. California.
Fairfield State Hospital. New England.
Fales, Almon L. New England.
Falls, O. M. Canada.
Fargo Engineering Co. Michigan.
Farmer, J. E. England (I. S. E.).
Farnham, Arthur B. New England.
Farnsworth, George L., Jr. Central States.
Farrant, James. New Jersey.
Farrar, J. H. California.
Farrell, Eugene J. New York.
Farrell, Michael. New York.
Farries, Gerald E. Central States.
Fassnacht, George G. New York.
Faulkner, T. G. England (I. S. E.).
Feltz, Fred C. Central States.
Fenaughty, Thomas. New York.
Fenger, J. W. New York.
Fenton, John V. New York.
Ferebee, James L. Central States.
Ferguson, G. H. Canada.
Ferguson, Gerald. New Jersey.
Fernandez, John U. New York.
Ferris, James E. New York.
Fidler, G. C. England (I. S. P.).
Field, W. T. New York.
Finch, J. England (I. S. P.).
Finch, Lewis S. Central States.
Finck, G. E. Maryland-Delaware.
Firth, E. W. New York.
Fischer, Anthony J. New York.
Fischer, Philip C. New York.
Fiscus, A. E. California.

Fishbeck, Kenneth. Michigan.
Fisher, Homer C. Central States.
Fisher, F. P. Ohio.
Fisher, L. M. Federal.
Fitch, T. A. California.
Fitzgerald, J. A. New York.
Fitzgerald, J. E., Jr. New England.
Fitzsimons, Richard H. New York.
Five, Helge. New York.
Flanagan, Jr., Joseph E. Federal.
Fleet, Gerald A. New York.
Fleming, M. C. Pennsylvania.
Fleming, Paul V. New England.
Flickinger, Lloyd H. Central States.
Flood, Frank L. New England.
Flower, G. E. Ohio.
Flowers, E. England (I. S. P.).
Foley, William M. New York.
Follett, Eli. Arizona.
Fontenelli, Louis. New Jersey.
Foote, Kenneth E. New England.
Forbes, Albert F. New York.
Ford, Curry E. Ohio.
Ford, Robert. Central States.
Foreman, Merle S. California.
Forsbeck, C. D. Pacific Northwest.
Forsberg, Ole. Central States.
Forster, M. H. New York.
Fort, Edwin J. New York.
Fortenbaugh, J. Warren. New York.
Forton, R. G. Michigan.
Foster, Herbert B., Jr. California.
Foster, Norman. Pennsylvania.
Foster, William Floyd. California.
Fowler, G. England (I. S. P.).
Francis Hankin & Co., Ltd. Canada.
Francis, Geo. W. Michigan.
Frank, Leslie C. Federal.
Franklin, W. M. North Carolina.
Franzozo, Anthony. New Jersey.
Fraschina, Keeno. California.
Fraser, Charles E. Canada.
Frawley, Daniel. New York.
Frazier, R. W. Central States.
Fredson, Anthony. Central States.
Freeborn, W. F. England (I. S. P.).
Freeburn, H. M. Pennsylvania.
Freeland, B. H. Central States.
Freeman, A. B. Federal.
French, R. Del. Canada.
Frenchman, J. L. New Jersey.
Frerking, A. G. Kansas.
Freund, J. P. Pennsylvania.
Frick, A. L. California.
Frick, Edward J. Ohio.
Frickstad, Walter N. California.
Friel, F. S. Pennsylvania.
Frisk, Paul W. North Carolina.
Frith, Gilbert R. Georgia.
Froehde, F. C. California.
Fuchs, A. W. Federal.
Fuhrman, Ralph E. Federal.
Fuller, Andrew J. New York.
Fuller, N. M. New York.
Fulmer, F. B. California.
Fulmer, Frank E. Central States.
Fulton, E. A. Central States.
Funk, John B. Maryland-Delaware.
Furphy, H. G. England (I. S. P.).

Gadomski, Albert J. New Jersey.
Gahagan, H. B. Michigan.
Gail, A. L. Central States.
Galata, Richard L. New York.
Ganshaw, Elmer. New York.
Gardner, George W. New York.
Gardner, R. T. California.
Garland, Chesley F. Maryland-Delaware.
Garner, J. H. England (I. S. P.).
Garrison, Peter L. Central States.
Garthe, E. C. Federal.
Gartner, W. H. Central States.
Garwood, Kirk. Iowa.
Gates, Justin F. New York.
Gates, Lloyd R. Michigan.
Gauntt, W. C. Texas.
Gavett, Weston. New York.
Gearhart, John C. Pacific Northwest.
Gehm, Harry Willard. New Jersey.
Gelbke, Arthur W. New York.
Gelder, R. W. Rocky Mountain.
General Electric Company. California.
Genter, Albert L. Maryland-Delaware.
Gerard, F. A. Central States.
Gerardi, Angelo P. New York.
Gerdel, W. E. Ohio.
Gere, William S. New York.
Gerecke, Edward R. New York.
Germond, Earl. New York.
Geupel, Louis A. Central States.
Geyer, John C. Maryland-Delaware.
Gibbons, M. M. New Jersey.
Gibeau, H. A. Canada.
Gidley, H. K. Pennsylvania.
Giesey, J. K. Central States.
Gifford, J. B. Central States.
Gilbert, A. J. Arizona.
Gilbert, Joseph J. Pennsylvania.
Gilcreas, F. Wellington. New Jersey, New York
Giles, J. Henry L. New England.
Gilkey, A. E. California.
Gill, A. F. Canada.
Gill, J. Francis. New York.
Gill, Paul. Pennsylvania.
Gillard, J. E. England (I. S. P.).
Gillespie, C. G. California.
Gillespie, Jr., Robert L. New York.
Gillet, R. T. England (I. S. E.).
Gilman, Floyd. New York.
Gilman, N. A. Pacific Northwest.
Ginsberg, S. D. Central States.
Gisborne, Frank R. New England.
Glace, I. M. Pennsylvania.
Gladding, Charles. California.
Gladue, Donat J. New England.

Glynn, William J. New York.
Gneagy, Harold. Central States.
Goff, James S. New England.
Goff, William A. Pennsylvania.
Goforth, W. W. Canada.
Goldenberg, Charles N. Rocky Mountain.
Goldsmith, Philip. New York.
Goldthorpe, H. H. England (I. S. P.).
Golly, M. R. Central States.
Gooch, E. W. Pacific Northwest.
Goodenough, Frank H. New York.
Goodman, Arnold H. Central States.
Goodridge, Harry. California.
Gordon, J. B. Federal.
Gorman, R. C. New York.
Gorman, William A. Pennsylvania.
Gotaas, Harold B. North Carolina.
Gottschalk, Harry. Central States.
Goudey, R. F. California.
Gough, T. England (I. S. P.).
Gould, Richard H. New York.
Grabbe Construction Co. Central States.
Grabowski, John J. Pennsylvania.
Grace, C. F. Pennsylvania.
Grace, Francis J. New York.
Grady, Robert H. North Carolina.
Graemiger, Joseph A. New England.
Graham, Edward J. New York.
Graham, J. A. England (I. S. P.).
Graham, James E. Michigan.
Gran, John E. Georgia.
Grand Junction, City of. Rocky Mountain.
Grant, Arthur J. California.
Grassie, C. A. Canada.
Gray, D. M. Ohio.
Gray, Harold F. California.
Gray, Odell W. Georgia.
Greek, Edward B. Central States.
Greeley, Samuel A. Central States.
Green, Carl E. Pacific Northwest.
Green, Herbert. New England.
Green, Howard R. Iowa.
Green, R. A. Michigan.
Green, Tom C. Texas.
Greendale, Village of. Central States.
Greenleaf, John W., Jr. New England.
Greenlee, J. L. North Carolina.
Greenwich Sewer Commission. New England.
Gregory, L. L. England (I. S. E.).
Gregory, Robert W. North Carolina.
Gregory, Ted R. California.
Greig, John M. M. New York.
Grelick, David. New York.
Grieff, Victor C. New York.
Griffen, F. T. New York.
Griffin, Guy E. New England.
Griffin, Ralph J. Central States.
Grinnell Co., Inc. North Carolina.
Groeu, Michael A. Michigan.
Gross, Carl D. Central States.
Gross, Dwight D. Rocky Mountain.
Grossart, L. J. H. Pennsylvania.
Grosshans, Edward W. Central States.
Grover, R. H. New York.
Growdon, Howard C. Ohio.
Grunsky, Eugene L. California.
Gruss, A. W. California.
Gulden, H. B. Pennsylvania.
Gustafson, Ivar. Michigan.
Gwin, Lewis L. Pennsylvania.
Gyatt, W. P. New York.

Haberer, John C. New York.
Habermehl, C. Austin. Michigan.
Haddock, Fred R. Pennsylvania.
Haemmerlein, Victor E. New York.
Hageman, Roy C. Central States.
Hager, Fred. Central States.
Hagerty, L. T. Ohio.
Hagestad, Herman T. Central States.
Hahn, Howard. Central States.
Hale, Arnold H. New York.
Hall, Claude R. Pacific Northwest.
Hall, G. Albro. Ohio.
Hall, G. D. Pacific Northwest.
Hall, Frank H. New York.
Hall, Fred B. New York.
Hall, Hilliard D. Arizona.
Hall, Harry R. Maryland-Delaware.
Hall, M. G. Iowa.
Hall, W. H. North Carolina.
Hallden, John T. Central States.
Hallock, Emerson C. New York.
Halm, Ernest W. New York.
Halpin, John. New York.
Halstead, Douglas M. New York.
Hambleton, F. T. England (I. S. P.).
Hamel, Edouard. Canada.
Hamilton, R. F. Pacific Northwest.
Hamlin, C. H. England (I. S. P.).
Hamm, William C. New York.
Hammond, F. D. Central States.
Hammond, F. G. New York.
Handley, L. W. Georgia.
Haneman, A., Jr. Texas.
Hanenberg, A. L. Canada.
Haney, Joseph E. Central States.
Haney, Paul. Kansas.
Hanke, Carl C. Central States.
Hanrath, William J. New England.
Hansell, Wm. A. Georgia.
Hansen, August E. New York.
Hansen, Paul. Central States.
Hansford, Albert E. Canada.
Hanson, George I. New England.
Hanson, John R. New York.
Hapgood, E. P. California.
Hardenbergh, W. A. New York.
Harding, J. C. New York.
Harding, Robert G. California.
Hardinge, Company. New York.
Hardman, Thomas J. Central States.
Hardy, W. R. Texas.
Harley, Frank E. New Jersey.
Harmeson, D. K. Central States.
Harmon, Jacob A. Central States.

Harmon, Judson A. California.
Harper, Charles E. Central States.
Harper, M. J. New England.
Harrington, J. H. California.
Harris, C. H. Ohio.
Harris, George C. Central States.
Harris, R. C. Canada.
Harris, Roy M. Pacific Northwest.
Harrison, Bert. Pacific Northwest.
Harrison, Edward F. New York.
Harroun, F. E. Ohio.
Hart, Charles G. New York.
Hart, W. B. Pennsylvania.
Hartman, B. J. Central States.
Hartman, Byron K. Central States.
Hartung, N. E. Central States.
Hartzell, E. F. Pennsylvania.
Harvey, Carl. New York.
Harvey, J. R. Pennsylvania.
Harwell, A. A. Arizona.
Haseltine, T. R. Pennsylvania.
Hasfurther, William A. Central States.
Haskins, Chas. A. Missouri.
Haste, J. R. Central States.
Hatch, B. F. Ohio.
Hatch, G. M. Texas.
Hatfield, W. D. Central States.
Hathaway, A. S. Central States.
Hauck, Charles F. Ohio.
Hauer, G. E. Michigan.
Havens, William L. Ohio.
Hawken, Dalton. Michigan.
Hawley, Arthur A. New York.
Haworth, J. Victor. Pennsylvania.
Haworth, W. D. England (I. S. E.).
Hawtrey, R. O. Canada.
Hay, Julian A. Central States.
Haydock, Chas. Pennsylvania.
Hayes, John A. New York.
Hayler, Geo. R. California.
Hayward, Homer. Michigan.
Haywood, R. W., Jr. North Carolina.
Hazen, Richard. New York.
Healy, William A. New England.
Heaslit, Walter. Rocky Mountain.
Hedgepeth, L. L. Pennsylvania.
Hedges, Horace P. New York.
Heeg, Herman H. Michigan.
Heffelfinger, D. D. Ohio.
Heger, Harold. Central States.
Heider, Robert W. Central States.
Hein, Walter E. Central States.
Heinemann, B. New Jersey.
Heiple, Loren R. Central States.
Heisig, Henry M. Central States.
Heiss, Edward A. Pacific Northwest.
Helland, H. R. F. Texas.
Henderlite, J. H. North Carolina.
Henderson, Chas. F. New York.
Henderson, C. N. New Jersey.
Hendon, H. H. New York.
Hendrie & Bolthoff Mfg. & Supply. Rocky Mountain.
Hendrix, George K. Central States.
Heneghan, George P. Central States.
Henel, Wm. F. New York.
Henkel, George E. New Jersey.
Henn, Donald E. Central States.
Henry, Augustine. New York.
Henry, B. F. California.
Herberger, Arthur Henry. New York.
Hermann, Frank. Central States.
Herr, H. N. Pennsylvania.
Herrick, T. L. Central States.
Herringer, Elmer J. Federal.
Hersig, S. B. Central States.
Hesford, L. England (I. S. E.).
Hess, Joseph C., Jr. Pennsylvania.
Hess, Seth G. New York.
Hetherington, W. G. Central States.
Heubi, Thomas. New York.
Heukelekian, H. New Jersey.
Hewitt, A. C. Pennsylvania.
Heydon, F. G. Central States.
Heyward, T. C. North Carolina.
Hibschman, Charles A. Pennsylvania.
Hicks, Geo. W. Central States.
Hicks, R. England (I. S. P.).
Higgins, William J. New York.
Highberger, W. W. New York.
Hilborn, Gerald. Pennsylvania.
Hill, Frank C. Rocky Mountain.
Hill, G. Everett. New York.
Hill, K. V. Central States.
Hill, Theo. C. Pennsylvania.
Hill, W. R. Pacific Northwest.
Hiller, Paul W. New England.
Hilton, Elton M. California.
Hinman, Jack J. Iowa.
Hinyard, J. N. Texas.
Hircock, Chas. W. Arizona.
Hirschel, Leslie. New York.
Hitchcock, Simon E. Canada.
Hitchner, A. H. California.
Hoad, William C. Michigan.
Hoak, Richard D. Pennsylvania.
Hobson, N. C. Canada.
Hockley, C. P. Pacific Northwest.
Hodge, W. W. Pennsylvania.
Hodges, H. E. W. England (I. S. E.).
Hodgin, S. W. Central States.
Hodgson, E. England (I. S. P.).
Hodgson, H. J. N. England (I. S. P.).
Hoeflich, G. C. Pennsylvania.
Hoefling, Wm. L. New York.
Hoey, John B. New York.
Hoff, Clarence W. Pennsylvania.
Hoffert, J. R. Pennsylvania.
Hogan, J. W. T. New York.
Hogan, William J. New York.
Hoganson, Lester O. Central States.
Hogg, Alex M. Canada.
Holbrook, A. R. New York.
Holden, E. G. Rocky Mountain.
Holderby, J. M. Central States.
Holderman, John S. Central States.

Holland, Frank H. New York.
Hollis, L. M. Federal.
Holloway, Frank M. New York.
Holmes, Glenn D. New York.
Holmes, Harry E. New England.
Holmgren, Richard F. New England.
Holmquist, Chas. A. New York.
Holroyd, A. England (I. S. P.).
Holst, J. S. Dakota.
Holter, A. L. Pacific Northwest.
Holtkamp, Leo. Iowa.
Holway, O. G. Central States.
Hommon, H. B. Federal.
Honens, R. W. Central States.
Honigman, Elkono G. New York.
Hoover, C. B. Ohio.
Hoover, Charles R. New England.
Hopkins, E. S. Maryland-Delaware.
Hopkins, L. S. R. New York.
Hopkins, O. C. Federal.
Hopper, Allen O. New York.
Horne, Ralph W. New England.
Horton, F. C. California.
Hoskins, J. K. Federal.
Hoskins, Nandy. England (I. S. E.).
Hoskinson, Carl M. California.
Hotchkiss, H. T., Jr. New York.
Hoth, Fred. Central States.
Houlihan, J. E. England (I. S. P.).
Houser, C. S. Ohio.
Houser, George C. New England.
Houston, W. J. Georgia.
Howard, C. M. Pacific Northwest.
Howard, N. J. Canada.
Howard, P. F. New England.
Howarth, J. P. England (I. S. P.).
Howe, Ben V. Rocky Mountain.
Howell, Eugene M. Rocky Mountain.
Howland, W. E. Central States.
Howson, J. T. New York.
Howson, L. R. Central States.
Hoy, J. R. Georgia.
Hoydar, A. L. Pacific Northwest.
Hoyle, W. H. England (I. S. P.).
Hromada, Frank. Central States.
Hubbard, Winfred D. New York.
Hubel, J. H. Canada.
Huber, Harold J. New York.
Huckeba, W. L. Georgia.
Hudson, Laverne D. Central States.
Huebner, Ludwig. California.
Hughes, W. P. Pacific Northwest.
Hulak, S. M. New York.
Hull, S. P. Central States.
Hults, William S., Jr. New York.
Humphrey & Sons, Howard. England (I. S. P.).
Hunt, L. W. Central States.
Hunter, A. England (I. S. P.).
Hunter, Harry. Central States.
Hupp, John E., Jr. Central States.
Hurd, Charles H. Central States.
Hurd, Edwin C. Central States.
Hurley, J. England (I. S. P.).
Hurst, William C. New York.
Hursting, R. C. Central States.
Hurwitz, Emanuel. Central States.
Hutchins, Will A. Central States.
Hutcheson, H. D. New York.
Huth, Norman A. California.
Hyde, Charles Gilman. California.
Hynes, H. A. Pennsylvania.

Illig, Louis. New York.
Illinois Dept. of Public Health. Central States.
Imbt, M. Russell. Pennsylvania.
Indiana State Board of Health. Central States.
Industrial Chemical Sales Co. Inc. New York.
Inertol Company. New York.
Ingols, Robert. New Jersey.
Ingram, Fred R. California.
Ingram, Wm. T. California.
International Filter Co. Central States.
Irwin, G. M. Canada.
Iscol, George. New York.

Jack, D. Canada.
Jack, Grant R. Canada.
Jacka, S. C. Michigan.
Jackson, J. Frederick. New England.
Jackson, James A. Central States.
Jackson, R. B. Michigan.
Jackson, T. B. Pacific Northwest.
Jackson, T. L. Michigan.
Jacobs, L. L. Georgia.
Jacobson, John. California.
Jarrett, J. M. North Carolina.
Jarvis, Alec C. England (I. S. P.).
Jeffrey, H. H. California.
Jellema, John F. Michigan.
Jenckes, J. Franklin, Jr. New England.
Jenks, Glen. Rocky Mountain.
Jenks, Harry N. California.
Jenne, Lyle L. Pennsylvania.
Jennings, A. England (I. S. P.).
Jennings, L. R. Michigan.
Jensen, Emil C. Pacific Northwest.
Jepson, C. England (I. S. P.).
Jeup, Bernard H. Central States.
Jewell, H. W. California.
Jewett, Herbert A. California.
Johns-Manville Corp. New York.
Johnson, Arthur H. Central States.
Johnson, Clement. New York.
Johnson, Earle P. Pennsylvania.
Johnson, Eskil C. New England.
Johnson, Floyd E. Central States.
Johnson, Francis M. North Carolina.
Johnson, Harry B. Pennsylvania.
Johnson, Herbert O. New York.
Johnson, John W. New York.
Johnson, L. J. Central States.
Johnson, Lloyd M. Central States.

Johnson, R. J. Central States.
Johnson, Verner C. California.
Johnson, W. T. Central States.
Johnson, Warren W. Kansas.
Johnson, W. H. England (I. S. P.).
Joiner, W. H. Texas.
Jonas, Milton R. Central States.
Jones, C. B. O. England (I. S. P.).
Jones, Daniel. New York.
Jones, Everett M. Pennsylvania.
Jones, Frank. Michigan.
Jones, Frank Woodbury. Ohio.
Jones, Howard H. Central States.
Jones, S. Leary. Federal.
Jones, T. A. Georgia.
Jones, Wayland. California.
Jordan, Edward C. New England.
Jordan, Harry B. New York.
Jorgensen, Homer W. California.
Joy, C. Fred, Jr. New England.

Kachmar, John F. Federal.
Kachorsky, M. S. New Jersey.
Kafka, John. Central States.
Kaiser, William B. New York.
Kaler, P. E. Kansas.
Kalste, Arthur. Central States.
Kammerling, Lane. Michigan.
Kane, James I. Central States.
Kappe, S. E. Pennsylvania.
Karalekas, Peter C. New England.
Karsa, William J. New York.
Kasperski, Frank E. Pennsylvania.
Kasser, Victor H. Central States.
Kass, Nathan I. New York.
Kay, L. A. Canada.
Kearney, E. W. North Carolina.
Keatly, C. R. Pennsylvania.
Kee, William J. New Jersey.
Keefer, C. E. Maryland-Delaware.
Keefer, R. K. Pennsylvania.
Keeler, J. Harold. New York.
Kehoe, Daniel J. New York.
Kehr, Robert W. Federal.
Kehr, Wm. Q. Missouri.
Keirn, K. A. New York.
Kelleher, Joseph A. New York.
Kelleher, Joseph A. New Jork.
Keller, Jacob. New York.
Keller, Lyndon M. New York.
Kelley, R. E. Michigan.
Kellogg, Clarence E. New York.
Kellogg, James W. North Carolina.
Kelly, Clarence. New York.
Kelly, Earl M. California.
Kelsey, Walter. Pennsylvania.
Kempkey, A. California.
Kemp, Harold A. New York.
Kennedy, C. C. California.
Kennedy, D. R. California.
Kennedy, R. R. California.
Kennedy, William. New York.
Kennedy, W. R. New York.
Kenney, Norman D. Maryland-Delaware.
Keown, Roy L. Georgia.
Kepner, Dana E. Rocky Mountain.
Kershaw, Arnold. England (I. S. P.).
Kessener, Ir. H. England (I. S. P.).
Kessler, Lewis H. Central States.
Ketcham, Charles G. New York.
Ketcham, Joseph M. New York.
Kewer, J. F. Central States.
Keyes, Harmon Edward. Arizona.
Kiker, John E., Jr. New York.
Kilcawley, Edw. J. New York.
Killam, E. T. New Jersey.
Killmar, C. M. Michigan.
Kimball, Jack H. California.
Kimberly, A. E. Ohio.
Kimler, Alexander. New York.
King, Henry R. Central States.
King, Kenneth K. Federal.
King, Richard. Central States.
King, William B. North Carolina.
Kingsbury, N. H. Central States.
Kingston, Paul S. Central States.
Kin, Stephen R. New York.
Kinney, E. F. Central States.
Kinney, J. B. Canada.
Kinsel, H. L. Pennsylvania.
Kinsey, L. B. Central States.
Kinsman, Frederick. California.
Kirchoffer, W. G. Central States.
Kirkpatrick, John W. Central States.
Kirsner, Charles. New York.
Kivari, A. M. California.
Kivell, W. A. New York.
Kjellberg, G. California.
Klang, Marvin. Michigan.
Klassen, C. W. Central States.
Klegerman, M. H. New York.
Kleiser, Paul J. Central States.
Klemme, Wm. W. New York.
Klinck, Frank. New York.
Kline, H. S. Ohio.
Klingbeil, Ray J. Ohio.
Klippel, Floyd. Iowa.
Knapp, H. A. Georgia.
Knechtges, O. Central States.
Knez, Cosmo M. New York.
Knight, Ray R. Canada.
Knittel, E. A. Pacific Northwest.
Knoedler, H. A. California.
Knowlton, Kenneth F. New England.
Knowlton, W. T. California.
Knox, Stuart K. New Jersey.
Knox, W. H. Ohio.
Koch, Philip L. Central States.
Kochin, Milton. Pennsylvania.
Kochititzky, O. W., Jr. Federal.
Koebig & Koebig. California.
Koetz, Lester. Central States.
Kolb, Fred W. California.
Koon, Ray E. Pacific Northwest.
Koplowitz, Sol. New York.
Korfmacher, John A. Central States.

Kozma, Albert B. New York.
Kraft, George M. Central States.
Kramer, David. Iowa.
Kramer, Harry P. Central States.
Kratz, Herman. Maryland-Delaware.
Kraus, L. S. Central States.
Krell, A. J. New York.
Kremer, Robert W. Pennsylvania.
Kressly, Paul E. California.
Kretschmar, G. G. Pacific Northwest.
Kreutter, Clarence. New York.
Kriegel, Paul O. New York.
Kronbach, Allan. Michigan.
Krohn, William. California.
Krum, Harry J. Pennsylvania.
Krumm, Harry J. Pennsylvania.
Kruniek, M.D. Ohio.
Kuhl, F. A. Central States.
Kulberg, Abraham J. New York.
Kulin, Harvey J. Central States.
Kulisch, Harry. Central States.
Kuhner, Frank G. Central States.
Kunowski, Peter. New York.
Kunsch, Walter. New England.
Kunze, Albert T. Michigan.
Kupper, C. J. New Jersey.
Kyte, W. O. California.

Lackey, J. B. Federal.
Ladue, Charles J. Michigan.
Lafreniere, Theo. J. Canada.
Lakeside Engineering Corp. Central States.
Lamb, Clarence F. New England.
Lamb, Miles. Central States.
Lamb, P. England (I. S. P.).
Lambert, Francis J. New York.
Lamoureux, Vincent B. Federal.
Lamson, B. F. Canada.
Lanigan, John A. Michigan.
Lang, Lloyd. Central States.
Langdon, L. E. Central States.
Langdon, Paul E. Central States.
Lange, John F. New York.
Langelier, Wilfred F. California.
Langford, Leonard L. New York.
Langwell, Louie. Central States.
Lannon, William. New England.
Lanphear, Roy S. New England.
Larkin, W. H. New York.
Larsen, Earnest A. New York.
Larsen, Stanley J. Central States.
Larson, C. C. Central States.
Larson, Keith D. Central States.
Larson, L. L. Central States.
Lassiter, Leroy Irving. North Carolina.
Lauer, Charles N. Pennsylvania.
Laughlin, W. C. New York.
Lauster, K. C. Dakota.
Lavalley, Edward C. New York.
Laverty, Francis J. New York.
Lawlor, Jerome N. New York.
Lawrence, John. New York.
Lawrence, William H. New York.
Lawson, W. S. Canada.
Lawton, George. Michigan.
Lea, J. E. England (I. S. P.).
Lea, Wm. L. Central States.
Lea, W. S. Canada.
Leach, Walter L. Ohio.
Leahy, S. James. New York.
Lebetkin, George. New England.
Lebosquet, M., Jr. Federal.
Leclere, Arthur B. North Carolina.
Ledford, George L. New York.
Ledwith, James J. New York.
Lee, Charles H. California.
Lee, Oliver. Central States.
Leemaster, J. F. Michigan.
Lefebvre, Fabian J. New York.
Lefever, R. W. California.
Leh, Willard. Pennsylvania.
Lehman Sewer Pipe Co., Inc. New York.
Lehmann, Arthur F. New Jersey.
Lehmker, William. Central States.
Lehner, Walter J. Michigan.
Lehr, Eugene L. New England.
Leiby, F. E. New York.
Leigh, H. G. England (I. S. P.)
Leist, Ervin F. Ohio.
Leitch, John C. Georgia.
Leland, Ben J. Central States.
Leland, Raymond I. Central States.
Lendall, Harry N. New Jersey.
Lenderink, Andrew. Michigan.
Lenert, Louva G. Georgia.
Lentfoehr, Charles E. Central States.
Leonard, O. M. Central States.
Leonard, W. V. Pacific Northwest.
Leonhard, Harold M. Michigan.
Lesher, C. E. Michigan.
Lesher, Carl. Ohio.
Lessig, D. H. Central States.
Lesslie, John N., Jr. North Carolina.
Levan, J. H. Federal.
Levine, Max. Iowa.
Levy, Harry W. New York.
Lewis, Clay W. Kansas.
Lewis, E. S. Arizona.
Lewis, John V. New York.
Lewis, R. K. Central States.
Lewiston, City of. Rocky Mountain.
Liddle, E. G. Michigan.
Lieber, Maxim. New York.
Limestone Products Corp. of America. New York.
Lind, A. Carlton. Central States.
Lind, Gunner W. Central States.
Lindell, O. V. Missouri.
Linders, Edward. Federal.
Lindsten, H. C. North Dakota.
Link Belt Company. New York, Pennsylvania, Central States.
Lingo, H. L. Kansas.
Linsley, Scott E. Central States.
Lippelt, Hans B. New York.
Littman, M. L. New Jersey.

Livingston, L. E. Texas.
Lock Joint Pipe Co. Rocky Mountain.
Locke, Edwin A. New England.
Lockett, W. T. England (I. S. P.).
Long, H. Maynard. Central States.
Long, George S. Pennsylvania.
Long, James C. New Jersey.
Loomis, Harry E. New York.
Lord & Burnham Co. New York.
Lord, Herbert O. Central States.
Los Angeles Public Library. California
Lose, Charles, III. New York.
Lose, Charles, Jr. New York.
Losee, James R. New York.
Louis, Leo. Central States.
Lounsbury, Elmer Irving. New England.
Lovejoy, W. L. Pacific Northwest.
Lovell, M. L. North Dakota.
Lovell, Theodore R. Iowa.
Lovett, M. England (I. S. P.).
Lowe, Thomas M. Georgia.
Lower, J. R. Ohio.
Lowther, Burton. California.
Lozier, William S. New York.
Lubow, Louis A. North Carolina.
Lubrecht, Frank S. Pennsylvania.
Lucas, W. R. Michigan.
Ludwig, Harvey F. California.
Luebbers, Ralph H. Missouri.
Lueck, Bernard F. Central States.
Luff, Reginald. Pennsylvania.
Luippold, G. T. California.
Lumb, C. England (I. S. P.).
Lund, Ralph F. California.
Lustig, Joseph. Central States.
Luther, L. L. New York.
Luther, Robert W. North Carolina.
Luton, Max. Rocky Mountain.
Lutz, Howland G. Pennsylvania.
Lynch, Daniel E., Jr. New York.
Lynch, James T. New York.
Lyndes, H. E. Rocky Mountain.
Lyon, A. S. North Carolina.

McAdoo & Allen Welting Co. Pennsylvania.
McAllister, Paul J. Pennsylvania.
McAnlis, Chauncey R. Central States.
McBreen, Charles. New York.
McBride, J. L. California.
McCall, Joseph F. New England.
McCallum, G. E. Federal.
McCannel, D. A. R. Canada.
McCarthy, J. J. Central States.
McCarthy, Justin J. New York.
McCarthy, William F. New York.
McCleary, E. L. Pacific Northwest.
McClenahan, W. J. Central States.
McClintock, H. C. Rocky Mountain.
McClure, Ernest. Central States.
McCoy, M. H. Central States.
McCrae, K. C. England (I. S. E.).
McDill, Bruce M. Ohio.
McDonald, John. New England.
McDonald, Michael D. New York.
McDonald, N. G. Canada.
McDonald, Roland G. New York.
McDonnell, George H. New York.
McDuell, John W. California.
McFarlane, W. D. Michigan.
McFaul, W. L. Canada.
McGrath, C. P. Michigan.
McGuire, C. D. Ohio.
McGuire, M. H. Pacific Northwest.
McIlvaine, Wm. D., Jr. Central States.
McInerney, Gerald J. New York.
McIntyre, Frank J. Ohio.
McIntyre, John C. Central States.
McKee, Frank J. Central States.
McKee, Jack E. New England.
McKeeman, Edwin C. New York.
McKenna, Harold R. Michigan.
McKinlay, Daniel. California.
McLaughlin, Carroll W. New York.
McLaughlin, R. M. New York.
McLean, Clement. New York.
McLean, R. F. Pacific Northwest.
McMahon, Walter A. New England.
McMenamin, C. B. New Jersey.
McMillan, Donald C. California.
McMorrow, Bernard J. California.
McNamara, W. P. Pacific Northwest.
McNamee, Paul D. Federal.
McNeal, Leonard. Ohio.
McNiece, L. G. Canada.
McPhail, James L. New York.
McRae, John. Michigan.
McShea, James. New York.
McWilliams, D. B. Canada.
MacAbee, L. Cedric. California.
MacCallum, C. New York.
MacLeod, Myron. New England.
MacCrea, J. M. New York.
MacDonald, G. A. Canada.
MacDonald, Hugh H. California.
MacDonald, J. C. Central States.
MacDowell, R. F. Ohio.
MacIntire, Kenneth. Pacific Northwest.
MacKenzie, C. J. Canada.
MacKenzie, Vernon G. Federal.
MacKin, John C. Central States.
MacLachlan, Angus. Ohio.
MacLean, J. D. Canada.
MacLaren, J. F. Canada.
MacLaren, L. A. Canada.
MacMurray, L. C. Maryland-Delaware.
MacNicol, N. Canada.
Madison, James W. Central States.
Magee, George W. New York.
Mahlie, W. S. Texas.
Maier, F. J. Federal.
Malcolm, Wm. L. New York, Canada.
Malick, Anthony J. New York.
Mallalieu, W. C. New Jersey.
Mallmann, W. L. Michigan.
Mallory, Edward B. New York.
Malloy, Howard. Michigan.

Malone, J. R. North Carolina.
Malony, W. L. Pacific Northwest.
Makepeace, W. H. England (I. S. P.).
Maguire, Chas. C. New England.
Mann, Alfred H. New York.
Mann, Uhl T. New York.
Mannes, Arthur S. Dakota.
Mannheim, Robert. New England.
Manning, P. Canada.
Mansfield, M. G. Pennsylvania.
Manteufel, Lawrence A. Central States.
Manz, Erwin C. Pennsylvania.
Mariner, W. S. New England.
Marrs, Paul. New York.
Marsh, H. M. Canada.
Marshall, E. A. New York.
Marshall Field Co. North Carolina.
Marshall, J. C. Michigan.
Marshall, Leslie S. New York.
Marshall, W. B. New York.
Martens, L. P. Central States.
Martin, A. E. New York.
Martin, Alexander G. New York.
Martin, Edward J., Jr. New York.
Martin, George C. Central States.
Martin, Geo. H., Jr. New York.
Martin, Phil J. Arizona.
Martin, Sylvan C. Central States.
Martin, Warren S. New York.
Marx, Frank. New York.
Maryland State Dept. of Health. Maryland-Delaware.
Marzec, E. J. Iowa.
Mason, Clarence A. Central States.
Mather, Edward K. Dakota.
Mathers, George. New York.
Matthew, R. P. California.
Mathews, E. R. Dakota.
Mathews, Frank E. Pacific Northwest.
Mathews, Henry M. Georgia.
Mathews, L. R. Central States.
Mathews, Richard. Michigan.
Mathews, W. W. Central States.
Mathis, Alice. Arizona.
Matter, L. D. Pennsylvania.
Mattheis, Clarence. Central States.
Mattimoe, George E. California.
Mattson, Walfrid I. Central States.
Mauldin, P. L. California.
Maurer, Peter J. Central States.
Max, John. Michigan.
Maxwell, G. E. Canada.
Maxwell, W. E. New York.
May, D. C. Michigan.
May, Harold L. California.
Meade, F. Griffith. Arizona.
Meadors, L. B. Central States.
Meats, G. R. E. England (I. S. P.).
Mechler, Louis W. California.
Meeker, Robert H. Kansas.
Megregian, Stephen, Jr. Federal.
Meiers, Walter W. New York.
Menantico Sand & Gravel Company. Pennsylvania.
Mendelsohn, I. W. New York.
Menefee, J. H. Missouri.
Meneke, K. E. Central States.
Mengel, Carl W. North Carolina.
Menzies, D. B. Canada.
Menzies, J. Ross. Canada.
Markel, Paul P. Pennsylvania.
Meron, L. A. New York.
Merrill, Walter E. New England.
Merritt, Will D. North Carolina.
Merryfield, Fred. Pacific Northwest.
Merwin, Willard. Central States.
Merz, H. Spencer. Central States.
Meserva, Charles. Michigan.
Metz, Roy L. Central States.
Meyer, Carl F. New England.
Meyer, Louis. California.
Michaels, John M. E. New York.
Mick, K. L. Central States.
Mickle, Chas. T. Central States.
Middleton, Francis M. Federal.
Miick, Fred E. California.
Miles, Henry J. New Jersey.
Milinowski, Arthur S. Central States.
Miljevic, Nicholas. New York.
Miller, A. J. Central States.
Miller, A. P. Federal.
Miller, A. Stuart. England (I. S. P.).
Miller, Alden W. Arizona.
Miller, David R. Central States.
Miller, E. P. Central States.
Miller, Fred M. New York.
Miller, J. John. Pennsylvania.
Miller, L. A. Central States.
Miller, Robert G. Iowa.
Miller, Roy. Pennsylvania.
Miller, W. C. Canada.
Miller, Wallace T. New York.
Milligan, Francis B. Pennsylvania.
Milliken, H. E. New York.
Milling, Martin A. Central States.
Mills, S. W. Canada.
Minneapolis-St. Paul San. Dist. Central States.
Mitchell, Ansel N. Kansas.
Mitchell, Geo. W.
Mitchell, Louis. New York.
Mitchell, Robert D. South Dakota.
Mittelstaedt, R. E. California.
Moat, C. P. New England.
Mock, Alvin M. Ohio.
Mogelnicki, Stanley J. Michigan.
Moggio, Wm. A. North Carolina.
Mohlman, F. W. Central States.
Molitor, Paul. California.
Moloney, Grant. Canada.
Monn, Edgar P. Pennsylvania.
Monroe, Lowell W. Pennsylvania.
Monroe, S. G. Federal.
Monsell, Harry M. New York.
Montagna, S. D. Pennsylvania.

Montes, Jose Garcia, Jr. England (I. S. E.).
Montgomery, J. Robert. Michigan.
Montreal Sewers Comm. Canada.
Mooney, Earl E. New York.
Moor, W. C. Texas.
Moore, Charles A. Pennsylvania.
Moore, Edward W. New England.
Moore, F. Owen. England (I. S. E.).
Moore, G. W. New York.
Moore, George S. North Carolina.
Moore, Herbert. Central States.
Moore, R. B. Central States.
Moore, W. A. Federal.
Morgenroth, Fritz. New York.
Morehouse, W. W. Ohio.
Morey, Burrows. New York.
Morgan, Edward F., Jr. New England.
Morgan, L. S. Pennsylvania.
Morgan, P. F. Central States.
Morkert, Kenneth. Central States.
Morrell & Company, John. Iowa.
Morrill, Arthur. Michigan.
Morris, Arval. California.
Morris, Lee. Dakota.
Morris, Paul J. Pennsylvania.
Morrison, C. B. California.
Morrow, Ben. Central States.
Moseley, Harry H. Ohio.
Moses, H. E. Pennsylvania.
Moss, F. J. Federal.
Mott, C. A. Canada.
Mount Penn, Borough of. Pennsylvania.
Mountfort, L. F. England (I. S. P.).
Mowbray, George A. New York.
Mower, Stanley E. New York.
Mowry, Robert B. Pennsylvania.
Mudgett, C. T. Michigan.
Muegge, O. J. Central States.
Mulcahy, James P. New York.
Muldoon, Joseph A. New England.
Mulvaney, M. B. Central States.
Munding, Germaine G. New York.
Mundt, Charles H. New York.
Munford, G. England (I. S. P.).
Munro, A. D. England (I. S. E.).
Munroe, E. H. Canada.
Munroe, W. C. Maryland-Delaware.
Munson, Laura A. California.
Murdock, Charles R. Canada.
Murdock, William. Pennsylvania.
Murphy, John A. Central States.
Murphy, Lindon J. Iowa.
Murphy, Reginald A. New York.
Murray, A. E. Scott. England (I. S. E.).
Murschel, Jacob. Dakota.
Musgrove, Robert. Michigan.
Muskegon, City of. Michigan.
Myatt, H. England (I. S. P.).
Myers, Harry L. Central States.

Nadin, Joe W. Central States.
Nagel, W. B. Ohio.
Nance, E. N. North Carolina.
Nash, D. A. Central States.
Nasi, Kaarlo. Pacific Northwest.
National Aluminate Corp. Central States.
Naylor, William. New England.
Nazareth Sewerage Company. Pennsylvania.
Necker, C. E. Canada.
Neiman, W. T. Central States.
Nelle, Richard S. Central States.
Nelson, Ben O. Pennsylvania.
Nelson, C. L. Central States.
Nelson, Frederick G. Ohio.
Nelson, George I. Central States.
Nemmers, W. P. Iowa.
Nesbit, George H. New York.
Nesheim, Arnold. Federal.
Nesin, Benj. C. New York.
Netto, J. P. De Lemos. New York.
Neves, Lourenco Baeta. New York.
Neville, Jabez E. California.
Nevitt, I. H. New York.
Newell, Town of. Iowa.
Newland, Stewart H.
Newlands, James A. New England.
Newlund, Walter W. Central States.
New Mexico Bureau of Public Health. Rocky Mountain.
Newsom, Reeves. New York.
Newton, R. O. Georgia.
Nichol, Gordon B. New Jersey.
Nichols, V. R. Pacific Northwest.
Nichols, Arthur E. New York.
Nichols, M. Starr. Central States.
Nicholas, Forrest A. Central States.
Nicholson, C. P. New York.
Nicklin, H. S. Canada.
Nicoli, Frank A. New England.
Nielsen, A. F. New York.
Niemi, Arthur G. Central States.
Niles, A. H. Ohio.
Nisbet, George A. Rocky Mountain.
Nisnevitz, Oscar. New Jersey.
Nolan, George H.
Nolte, Fred W. Pacific Northwest.
Noreom, George D.
Nordell, Carl H. Central States.
Norgaard, John.
Norris, Finlay J. California.
Norris, Francis I., Jr. Federal.
Norris, Harold E.
Noth, Melvin J. Central States.
Nugent, Franklin J. Pennsylvania.
Nussbaumer, Newell L. New York.
Nussberger, Fred. New York.

Obma, Chester A. Central States.
O'Brien, Earl F. New York.
O'Brien, James E. New York.
Ocean City Sewer Service Co. New Jersey.
Ockershausen, R. W. Central States.
O'Connell, Wm. J. California.
O'Connor, William F., Jr. New York.
O'Dell, W. H. New York.
O'Donnell, Frank. New York.

O'Donnell, R. Pennsylvania.
Oeffler, W. A. Central States.
Oehlke, Henry E. Michigan.
Oeming, L. F. Michigan.
O'Flaherty, Fred. Ohio.
Ogden, Henry. New York.
Ogle, Harry B. California.
O'Hara, Franklin. New York.
Ohr, Milo F. Michigan.
Ojai, City of. California.
Oke, Ernest E. W. Canada.
Okun, Abraham H. New York.
Okun, Daniel A. Central States.
Okun, W. H. New York.
Old, H. N. Federal.
Older, Fred. Michigan.
O'Leary, William A. New York.
Oleri, Frank J.
Olewiler, Grant M. Pennsylvania.
Olmsted, C. Henry New England.
Olney, H. Ross. California.
Olsen, Wm. C. North Carolina.
Olson, Frank W. Central States.
Olson, Herbert A. Michigan.
O'Mara, Richard. Central States.
O'Neill, Ralph W. California.
Ongerth, Henry J. California.
Orchard, W. J. New Jersey.
Ortiz, Pedro C.
Orton, J. W. Michigan.
Orwicz, Bernard. Central States.
Osage, City of.
Osborn, L. C. Rocky Mountain.
Owen, Mark B. New York.
Owings, Noble L. Maryland-Delaware.

Pacific Flush Tank Co. Central States, Rocky Mountain.
Pacific Foundry Company, California.
Packard, O. E. Michigan.
Page, R. W. Central States.
Paige, F. O. Central States.
Painter, Carl E. California.
Pallo, Peter E.
Palmer, Benjamin M. New England.
Palmer, Fred C. Canada.
Palmer, Gilbert. Pennsylvania.
Palmer, Harold K. California.
Palmer, I. Charles. Pennsylvania.
Palmer, John R. Central States.
Palmer, Ralph M. Central States.
Paloesay, Frank S. Ohio.
Pardee Engineering Co., Inc. New York.
Parkes, G. A. Calif.
Parker, Charles F. New York.
Parker, J. C. North Carolina.
Parker, R. J. England (I. S. P.).
Parks, W. J., Jr. North Carolina.
Parr, James. California.
Parsons, F. W. California.
Parsons, Norman W.
Parsons, R. H. Canada.
Patterson, W. E. Canada.
Patterson, Orville W. Central States.
Patterson, Richard L. California.
Patterson, Roy K. New York.
Patriarche, John M. Michigan.
Paul, Lewis C. New York.
Paulette, R. J. Kansas.
Payrow, Harry G. Pennsylvania.
Payton, Lyle. California.
Pearce, Geo. W. Arizona.
Pearse, Langdon. Central States.
Pearson, S. R. Pennsylvania.
Pease, Maxfield. Ohio.
Peart, Robt. Kansas.
Peck, E. M. Central States.
Peck, Lawrence J. New York.
Pecker, Joseph S. Pennsylvania.
Peirce, W. A. Central States.
Peirson, Nat. D. North Carolina.
Pekin, City of. Central States.
Peller, Leo R. Central States.
Pennsylvania Salt Mfg. Co. New York.
Pensinger, L. C. Kansas.
Perkins, J. L. North Carolina.
Perlstein, Edward. New York.
Perrine, J. F. New York.
Perroni, Joseph. New York.
Perry, A. H. Canada.
Perry, Earl R. New England.
Peterson, Earl L. New York.
Peterson, Ivan C. Central States.
Peterson, J. H. California.
Peterson, Myhren C. Central States.
Peterson, R. W. Central States.
Petrie, William P. New England.
Pettit, Charles. Ohio.
Pfeifer, Willard. Central States.
Pfeiler, L. F. Central States.
Pfreimer, Harold A. Pennsylvania.
Phelps, B. D. California.
Phelps, E. B. New York.
Phelps, E. K. New York.
Phelps, Geo. Canada.
Phelps, T. I. California.
Philadelphia, City of. Pennsylvania.
Philion, W. I. New York.
Phillips, H. N. New York.
Phillips, Roy L. Pennsylvania.
Phillips, R. S. North Carolina.
Piatt, Wm. M. North Carolina.
Pickett, Arthur G. California.
Pierce, C. L. California.
Pierce, George O. Central States.
Pierce, W. E. Michigan.
Pierron, Wm., Sr. Pacific Northwest.
Pierson, Otto J. Michigan.
Pincus, Sol. New York.
Pinkney, Glenn E. New York.
Pinney, F. W. North Dakota.
Pitkin, Ward H. New York.
Pittsburgh Equitable Meter Co. New York.
Placek, O. R., Jr. Federal.
Plamondon, Sarto. Canada.
Pleasanton, Town of. California.

Pledger, A. England (I. S. P.).
Plummer, Raymond Benton. Central States.
Poindexter, G. G. Central States.
Polakov, Nicholas N. New York.
Pollock, John M. New York.
Pollock, John M. North Carolina.
Pomeroy, Clarence. Michigan.
Pomeroy, Richard. California.
Pontbriand, P. N. Canada.
Ponto, Willard. Michigan.
Pool, Charles L. New England.
Poole, B. A. Central States.
Poole, S. B. England (I. S. P.).
Pope, Lester. New Jersey.
Popp, W. L. California.
Porges, Ralph. New Jersey.
Porteous & Company, W. K. England (I. S. E.).
Porter, Harold. California.
Porter, William, New York.
Post, Fred W. California.
Poston, R. F. South Dakota.
Potter, Alexander. New York.
Potter, R. E. Canada.
Pottingham, W. P. Central States.
Potts, Clyde. New York.
Potts, Harry C. Michigan.
Powell, A. R. New York.
Powell, J. C. Central States.
Powell, S. T. Maryland-Delaware.
Powell, W. B. New York.
Powell, W. L. Texas.
Powers, Thos. J. Michigan.
Pratt, Gilbert H. New England.
Pratt, Jack W. California.
Price, Charles R. South Dakota.
Price, D. H. A. England (I. S. P.).
Price, R. C. Central States.
Primmer, B. J. California.
Pringle, H. L. Canada.
Proctor, J. W. England (I. S. P.).
Proudman, Chester F. New England.
Prough, Fred K. Central States.
Provost, Andrew J., Jr. New York.
Puffer, Stephen P. New England.
Purdie, David J. New York.
Purdy, William C. Federal.
Purser, John R., Jr. North Carolina.

Quaely, Martin F. New York.
Queens Borough Public Library. New York.
Queen's University Library. Canada.
Quigley, T. T. Central States.
Quinn, Francis T. New England.
Quinn, Thomas A. New England.

Racek, L., Jr. Central States.
Raisch, William. New York.
Raiter, Clifford R. Central States.
Ralston, George E. Central States.
Ralston, Wilmer R. Pennsylvania.
Ramseier, Roy E. California.
Ranagan, Fred E. California.
Randall, C. C. North Carolina.
Randall, Odie L. Arizona.
Randolph, Verdun. Central States.
Rankin, R. S. Central States.
Rantsma, W. F. California.
Rath, Henry M. New York.
Rawn, A. M. California.
Rawson, E. Otto. Canada.
Raymond, Herbert E. New England.
Raymond, Nelson I. Michigan.
Ray, Frederick. Central States.
Read, Homer V. Central States.
Ream, Edward F., Jr. Central States.
Reardon, Joseph F. New York.
Reardon, Wm. R. Central States.
Redding, Harry P. North Carolina.
Redfern, W. B. Canada.
Red Wing Sewer Pipe Corp. Central States.
Reed, Geo. D. Federal.
Reed, J. H. Pennsylvania.
Reed, Paul W. Central States.
Reed, Ralph. South Dakota.
Reedy, Timothy D. Michigan.
Rees, N. B. Central States.
Regan, T. H. Central States.
Regelsen, Alfred E. New York.
Regester, Robert T. Ohio.
Reilly, John J. Pennsylvania.
Rein, L. E. Central States.
Reinke, Edward A. California.
Reinoehl, Don. California.
Reisch, Eugene A. New York.
Reisert, Michael J. New York.
Renfrew, J. Harvey. England (I. S. E.).
Requardt, G. J. New York.
Reuning, Howard T. Pennsylvania.
Reybold, D. C. Central States.
Reynolds, A. V. England (I. S. P.).
Reynolds, Leon B. California.
Reynolds, M. W. Michigan.
Rhoads, Edward J. Pennsylvania.
Rhyne, C. E. North Carolina.
Ribal, Raymond Robt. California.
Ribbius, F. J. England (I. S. P.).
Ribner, Morris. New York.
Rice, John M. Pennsylvania.
Rice, Lawrence G. New York.
Rice, Lawrence H. New York.
Rice, Palmer J. North Carolina.
Richards, P. W. Central States.
Richardson, Charles G. New England.
Richardson, Charles S. New England.
Richey, C. E. Iowa.
Richgruber, Martin. Central States.
Richmen, W. F. Central States.
Richter, Paul O. Central States.
Rickard, Grover E. New York.
Ricker, W. H., Jr. Pennsylvania.
Ricketts, Allan T. Federal.
Riddick, Thomas M. New York.
Ridenour, G. M. New Jersey.
Riedel, John C. New York.
Riedesel, Henry A. Central States.

Riehl, W. H. Canada.
Riley, Harley M. New York.
Riordan, James T. New York.
Ritter, Bruce. Michigan.
Roab, F. H. Central States.
Robb, Charles G. New England.
Roberton, L. T. Canada.
Roberts, C. R. New York.
Roberts, F. C., Jr. Arizona.
Roberts, Jack. New York.
Roberts, L. M. New Jersey.
Roberts, W. C. California.
Robinson, B. Canada.
Robinson Clay Products Co. New York.
Robinson, George L. New York.
Robinson, I. F. Canada.
Robinson, J. C. South Dakota.
Robinson, T. C. North Carolina.
Robinson, Willis S. California.
Robins, Maurice L. Central States.
Robles, George C. California.
Rocco, John. New York.
Roche, Edward C. New England.
Roche, J. P. New England.
Rocker, Christian G. New York.
Rockne, T. B. Central States.
Roe, Frank C. New York, Central States, Canada.
Rogers, Allan H. New York.
Rogers, D. Paul. Pennsylvania.
Rogers, Harvey G. Central States.
Rogers, H. L. Pennsylvania.
Rogers, John A. New England.
Rogers, M. W. Canada.
Rogers, W. H. Central States.
Rohlich, Gerald A. Central States.
Roland, Robert J. Central States.
Romaine, Burr. Central States.
Rooks, C. P. Michigan.
Rosemeyer, Alfred. Central States.
Rosengarten, W. E. Pennsylvania.
Ross, John T. Pennsylvania.
Ross, W. E. Central States.
Rostenbach, Royal Edwin. Iowa.
Roth, B. F. Ohio.
Rowan, Thos. C. New York.
Rowen, R. W. Central States.
Rowinski, N. M. Central States.
Rowntree, Bernard. California.
Roznoy, Louis W. New Jersey.
Ruble, E. H. Central States.
Ruchhoft, C. C. Central States, Federal.
Ruck, Franklin. Ohio.
Rudd, Wm. C. Michigan.
Rudolfs, Willem. New Jersey.
Rugdal, H. T. Central States.
Rule, Harry A. Central States.
Rumsey, James R. Michigan.
Rupp, Daniel H. Ohio.
Rush, Dewitt E. New Jersey.
Rush, Frank O. Central States.
Russell, Don B. Iowa.
Russell, George. Missouri.
Russell, J. H. Central States.
Russell, J. P. Canada.
Ruth, Leo. W., Jr. California.
Rutter, Lee D. Pennsylvania.
Ryan, Joseph P. Central States.
Ryan, J. Samuel. New York.
Ryan, T. J. Texas.
Ryan, Wm. A. New York.
Ryon, Henry. New York.

Saetre, Leif. New York.
Sage, Howard D. New York.
Sageman, Norman. Michigan.
Sager, John C. New England.
Sakellariou, Evans N. Central States.
Salle, Anthony. New York.
Salvato, Joseph A., Jr. New York.
Sammis, L. A. New York.
Sampson, J. A. Iowa.
Samson, Channel. New York.
Sanborn, J. F. New York.
Sanders, M. D. Central States.
Sanderson, W. W. New York.
Sanford, Chester. New Jersey.
Santilli, Frank. New York.
Sargent, H. H. Central States.
Savage, Edward. New York.
Saville, Thorndike. New York.
Sauer, Victor W. California.
Saunders, James B. Arizona.
Sawyer, Clair N. Central States.
Sawyer, Robert W., Jr. New England.
Seiver, A. England (I. S. E.).
Schade, Willard F. Ohio.
Schaetzle, T. C. Ohio.
Schaefer, Edward J. New York.
Schafler, Norbert C. Central States.
Schapp, A. California.
Schaut, George G. Pennsylvania.
Schcak, H. M. Canada.
Scheffer, Louis K. Pennsylvania.
Scheidt, Burton A. Central States.
Scheller, Geo. M. New York.
Schenk, E. E. Iowa.
Scherer, Paul. New York.
Schier, Lester C. Central States.
Schildmann, W. H. Central States.
Schiller, Bernard. Arizona.
Schirk, J. M. Rocky Mountain.
Schlenz, H. E. Central States.
Schliekelman, R. J. Iowa.
Schmidt, Otto J. Central States.
Schmidt, William F. New York.
Schmuller, Frederick M. New York.
Schneider, J. J. Central States.
Schnupp, Leonard J. Pennsylvania.
Schrack, Bert. Iowa.
Schreiner, W. R. New York.
Schriner, P. J. Central States.
Schroeder, A. W. Central States.
Schroeder, W. L. South Dakota.
Schroepfer, George J. Central States.
Schulz, E. H. South Dakota.

Schwark, Wm. A. Central States.
Schwartz, H. L. Pennsylvania.
Schwartz, Louis. New York.
Schwartz, Oswald. Central States.
Schwob, Carl E. Central States.
Scott, Cliffton A. Central States.
Scott, Guy R. Federal.
Scott, R. D. Ohio.
Scott, Roger J. Central States.
Scott, Rossiter S. New York.
Scott, Roy D. New York.
Scott, W. England (I. S. P.).
Scott, Warren J. New England.
Scott, Walter M. New York.
Scott, W. M. Canada.
Scouller, W. D. England (I. S. P.).
Scovill, John R. New York.
Scudder, Aubrey P. New York.
Seaman, Henry. North Carolina.
Searight, Geo. P. Pennsylvania.
Searls, Glenn. New York.
Seely, Geo. A. Arizona.
Sedlacek, A. J. Iowa.
Segel, A. California.
Seid, Sol. New Jersey.
Seifert, William P. New York.
Seltzer, J. M. Pennsylvania.
Semon, H. G. New York.
Senseman, Wm. B. California.
Setter, Lloyd R. New Jersey, Pennsylvania.
Seufer, Paul E. Pacific Northwest.
Sexton, J. P. Arizona.
Seydel, H. New Jersey.
Shapiro, Charles M. New York.
Shapiro, Robert. New York.
Shaw, George H. Pennsylvania.
Shaw, Frank R. Federal.
Shaw, Paul A. California.
Shea, Walter J. New England.
Shearer, A. B. California.
Sheen, Robert T. Pennsylvania.
Sheets, W. D. Ohio.
Shelley, Harry. Pennsylvania.
Shelton, Edw. N. Georgia.
Shelton, M. J. California.
Shephard, W. F. Michigan.
Sheppard, Frederick. New York.
Shera, Bryan. Pacific Northwest.
Sheridan, City of. Rocky Mountain.
Sheridan, Thomas J. New York.
Sherman, Leslie K. New England.
Shertzer, J. H. Pennsylvania.
Shete, V. G. England (I. S. E.).
Shick, V. R. Ohio.
Shiffer, J. Paul. Pennsylvania.
Shirley, Donald L. Pacific Northwest.
Shockley, Homer G. New York.
Shook, H. E. California.
Shook, Howard R. Canada.
Shubart, C. A. Central States.
Shupe, S. Canada.
Sibbald, Charles T. A. New York.
Sibila, Rocco. New Jersey.
Sickler, Archie H. New York.
Sidle, R. S. England (I. S. P.).
Sidwell, Clarence G. Central States.
Siebert, Christian L. Pennsylvania.
Sieg, J. G. Central States.
Sieverding, O. C. New England.
Signor, C. V. Pacific Northwest.
Sigworth, E. A. New York.
Silberbauer, Walter R. California.
Simmerman, John S. New Jersey.
Simon, Samuel S. New York.
Simonton, Lewis. Georgia.
Simplex Ejector & Aerator Corp. Central States.
Simplex Valve and Meter Co. New York.
Simpson, R. W. New York.
Simpson, Jr., George. Rocky Mountain.
Simson, Paul W. New York.
Singer, L. P., Jr. California.
Skinner, J. F. California.
Skinner, W. V. California.
Slagle, E. A. New Jersey.
Slagle, Elmer C. Central States.
Slausson, J. B. Michigan.
Slee, Angus E. Rocky Mountain.
Sleeger, Warren H. Central States.
Slocum, Adelbert I. New York.
Slough, John. New York.
Small, R. L. Pacific Northwest.
Smalley, R. T. Arizona.
Smallhorst, David. Texas.
Smedberg, C. W. North Carolina.
Smigel, Walter A. Ohio.
Smiley, Paul E. Ohio.
Smith Company, A. H. Ohio.
Smith, Alva J. California.
Smith, B. G. Pacific Northwest.
Smith, Benjamin L. New York.
Smith, Charles E. Iowa.
Smith, Chester A. California.
Smith, Dell. Central States.
Smith, E. A. Cappelen. New York.
Smith, Edward J. New York.
Smith, E. E. Ohio.
Smith, Frank E. California.
Smith, Fred J. Central States.
Smith, G. C. England (I. S. P.).
Smith, H. G. California.
Smith, Harold. New York.
Smith, Harold. Michigan.
Smith, Harvey J. Pacific Northwest.
Smith, J. F. California.
Smith, J. Irwin. Central States.
Smith, Levi B. Kansas.
Smith, L. R. New York.
Smith, Marvin L. Pennsylvania.
Smith, Merlin D. Pennsylvania.
Smith, P. A. New Jersey.
Smith, Paul L. Maryland-Delaware.
Smith, Ralph A. Central States.
Smith, R. C. New Jersey.
Smith, Robert J. Michigan.
Smith, Russell S. Federal.

Smith, R. Trumbull. Central States.
Smith, S. H. Michigan.
Smith, Waymon, North Carolina.
Smith, Walter B. Michigan.
Smith, Walter R. New York.
Smith, Wendell H. Pacific Northwest.
Smith, W. T. E. Canada.
Smithwick, John J. New England.
Snapp, Russell G. Federal.
Snedeker, L. Laverne. Michigan.
Snell, J. R. New England.
Snelsire, William. Pennsylvania.
Snow, Donald L. Central States.
Snow, Willis J. New England.
Snyder, M. K. Pacific Northwest.
Snyder, N. S. New York.
Snyder, R. F. Ohio.
Solander, Arvo A. New England.
Solomon, G. R. New York.
Solvay Sales Corp. New York.
Soper, Romayne. New York.
Sorbel, J. L. South Dakota.
Soreff, Joseph. New York.
Soroker, Sam. California.
Sorrell, W. H. Central States.
Sotter, R. R. California.
Soule, Ralph M. New England.
Souther, Fred L. California.
Spacey, T. England (I. S. P.).
Spaeder, Harold J. Central States.
Spaeth, Julius. Kansas.
Sparr, A. E. New York.
Spear, William B. Pennsylvania.
Speiden, H. W. Pennsylvania.
Speirs, George W. New York.
Spellman, W. A. Canada.
Spence, W. O. North Carolina.
Spencer, Albert M. New York.
Spencer, C. C. Central States.
Sperry, Walter A. Central States.
Spiegel, Milton. Central States.
Spieker, Roy G. South Dakota.
Spier, D. R. New York.
Spies, Kenneth H. South Dakota.
Spiess, Reinhold. Central States.
Splitt, Howard A. New York.
Spragg, H. J. Iowa.
Spry, Fred J. New York.
St. Louis Public Library. Missouri.
St. Michaels Industrial School. Pennsylvania.
Stache, Paul. New York.
Stalbird, James A. New York.
Staley, H. H. Kansas.
Stalker, W. D. Canada.
Stanbridge, H. H. England (I. S. P.).
Stanley, C. M. Iowa.
Stanley, Stephen. England (I. S. E.).
Stanley, Wm. E. New York.
Stapleton, K. K. Central States.
Stapley, Edward R. Oklahoma.
Starling, Charles H. North Carolina.
Stauff, Paul V. Central States.
Staynes, E. H. England (I. S. P.).
Stearns, Donald E. New England.
Steel, E. W. Texas.
Steindorf, R. T. Central States.
Steffen, A. J. Central States.
Steffensen, S. W. New York.
Steffes, Arnold M. Central States.
Stegeman, Paul. Michigan.
Stemper, J. Alex. Central States.
Stepanek, Charles H. B. New York.
Stepsis, John S. New York.
Sterling, Clarence I. New England.
Sterns, Edward A. New York.
Stevenson, Albert H. New York.
Stevenson, Ralph A. California.
Stevenson, W. L. Pennsylvania.
Stewart, F. D. Ohio.
Stewart, Henry. Michigan.
Stewart, H. M. Pennsylvania.
Stewart, Morgan E. California.
Stielstra, Clarence. Michigan.
Stiles, Morrison N. Pennsylvania.
Stilson, Alden E. New York.
Stites, H. L. California.
Stock, Mitchell B. New England.
Stockman, L. R. Pacific Northwest.
Stone, A. England (I. S. P.).
Storey, Ben M. Central States.
Storrie, Wm. Canada.
Stolz, Stanley B. New York.
Strait, Ernest C. New York.
Strangard, Edward L. California.
Straub, Conrad P. New York.
Strayer, Elmer C. California.
Streeter, H. W. Federal.
Streeter, Robert L. Rocky Mountain.
Streeter, S. H. England (I. S. E.).
Strelow, J. L. Iowa.
Striger, R. M. Central States.
Strong, Bruce F. New York.
Strong, David H. M. Rocky Mountain.
Strowbridge, John C. New York.
Stuart, Archer B. California.
Stuart, F. E. New York.
Studley, E. G. California.
Stutz, C. N. Central States.
Sulentic, S. A. Kansas.
Sullivan, J. Donald. Michigan.
Sullivan, E. C. Federal.
Sullivan, Ernest J. New England.
Sullivan, L. E., Jr. New York.
Summers, M. W. England (I. S. E.).
Sund, Gutorm. Central States.
Susa, Stephen A. Pennsylvania.
Suter, Max. Central States.
Suttie, R. H. New England.
Svenson, Sven H. New York.
Swab, Bernal H. Pennsylvania.
Swanker, R. L. Ohio.
Swanson, S. C. California.
Swartz, Martin. North Carolina.
Swanz, Howard G. New York.
Sweeney, R. C. New York.
Sweeney, Willard G. New York.

Swinehart, Eugene B. Pennsylvania.
Swope, Gladys. Central States.
Symes, C. B. Canada.
Symons, G. E. New York.
Sylliassen, M. O. Pacific Northwest.
Sylvester, Robert O. Pacific Northwest.
Sylvester, William L. New York.

Taggart, J. M. California.
Taggart, Robert S. New York.
Talbot, F. D. California.
Tallamy, Bertram Dalley. New York.
Tanari, Myron. Central States.
Tapax Manufacturing Co. New York.
Tapleshay, John A. Central States.
Tapman, Walter P. New York.
Tapping, C. H. Central States.
Tarbell, J. Michigan.
Tarbett, R. E. Federal.
Tarlton, Ellis Alvord. New England.
Tarman, John E. Pennsylvania.
Tate, Guy M., Jr. Federal.
Tatlock, M. W. Ohio.
Taylor, Frank S. Ohio.
Taylor, Godfrey M. C. England (I. S. E.).
Taylor, H. England (I. S. P.).
Taylor, Harold. England (I. S. P.).
Taylor, H. W. England (I. S. P.).
Taylor, Henry W. New York.
Taylor, J. England (I. S. P.).
Taylor, Warren G. New York.
Tegtmeyer, L. C. California.
Tempest, N. F. Central States.
Tenenbaum, Meyer. Ohio.
Tennant, Carl F. California.
Tentschert, Francis E. New York, New England.
Terhoeven, G. E. New York.
Ternent, A. Canada.
Tetzlaff, Frank. New York.
Terwilliger, Frank. New York.
Thalheimer, Maree. Central States.
Thamasett, Otto E. New York.
Thatcher, Lynn M. California.
Thayer, Paul M. Central States.
Thayer, R. H. New York.
Theaker, K. Canada.
Theriault, E. J. Federal.
Theroux, Frank R. Michigan.
Thews, Vernon W. California.
Tholin, A. L. Central States.
Thomas, Ariel A. Central States.
Thomas, A. H. R. Canada.
Thomas, E. R. North Carolina.
Thomas, Franklin. California.
Thomas, F. W. Texas.
Thomas, Howard S. New York.
Thomas, R. Allen. North Carolina.
Thompson, E. H. New England.
Thompson, H. E. North Carolina.
Thompson, J. T. England (I. S. P.).
Thompson, M. H. New York.
Thompson, Robert B. New England.
Thompson, Thomas C. New York.
Thomson, F. N. New York.
Thomson, J. B. F. New York.
Thomson, William R. Canada.
Thorn, William J. Pennsylvania.
Thornhill, S. England (I. S. P.).
Thornton, Arthur F. Central States.
Tierney, Lawrence J. J. New England.
Tigar, Leonard Aldridge. England (I. S. E.).
Tillotson, John. California.
Timmers, Walter W. New York.
Tinning, J. D. Texas.
Todd, J. A. Central States.
Toledo, City of. Iowa.
Tolles, Frank C. Ohio.
Tolman, S. L. New York.
Toman, George J. North Dakota.
Toman, R. S. California.
Tomek, A. O. Central States.
Tompkins, James. New York.
Torpey, Wilbur N. New York.
Torrey, Wm. L. New York.
Tove, William B. New York.
Towers, Charles. California.
Towne, W. Waldo. South Dakota.
Townend, C. B. England (I. S. P.).
Townsend, Darwin W. Central States.
Tozzi, John. New Jersey.
Trager, Leonard W. New England.
Travaini, Dario. Arizona.
Travis, Frank D. Central States.
Trebler, H. A. Pennsylvania.
Trenthart, L. S. Central States.
Trescott, Boyd. Pennsylvania.
Trimble, Earle J. New York.
Troemper, A. Paul. Central States.
Trotti, Patrick J. New York.
Trubnick, Eugene. New Jersey.
Trulander, Wm. M. Central States.
Tubich, George. Central States.
Tull, E. R. North Carolina.
Turbine Sewer Machine Sales Co. New York.
Turner, E. S. Pacific Northwest.
Turner, J. R. Ohio.
Turpin, U. F. Central States.
Tuttle, Leon E. New England.
Tygert, C. B. Pennsylvania.
Tyler, R. G. Pacific Northwest.
Tyner, E. L., Jr. Central States.

Ullrich, C. J. California.
Umbenhauer, E. J. Pennsylvania.
Underpinning & Foundation Co., Inc. New York.
Unger, Carl. California.
Unger, G. C., Jr. Central States.
University of California Library. California.
University of Maine. New England.
University of Southern California. California.
Updegraff, W. R. California.
Urbana & Champaign San. District. Central States.

Urban, W. J. Central States.
Ure, Wilfred Gordon. Canada.

Valerio, Paul F. New York.
Van Benschoten, J. Canada.
Van Breda, A. J. Central States.
Van Camp, Paul M. North Carolina.
Van Denburg, J. W. New York.
Vanderlip, Arthur N. New York.
Van Deusen, E. J. New York.
Van Horn, R. B. Pacific Northwest.
Van Kleeck, Leroy W. New England.
Van Norman, James H. California.
Van Praag, Alex., Jr. Central States.
Van Wyck, George W. New York.
Vaughan, E. A. California.
Veatch, F. M., Jr. Central States.
Veigel, L. W. North Dakota.
Veitch, Wm. M. Canada.
Velz, C. J. New York.
Velzy, Charles R. New York.
Venn, Frank. Michigan.
Verdow, William H. New York.
Vermette, Floyd. Michigan.
Vest, W. E. North Carolina.
Victoria, John. New York.
Viggo, Westergaard. New York.
Vigna, John B. Central States.
Villaruz, Primo. California.
Vognild, R. O. Pacific Northwest.
Voight, Richard C. New York.
Voorhis, Chester E. New York.
Vredenburg, Edward L. New York.
Vrooman, Morrell. New York.

Wadhams, S. H. New England.
Wagenhals, H. H. New York.
Waggoner, E. R. California.
Wagner, Edwin B. Pennsylvania.
Wagner, Edward P. New York.
Wahlstrom, Carl A. Central States.
Wahmoff, John J. Ohio.
Wailes Dove Hermiston Corp. New York.
Walbridge, Thornton. Central States.
Wald, David. New York.
Walker, C. C. Ohio.
Walker, Chas. L. New York.
Walker, Donald. Central States.
Walker, Edward A. Pennsylvania.
Walker, Elton D. Pennsylvania.
Walker, J. W. Georgia.
Walker, Philip B. New England.
Walker, P. S. England (I. S. E.).
Walker, Vernon L. Central States.
Walker, Walter J. California.
Walker, William W. Federal.
Walraven, W. B. Central States.
Walters, Grover L. California.
Walton, Graham. Central States.
Wannenwetsch, T. A. New York.
Ward, A. R. England (I. S. P.).
Ward, C. N. Central States.
Ward, George C. New York.
Ward, Oscar. Central States.
Ward, Paul. Pacific Northwest.
Wardle, J. McClure. New York.
Wardman, F. L. England (I. S. P.).
Wardwell, T. M. Central States.
Ware, Howard. New York.
Waring, F. H. Ohio.
Warner, E. L. Pacific Northwest.
Warren, A. K. California.
Warren, George D. New York.
Warren, L. B. England (I. S. E.).
Warren State Hospital. Pennsylvania.
Warrick, L. F. Central States.
Washburn, Howard C. New York.
Waterhouse, A. G. England (I. S. P.).
Waterman, Earle L. Iowa.
Watertown Fire District. New England.
Waters, Leslie W. New York.
Watkins, H. H. New York.
Watkins, William W. New York.
Watmough, W. W. Canada.
Watson, Carl H. New York.
Watson, David M. England (I. S. E.).
Watson, Henry G. Rocky Mountain.
Watson, W. England (I. S. P.).
Watters, T. C. Central States.
Wayne Laboratories, The. Pennsylvania.
Weachter, Horace. Pennsylvania.
Weart, James G. Central States.
Weaver, W. H. Georgia.
Webb, L. C. California.
Weber, E. J. Central States.
Wechter, William H. New York.
Weeber, Earle R. Michigan.
Weeber, W. Keith. Central States.
Weed, Sam. California.
Wegner, Herman R. Michigan.
Weibel, S. R. Federal.
Weil, M. L. Central States.
Weir, E. McG. England (I. S. P.).
Weir, Paul. Georgia.
Weisel, W. O. Pennsylvania.
Weisler, Leonard. New York.
Weiss, H. New Jersey.
Weiss, R. H. Texas.
Welch, Pierre R. Michigan.
Welker, Leland A. New York.
Wells, E. Roy. Central States.
Wells, William N. Texas.
Welsch, W. Frederick. New York.
Welsford, H. R. Pennsylvania.
Welsh, William J. New England.
Wegner, J. H. Ohio.
Wennholm, S. V. England (I. S. E.).
Wentworth, John P. New England.
Wertz, C. F. Pennsylvania.
Westcott, Arthur. New York.
Weston, Arthur D. New England.
Weston Company, L. A. New York.
Weston, Roy F. Pennsylvania.
Weston, R. S. New England.

West, A. W. Central States.
West, Ezra. California.
West, Leslie E. New Jersey.
Westwood, Hector W. England (I. S. E.).
Wetherell, Joseph H. New York.
Wheatly, Wm. D. Missouri.
Whedbee, Edgar. Texas.
Wheeler, C. E. Central States.
Wheeler, Duane. Central States.
Wheeler, Robert C. New York.
Whelchel, H. E. Georgia.
Whipple, Melville C. New England.
Whirl, William H. Ohio.
Whisler, Ben A. Iowa.
Whitby, Steve. Pennsylvania.
Whitcomb, Leon R. Pennsylvania.
White, George C. California.
White Haven Sanatorium. Pennsylvania.
White, R. E. California.
White, W. W. California.
Whitley, F. H. New York.
Whitlock, Henry C. New England.
Whitman, Requardt & Smith. Maryland-Delaware.
Whitmore, Earle R. Michigan.
Whittaker, H. A. Central States.
Wickenburg, Town of. Arizona.
Wiest, Gordon J. Pennsylvania.
Wieters, A. H. Iowa.
Wigg, C. V. Michigan.
Wiggin, David C. New England.
Wigley, Chester G. New York.
Wilbur, C. C. Central States.
Wilder, A. D. California.
Wileman, Crozier S. Central States.
Wiley, John S. Federal.
Wiley, Ralph B. Central States.
Willcomb, George E. New York.
Willett, C. K. Central States.
Willey, Charles L. Pacific Northwest.
Williams, A. C. Pennsylvania.
Williams, C. B. North Carolina.
Williams, Chas. H. Pacific Northwest.
Williams, Clyde E. Central States.
Williams, G. Bransby. England (I. S. E.).
Williams, James C. Pennsylvania.
Williams, L. O., Jr. Rocky Mountain.
Williams, Leon G. Central States.
Williams, Macon M. North Carolina.
Williams, P. A. Ohio.
Williams, R. L. New York.
Williams, Stanley D. New York.
Williams, W. B. Michigan.
Williams, William D. Central States.
Williamson, A. E. Maryland-Delaware.
Williamson, F. Martin. Central States.
Williamson, R. C. Canada.
Willis, Robert E. Ohio.
Wills, Walter. Central States.
Wilke, Harvey R. Missouri.
Wilkins, Homer J. Texas.
Wilkinson, F. England (I. S. P.).
Wilson, C. R. New York.
Wilson, C. T. Iowa.
Wilson, Harry L. Central States.
Wilson, J. B. Central States.
Wilson, John. Central States.
Wilson, Murray A. Kansas.
Wilson, Thomas M. Pacific Northwest.
Wilt, Marlin E. Pennsylvania.
Winch, Norman M. New England.
Wing, Frederick K. New York.
Winnie, George. New York.
Winslow, George W. New York.
Wintersgill, A. T. California.
Wirt, J. B. California.
Wirt, R. M. Pennsylvania.
Wirth, Harvey E. Central States.
Wirts, J. J. Ohio.
Wisley, F. E. Central States.
Wisley, W. H. Central States.
Wishart, J. M. England (I. S. P.).
Wisniewski, T. F. Central States.
Witcher, C. Preston. Michigan.
Wittenborn, E. L. Central States.
Witter, Carl W. New Jersey.
Wittwer, Norman C. New Jersey.
Woelfle, Arthur H. New York.
Woese, Carl F. New York.
Wolman, Abel. Maryland-Delaware.
Wolohan, L. J. Michigan.
Woltmann, J. J. Central States.
Wontner-Smith, H. England (I. S. P.).
Wood, Herbert M. New York.
Wood, J. R. Canada.
Wood, Lawrence E. Kansas.
Woodhull, Charles R. New York.
Woodman, L. E. Central States.
Woodring, R. W. Pennsylvania.
Woods, F. X. Arizona.
Woodward, F. L. Central States.
Woodward, John D. Pennsylvania.
Woodward, R. D. California.
Woodward, Richard L. Federal.
Woodward, William H. New England.
Woolley, B. C. Iowa.
Wooten, M. Frank, Jr. North Carolina.
Worthington, Erastus. New England.
Worthington Pump & Mach. Corp. New York.
Wright, C. T. Federal.
Wright, Chilton A. New York.
Wright, Edward. New England.
Wrigley, Frank. England (I. S. P.).
Wuraftic, Joseph. New England.
Wyckoff, Charles R. New York.
Wyllie, George F. Michigan.

Yaffe, C. D. Federal.
Yatteau, George A. New York.
Yeager, Bert T. Central States.
Yenchko, John. Pennsylvania.
Yeomans Brothers, Company. Central States.
Yerkes, Milton R. Pennsylvania.
Young, C. H. England (I. S. E.).

Young, C. H. Pennsylvania.
Young, C. R. Canada.
Young, F. D. Ohio.
Young, Frank E. Iowa.
Young, Lewis A. Kansas.
Young, Norman C. Pennsylvania.
Young, Robert A. Central States.
Youngs, Benjamin K. New York.
Yow, W. E. North Carolina.
Zack, Samuel I. New York, Central States.
Zeigler, Frederick C. New York.
Zeitler, Braman E. New York.
Zieres, Floyd B. New York.
Zimmer, W. E. Michigan.
Zollner, Frederick D. New York.
Zuckweiler, G. C. California.
Zuppinger, William. New York.
Zurbuch, N. F. Central States.



Here's the CORNERSTONE For Efficient Public Works Design . . .

Among the new water works and sewage plants that stand out as models of advanced efficiency, a growing number owe their leadership largely to a progressive principle in designing. Like efficient process plants in commercial industries, they are laid out from their very inception on a basis of complete, centralized instrumentation by Foxboro.

Many public works engineers now consult Foxboro before the plans are on the boards. Foxboro engineers were earliest pioneers of modern process control instruments . . . the originators of many important types, such as flow controllers, recording controllers and throttling controllers with automatic reset. Through long experience in instrumenting processes in industry as well as public works, they are uniquely equipped to help you.

Write for Foxboro Instrumentation Bulletins **232**, on sewage plants, and 233, on water works. **The Foxboro Company, 162 Neponset Ave., Foxboro, Mass., U. S. A.** Branches in principal cities of the United States and Canada.

FOXBORO
REG. U. S. PAT. OFF.
Instrumentation
FOR WATER WORKS AND SEWERAGE SYSTEMS



U. S. Cast Iron Pipe is installed below the surface of the trickling filter of the Lebanon, Pa., Sewage Treatment Plant

IN TRICKLING FILTERS, as in sewage treatment processes generally, cast iron pipe installations are for the most part below the surface. That is one reason why cast iron pipe is so largely used for sewage works construction. With permanently tight joints and effective resistance to corrosion, cast iron pipe can be installed with confidence under conditions where repairs would be difficult and costly. We carry large stocks of Super-de Lavaud centrifugally cast pipe, pit-cast pipe and standard fittings at plants and storage yards throughout the U. S. A.

UNITED STATES PIPE AND FOUNDRY COMPANY

General Offices: BURLINGTON, NEW JERSEY

Foundries and Sales Offices Throughout the United States

U. S. CAST IRON PIPE

for sewers and sewage treatment plants

HOW "FLUSH-KLEEN" SYSTEM PREVENTS PUMP CLOGGING

Rags and Other Coarse Sewage Matter Do Not Pass Through Impellers.

Pumps Handle Strained Sewage Only.

While one pump is operating, sewage flows into basin through idle pump.

FILLING WET WELL

① Sewage flows through inlet pipe.

② Coarse sewage matter is retained by strainer.

③ Strained sewage flows through idle pump to basin.

PUMPING

③ Strained sewage is pumped from basin.

② Coarse sewage matter is backwashed from strainer.

④ Special check valve closes; sewage and coarse matter are pumped to sewer.

Both pumps operate under peak flows.



Fig. 2037—"Flush-Kleen" Sewage Pumping Station. While one pump is operating, sewage flows into the basin through the idle pump, as indicated by arrows. Coarse sewage matter is retained by the "Flush-Kleen" strainer in the idle pump (2). Only strained sewage passes through impeller to wet basin. When the idle pump operates, the coarse sewage matter in the strainer chamber is flushed out through the discharge pipe with the strained sewage from the wet basin. The check valve prevents operating pump from discharging back through the inlet line. In the meantime, sewage flows into the wet basin through the idle pump. Automatic Alternator transfers operation from one pump to the other. Both pumps may operate during peak flow, at which time sewage inflow is through overflow strainer.

OVER 2,5000 INSTALLATIONS
IN
SHIPS
BUILDINGS
INSTITUTIONS
MUNICIPALITIES
ARMY AND NAVY PROJECTS

SEND FOR BULLETIN 122 WITH COMPLETE "FLUSH-KLEEN" ENGINEERING DATA

CHICAGO PUMP CO. SEWAGE EQUIPMENT DIVISION

2336 Wolfram Street, CHICAGO, ILL.
Phone BRUnswick 4110

VACUUM—CONDENSATION—CIRCULATING—BILGE
FIRE—HOUSE—SEWAGE—SCRU-PELLER PUMPS
AERATORS—COMMINUTORS—SAMPLERS

REPRESENTATIVES THROUGHOUT THE UNITED STATES AND FOREIGN COUNTRIES



WORTHINGTON EQUIPMENT FOR SEWAGE PLANTS

CENTRIFUGAL PUMPS
FOR RAW SEWAGE, SEWAGE SLUDGE AND GENERAL SERVICES

SEWAGE GAS ENGINES DIESEL ENGINES

CONVERTIBLE GAS-DIESEL ENGINES

STEAM AND POWER PUMPS

TURBINE WELL, SUMP AND DRAINAGE PUMPS

STEAM CONDENSERS AND AUXILIARIES

FEEDWATER HEATERS

VACUUM PUMPS STEAM JET EJECTORS

MOORE STEAM TURBINES

REDUCING AND INCREASING GEARS

STATIONARY AND PORTABLE AIR COMPRESSORS

ROCK DRILLS AND CONSTRUCTION AIR TOOLS

MULTI-V-BELT DRIVES AIR LIFTS

• Descriptive literature is available on request

ICO-44

WORTHINGTON PUMP AND MACHINERY CORPORATION
General Offices: HARRISON, NEW JERSEY • Branch Offices and Representatives in Principal Cities throughout the World

WORTHINGTON

NEW PUBLICATIONS

of the

American Public Health Association

■

DIAGNOSTIC PROCEDURES AND REAGENTS

An authoritative volume descriptive of technics for the laboratory diagnosis and control of the communicable diseases. Prepared by the Standard Methods Committee on Diagnostic Procedures and Reagents, William A. Stovall, M.D., Chairman.

368 pp., cloth bound *Price $2.75*

THE CONTROL OF COMMUNICABLE DISEASES

A Report by the Committee of the same name, Haven Emerson, M.D., Chairman. Revised, 1940.

96 pp., pocket edition, paper bound *Price $.25*
Quantity quotations on request

COMMUNITY ORGANIZATION FOR HEALTH EDUCATION

A Report by the Committee of the same name, C. E. Turner, Dr.P.H., Chairman.

136 pp., paper bound *Price $.09 (stamps)*

STANDARD METHODS FOR THE EXAMINATION OF DAIRY PRODUCTS

Eighth Edition. Revised. Includes for the first time methods for the microbiological examination of frozen desserts.

(In preparation) *Price $2.50*

TRANSACTIONS OF THE SEVENTH INSTITUTE ON PUBLIC HEALTH EDUCATION

Fifteen discussion outlines and reading lists and four major papers.

93 pp., paper bound *Price $1.00*

■

Order from

THE BOOK SERVICE

American Public Health Association

1790 Broadway **New York, N. Y.**

CASTALOY



Laboratory Appliances

Each Castaloy clamp, holder and support has every detail designed to perform its intended function more satisfactorily. Up-to-date laboratories now use Castaloy Appliances exclusively because of their utility, convenience and enduring service.

Castaloy appliances are stronger than those made of cast iron or stamped steel. They do not rust; they resist corrosion and have distinctive mechanical features. Castaloy appliances cost less because they last longer and they are a big improvement in appearance.

FISHER SCIENTIFIC CO.
711-723 Forbes St., Pittsburgh, Pa.

EIMER & AMEND
205-223 Third Ave., New York, N. Y.

HELLIGE
AQUA TESTER

New, radically improved Model



MADE IN U.S.A.

This new model is, we believe, the most advanced type ever brought on the market for the accurate analysis of water, sewage, and industrial wastes.

Permanent reliability by the use of non-fading *Glass Color Standards* and the ease of operation make this a most desirable piece of equipment for all popular A. P. H. A. and A. W. W. A. methods.

HELLIGE, INC. 3718 NORTHERN BLVD. LONG ISLAND CITY, N. Y.

Prevent Wear and Cutting of Rods, Plungers, Shafts and Valve Stems

by using

MABBS RAWHIDE PACKING

Trade Mark

Reg. U. S. Pat. Off.

In Your Water Works and Sewage Plants

It lasts longer, is antifrictional, saves power, labor and repairs. Will prove the most economical packing that can be bought. These are the reasons why the United States Government has been using Mabbs Rawhide Packing on their hydraulic dredges for more than 35 years.

It Would PAY YOU to Use It on Your Water Works and Sewage Pumps and Valves.

Mabbs Hydraulic Packing Co.
Inc. 1892
431 S. Dearborn St. Chicago, Ill.

JOIN

Your State or Local

SEWAGE WORKS ASSOCIATION

AFFILIATE WITH THE NATIONAL FEDERATION OF SEWAGE WORKS ASSOCIATIONS

50 YEARS

Dr. Edward Goodrich Acheson whose inventive genius in creating the first man-made grinding material gave such impetus to the development of abrasive products that they have become all important factors in making possible vastly increased production and greater precision throughout all industry.

● Never before in history has life been so enriched by scientific discovery and industrial progress as in the half century just completed. We have seen amazing strides in means of transportation . . . the automobile, the airplane, the streamlined train of stainless steel. The electric furnace has given industry new chemicals, new steels, new alloys. We have witnessed the creation of new synthetics, the perfection of the machine tool, the enormous development of mechanical efficiency in every field and the production of countless commodities that promote and protect our way of life.

Of all these varied advances none surpass the progress made in the abrasive field. When Dr. Edward Goodrich Acheson created the first man-made abrasive fifty years ago, little did he foresee that modern abrasive products would become one of industry's most important tools for the shaping, grinding and finishing of almost every device of the useful arts. It shapes the tiny balances of our watches. It smooths the massive casting. It grinds tons of wood pulp for paper making. It fashions marble and stone, finishes wood and leather and sharpens the tools of every craft.

In other words manufactured abrasives are intimately integrated with the very structure of industrial life . . . meeting its fundamental needs, furthering its progress, translating yesterday's luxuries into today's commonplace necessities.

It is with justifiable pride, therefore, that we of The Carborundum Company pay tribute to the late Dr. Edward Goodrich Acheson in commemorating the Fiftieth Anniversary of his creation of silicon carbide, trade named "Carborundum," the first man-made abrasive. It is fitting also that we choose this occasion to acknowledge the splendid cooperation of our friends in industry in bringing his work to fruition and to rededicate this Company's efforts to a continuing service to industry and to the betterment of America's way of life.

Frank J. Tone

FRANK J. TONE, *President,*
THE CARBORUNDUM COMPANY,
NIAGARA FALLS, N. Y.

:: DIRECTORY OF ENGINEERS ::

ALBRIGHT & FRIEL, INC.
Consulting Engineers
Water, Sewerage, Industrial Waste, Garbage, Power Plant and Valuation Problems
1520 LOCUST ST.
PHILADELPHIA, PENNA.

John W. Alvord Louis R. Howson
Charles B. Burdick Donald H. Maxwell
ALVORD, BURDICK & HOWSON
Engineers
Water Works, Water Purification, Flood Relief, Sewerage, Sewage Disposal, Drainage, Appraisals, Power Generation
Civic Opera Building Chicago

BUCK, SEIFERT AND JOST
Consulting Engineers
(FORMERLY NICHOLAS S. HILL ASSOCIATES)
Specializing in Sewerage and Sewage Disposal, Water Supply and Water Purification, Valuations and Reports
Chemical and Biological Laboratories
112 East 19th Street New York, N. Y.

THE CHESTER ENGINEERS
Campbell, Davis & Bankson
Water Supply and Purification, Sewerage and Sewage Treatment, Power Development and Applications, Valuations and Rate Investigations.
210 E. PARK WAY AT SANDUSKY ST.
PITTSBURGH, PA.

BLACK & VEATCH
Consulting Engineers
4706 Broadway, Kansas City, Mo.
Sewerage, Sewage Disposal, Water Supply, Water Purification, Electric Lighting, Power Plants, Valuations, Special Investigations, Reports and Laboratory Service
E. B. BLACK N. T. VEATCH, JR. A. P. LEARNED H. F. LUTZ
F. M. VEATCH J. F. BROWN R. E. LAWRENCE E. L. FILBY

GREELEY & HANSEN
Engineers
SAMUEL A. GREELEY PAUL HANSEN
PAUL E. LANGDON KENNETH V. HILL
THOMAS M. NILES SAMUEL M. CLARKE
Water Supply, Water Purification, Sewerage, Sewage Treatment, Flood Control, Drainage, Refuse Disposal
6 N. Michigan Ave., Chicago

HAVENS AND EMERSON
(formerly Gascoigne & Associates)
W. L. Havens C. A. Emerson
A. A. Burger F. C. Tolles F. W. Jones
Water, Sewage, Garbage, Industrial Wastes, Valuations.—Laboratories
Leader Bldg. Cleveland Woolworth Bldg. New York

METCALF & EDDY
Engineers
Water, Sewage, Drainage, Garbage and Industrial Wastes Problems
Laboratories Valuations
Boston, Mass.
Statler Building

MORRIS KNOWLES, Inc.
Engineers
Water Supply and Purification, Sewerage and Sewage Disposal, Valuations, Laboratory, City Planning.
Westinghouse Bldg. Pittsburgh, Pa.

ROBERT T. REGESTER
Consulting Engineer
Sewerage—Sewage Treatment
Water Works—Industrial Wastes
Drainage—Flood Protection
Advisory Service, Reports and Designs
Baltimore Life Building
Baltimore, Md.

WHITMAN, REQUARDT AND SMITH
Engineers
Ezra B. Whitman Norman D. Kenney
Gustav J. Requardt A. Russell Vollmer
Benjamin L. Smith Theodore W. Hacker
WATER WORKS—SEWERAGE—UTILITIES
Baltimore, Md. Albany, N. Y.

"TAFFY" TROUBLE?

℞ Penn Salt
Liquid Chlorine

"TAFFY," "chlorine gum," "chlorine butter," and "goo" are a few of the names given this sticky mess which at times clogs up the gas passages and orifices of chlorinators.

You can cure your taffy troubles by using taffy-free chlorine and tightening up chlorinator maintenance to exclude moisture, lubricants, bits of packing, and other foreign matter from the chlorine lines and chambers. Specify Penn Salt Liquid Chlorine made in our special fractionating column which produces gum-free liquid chlorine.

You receive Penn Salt Liquid Chlorine in double-checked cylinders which have been carefully cleaned, fitted with new or reconditioned valves, and twice inspected against leaks.

Write us for your free copy of the wall display card, "Handling Liquid Chlorine"—useful information to hang up near your chlorinator. Pennsylvania Salt Manufacturing Co., Widener Bldg., Philadelphia, Pa.—New York • Chicago • St. Louis • Pittsburgh • Tacoma • Wyandotte.

PENNSYLVANIA SALT
MANUFACTURING COMPANY
Chemicals

Coagulant Economy comes to you with

Ferri-Floc
TC TENNESSEE CORPORATION
FERRIC SULPHATE

YOU SAVE

- By conditioning sludge with ferri-floc. Atlanta's Clayton plant now uses ferri-floc, alone. No lime required to condition this sludge.

TC TENNESSEE CORPORATION

- **YOU SAVE** When you use ferri-floc as a coagulant for all types of water treatment and sewage. Also adaptable for waste water treatment.

Get a sample to test in your plant

- **YOU SAVE** *when you write immediately to*

TENNESSEE CORPORATION

ATLANTA, GA. LOCKLAND, OHIO

HERE'S A NEW, SMOOTHER OPERATING *PERIPHERAL DRIVE* CLARIFIER

- **Improves Sedimentation**
- **Produces Clearer Effluent**

This is the new, ultra-smooth Infilco PD Clarifier that provides better, more complete sedimentation and clearer effluents than conventional equipment.

Unexcelled performance is obtained in this new clarifier by the application of power from a *positive peripheral drive*. A stationary peripheral ring gear and pinion drives the rotating member at a constant, slow and uniform speed.

There are *no* disturbances with the PD Clarifier—all vibrations and uneven motions have been eliminated. Anti-friction bearings are used throughout. All bearings and reduction gears are enclosed and operate in oil.

PD Clarifiers are available from 30 ft. to 150 ft. in diameter—at size intervals of 5 ft.

Inquiries concerning this equipment are invited and will be answered promptly. Write to:

INTERNATIONAL FILTER CO., 325 W. 25TH PLACE, CHICAGO, ILL.

EQUIPMENT FOR CHEMICAL, BIOLOGICAL AND MECHANICAL TREATMENT OF SEWAGE

THESE ARE THE REQUIREMENTS...
CAN YOU MEET THEM?

TO INCINERATE A COMBINATION OF GREEN GARBAGE AND SEWAGE FILTER CAKE..

TO INCINERATE GREEN GARBAGE ALONE....

TO INCINERATE SEWAGE FILTER CAKE ALONE..

TO GUARANTEE PERFORMANCE...

YES! ... Said Incineration Headquarters!

INCINERATION HEADQUARTERS —— ... the country's most authoritative organization on all matters relating to the incineration of municipal wastes . . . maintains an integrated program of laboratory study, field research and plant design, assuring only equipment that is tried and proven.

Now, let the Rock Island Argus tell the story—

"On recommendation of the committee sent to Maryland and New Jersey last week to inspect incinerators, the council awarded the Nichols Engineering and Research Corporation of New York City the contract for furnishing and installing incinerator equipment at a cost of $68,750.

The committee reported that incinerator equipment costing about $50,000 less, on which bids were received last week, was unsatisfactory. Members explained the equipment would burn garbage alone and garbage and sewer sludge combined, but would not burn sewer sludge alone, as will be necessary in Rock Island, without the use of considerable additional fuel.

Committee members, in explaining their recommendation for the purchase of the more expensive incinerator equipment, said the cheaper equipment failed to burn the sludge and garbage thoroughly and that working conditions in plants where such equipment was in operation were far from proper."

Quoted from The Rock Island Argus, 1-23-40

NICHOLS ENGINEERING & RESEARCH CORPORATION

60 WALL TOWER BLDG., NEW YORK, N. Y. NERCO UNIVERSITY TOWER BLDG., MONTREAL, P. Q.

THEY "SHOW UP" IN SLUDGE LINES

Crane No. 778
Light Standard
Double Disc Gate Valves

At a glance, these iron body outside screw and yoke valves show exact position of the disc. Ideal for manifold service in sludge tank lines. Rated at 100-pounds water, they save the extra cost of heavier valves. Crane non-jamming disc design assures smooth operation and tight seating.

• • •

For the right valves for specific working conditions, look to the Crane line of over 38,000 piping items for every service. There's a Crane Branch or Wholesaler nearby—ready to serve you.

CRANE

VALVES • FITTINGS • PIPE • PLUMBING • HEATING • PUMPS

CRANE CO., GENERAL OFFICES: 836 S. MICHIGAN AVE., CHICAGO

DE LAVAL
CLOGLESS PUMPS



1—Can be disassembled without disturbing piping.
2—The impeller has wide passages without sharp corners, but provides guidance for the water to obtain high efficiency.
3—Wearing rings protect both impeller and casing to reduce leakage. Can be sealed with clear water.
4—To reduce overhang of impeller, stuffing box is over hub of impeller, which is protected by a renewable sleeve. Can be clear-water sealed.
5—Heavy shaft carried in ball bearings spaced well apart.

Ask for paper P-3302 on SEWAGE PUMPS, by A. Peterson.

DE LAVAL STEAM TURBINE CO.
TRENTON, N. J.

MORRIS
CENTRIFUGAL PUMPS



High-efficiency
Non-clogging
SEWAGE PUMPS
Send for catalog

MORRIS MACHINE WORKS
BALDWINSVILLE, N.Y.

ADVERTISE IN
SEWAGE WORKS JOURNAL

It Gets Results

Proof—Paid advertising increased 39% in 1940.

Total subscribers as at December 31, 1940—3200

For rate card and other relevant data write to:

ARTHUR A. CLAY, *Business Manager*
654 MADISON AVENUE
NEW YORK, N. Y.

The ABC OF SEWAGE GAS CONTROL & SAFETY DEVICES



FIGURE No. 440

VAREC" *Approved*
PRESSURE RELIEF AND FLAME TRAP ASSEMBLY

Diaphragm operated Regulator, Flame Trap and Thermal Shutoff Valve. Throttling Type—cannot chatter. Maintains predetermined back pressure, passing surplus gas to burner. Stops flame.

Patented telescopic Flame Trap element simplifies inspection and maintenance.

Pure aluminum—18-8 stainless steel—noncorrosive.

2″ to 10″.

"VAREC" *Approved*
FLAME TRAP ASSEMBLY
Patent No. 2068421

FIGURE No. 450

Flame Trap and Thermal Shutoff Valve.

It arrests and stops flame propagation.

Simplifies inspection and maintenance.

Pure aluminum and 18-8 stainless steel—noncorrosive.

2″ to 10″.

FIGURE No. 58C

"VAREC" *Approved*
PRESSURE RELIEF AND VACUUM BREAKER VALVE WITH FLAME ARRESTER

Installed on digester and gas holder domes, affords Emergency Pressure and Vacuum Relief and prevents flame entrance from atmospheric disturbances.

Easy inspection and maintenance.

Pure aluminum construction—noncorrosive.

2″ to 10″.

FIGURE No. 236

"VAREC" *Approved*
WASTE GAS BURNER

"VAREC" *Approved* SAMPLING HATCH COVERS

For use on digester domes. Noncorrosive, gastight, self-closing, sparkproof.

4″ to 10″.

FIGURE No. 48

"VAREC" *Approved* MANHOLE COVERS

For use on digester and gas holder domes. Sparkproof. Gastight. Easily accessible.

18″ and 20″.

FIGURE No. 220A

VAREC" *Approved* SUPER-SENSITIVE PRESSURE REGULATOR—DOUBLE PORT



FIGURE No. 187

Maintains upstream or downstream pressure to within 0.2″ of water of predetermined pressure.

Standard working parts 18-8 stainless steel with synthetic rubber diaphragm.

½″ to 10″.

"VAREC" *Approved*
MANOMETERS

Single or Triple open or push button control types. Leakproof. Accurate. Aluminum housing, bronze fittings, pyrex glass.

FIGURE No. 216A

"VAREC" *Approved*
SENSITIVE PRESSURE REGULATOR SINGLE PORT

Maintains upstream or downstream pressure to within 0.5″ of water of predetermined pressure.

2″ to 6″.

FIGURE No. 387

FIGURE No. 232D

"VAREC" *Approved*
SEDIMENT TRAP AND CONDENSATE DRIP TRAP ASSEMBLY

Cast iron construction—18-8 stainless steel working parts.

2″ to 4″.

"Varec" APPROVED EQUIPMENT

THE VAPOR RECOVERY SYSTEMS COMPANY
CONSULTANTS, DESIGNERS AND MANUFACTURERS OF GAS CONTROL AND TANK EQUIPMENT
Main Office and Factory
2820 No. Alameda Street • Compton, California
BRANCH OFFICES AND STOCKS New York City, Houston, Texas

Everdur

COPPER-SILICON ALLOY

Gets the Call in Sewage Treatment

COMBINING high resistance to corrosion with high strength, ease of fabrication and ready weldability, Everdur is uniquely adapted to light weight structures built of wrought metal. Over a period of 14 years, this moderately priced copper-silicon alloy has demonstrated its superiority for sewage treatment equipment under a wide variety of operating conditions. Anaconda Publication E-11 contains detailed information of interest to sewage and water works engineers.



(above)
• One of five easily *hand-operated* Everdur shut-off gates in the screen room of the Rahway Valley Joint Meeting Sewage Treatment Works, Rahway, N. J. The frame is cast Everdur, the plate is rolled Everdur, the 2½" spindle is machined Everdur rod. Height of frame—10′ 3″; total weight only 1,624 lbs.

(above)
• Control mechanism of 12″ diameter Everdur float tubes. Designed and built by Krajewski-Pesant Mfg. Corp., for the Ward's Island Sewage Treatment Works of the City of New York. In the air filters in both primary and secondary rooms at Ward's Island, entire filter structures, filter holders, retaining mesh and rotating screen were made of Everdur by the American Air Filter Co., Inc., Louisville, Ky.

(right)
• Two types of Everdur screen frames used by New Haven Water Company at main outlets in reservoirs. Principal uses of Everdur in reservoirs and water distribution systems include screens, fittings, bolts, steps, valve stems and pipe. 41147-A



"EVERDUR" is a trademark of The American Brass Company, registered in the United States Patent Office.

Everdur Metal ANACONDA

THE AMERICAN BRASS COMPANY, General Offices: WATERBURY, CONNECTICUT

In Canada: ANACONDA AMERICAN BRASS LTD., New Toronto, Ont. • *Subsidiary of Anaconda Copper Mining Company*

ABANDON CENTRIFUGAL SEWAGE PUMPS ON SMALL FLOWS!

THE centrifugal pump *can* be scaled down to a size too small for effectiveness . . . *can be made so small* that it will not pass the normal and troublesome solids . . . and therefore requires a crutch, a mechanical shredder, screens, etc. At this point sewage engineering must shift. And here's the simple answer:

The YEOMANS "EXPELSOR"—One of the four types of pneumatic sewage pumping equipment for varying needs

WHAT MEDIUM-TO-SMALL PUMPING SYSTEMS NEED

Yeomans Pneumatic Pumping Systems were designed for that place in sewage work. They handle *actual* flows . . . and so they do not attempt to make a piece of machinery do something it wasn't intended to do. (Instead, Yeomans suits the equipment to the work.)

Yeomans Pneumatic Systems have no screens, no shredders, no impellers, no moving parts, no wet well, no sewage gas, no complex piping, no extra equipment, no multiplied maintenance problem. In general the cost is no more and often less than centrifugals.

They move small flows effectively, and without complexity. Isn't that *your* idea—and isn't that the object of good engineering?

WRITE! GET COMPREHENSIVE BULLETINS

YEOMANS BROTHERS COMPANY

1411 N. Dayton St. CHICAGO, ILL.

GREASE FLOTATION IN DEFENSE PROJECTS

The quantity of grease found in sewage from Military Camps is from two to three times that normally found in domestic sewage. Experience with older camps indicates clearly that special grease removal is required.



Grease floats and accumulates as a blanket on the quiescent tank surface.

THE "AMERICAN" GREASE FLOTATION UNIT

utilizes a low head pump mechanically entraining finely divided air which is ejected radially across the tank floor at a high velocity.

Swirling eddy currents at the tank bottom form a grease froth which floats to the quiet tank surface where it forms a blanket.

Finely divided air intimately diffused throughout the tank effects 60 to 70 percent B.O.D. removal.

TYPICAL INSTALLATIONS

Camp Claiborne, Louisiana—Camp Robinson, Arkansas—Fort Sill, Oklahoma.

THE AMERICAN WELL WORKS
MANUFACTURERS
PUMPING AND SANITATION EQUIPMENT
AURORA, ILLINOIS

INDEX TO ADVERTISERS

	Page
Albright & Friel, Inc.	24
Aluminum Co. of America	4
Alvord, Burdick & Howson	24
American Brass Co.	31
American Journal of Public Health	21
American Well Works	33
Black & Veatch	24
Buck, Seifert & Jost	24
Carborundum Company	23
Cast Iron Pipe Research Assn.	16
Chain Belt Company	5
Chapman Valve Mfg. Co.	6 and 7
Chester Engineers, The	24
Chicago Pump Company	19
Crane Company	28
De Laval Steam Turbine Co.	29
Dorr Company, Inc., The	2
Dresser Mfg. Co.	15
Eimer & Amend	22
Filtration Equipment Corp.	3
Fisher Scientific Co.	22
Foxboro Company	17
General Chemical Co.	9
Greeley and Hansen	24
Havens and Emerson	24
Hellige, Inc.	22
International Filter Co.	26
Johns Manville Corp.	10
Knowles, Inc., Morris	24
Link Belt Company	8
Mabbs Hydraulic Packing Co.	22
Metcalf & Eddy	24
Morris Machine Works	29
Nichols Eng. & Research	27
Norton Company	12
Pacific Flush-Tank Company	11
Pennsylvania Salt Mfg. Co.	25
Pittsburgh Equitable Meter Co.	14
Regester, Robert T.	24
Royer Foundry & Machine Co.	13
Tennessee Co.	26
U. S. Pipe & Foundry Co.	18
Vapor Recovery Systems Co.	30
Wallace & Tiernan Company, Inc.	Back Cover
Whitman, Requardt & Smith	24
Worthington Pump & Machinery Corp.	20
Yeomans Bros.	32

When writing these, please mention the

SEWAGE WORKS JOURNAL





At Veterans' Home, Yountville, Calif., 2 Visible Vacuum Chlorinators prechlorinate on a schedule and chlorinate final effluent proportional to flow.

Substantial chlorine economies are effected by this W&T Chlorinator installation for preventing obnoxious odors and disinfecting final effluent.

Odor prevention requires adequate chlorination of raw sewage. There is a changing chlorine demand . . . because of variations in flow, character and strength of raw sewage and temperature influences. All these variations follow a reasonably consistent daily time cycle.

Program devices automatically vary the feed rate from one W&T Visible Vacuum Chlorinator conforming to the four distinct steps of a time cycle indicated by plant studies.

Similar programmed installations have reduced chlorine consumption as much as 50%.

Disinfecting the stabilized effluent from the Bio-Filters requires a constant rate of chlorine dosage always proportional to the varying flows. A W&T Automatic Visible Vacuum Chlorinator, weir head controlled, handles this phase of the program.

Specialized knowledge—acquired over 27 years of experience with over 20,000 installations, solves chlorination problems like this. Entrust your problems to W&T equipment and W&T trained personnel.

Ask for a copy of Technical Publication 473 "Problems and Progress in Sewage Chlorination"—Today!

"The Only Safe Sewage is Sterilized Sewage"

BA-102

WALLACE & TIERNAN CO., Inc.

Manufacturers of Chlorine and Ammonia Control Apparatus

Newark, New Jersey — Branches In Principal Cities